MOHENJODARO AND THE INDUS CIVILIZATION



JOHN MARSHALL

CC-8. Gurukul Kangri University Haridwar Collection, Digitized by S3 Foundation USA

अवस्था अ

:672.86 V-13/2/24/21/24 CC-0. Gurukul Kangri University Haridwar Collection. Digitized by S3 Foundation U



MOHENJO-DARO AND THE INDUS CIVILIZATION

MOHENJO DARO AND THE INDUS CIVILIZATION

Being an official account of Archæological Excavations at Mohenjo-daro carried out by the Government of India between the years 1922 and 1927

Edited by

SIR JOHN MARSHALL, C.I.E., Litt.D., Ph.D., F.S.A., Hon. A.R.I.B.A., Hon. Fellow of King's College, Cambridge

Late Director-General of Archæology in India

In three volumes, with plan and map in colours, and 164 plates in collotype

Volume II: Text. Chapters XX—XXXII
Appendices and Index

Company

INDOLOGICAL BOOK HOUSE

DELHI-

VARANASI

1973

Published by Sh. Gajendra Singh for Indological Book House Delhi and Printed at Delux Offset Printers Delhi 7.

Processed Dy S. P. Sachdeva at Delux Process, 308/5, Shahzada Bagh, Old Rohak Road, Delhi-7

TABLE OF CONTENTS

CHAPTER XX

FAIENGE	AND	STONE	VESSELS
By	Erne	st Macka	y

	PAGE	9	
Faience Vessels. Mode of Manufacture;	List of	Stone Vessels; Varieties of Stone used;	List of
Objects; Imitation of Pottery Forms	365-6	objects; Rivet repairs; Grinders;	Stone
		Boxes: Incised Decoration	3

CHAPTER XXI

367-9

SEALS, SEAL IMPRESSIONS, AND COPPER TABLETS, WITH TABULATION By Ernest Mackay

PAGE	PAGE
Types of Seals. Cylinder Seals; Square,	Mythological Creatures
Rectangular, Button, Cube, and Round seals	Plant Forms; Animals figured in Script . 390-2
370-6	Seal Impressions; Types and Descriptions; Rect-
Seals of Unusual Character 376-7	angular and Square Tablets; Triangular
Method of Manefacture; Purpose of the Seals;	Prisms; Round Tablets; Impressions on
Use as Amulet Cases 377-81	Pottery Vessels
Animals Represented on the seals; So-called	Unclassified Impressions
Unicorn; The Cult Standard and its purpose	Copper Tablets; Animals pictured; Use of
382-5	Tablets
Short-horned Bull; Buffalo; Brāhmanī Bull;	Tabulation of Seals 402-5
Rhinoceros; Tiger; Elephant; Ghariāl;	
Antelone 385-0	

CHAPTER XXII

, SIGN-LIST OF EARLY INDUS SCRIPT

PART I. SOME EXTERNAL FEATURES OF WRITING

By C. J. Gadd, M.A., F.S.A., Assistant Keeper in the Department of Egyptian and Assyrian Antiquities, British Museum

Indus Seals found in Mesopotamia; Difficulty of Few resemblances between Indus and Sumeri	
	an
classifying signs; Device and Legend un- Signs; Analogies of Indus and Mino	
connected; Signs pictographic, but few Scripts	. 41
objects identifiable 406-9 Script not Alphabetic, but probably Syllabic .	411-
Modification and Combination of Signs; Additions Inscriptions probably contain Names and Titles.	4 41
and Enclosures 409 Numerical Signs; Indus Seal from Ur; Device	es
Direction of Writing ordinarily from right to left on later Indian Coins compared	412-
409-11 A Conjectural Reading	. 4

PART II. MECHANICAL NATURE OF THE EARLY INDUS WRITING

By Sidney Smith, M.A., F.S.A., Keeper in the Department of Egyptian and Assyrian Antiquities, British Museum

^ ^		•						0
					PAGE			PAGE
Mechanical and Material Natu	re of V	Writin	ng		415	Analysis of an Inscription		419
Classification of Signs; " End'	and '	Beg	innin	g "		Signs as ideograms and their relative positions.		420
Signs				415	-16	Proper Names and other Elements		421
Numerical and other Signs .				417	7-18	Longer Inscriptions discussed	42	1-2
Older Signs from Harappa.	0				418	Difficulty of classifying Signs; Arab and Africa	n	
Strokes at beginning or end					419	Signs		422

CHAPTER XXIII

THE INDUS SCRIPT

By S. Langdon, M.A., Ph.D., Shillito Professor of Assyriology, University of Oxford

PAGE	PAGE
Foreword: Derivation of Early Brahmi from	Accents and their Significance; Detached Accents
Indus Script 423	428-9
Resemblance of Indus Signs to Egyptian Hieroglyphs 424	Determinatives
Indus Seals from Mesopotamia of pre-Sargonic	Suggestions for decipherment . • 431-2
Age 424-6	Table of Brāhmī Characters derived from Indus
Cunningham's and Bühler's Theories 426-7	Script
Great antiquity of Indus Script; its direction from	Sign-List of the Indus Script 434-52
right to left	Postscript

CHAPTER XXIV

HOUSEHOLD OBJECTS, TOOLS, AND IMPLEMENTS

By Ernest Mackay

PAGE	PAGE
(a) OBJECTS OF KNOWN USE	Needles and Awls; Ladles 470-2
Querns; Palettes; Flint Implements 456-9	Handles; Cake Moulds 472-3
Dish-borer; Burnishers; Mace-heads and their	(b) Objects of Uncertain Use
types 459–61	Stone Rings; Rings with Wavy Tops and Bases;
Weights; Types of Weights; Perforated Weights	Shell Replicas 473-5
. 461-4	Mace-like Objects; Possibly Cult Objects . 475-6
Net-sinkers; Whetstones; Anvils (?); Gratings;	Conical Stones; Conical Stones with Heads 476
Pallista Balls (?) 464-6	Small Cones; Types and Materials 477-8
Sling Balls; Flesh-rubbers; Spindle-Whorls and	Cylindrical Objects of Pottery; Shell Caps;
their Types	Pedestal (?); Roundel; Pottery Tablets 479-80

CHAPTER XXV .

COPPER AND BRONZE UTENSILS AND OTHER OBJECTS

PART I. Sources and Metallurgy of Copper and its Alloys

By Muhammad Sana Ullah, M.A., BeSc., Archæological Chemist to the Government of India

PAGE	O PAG
Metals of the Indus People; Early use of Bronze;	Analyses of Copper and Bronze 48
Scarcity of Tin	Varieties of Copper and its alloys at Mohenjo-daro 485-
Copper-Arsenic alloy; Copper and Bronze in Egypt	Analyses of Copper and Bronze from Sind and
and Sumer	Balūchistān, by Professor C. H. Desch; Age
Early Copper Utensils in Central India; Sources	of Specimens analysed 486-
of Copper and Tin	0

PART II. TECHNIQUE AND DESCRIPTION OF METAL VESSELS, TOOLS, IMPLEMENTS, AND OTHER OBJECTS

By Ernest Mackay

PAGE	PAGE
Technique; Copies of Pottery Forms; Casting 488-9	Spear and Lance Heads; How made and hafted;
Copper and Bronze Vessels found together;	List of Examples 497-9
Detailed Descriptions 490-3	Arrow-heads; Knives and Daggers 499-500
Silver Vessels; Jewellery Contents 493	Razors; Saws; Sickles; Fish-hooks 500-1
Blade-axes; Mode of Manufacture; Comparisons	Types of Chisels; Descriptions of Examples . 501-3
with Other Countries; Types and General	Awls and Reamers; Needles; Metal Rods 504
Description	Finger-rings; Earrings; Bracelets; Miscellaneous
	Objects 504-8

CHAPTER XXVI

PERSONAL ORNAMENTS

By Ernest Mackay, with Appendix by A. L. Coulson, M.Sc., Geological Survey of India

PAGE	PAGE
Use of Jewellery; Types of Beads; Decorated	Bracelets; Materials and Descriptions 529-31
Carnelian Beads and Imitations 509-17	Hair-pins and Hair-pin Heads; Combs; Buttons;
Spacers; Terminals; Multi-stringed Necklaces 517-18	Bullae
Hoards of Jewellery described 519-23	APPENDIX
Capped Beads; Silver; Gold and Electrum Beads,	
Indian Lead 523-4	Introduction
Stones used in the making of Beads; Mode of	Determination of Beads; Densities and Other
Manufacture 525-6	Physical Properties 536-41
Fillets; Finger-rings; Earrings; Ear and Nose	Descriptive Notes 541-8
	•
Studs	

CHAPTER XXVII GAMES AND TOYS By Ernest Mackay

PAGE	PAGE
Human Figures . a . , 549-50	Casting Bones (?); Their possible use; Fish-
Toy Animals; Clar Baking Pans, Whistles;	forms; Markings 556-7
Rattles	Gamesmen or Amulets; Inlay and Markings;
Dice; Galls and Marbles; Absence of Knuckle-	Tetrahedral Forms 557-9
bones	Absence of model boats; Model Chairs; Bird-
Wheels; Toy Vehicles; Cart-frames; Early	chariots; Their use in India and China. 560-1
Chariots 2	•
,,,,,	
· ·	
Снартек	XXVIII
IVORY, SHELL, FAIENCE, AND OTHER	R OBJECTS OF TECHNICAL INTEREST
. Dy Ernes	st Mackay
Ivory; Its scarcity; Ivory Plaque; Sticks,	Faience; Body and Analyses; Use of Powdered
Combs and Cylinders	
	Steatite; Colours
Shell; Value as a material; Species used; Modern	Glazed Pottery; Analyses; Earliest Examples 577-8
shell-working; Manufactories 563-5	Early History of Faience, Vitreous Paste, and
Shell-Inlay; Method of manufacture; Cements;	Glass
Designs and Details	Decorated Carnelian; Imitations; Compositions 583-4
Faience and Paste; Inlay; Covers; Bracelets;	Bronze Cells for Inlay; Worked Agate . 584-5
Spindle-whorls; Description of Objects 570-4	Textiles; Discovery of Woven Cotton Material 585-6
Vitreous Paste; Analyses; Preparation; Mode of	Cereals and Fruits; Wheat; Barley; Dates . 587
use; Inlaid work 574-6	Medicines; Śilājīt; its use and provenance. 587-8
	"
Снарте	XXIX
SYSTEM OF WEIGHT	S AT MOHENJO-DARO
	my, B.A., M.Sc.
Dy 11. 0. 11em	n), D.M., 141.51.
PAGE	PAGI
General observations 589	Table VII. Weights on Babylonian System
Table I. Weights at Mohenjo-daro 590	found at Susa 593
',, II. Weights at Harappa 590	,, VIII. Approximations of Indus Valley
., III. Weights found at both Mehenjo-	weights to the Babylonian System 594
daro and Harappa 591	IV Approximation of aberrant weights
" IV. Exceptional weights at Mohelijo-	found in Iraq and Susa to Indus
10	Valley Weights 599
V Tiche Debut : 0.0	
VI Ham Ami C C	Conclusions
71. Heavy Assyrian System 502	Appendix I. Weights at Working date 1996.
	Appendix II. List of weights from Harappa . 597
	0 0

TABLE OF CONTENTS

Chapter XXX HUMAN REMAINS

By Colonel R. B. Seymour Sewell, M.A., Sc.D., F.A.S.B., Director, Zoological Survey of India, and B. S. Guha, A.M., Ph.D., Anthropologist to the Zoological Survey of India.

PAGE	PAGE	
Condition of Bones; Number of Skeletons;	Table II. Indices 646	,
Circumstances of finding 599	" III. Average measurements of the	
Description of Skeletons No. 1 to 26 600-6	different groups 647	
Description of Skulls Nos. 1 to 26 606-35	" IV. Average indices of the different	
Description of Skull M 635	groups 647	
Conclusions as to races at Mohenjo-daro	" V. Measurements on Craniograms . 648	;
Type I. Proto-Australoid. Race 638	" VI. Facial measurements in an antero-	
" II. Mediterranean Race 642	posterior plane 648	}
,, III. Mongolian Branch of the Alpine stock 643	" VII. Measurements showing the projection	
" IV. Alpine Race 644	of the cheek in an antero-posterior	
Table I. Measurements 645	plane 648	3

CHAPTER XXXI ZOOLOGICAL REMAINS

By Colonel R. B. Seymour Sewell and Dr. B. S. Guha

General condition of the animal remains 649 Table III. Measurements of Skull and Horn- Core of Bos indicus 657 Aves 662 Reptilia 662 Order Carnivora 650 Chelonia 662 Order Rodentia 653 Order Ungulata 653-61 Table I. Dimensions of Teeth of Equus 654 Caballus 654 Animals maintained in a state of domestication 669 Teeth in different series of Bos indicus 671 I. Measurements of Skull and Horn- Core of Bos indicus 657 Aves 662 Reptilia 662 Chelonia 662 Chelonia 664 Mollusca 664 Mollusca 664 Animals maintained in a state of domestication 669 Animal remains imported for ornament 670 Animal remains imported for medicine 671 List of specimens 672		PAGE	PAGE
MAMMALIA Aves Corder Carnivora Order Rodentia Order Ungulata Order Ungulata Caballus Caballus Teeth in different series of Bos indicus indicus Mammalia Aves Aves Aves Aves Geballia Aves Reptilia Chelonia Geballia Mollusca Geballia Gastropoda Animals maintained in a state of domestication Animals caught for food Animal remains imported for ornament Aves Reptilia Geballia Aves Aves Aves 662 Reptilia Geballia Acceptilia Accep	General condition of the animal remains	649	Table III. Measurements of Skull and Horn-
MAMMALIA Reptilia Reptilia Corder Carnivora 650 Chelonia 662 Order Rodentia 663 Order Ungulata 653 Order Ungulata 654 Table I. Dimensions of Teeth of Equus Caballus 654 Animals maintained in a state of domestication 669 Animals caught for food 700 Teeth in different series of Bos indicus 656 Animal remains imported for ornament 670 Animal remains imported for medicine 671	The species represented in the collection	650	
Order Carnivora	•		11100
Order Rodentia	Mammalia		Reptilia
Order Ungulata	Order Carnivora	650	Chelonia
Table I. Dimensions of Teeth of Equus Caballus	Order Rodentia	653	Pisces
Caballus	Order Ungulata	. 653-61	Mollusca
"II. Measurements of 2nd and 3rd Molar Animals caught for food	Table I. Dimensions of Teeth of	Equus	Gastropoda 665
Teeth in different series of Bos Animal remains imported for ornament	Caballus	654	Animals maintained in a state of domestication . 669
indicus . • 656 Animal remains imported for medicine 671	" II. Measurements of 2nd and 3rd	Molar	Animals caught for food 670
	Teeth in different series	of Bos	Animal remains imported for ornament 670
List of specimens	indicus. •	656	Animal remains imported for medicine 671
			List of specimens 672

CHAPTER XXXII

MINERALS AND METALS

By Sir Edwin Pascoe, M.A., Sc.D., D.Sc., F.G.S., F.A.S.B., Director, Geological Survey of India

	INGL		
Gold	674	Agate, Carnelian, Onyx, and Chalcedony	. 681
Silver	675 .	Jasper, Agate-Jasper, and Bloodstone .	. 681
Copper; Lead	676	Plasma, Tin, Bitumen, Red Ochre .	. 682
Lapis-lazuli; Turquoise	677	Basalt, Tachylite, Nepheline-Sodalite rock	. 683
Amazon Stone; Crystal; Steatite	678	Jadeite	. 683
Alabaster	679	Löllingite	. 684
Haematite; Amethyst; Slate	680	Green Earth	. 685

TABLE OF CONTENTS

APPENDICES

0	PAGE	PAGE
I. Notes and Analyses. By Muhammad Sana		Silājīt and its Analysis 690
Ceramic Wares; Faience	686	Löllingite and its Analysis 690
Steatite Frience, Glaze	687	II. Note on Glazed Pottery. By H. J. Plenderleth,
Steatite; Mortar; Pigments	688	M.C., Ph.D., of the British Museum
Table I: Chemical analyses of Ceramic materials	689	Microscopic examination and hardness 692
Table II: Mortars	689	in the second can all a market second

TEXT ILLUSTRATIONS

												-			
Fig. 11.	Skull I. Norn	na Facialis •			•	: .				•	•	٠, ١	, .		. 668
Fig. 12.	Skull I. Norn	na Lateralis	•	,						•					. 609
Fig. 13.	Skull I. Norn	na Verticalis	.0												. 609
Fig. 14.	Skull II. Nor	rma Lateralis	•							• 1					. 611
Fig. 15.	Skull III (132	b). Norma Facial	is.			•	•			•					. 613
Fig. 16.	Skull III. No	orma Lateralis					•								. 614
Fig. 17.	Skull VI. No	orma Facialis													. 616
Fig. 18.	Skull VI. No	orma Lateralis						•							. 617
Fig. 19.	Skull VII. A	Norma Facialis	•	•		•									. 618
Fig. 20.	Skull VII. A	Norma Lateralis						•.		•					. 619
Fig. 21.	Skud VII.	Norma Verticalis											•	•	. 620
Fig. 22.	Skull VIII.	Norma Facialis													. 621
Fig. 23.	Skull VIII.	Norma Lateralis					•								. 622
Fig. 24.	Skull X. No.	rma Lateralis													. 624
Fig. 25.	Skull XI. N	orma Facialis													. 625
Fig. 26.	Skull XI. N	orma Lateralis													. 626
Fig. 27.	Skull XI. N	orma Verticalis							•						. 627
Fig. 28.	Škull XIV.	Norma Facialis	•									•	•.		. 628
Fig. 29.	Skult XIV.	Norma Lateralis													. 629
Fig. 30.	Skull XIV.	Norma Verticalis	•.								•				. 630
		Norma Facialis				0						•			. 631

692

Fig. 41. Microphotograph of glazed pottery, showing fracture of glaze .

ABBREVIATIONS

ASI. Archæological Survey of India. Memoirs of the Archaeological Survey of India. Arch. Mem. or Mem. ASI. ASR. Annual Report of the Archæological Survey of India. ASWI. Archæological Survey of Western India. Ant. Journ. Antiquaries Journal. BSA. British School at Athens. CAH. Cambridge Ancient History. CHI. Cambridge History of India. Ency. Britt. Encyclopædia Britannica. ERE. Encyclopædia of Religions and Ethics. Edited by J. Hastings. Grundriss der indo-arischen Philologie und Altertumskunde. Grund. d. indo-ar. Phil. IA. Indian Antiquary. ILN. Illustrated London News. Imp. Gaz. Imperial Gazetteer of India. TA. Journal Asiatique. 7AOS. -Journal of the American Oriental Society. JASB. Journal of the Asiatic Society of Bengal. JBORS. . Journal of the Bihar and Orissa Research Society. Jour. Eg. Arch. Journal of Egyptian Archæology. TRAI. . Journal of the Royal Anthropological Institute. TRAS. . Journal of the Royal Asiatic Society. Mém. Dél. Perse Mémoires de la Délégation en Perse. Min. Mag. Mineralogical Magazine. NH. or Nat. Hist. Naturalis Historia. Obv. Obverse. OECT .. . Oxford editions of Cuneiform Texts. Palæo. Sin. Palæontologia Sinica. Proc. A.S.B. Proceedings of the Asiatic Society of Bengal. RA. or Rev. Ass. Revue d'Assyriglogie. Recherches sur l'origine de l'écriture Cunéiforme, par Thureau-Dangin. REC. Records of the Indian Museum. Rec. Ind. Mus. Rev. Reverse.


xiii

Rigveda.

Zeitschrift für Ethnologie.

Rv. .

Zeit. für Ethn.



CHAPTER XX

AND STONE

Faience Vessels (Pl. CI, 1-10; Pl. CLVII, 32 and 33; Pl. CLIX, 5 and 4)

AIENCE ware is found in both the Intermediate and Late levels at Mohenjo-daro, Levels. and it will probably also be found in the Early levels when we get down to them. Not many complete vessels of faience have been found at Mohenjo-daro, for this Reasons for relatively soft material is easily broken or damaged by salt. Hence the scarcity of faience scarcity. vessels does not prove that they were not in common use. All those found are of small size and very well made. It is probable that they were used for cosmetics; indeed, a trace of Suggested use. a yellow substance is still to be seen in one of them (No. 8 in Pl. CI). None of them contained eye-paire, as anything of this nature invariably leaves traces behind. Judging from the comparatively large apertures of all these jars, the substances they once contained were fairly thick, and an unguent suggests itself as their probable content, though in few of them is the aperture large enough to allow of a finger being inserted. I would, therefore, suggest that some kind of powder was kept in these jars; that it was costly is implied by the very small size of the jars. Indeed, Nos. 1, 3, and 8 are so small that they might almost be children's toys, were it not unlikely that children would be given playthings made of such a material as faience.

It will be noted that few of these faience jars have a substantial base; they are mostly Bases. incapable of standing alone. On this account it is probable that they were kept in toilet

boxes or other receptacles.

Several of these vessels still show traces of colour; those illustrated in Pl. CI, 4, 8 and 10, Colour. are smoothly coated with a glaze of a light apple-green colour. The glaze of Nos. 3 and 9 is well preserved and still retains its original colour, turquoise-blue. jars have lost both colour and glaze.

There is a small hole in the side of the neck of No. 10 in Pl. CI to take a thread to Holes for fasten on a cover. No. 3 has two small holes, one on either side of the neck. The neck of covers.

No. 1 is grooved to take a cord for tying on the lid which is missing.1

Some difficulty seems to have been experienced in making these jars; their sides and Manufacture. especially their bases are remarkably thick. No. 8, for instance, would hardly contain anything at all, and Nos. 1 and 6 would hold but little. The makers were evidently uncertain of their material and feared to risk making the jars any thinner.

The paste of those jars which were broken and could consequently be properly examined Paste. was white or ash-grey in colour, and in most cases the glaze had penetrated well into it, both on the inside and outside of the jar. In the manufacture of the little jar, Pl. CI, I, a certain amount of frit was mixed with the paste itself as well as being applied to it both inside and This process, which results in strengthening the articles so treated, has also been

1 Possibly in this case the cover was made of cloth or leather.

noticed in other faience objects at Mohenjo-daro. This treatment, of course, requires considerably more heat than if the surfaces alone were glazed.

importations.

Descriptions.

It is quite evident that these jars were not imported from outside India, and quite possibly they were actually of local make. Many of the shapes are copies of pottery ware, and in the list below I have made the necessary comparisons :-

Plate CI, No. 1 (HR 994) is a beautifully made little vessel that was found 9 feet below the surface in the N.W. corner of House III, Block 2, Section A of the HR Area. It has a groove around its neck which obviously took the string which tied on the cover. In shape it resembles some of the storage jars; for instance, Nos. 1 and 2 in Pl. LXXXV.

No. 2 (SD 1705) seems to be a portion of a faience jar that was made in two pieces, the part preserved being the neck. On the other hand, it might equally have served the purpose of a jar-stand. It came from 8 feet below the surface of the ground in the lane between Blocks 4 and 5, Southern Buildings Section.

No. 3 (HR 5024) with its deeply scored middle is a passable imitation of the "B" type of pottery illustrated in Pl. LXXX. It was unearthed from 5 feet below the surface in

Room 118, House XI, Block 2, HR Area.

Imitation of pottery forms.

No. 4 (SD 258) was made in two pieces and skilfully joined together at the junction of the shoulder and body. In shape it resembles the pottery jar No. 21 in Pl. LXXXI, but it has a wider aperture.

No. 5 (C 364) resembles a shape that was very commonly made in pottery, and so we are justified in restoring its upper portion as has been done (cf. Pl. LXXX, 9-07). Chamber

11, Block 12, Section C, DK Area, Level, 4 feet below the surface.

No. v (HR 5548) came from 4 feet below the surface in Room 65, House XXXI, Block 5, of the HR Area. It is evidently an imitation on a small scale of the large water-jars illustrated in Pl. LXXXV, 7 and 6.

Except for the beading around its base, No. 7 (E 387) is clearly duplicated by the pottery

jar pictured in Pl. LXXX, 46.

No. 8 (DK 1933) is evidently copied from the pottery forms seen in Pl. LXXXI, 50-2. Found in the room north of No. 4, House XIV, Block 4, Section B, DK Area, 2 feet below surface.

No. 9 (SD 2390) was found at a level of 5 ft. below the surface in Chamber 15 of the Great Bath building; it is evidently a copy of some of the pottery illustrated as Type G in Pl. LXXX.

No. 10 (C 3063), like No. 4, was made in two pieces. In form it is quite unlike most of the pottery of Mohenjo-daro. The nearest approach to it is No. 7 in Pl. LXXXII.

From Room 1, Plock 6, Section C, DK Area. Level, 2 feet below surface.

Pl. CLIX.—Nos. 1 and 2 in Pl. CLIX are two fragments of great technical interest; they are the only examples of glazed pottery that have as yet been found at Mohenjo-daro. For this reason they are reserved to and fully described in Chapter XXVIII on ivory, shell,

faience, and other objects of technical interest.

No. 3 (HR 5843) in Pl. CLIX is also fully described in that chapter owing to its being exceptional in its make. It is but a fragment of a medium-sized jar, measuring 3 inches across. Its ground colour is a light-blue and the inlaid bands that decorate it are white. The composition of its paste is a powdery-looking material that has apparently been plentifully mixed with a coloured frit and then baked until vitrified. Found in House XXXII, Block 5, Section B, HR Area, at a depth of 2 ft. 6 in. below the surface.

No. 4 (A 129) on the same plate was part of a jar about 2 inches high. It is of ordinary frience, now a light-blue colcur and decorated with thin bands of purplishblack paint. These bands were painted with a frit that had been coloured with manganese,

Painted bands.

Glazed pottery.

Inlaid

decorations.

and not fused properly, owing perhaps to the risk of the colour spreading and staining the surface of the jar. This fragment was found at a depth of 3 feet below the surface of the ground, in Room 13, Block 1, Section A, DK Area.

Stone Vessels (Pl. CI, 11-32, 34, and 35; Pl. CXXXI, 36 and 37)

Stone vessels are comparatively rare at Mohenjo-daro; only twenty-six in all have been Stone vessels found, most of which are in a fragmentary condition. This does not include Nos. 33 not popular.

and 36 of Pl. CI, which are alabaster jar-stands.

All the vessels are of alabaster with the following exceptions: No 21, a dish of red Materials. stone that resembles sandstone; No. 24, brown limestone; No. 26, a greenish-grey slate; and No. 32, a dark-coloured limestone that is almost black. The two boxes illustrated in Pl. CXXXI, 36 and 37, are of steatite.

The soft white alabaster used to make these vessels is of very poor quality. It closely Alabaster. resembles Italian alabaster and is quite unlike the harder veined varieties that were used in early Sumer and Egypt.1 Most of the vessels made of it have been badly damaged by salt. The frequent use of alabaster despite its poor quality was doubtless due to its being easily worked. This was a consideration when, as at Mohenjo-daro, the technique of making stone vessels was not of a very high standard.

Most of the vessels are thick and clumsy-looking and it is evident that no particular care Clumsy make. was taken in their manufacture. It is rather difficult to account for this fact, for that the inhabitants of Mohenjo-daro clearly understood the art of working hard stones, is proved by the excellent beads that they made.2 One would have expected their stone vessels to have been as good.

It appears that stone bowls were sometimes used as strainers, for a small portion of a dish Strainers. was found perforated with holes, each 0.17 in. in diameter. This strainer must have been used for thicker liquids than water, for alabaster is to a certain extent soluble in the latter. Oil also penetrates this stone.

Plate CI, 11-36.—It will be noticed that the smaller vessels, Nos. 11-16, are very Details. clumsy and mostly only half-bored. Yet that they were finished specimens is proved by the polish of the outside. The little alabaster vessel (VS 2868), No. 11 in Pl. CI, was found in House XII of the VS Area at a depth of 2 feet below the surface of the ground; No. 12 (VS 2671), made in the same material, came from Chamber 76, House XIII, VS Area, and No. 14 (HR 2656), also of alabaster, from House IV, Block 2, Section A, of the HR Area. No. 15 (VS 2877) was unearthed in Chamber 76, House XIII, VS Area.

In No. 16 (HR 3729) part of the core was left adhering to the base inside, showing Tool used in that it was bored with a tubular drill. This was the method employed in making all these boring. stone vessels, and the softness of the material would allow of even a hard wooden drill, such as a piece of bamboo, being used, especially if wet sand were employed as an abrasive. This vessel, No. 16, was found in the room south of Chamber 43, House V, Block 2, HR Area, at a depth of 5 feet below the surface.

No. 18 (HR 146), which resembles the pottery vessel in Pl. LXXXIII, 20, is of Feeding cup ??). considerable interest.3 It may be a portion of a spoon whose hollow handle is missing or, more likely, the missing portion was a hollow spout, though why a spout should be at the base of a vessel it is difficult to understand, unless this object is a feeding cup.

1 Cf. p. 33 supra.

² Fragments of hard stone vessels have been found at Harappā.—[ED.]

³ Cf. a vessel in Arch. Surv. Nubia, 1910-11, pl. 25 (c).

No. 19 (HR 396), of alabaster, in shape is exactly like some of the pottery cups so common at Mohenjo-daro. Found in Court 13, House II, Block 2, Section A, of the HR Area, at a depth of 2 feet below the surface.

Red limestone dish.

No. 20 (VS 2304) is a badly weathered alabaster dish that was found at a depth of 13 feet below the surface in Room 28, House XXXI, VS Area. No. 21 is made of dark-red limestone, and, though thick and heavy, is better finished than the majority of the dishes. It came from Chamber 16, House XIII, of the VS Area, from a depth of 13 feet below the surface.

Two piece jars.

Nos. 22 and 30 (HR 1887), which were found in House II, Block 2, Section A, HR Area, at a level of 6 feet below the surface of the ground, formed the top of an alabaster jar that was made in more than one piece. The jar to which this neck and rim once belonged was probably globular in shape, and as it proved impossible to bore it satisfactorily through a very narrow neck, it had to be made in two portions. Vessels have been made from more than one piece of stone at all periods in the ancient East.

Brown limestone dish.

No. 23 (HR 5214) is a small alabaster vessel that was found in the space (92) east of House XXXIX, Block 5, of HR Area, where it was lying at a depth of 6 feet below the surface; and the small but heavy brown limestone dish, No. 24 (VS 2646), came from a level of 5 ft. 4 in. below the surface in House IX, VS Area.

Nos. 25 and 29 (HR 5780), which are both of alabaster, were found together in Room 54,

House V, Block 2, of the HR Area, at a depth of 8 feet below the surface.

Slate.

No. 26 (HR 5212) is a dish of a greenish-grey slate; it was unearthed in the open space (92), east of House XXXIX, Block 5, HR Area, where it was found at a depth of 6 feet below the surface.

No. 28 (HR 5985), of alabaster, comes from a depth of 8 feet below the surface of the ground in Room 87, House IX, Block 2, HR Area.

No. 31 (SD 2552) was in a very fragmentary condition, but enough remained to allow of its shape being drawn. It was found in the Great Bath Section, at a level of 18 inches below the surface.

Dark limestone.

No. 32 (VS 2941) is a dark-brown, almost black limestone and, though thick and heavy, is carefully made and has a semi-polished surface. It was found in two pieces, at a depth of 5 ft. 6 in. in Chamber 76, House XIII, VS Area.

Jar-stand.

No. 33 (VS 2939) is an alabaster jar-stand that was broken into two pieces. It was unearthed from a depth of 5 ft. 6 in. in the same chamber as No. 32. Another jar-stand, No. 36 (HR -944), which is also made of alabaster, came from a depth of 6 feet in Room 37, south of House VI, Block 2, in the HR Area.

Nos. 34 and 35 (DK 27.98) are shallow dishes of alabaster, which were found together in the DK Area. Both were badly broken, but enough remained of each to draw them. Room 3, Block 1, Section B, DK Area. Level, 3 feet below surface.

Little variety in shape.

There is but little difference in the shapes of the dishes found at the various levels. For instance, No. 20, found 13 feet below the surface of the ground is just as poor in workmanship and as simple in design as No. 28, which was 8 feet down, and No. 31, which was only 1 ft. 6 in. below the surface.

Adeption of pottery forms.

It will be seen that some of these stone vessels resemble certain pottery vessels in shape. For instance, Nos. 14 and 17 very closely resemble the goblets seen in Pl. LXXXI, 50-2; like them they have solid bases. The resemblance between No. 18 and the feeding-cup (?) seen in Pl. LXXXIII, 20, has already been noted. No. 23 is obviously a copy of a type of pottery vessel which is found in hundreds at Mohenjo-daro (Pl. LXXX, 10). The badly broken alabaseter vessel, No. 27, has a base exactly similar to that of the pottery jar illustrated

in Pl. LXXX, 29, and as there is every reason to think that its upper portion was similar in shape, it has been so restored. Yet none of the stone dishes closely resemble the pottery ones, and we have yet to find examples of the latter with rounded bases. These round-based stone dishes must have been kept on stands of some kind, otherwise they would have spun on hard brick floors.

No. 35, of which only two very weathered fragments remain, was broken anciently and Rivet repairs. repaired with rivets; there are rivet holes in both pieces. This method of repairing stone vessels was also practised in ancient Egypt in the earliest times and in Mesopotamia in pre-Sargonic days. In the latter country, copper, lead, and silver wire were used for riveting, but there are no indications on our pieces of what metal was employed.1 It is evident that these dishes, though made of inferior stone, were greatly prized at Mohenjo-daro; otherwise no attempt would have been made to repair them.

The interiors of the dishes appear to have been hollowed out by means of & hard stone Grinders. grinder, such as that illustrated in Pl. CXXX, 35. At first sight this grinder appears to be a kind of battle-axe, but one side is slightly concave and the other convex, and the two edgelike ends are rounded. A forked stick was probably used to grip this tool, which was rotated by means of another stick at right angles at its upper end. A very similar method was adopted in making the harder stone dishes of early times in Egypt, emery or very fine sand being used as an abrasive.2

Plate CXXXI, 36 and 37.—The first (VS 2881) of the two vessels illustrated in Stone boxes. Pl. CXXXI, 36 and 37, is a badly broken box, 2.5 inches high, with undecorated sides 0.25 in. thick. It had four compartments, of which the only intact one measures 1.5 by 1.6 inches. There is a slight rebate at the edge to take a cover, which was tied on by a cord carried through a small horizontal hole bored diagonally through the corner of the box. This box was found 7 feet below the surface in Chamber 76, House XIII, of the V3 Area.

No. 37 (VS 2505) is a better preserved box of four compartments, each of which measures Incised 1'4 by 1'5 inches at the base. The partitions between the compartments are 0'3 inches decoration. thick at the base and thin out to 0'1 at the top. When complete, this box must have measured 3.8 inches square by 2.45 inches high. The rim is rebated to take a cover, and a small horizontal hole runs diagonally through each corner at a depth of 0.4 in below the rim. The sides and remaining end of the box are divided into two registers by a thin border of two parallel lines with vertical lines between. Each register is decorated with an incised motif of triangles set one inside the other. Though there is no trace of a white filling in any of the incisions, there is reason to think that it originally existed, for the box which was probably used for cosmetics, appears to be an imitation of the black, incised ware of Sumer and other places, in which the designs were inset with gypsum or a similar white material. Indeed, this box might easily be taken for Sumerian work in shape as well as decoration.3 Level, 5 feet below surface. Room 76, House XIII, VS Area.

¹ It may also have been leather or some sort of fibre.

² Cf. a similar object illustrated in Petrie, Tools and Weapons, pl. lii, fig. 73.

³ It may quite well have been an importation; its decoration suggests Sumerian work.

CHAPTER XXI

SEALS AND SEAL IMPRESSIONS, COPPER TABLETS, AND TABULATION

THE seals and fragments of seals found in such remarkably large numbers at various levels at Mohenjo-daro are perhaps the most interesting of all the objects that have been unearthed there.

Number of seals.

Up to date, 558 specimens have been recovered, the majority of which bear one, and sometimes two, lines of pictographs in addition to the representation of an animal. In this chapter, I purpose only to deal with the technical aspect of these seals, leaving to others the interpretation of the signs engraved upon them. And first let me remark that the illustrations of the seals reproduced in Plates CII to CXV are photographs of impressions on wax of the actual seals. It should, therefore, be borne in mind that these illustrations are the reverse of the seals themselves. Thus an animal that faces to the left on the actual seal faces to the right on the seal impression. In other words, the seals are shown as they would appear stamped on a bale of merchandise or on the sealing of a jar. In speaking, therefore, of the direction in which an animal is facing, it is to the impression of the seal and not to the actual seal itself that reference is made. Most of the seals in the illustrations have been photographed to natural size.

First discovery.

Seals of this type were first published by Sir Alexander Cunningham, who secured several specimens of them from villagers in the neighbourhood of Harappā in the Montgomery District of the Panjāb.²

Types of Seals

Types of seals.

The seals of Mohenjo-daro can be conveniently classified in ten different groups :-

- (a) Cylinder seals (?).
- (b) Square seals with perforated boss on reverse.
- (c) Square seals with no boss and frequently inscribed on both sides.
- (d) Restangular seals without boss.
- (e) Button seals with linear designs.

1 May, 1927.

² Cunningham's Archaol. Reports, vol. v (1875), p. 108; pl. xxxiii, fig. 1. A short note on these particular seals by the late J. F. Fleet appears in the JRAS for 1912.

According to Professor Sayce, a seal from Harappā, now in the possession of the British Museum, was published many years ago by Terrien de Lacouperie in the *Proceedings of the Society of Biblical Archæology*. See *Antiquity*, June, 1927, p. 206, note.

- (f) Rectangular seals with perforated convex back.
- (g) Cube seals.
- (h) Round seals with perforated boss.
- (i) Rectangular seals with perforated boss.
- (i) Round seals with no boss and inscribed on both sides.

(a) Cylinder Seals (?) (Pl. CXIV, 529-33)

Seals of this group, if indeed they are seals, are very rarely found at Mohenjo-daro, Cylinder seals. only five specimens being obtained in all. They are all made of ivory and differ from the cylinder seals of other countries in being very long and thin; nor are they perforated for suspension on a cord. It is possible that these so-called seals are not true seals at all. The incised characters upon them might conceivably be identification marks for a game or something similar. On the other hand, they are certainly suitable for use as seals and on this account they are included in this chapter. For the sake of clearness the actual seal is shown side by side with each impression.

No. 529 (Pl. CXIV, HR 5515). Ivory. 2.7 inches long by 0.25 in. in diameter. Details. Double groove at one end for attachment of cord. The other end is decorated with three parallel grooves. Level, 4 feet below surface. Central Courtyard (30), House LIII, Block 7, HR Area.

No. 530 (Pl. CXIV, HR 4985). Ivory. 2.05 inches long by 0.25 in. in diameter. Double-groove at one end for a cord; the other end is broken. Level, 3 feet below surface.

No. 531 (Pl. CXIV, DK 2666). Ivory. Now 2.05 inches long by 0.3 in. in diameter. Its polish shows that it has been much used. About one-half of the seal is covered with an inscription, deeply and roughly incised and bordered by two deeply cut lines. One end of the seal is shaped into a conical head with a deep groove possibly intended for a cord. The seal is not bored; nor is it perfectly round. Level, 4 feet below surface. Street between Blocks 1 and 2, Section B, DK Area.

No. 532 (Pl. CXIV, VS 875). Ivory. Now 2 inches long by 0'3 in. in diameter. One end is broken and a small piece is missing. The seal tapers slightly towards its complete end. Five deeply incised characters occupy a space of about two-thirds of the circumference of the seal. Level, 12 feet below surface. Found in front of Room 70, House XXVII, VS Area.

No. 533 (VS 958). Ivory. 2.75 in. long by 0.3 in. in diameter. Decorated at 0.5 in. from each end with a deeply incised cross-hatched border. Towards one end of the intervening space are two deeply incised characters. This seal is not perfectly round. Level, 10 feet below surface of ground. From Room 69, House XXVII, VS Area.

It will be noticed that there is a considerable variation in the levels below ground at Reed-like shape. which the above specimens were found, and that, therefore, they cannot be relegated to one and the same period. In shape they closely approximate to what is supposed to have been the origin of the cylinder seals of other countries, namely, a short piece of reed or cane. But it is not suggested that cylinder seals originated in Sind.

The ends of three of the seals are knob-like, which certainly supports the idea that they were once tied to a cord.

(b) Square Seals with Perforated Boss on Reverse (Pl. CII, a, b, and c)

Seals of this type appear to be always made of steatite, and they have been found in such numbers that it is impossible to deal with them individually, beyond mentioning those that are in some way peculiar. Typical seals of this group bear a representation of an animal with one or more lines of pictographs along the top. They are nearly always perfectly square and vary considerably in size. The following list of the sizes of 328 perfect specimens is given for the use of those interested in metrology:—

Inches.	Examples.	Inches.	Examples.
0.5 × 0.5	5	0.55 × 0.55	6
0.6 × 0.6	9	0.65 × 0.65	8
0.7 × 0.7	20	0.75 × 0.75	- 14
0.8 × 0.8	16	0.85 × 0.85	23
0.9 × 0.9	18	0.95 × 0.95	16
1.0 × 1.0	22	1.02 × 1.02	20
I.I × I.I	28	1.12 × 1.12	17
I.5 × I.5	23	1.25 × 1.25	9
1.3 × 1.3	15	1.32 × 1.32	10
1.4 × 1.4	14	1.45 × 1.45	4
1.2 × 1.2	5	1.22 × 1.22	3
1.6 × 1.6	4	1.65 × 1.65	I
1.7 × 1.7	I	1.75 × 1.75	. I
1.8 × 1.8	3	1.85 × 1.85	5
1.9 × 1.9	I	1.95 × 1.95	Nil.
2.0 × 2.0	2	2.05 × 2.05	Nil.
5.1 × 5.1	I	2.12 × 5.12	Nil.
3.5 × 5.5	Nil.	2·25 × 2·25	I
5.3×5.3	Nil.	2.35 × 2.35	1
2.4 × 2.4	Nil.	2.42 × 5.42	
5.2 × 5.2	İ	2.55 × 2.55	Nil.
2.6×2.6	Nil.	2·7 × 2·7	I

Most favoured sizes.

From the above figures it is clear that the favourite size for seals of this type was 1.1 by 1.1 inches, followed fairly closely by seals measuring 0.85 by 0.85 in. and 1.2 by 1.2 inches. Seals of very large size were not popular, none being found above 2.7 by 2.7 inches. Parenthetically, it may be observed that after these seals had been cut to a definite size, subsequent trimming and polish would reduce their sizes considerably.

The thickness of the seals was not measured, as it was found to vary greatly in seals from the same area. The average thickness of a seal measuring 0.5 by 0.5 in. was 0.3 in.; and of a seal 2.6 by 2.6 inches square, it was 0.75 in. These thicknesses do not include the boss at the back.

(c) Square Seals with no Boss and frequently Inscribed on both Sides (Pl. CII, n, o, and p)

Altogether twe've seals of this type were found, all except five (C 2631; E 904; HR 2739; HR 2240; HR 4264) being pierced with a small hole to take a cord. Nine are of fine white steatite, one of black steatite and two of pottery, a very unusual material. Of the last two, one (HR 4264) is not cut, but moulded from the impression of another seal.

¹ Seals of equal weight but of a different shape were carried on the wrist in Mesopotamia.

Seals of this type vary in size from 1.1 inches equare and 0.5 in. thick down to 0.55 in.

square and o 3 in thick. The majority are well made with clean sharp edges.

Four of these seals are inscribed on both their faces (E 904; HR 2739; HR 2596; Instribed on I'wo are inscribed on two of their sides as well as on their two faces both faces. (L 323; HR 2240). On one of these (L 323), there is a unicorn on both faces, but not the same inscription. A very curious figure is cut on two of the sides, which may possibly represent the Sumerian hero Enkidu. On another seal (HR 2596), one side bears the representation of a fabulous animal and the other a unicorn. The inscription, consisting of two characters, is the same on both sides of this seal. There is a short-horned bull on one side of HR 4503 and a svastika on the reverse. HR 2240 has an inscription on each face, and also pictographs on two of the sides.

HR 2739 is very thin for its size, measuring 1 inch square and only 0.15 in. thick. On one side there is a svastika and on the other an involved design of triangles. It is in a much-weathered condition, and for that reason no impression could be taken of it.

It is somewhat surprising that seals of this type were not more popular. They are Type not convenient in size and shape, and lack the ugly boss at the back. For the latter reason, they popular. were made of a convenient thickness to hold with the fingers. Two of them, however, differ from the rest in being exceptionally thin, viz. about 0.12 in. in thickness. Some little difficulty must certainly have been experienced in holding these two seals to make their impressions.

The verage diameter of the hole in those that were pierced is 0.1 in. In every case, even in the smallest specimens, the hole was bored from both sides of the seal. The edges of the holes show little or no evidence of wear (Nos. 120, 311, 356, 378, 471, 472, 475-7).

(d) Rectangular Seals with no Boss

Of this type of seal only six examples have been found. Five are made of steatite Rare type. (A 148; E 2039; HR 3732; HR 5248; and VS 208), two yellow, one grey, one black, and one white. The sixth (HR 1695) is made of faience. They are all simple blocks of rectangular shape, and with one exception perforated by a small hole that was bored from both sides of the seal. All six bear plain inscriptions, without any animal devices. Only two are inscribed on both sides (A 148 and E 2039), and on none of the seals are the sides or ends inscribed (Plate CXIII, Nos. 412, 413, 435, 440, 441, 442, 459).

(e) Button Seals with Linear Designs

Altogether, twenty-two examples were found of this variety of seal, twenty of which are Pintaderas (?) illustrated in Pl. CXIV. All are square, thin, and provided with a shallow perforated boss at the back. Five of these seals are of steatite (B 650; C 2927; HR 2728; HR 6207; Mus 8). The remainder are of faience, which in every case is colourless. The paste itself varies in colour from white to light-yellow. The button seals that were made of faience were all moulded and vary so little that it is hard to believe that they were used actually as seals, which necessarily require a measure of individuality. They may have served to stamp impressions for some religious purpose, like the caste-marks of to-day.1 .

The seals of this group range in size from 0.5 to 0.95 in. square. The boss at the back is in most cases a mere loop. It is best finished in the seals made of stone, where the boss is divided into two by a shallow groove, as in the seals of Type b.

¹ In a similar manner to the pintaderas used in Danubian II, Thracian copper age, and early Greece, etc.

Svastika.

The design most frequently found on seals of this description is the svastika (Nos. 500–515). This symbol was known in most parts of the ancient world, and it is quite impossible to determine the country of its origin. It is found in Crete 1 and Cappadocia, 2 and was common at Troy, where it appears among the motifs with which spinning whorls were decorated. It occurs on pottery from Susa and Musyān 3 in its simple form as well as in its derivatives. 4 For some reason, not yet explained, it is not known in Babylonia, 5 neither does it occur in Egypt. In India at the present day, both name and symbol are emblems of good luck.

Arms of svastika.

It will be noticed that the arms of the svastika turn sometimes one way, sometimes the other. In historic India the direction of the arms has generally been towards the right, for the symbol was considered unlucky if the arms were turned towards the left. That no such feeling existed at Mohenjo-daro seems evident from the impartiality with which the arms were turned in either direction, though a clockwise direction is, if anything, less common than the reverse.

Design of squares.

The seal illustrated as No. 516, which bears a design consisting of a number of squares set inside the other, is the only one of its kind found at Mohenjo-daro. It is known however, at Susa and dated there to the proto-Elamite period. The designs on seals Nos. 536 and 537 are also unusual, though of a very simple nature.

The motif in Nos. 520 and 521 is again very rarely found. It appears to be a simple adaptation of the stepped triangle motif that is so common on the pottery from Nal, a design which is also known in some of the shell-inlay found at Mohenjo-daro (Pl. CLV, 33) and on a cylinder seal from Susa.8

The design shown in No. 522 appears to be made up of two parallel lines enclosed in a square and linked up in the middle by rough scratches.

Unfortunately, the largest seal of this type (HR 6006) was too defaced to be

photographed.

There is a very similar motif to that of seal No. 528b on a jar belonging to the First Period of Susa, but this motif is rare at both Susa and Musyān.

(f) Reclangular Seals with Perforated Convex Back (Pl. CII, d, e, and f)

Of this type of seal there are sixty-four examples, ranging in size from 0.6 in. to 2.2 inches long. Most of the specimens are of white steatite, but there are eleven seals of black steatite, three grey (C 1878; D 114; HR 1050), and one yellow steatite (HR 6210).

- A very complex form of the svasika appears on an ivory seal from Hagia Triada, dated to the E.M. III Period. See Evans, Palace of Minos, vol. i, p. 221, fig. 90a. In the same period it appears on seals in a simple form with curved arms. Later on in the M.M. I Period it is found on pottery, first with the arms curved, then with straight arms. Ibid., vol. i, pp. 185, 515, 640; vol. ii, pt. i, p. 197.
- ² Catalogue des cylindres orient., Musée du Louvre, vol. ii, pl. 98, fig. 12 b; Frankfort, Studies in Early Pottery of the Near East, ii, pl. ix, fig. 2; p. 164, fig. a.
 - 3 Mém. Dél. en Perse, t. viii, p. 110, fig. 176; t. xiii, pl. xli, fig. 3. Delaporte, Cat. cyl. orient., t. i, pl. 17, fig. 1.

4 Mém. Dél. en Perse, t. xiii, p. 71, fig. 193.

5 See, however, Herzseld, Die Ausglabungen von Samarra, 5, pp. 13, 16, 17, etc.

- For convenient illustrations see de Morgan, La Préhistoire orientale, t. ii, p. 266, fig. 293. The potter of Elam seems to have drawn the arms of the swassing clockwise or counter-clockwise indifferently.
- ⁷ Mém. Dél. en Perse, t. xvi, pl. i, fig. 8. The same motif, but on painted pottery, has been found by Sir Aurel Stein in northern Balūchistān. Mem. Archl. Surv. of India, No. 37, pl. xv.
 - 8 Catalogue des cylindres orient., Musée du Louvre, *. i, pl. xvi, fig. 10.
 - 9 Mém. Del. en Perse, t. xiii, pl. xxi, fig. 4.

Three pottery seals of this type (C 656; HR 116; and HR 6187) are of particular Pottery seals. interest, inasmuch as pottery seals of any type are comparatively rare at Mohenio-daro. Two are somewhat roughly made with rounded backs instead of the flat back and bevelled ends that are usual in this type. The third example (HR 6187) is better made; it is smoothly coated. with a polished red slip. The inscriptions on these three seals were cut before the seals were baked. On the best finished specimen the cutting is exceptionally well done, the characters being very even and clear (seal 402). And this seal has a hole through its width for a cord, whereas the other two are not perforated. All the steatite seals have a hole, which was bored from both sides for threading on a cord.

The seals of this type bear inscriptions only, some of which are exceptionally well cut. No pictographs ever appear on the sides or backs of these seals.

Cube Seals

Only five examples of this type of seal have been found at Mohenjo-daro, averaging Yellow paste. in size 0.7 in. each way. They are all roughly made of a sandy-yellow paste, which appears to have once been glazed. Evidently but little care was taken in their manufacture. On four of these seals sets of parallel lines crossing one another have been roughly scratched on two opposite sides. On the fifth seal the same motif occurs, but on one side only, the opposite side being slightly rounded as if to be held between the fingers. The remaining sides of three of the seals bear representations of the unicorn in relief, apparently impressed by a small seal of the usual type. The pictographs above the animals on all these seals are too weathered to be legible.

• The fact that some of the sides bear seal impressions, whereas the other sides might serve Hatching. as actual seals, makes it difficult to say what these specimens really are. A series of parallel lines crossing one another at various angles was a favourite design in the ancient world for the less elaborate types of seals. Examples have been found at Kish and at Jemdet Nasr, in Mesopotamia, and the motif is well known at Susa,1 where it has been found on seal impressions in clay. It is known, too, on a rough steatite seal from Cappodocia,2 and the design occurs on some early seals from Crete and Egypt.3

One might be tempted to think that a uniform design of this sort would be useless for the purpose of a seal; as a fact, however, it is extremely effective, since the irregularity of the lines makes it almost impossible to forge. It had this added advantage, moreover, that the very poor could make such seals for themselves and thus avoid resorting to an expensive seal-cutter. (See Pl. CXIV, 523, 524, 525, 526, 528.)

(h) Round Seals with Perforated Boss (Pl. CII, k, l, and m)

• Only three of these seals have been found (E 1886; HR 4393; and VS 3027). They Resemblance to are all well made with flat base and top; and the boss in the centre of the former is partially seal from subdivided by a groove across the middle and is perforated with a hole averaging o'r in. in Telloh. diameter. Unfortunately, two of these seals are broken and all show signs of a considerable amount of wear; their edges are rubbed and slightly rounded. The edges of all three were originally slightly bevelled, a feature that is especially noticeable in HR 4393. The

¹ Mém. Dél. en Perse, t. xvi, ple i, fig. 1.

² Catalogue des cylindres orient., Musée du Louvre, vol. i, pl. exxxviii, fig. 6; vol. ii, pl. xcviii, fig. 6b. Also Legrain, Culture of the Babylonians, pl. i, fig. 4.

³ Hall, The Civilization of Greece in the Bronze Age, pp. 78, 71, figs. 73 and 75.

designs on these seals are illustrated in Nos. 309, 383, and 478. A seal of exactly the same type as those just described was found by de Sarzec at Telloh in Mesopotamia. It very closely resembles No. 309, and is described as being made of a soft, greenish-grey stone, probably steatite.

(i) Reclangular Seals with Perforated Boss

Rare type.

Only one seal (VS 2846) of this type was found. It is of steatite and measures 0.9 by 0.7 in. The inscription upon it, of three characters only, is illustrated in No. 460. Though well made and finished, this steatite seal looks as if it had been cut down from a larger one since it is unduly thin for its size. The boss, however, is exceptionally well finished, which is not usually the case with seals that have been cut down.

(j) Round Seals with no Boss and Inscribed on both Sides

Tree.

Seal E 1908, which is badly broken, is made of calcite and measures 0.75 in. in diameter and 0.15 in. thick. Both sides are deeply incised. On one side are characters arranged in three registers; on the other side is the representation of a large tree, a very unusual motif for a seal. This seal has no boss to hold it by, nor has it a hole. If it was actually used as a seal, it must have been difficult to hold because of its thinness. Both sides of this seal are illustrated (No. 527).

Seals of Unusual Character

Such of the seals from Mohenjo-daro as exhibit exceptional features are described seriatin below.

Top edge lowered.

Seal 9 (C 1895). Type B. The inscription at the top of this seal has been entirely removed by sawing off a piece o'3 in. deep by o'5 in. wide. As the seal is badly broken, though it shows signs of but little wear, the possibility must not be lost sight of that it had been discarded and was being cut up for its material. It is possible also that a new piece of stone was inserted to take another inscription.

Inscribed boss.

Seal 18 (HR 5804). Type B. A part of the boss of this seal has been split away; and on the remaining portion that was roughly smoothed down, a single character, like the third sign on No. 463, was cut.

Seal 304 (L 385), which has no inscription, has had its corner sawn away. Perhaps this seal was discarded and a piece taken from it to serve some other purpose.

Bevelled edges.

Seals 335 (HR 2657) and 337 (B 588). Type B. In No. 335 the two edges in front and behind the animal were bevelled. In No. 337 the edge in front of the animal only is bevelled. This bevelling was possibly due to the stone being faulty and splitting when the seal was engraved, or a mistake made in the cutting of the device was rectified by lowering the ground. Whatever the reason may have been, both seals give perfectly good impressions.

Two registers.

Seal 376 (HR 4212e), type B, has two registers. A fabulous animal with an elephant's trunk occupies the upper, and an elephant the lower division.

¹ Catalogue des cylindres orient., Musée du Louvre, vol. i, pl. ii, figs. 8a and 8b. The same seal is published in L. Heuzey, Découvertes en Chaldée, pl. xxx, fig. 3a.

² This is quite apparent, though the greater part of the front edge is missing.

Seal 389 (D 171). Type B. The peculiarity of this seal lies in there being no representation of an animal upon it. The same remark also applies to seal 395 (VS 1190).

Seal 396 (HR 5676) and Seal 400 (HR 3005). Type B. These two seals are unusual Triple row of in that their faces are entirely filled up with three rows of pictographs; the animal figure pictographs. that is a regular feature on seals of this type is omitted.

Seal 394 (C 3158). Type B. The face of this seal is divided into two equal portions by a thin incised line, on one side of which are two characters, while the other half of the seal

has been left blank.

VS 3480, which is not illustrated, is an unfinished seal of type B without any engraving; it measures 0.8 in. square. Such unfinished seals are very rare.

A few of the seals, besides having devices and inscriptions on one or both faces, also

have, as already stated, either figures or signs engraved on one or more of their sides.

Seal L 323, whose two faces are seen in Nos. 227 and 230, has the figure of a man with Mythological bull's horns, legs, and tail, on two sides. These figures are identical and are illustrated figure. in No. 356. As suggested above, they may represent the Sumerian hero, Enkidu.

• Two fragmentary seals (271 and 293) have a single pictograph on the upper edge. The fine seal figured in No. 325 also has an inscription along its upper edge, as shown in the illustration.

Nos. 471, 472, and 473 are illustrations of different faces of the same seal. The first two are impressions of the obverse and reverse; the last shows two of the sides. The upper and lower edges of the seal are blank.

The seal whose obverse and reverse are illustrated in Nos. 252 and 378, is especially interesting in that the same inscription occurs on both faces above animal devices which are

entirely different.

It will be remembered that the comb motif appears on the painted pottery of both Comb motif. Mohenjo-daro and Elam, and on Hittite ware. It also seems to figure amongst the characters on the seals, e.g. Nos. 142, 161, 329, and 413.

Method of Manufacture

The stone seals were first cut into shape by means of a saw, the marks of which are Use of saw. clearly seen on unfinished seals or those that have been altered. The average thickness of the saws used in this process was 0.025 in. After the seal had been cut to the size required, if it was to have a boss, this was roughly cut into shape with the saw; a horizontal cut was made from each side of the seal towards the centre and four vertical cuts were then made downwards to meet the horizontal ones. A rough square projection, the size of the boss, was thus left at the back of the seal. The boss was then carefully rounded off after the groove that always runs across its centre had been roughly made by a V-shaped cut. The rounding of the boss was apparently done with a knife and finished off with an abrasive, after which a hole was bored through it from opposite sides to take a cord. The hole for the cord was sometimes bored horizontally, but more generally it dips slightly from the two ends towards the centre. As Steatite has a tendency to split along the cleavage planes, the probable idea of these converging holes, which are too common to be accidental, was probably to carry the hole into the substance of the seal itself rather than to rely solely on the boss, which owing to its prominence and the nature of the stone was always liable to be knocked off. Indeed, this actually happened to many of the seals and was remedied by cutting fresh bosses with a consequent thinning of the seal.

378

Repairs.

Such an accident happened to seal L 384 (No. 382), which was apparently repaired by the owner himself; he cut another boss very roughly with a saw, but did not take the trouble to round it off or even to remove the saw-marks.

From the evidence afforded us by seal L 351 (No. 307), it would seem that in some cases, at all events, the device and characters on the seal were cut either before the preliminary shaping of the boss or before it was rounded off and finished. This seems a sensible procedure, for if a seal were damaged in the engraving or a mistake made, not much work would be wasted. The seal in question also seems to have been the work of an inexperienced engraver, for the cutting is very shallow and roughly done.

As a general rule, the bosses on the seals occupy about a third of the area of the back of the seal, and but-for the grooves down the centre of each, which give them an appearance of being double, they are hemispherical in shape. In rare cases, however, the boss is very much smaller in proportion to the size of the seal, and in seal L 386 (No. 341) it is elongated and slightly concave, with a slight raised beading at each end.

Use of burin.

Bosses.

The designs appear to have been cut with a burin, and in the majority of seals the work is cleanly done, even curved lines, such as those needed for the horns of animals, being cut without the slightest trace of hesitation. Though carefully looked for, there is no evidence that a drill was first used for outlining the figures—a common feature of the archaic seals of Elam and Sumer. But both pointed and hollow drills were used to put in details, e.g., the roughnesses of the hide of the rhinoceros, the ornamentation of the cult-object in front of the so-called unicorn, and the spots on the fabulous animal in No. 385. In no case did the seal-cutter use the drill to portray the eyes of any of the animals, with the sole exception of the fabulous creature above mentioned.

Method of carving.

No. 256 is a good example of a seal that has been left unfinished. In this case we know that the seal itself was finished before the engraving was started, for the boss is complete and perforated, and even polished. In engraving the seal, the artist started his work in a somewhat curious way. Instead of first outlining the whole figure of the animal and then cutting deeper, he started on the body and apparently completed it before outlining the other parts. Even the trappings over the withers of the animal are finished, a detail that one would have expected to be left to the last. It is clear that the engraver was so familiar with his work that he could start on and complete any part of an animal without having the whole outline before him.

It is, of course, possible that the outlines of the animal were first drawn with paint or ink; the seal, however, shows no evidence of this, though on a damp site like Mohenjo-daro it is unlikely that any paint or ink would remain.

inscriptions added later.

The crookedness of some of the characters in the inscriptions suggests that they were added later. This seems the more probable, as owing to the great variety of these inscriptions, they can hardly refer to the animal below. When, if ever, these inscriptions are deciphered, we shall probably find them to be personal names, perhaps coupled with titles or occupations. The seal-cutters probably kept a stock of seals by them and added the inscriptions as required.

Cramping of characters.

The inscriptions as a rule are neatly arranged in a single line along the top of the seal. If there was not sufficient room, a second line was added, and sometimes the characters of this second line, owing to lack of space, are smaller than those in the line above (Nos. 101, 139, 237, 253, etc.). Occasionally—also on account of lack of room—the arrangement of the characters is quite haphazard, instead of in two definite lines, though this is very rare

¹ This seal, which is thin, may have had the face removed for the purpose of re-cutting.

(Nos. 32, 247). The seals shown in Nos. 93, 302, 387, 550 are the only ones on which the characters are placed otherwise than along the top, except for No. 387, whose motif is so entirely unusual that one hardly wonders at the inscription occupying a different position.

Almost all the seals, of whatever type, are coated or have been coated, with a smooth, Coating. glassy-looking substance which was at first thought to be the remains of a glaze, whose colour has entirely disappeared. Under a strong glass, this coating shows definite cracking on some of the seals. All the seals have been carefully examined for traces of colour, but without success. The coating has, moreover, been analysed by the Archaeological Chemist in India, who reports negative results as regards traces of copper. On the other hand, the glaze of a seal of exactly the same description as those of Mohenjo-daro and Harappa, which I found at Kish in Mesopotamia, still showed traces of its original blue or green colouring. There is thus no evidence that the seals of Mohenjo-daro were originally coloured.1 If they were so coloured, all traces of the pigment have entirely disappeared through long deposit in the damp and salty soil of the site. That a copper compound can be entirely removed in the course of time through the action of salt is well known, though the glaze may remain quite intact.

Mr. Sana Ullah has since made an exhaustive analysis of the surface coating on one Analysis of of these seals (DK 4479), and his results are given below:-

			F	er cent	0
Silica				61.2	
Oxides of aluminium	and i	iron		2.4	
Lime				Nil.	
Magnesia				34.6	
Water (by difference)				1.8	
		-			
		Total		100.00	

In another seal (DK 3557), the amount of water was found to be 2.17 per cent. analyst remarks that "this surface substance is steatite or tale that has been deprived of the greater part of its water, which is only possible by ignition ".

It seems certain, therefore, that the coating upon these seals is made of the same material Coating same as the seals themselves. There is reason to think, however, that the coating was an applied material as seal. one, for it scales off in the same manner as a slip would do. Possibly, before a seal was considered ready for engraving, it was coated in order to conceal blemishes and then was baked in a kiln. The result of the firing was undoubtedly to whiten and improve the outside; for many of the broken seals show that the colour of the stone of which they were made was originally grey. Besides whitening the surface of a seal, the baking would materially assist in hardening it owing to the loss of water that would result. The process appears to have been carried out before the seals were engraved, for the deeper incisions frequently betray the inferior colour in the core of the seals.

. Purpose of the Seals

It is not quite certain whether these objects should rightly be classed as seals only of as Sealings. amulets, for the reason that up to the present there has not been found at Mohenjo-daro a single true sealing; that is, an impression on a piece of clay or other substance that had been attached

CC-0. Gurukul Kangri University Haridwar Collection. Digitized by \$3 Foundation USA

¹ That the art of glazing was practised at Mohenjo-daro is amply proved by the number of faience objects that have been unearthed.

to a jar or other article of merchandise, of the kind so well known at other ancient sites, where they were fastened to the object to be sealed by means of a cord, or else they bear traces on their backs of some fabric to which they were once attached. The only sealimpressions which have been found at Mohenjo-daro are on baked clay or faience, and as there is reason to infer that they served as amulets, they are described as such later in this

Use of materials

Though clay may not have been used for seal impressions, it is likely enough that some other than clay. other plastic material, such as bitumen, may have taken its place. Bitumen, when old, breaks up into granular fragments except under favourable circumstances, and sealings in this materlal would be very difficult to detect in such a site as Mohenjo-daro. Another substance that might equally well have been used is resin, and this material is sometimes liable to granulation in a damp climate. We have, actually, found no traces of either of these two materials, except for the bitumen that was employed, in one building only, for waterproofing the walls of a tank.

Personally, I am of the opinion that these seals were used almost exclusively for stamping sealings of clay, which, unless it were baked or of a special quality, would be unlikely to survive in a site that is, or has been, damp. It is quite possible that clay sealings

have not been found at Mohenjo-daro for this reason.

Seal impressions from Yokha.

That these objects from Mohenjo-daro were actually used to stamp sealings rseems to be proved from an impression found at Yokha in Babylonia, which has been published by Dr. Scheil.2 This clay sealing bears the figure of a bull with a line of pictographs above it, and both the form of the bull and the characters of the script are identical with those on the seals we are discussing. The back of this sealing bears the impression of some woven material, showing, Professor Sayce suggests,3 that it was once attached to something in the nature of a bale, which would probably have come from India.

Use of seals for colours.

Another suggestion has been put forward, namely, that these seals were used, not for stamping plastic materials, but for making coloured impresses on other substances. This theory is, I think, untenable; for if they had been used for this purpose, they need not have been cut so deep. And details on the lower parts of the engraving of the seals would not have shown at all in an impression made with colour.

Use as amulets.

It has also been suggested that these objects were used as amulets. The fact, however, that most of them have a projecting boss at the back seems to me to disprove this theory, to which I was myself at first inclined. An amulet to be effective must be worn on the person, suspended either by a cord or enclosed in a case. It is certain, I think, that the primary object of the boss was to provide a finger-hold. As a means solely of suspension, it would not be so convenient as a hole through the amulet itself. Moreover, the boss would prevent the seal from lying close to the skin.

Seals to contain amulets.

The amulet theory finds some support, however, in the shape of seal HR 4629 (Pl.-CII, q). This seal measures 0.77 in. square and 0.3 in. thick, excluding its boss. The interior has been carefully hollowed out to form a compartment measuring 0.65 in. square by 0.1 in. deep. This little chamber was formerly closed by a sliding cover that fitted into grooves cut in the two sides of the seal. Practically all the face of the seal is missing, but enough remains to show that the animal represented on it was the unicorn and that there was the usual line of inscription above it. An impression of this broken face is shown as No. 293 in the seal plates. Two of the sides of this seal bear a single character each. Except

¹ It is worthy of remark, however, that quantities of clay sealings have been found on sites of the historic period in India, where the rainfall is much heavier than in Sind .- [ED.]

² Revue d'Assyriologie, xxii, 2 (1925).

³ Antiquity, June, 1927, p. 205, note.

for the compartment inside it and the characters on its edges, this seal resembles the others of its type in every way.

Owing to its necessarily small size, the compartment would be of little use except to hold a sacred object. This may have been an inscribed copper tablet, similar to the many found at Mohenjo-daro, or an inscription written on some material such as back or leather, which could conveniently be folded up small. This type of seal would, like the Egyptian scarab, serve the dual purpose of amulet and seal.1

Were it not for the inscriptions upon them, these seals would be useless as such, for it Animal device would be difficult to tell them apart owing to the sameness of the animal motif on the majority itself useless as of them. The animal itself should be regarded, I think, as possessed of special powers; a seal. and it was perhaps primarily for this reason that it was engraved on the seals.

The inscription, which from its variation seems to bear no reference to the animal figured below it, may be assumed to be the name of the owner of the seal. Of the five fragments of pottery that have been found bearing seal-impressions, three appear to have been marked with a rectangular seal, and two with a square seal.2 In one case, however, the animal appears faintly below, as if by mistake (Pl. LXXVIII, 3).

It would, therefore, appear that these so-called seals were in fact actually used for sealing Dual use. purposes. Of this use the Yokha sealing seems conclusive evidence. Sometimes the whole seal and sometimes only its inscribed portion was employed. The certainty that these seals were used to stamp pottery vessels, the impressions being made before the jars were baked, is significant.

On some of the seals there is barely room to accommodate the inscription, e.g., on Inscriptions. Nos. 237, 253, 373, etc., whereas on others only two or three signs were required, as in Nos. 244, 252, 254, 378, etc. It is possible that the shorter inscriptions are simply the owner's name and that the longer ones include titles that the owner of the seal happened to poseess. It is noticeable, moreover, that many of the inscriptions begin with the same sign, which may possibly be an invocation; it would more likely occur at the beginning of an inscription than at the end. On the other hand, many of the inscriptions, if they are to be read from left to right, terminate in the same sign, as, for instance, Nos. 105, 109, 110, 134, 148, etc.

None of the seals of other ancient civilizations resemble those that have been found at No resemblance Harappā and Mohenjo-daro, either in their devices or the pictographs they bear, or even in to foreign seals. shape. It is difficult to understand why the superiority of the cylinder seal over the stamp seal was not appreciated by the people of the Indus Valley civilization.3 That they must have known it is indicated by the fact that seals from Mohenjo-daro or similar sites have been found both in Elam and Sumer, which argues that these two countries were visited by Indians, probably in the way of trade. We have, however, no definite evidence that India was equally well known to these two countries, although the painted pottery and other objects demonstrate a connection between them all.

The large number of the seals found at Mohenjo-daro and at Harappa seems to call for explanation.

- 1 Since the above was written, other hollow seals of this type have been found at Mohenjo-daro and elsewhere.
- ² See Pl. LXXVIII, 1 and 3, and Pl. CXV, 558, 559, and 560.
- 3 Since writing, a cylinder seal has been found at Mohenjo-daro. The devices upon it are quite unlike anything that we know outside India. It is not known whether the stamp form of seal antedates the cylinder seal or not. The probability is that it does. In Egypt, however, the cylinder seal gave place to the stamp-seal. At Jemdet Nasr, the oldest site that has hitherto been found in Mesopotamia, the stamp and the cylindrical form of seal are found together. In Elam, stamp-seals are only found in levels belonging to Susa I. At the time of Susa II, the cylinder seal appears.

Judging from the number that have been found in the houses of the poor and rich alike, it is reasonable to surmise that they were not always carried on the person; indeed, the very

large size of some of them would make them awkward things to carry.

We have as yet no definite knowledge of how the Indus Valley people disposed of their dead. If cremation was practised, the seals seem to have been removed from the bodies, as they are for the most part untouched by fire. If the bodies were buried, the seals may also have been removed, though this was not the case in Babylonia, where men and women took their seals with them to the grave. Assuming that the seals were used for legal purposes by the people of Mohenjo-daro, they would doubtless have been regarded as valued possessions, and, to avoid forgery, care would have been taken to prevent their getting into unauthorized hands. They would thus have been removed from the dead and kept by relatives until time rendered them of no further use.

The number of broken and damaged seals that have been found, which may have been accidentally lost or purposely discarded, is comparatively small. The majority are in

a good state of preservation ; indeed, some show but little evidence of use.

THE ANIMALS REPRESENTED ON THE SEALS

The So-called Unicorn

One-horned (?) beast.

The animal most often represented on the seals is the apparently single-horned beast seen on Nos. 1-297 and 537-57. There is a possibility, I think, that the artist intended to represent one horn behind the other.² In the other animals, however, the two horns are

shown quite distinctly.

In some respects the body of this beast, which is always a male, resembles that of an antelope of heavy build, such as the eland or oryx, and in others that of an óx. The long tufted tail may belong to either class. The horn is sometimes smooth (Nos., 2, 4, 15, 18, etc.); sometimes it has transverse ridges (Nos. 6, 9, 11, etc.). In the latter case, the possibility of the creature being an ox is ruled out. The long pointed ears are also characteristic of the antelope. Perhaps we have here a fabulous animal which is a composite of the ox and the antelope. And yet to the casual eye there is nothing fantastic about it, as about some of the other animals represented on the seals; nor does it in any way resemble the unicorn of heraldry, which is made up of different parts of a number of animals, though it must be noted that the traditional unicorn was supposed to have originated in India. It is mentioned by Ctesias and Aristotle as peculiar to that country and is called by them the Indian ass. For the sake of convenience, however, we shall designate this animal a "unicorn", until a more fitting name has been found for it.

Markings.

The curious markings that occur on the shoulders of these animals, and of these alone, appear to represent trappings of some kind rather than muscles or wrinkles in the skin. The curious lines around the neck of the animal on some of the seals (Nos. 4, 12, 36, etc.) certainly suggest folds of skin, but they do not occur in all the animals. Possibly they represent wire ornaments suspended round the neck, but against this theory is the fact that similar markings occur on the heads of the animals. Perhaps these lines are intended to represent hair.

In other cases (Nos. 2, 15, 22, 23, 29, etc.), a more or less elaborate necklace is substituted for these lines.

1 See, however, Chap. VI supra.-[ED.] "

² The same type of animal, but with two horns, has now been found on a seal from Harappā. These horns, however, resemble in shape the horns of an ox rather than the long projecting horn that the unicorn on our seals always has. Animals in profile are quite commonly represented with one horn on Sumerian seals.

A prominent feature about this beast is the striking eye and the well-marked eyelid above Eye. It is, however, not characteristic of all the animals of this type, as may be seen by comparing Nos. 2 and 4 with Nos. 16 and 17, for instance. In the former, the eyes are definitely cow-like and, moreover, set in their proper place in the head, whereas in the latter, the eye is entirely different and has something of the camel's eye about it.1

There is always a very curious standard-like object in front of this so-called unicorn Standard in that appears in conjunction with no other animal.2 The lower portion of this object appears front of animal. to be a bowl-like receptacle on an upright support. In some cases this bowl—if indeed it is hollow—appears to be made of basket-work (Nos. 4, 21, 22, 25, 32, 33, etc.), in others of some embossed material, perhaps leather (?) (Nos. 3, 9, 11, 15, 16, 18, etc.). Sometimes the bosses entirely cover the outer surface of the bowl, in appearance recalling the knobbed pottery illustrated in Pl. LXXVIII, 16.3 I suggest leather as the material used for these bowl-like objects, as rosettes could hardly have been attached to basket-work; but wood may have been employed as well.

It is not clear whether or not these bowls were closed in at the top. I am inclined to think that they were, for the supports of the upper portion of the object apparently rest on the upper surface of the bowl. These supports appear to be single on some of the seals (e.g., Nos. 11 and 18), on others they have a stay-like appearance (e.g., Nos. 15 and 38). A very curious variation, of which only one example is known at present, is a series of points placed either around the rim of the bowl or over its upper surface (Pl. CII, c, and No. 38).

Each of these apparent standards has a staff-like support that appears to run right up Support of through the bowl to the object above it. A pin is sometimes shown run through the staff standard. to prevent the bowl from slipping down, as is seen in seal 38 and less distinctly in others, e.g., Nos. 2, 11, 16, 66, etc. The base of the staff invariably thickens towards the foot, as would be the case with any pole, if not especially trimmed. We may take it for granted that the staff is of wood or metal, and not of pottery like the ordinary offering-stands that are so common at Mohenjo-daro and Harappa. The stem is much too thin to be made of anything but wood or metal, and the deep bowl-like object above it is quite unlike the shallow pans of the offering-stands. It is not apparent whether the base of the staff was fixed in the ground, but as it is always represented as being on exactly the same level as the feet of the beast behind it, we may suppose that it was so fixed.

The object above the bowl is also very puzzling. On all the better finished seals it Possible cage. appears to be openwork, whether made of metal, wood, or basket-work.5 Its shape is fairly uniform—either bee-hive shaped or square with incurved sides. It was possibly a cage, and we may perhaps compare it with the pottery cages seen in Pl. LXXXIV, 1 and 2. On some of the seals it appears to be closed in above (Nos. 2, 3, 9, 11, 15, 16, 17, 18, etc.), so that it could hardly have been used as a manger. Indeed, in Nos. 3, 15, 17, 19, etc., it appears to have a knob or handle on the top.

Whether the staff ran right through the upper object we do not know, though the general

What seems to be the same animal, but modelled in clay, is shown on Pl. XCVI, 23.

2 There are, however, exceptions. In front of the animal on seal 550 there is what may be either a pictographic sign or a feeding trough divided into compartments. Seal 93, which is also peculiar in other ways, is another exception, and a third is No. 167, on which a plant or a symbol of some kind stands in front of the animal.

3 No bowls, however, have as yet been found made of knobbed ware, which is at present only known in two particular shapes.

4 That is, at Mohenjo-daro. Other examples occur at Harappa. For an explanation of these "points", see p. 69 supra - [ED.]

The varying weaves are certainly suggestive of basket-work.

appearance of these apparent standards certainly suggests that it did. On the other hand, in seal 17 the portion of the support between the bowl and the upper object takes a lattice-work form.

These "standards" appear always to have been made of perishable material, and it seems likely that we shall never find any actual examples at Mohenjo-daro to elucidate their make and purpose.

Variation in slape.

The variety of ways in which these apparent standards are portrayed upon the seals suggests that they were not all copied from a single original kept in some temple or other building. The representations on the seals are evidently copies of objects of which many existed, and in the rhaking of which a certain amount of latitude was permitted. For instance, there are several points of difference in those seen on seals 15 and 18, and again on Nos. 37, 38, and 40. The upper portion alone varies in shape, but both the upper and lower objects differ in structure and mode of decoration.

Suggested. interpretation. Unfortunately, I am unable to suggest the significance of these apparent standards. Cult objects such as these seem rarely to be capable of explanation, unless one has the actual objects to examine and not only representations of them. The looseness of the weave of the upper portion of the standard certainly suggests a cage, and with diffidence I suggest that it held a bird. As is well known, birds are often intimately connected with bovine and other creatures, helping to relieve them of ticks and sometimes giving alarm at the approach of danger. If such an animal as this so-called unicorn really once existed, and if it was considered sacred, it seems to me that any animal associated with it would also be considered sacred.

Used in processions.

On two impressions which were evidently made from the same seal (Pl. CKVI, 5 and 8; Pl. CXVIII, 9), there is a most interesting little scene showing four men in file, each carrying a standard. Owing to the impression being smaller than the seal, the upper parts of the standards and the legs of the bearers are missing. Fortunately, however, enough remains of the two last standards to show that the animal on the last but one is the same as the "unicorn" type of animal. The object on the standard behind appears to be identical with the supposed cult object that is always placed in front of the unicorn on the seals. There is no doubt, I think, that on this impression we have the representation of a sacred animal being carried along in procession.²

Possible deities.

This little scene opens up a new vista; it indicates that at least one animal was worshipped either as a god itself, or, which is more probable, as a manifestation of a god. If this should subsequently prove to be true, there is every probability that the other animals portrayed on the seals also represent deities; possibly of lesser rank, since they figure less frequently.

If we ever find the seal from which these two impressions were taken, we shall perhaps find others or all of the animals represented on the seals taking their places in the procession. As before mentioned, the seal was considerably larger than the impression, and it is possible that the owner of the seal required only the impression of the "unicorn" for his purpose.

It should, however, be borne in mind that these animals may perhaps represent the deities of provinces, in exactly the same way as do the "nome" animals of Egypt, all of which are commonly shown on standards very similar to the ones carried by the men in the Mohenjo-daro impressions. There is, however, a serious argument against this latter theory. The unicorn type of animal occurs just as frequently on the seals from Harappa, 400 miles away, as at Mohenjo-daro, which would hardly be the case if the animal was the symbol of a province.

1 For a different explanation of these curious objects, see supra, p. 69.—[ED.]

² Cf. this scene with one on the mace of Narmer. See Quibell, Hierakonpolis, pt. i (1900), pl. xxvi.

I do not suggest that Mohenjo-daro had anciently any considerable connection with Nome-Egypt. But in some small respects the beliefs of the two peoples were clearly similar. facts that at Mohenjo-daro certain animals were probably sacred, that a cult object was associated 🗸 💿 with the chief of them, and that both animal and cult object were sometimes carried on standards in procession, are strongly reminiscent of the practice of ancient Egypt, where cult objects were always associated with the sacred or "nome" animals carried there on standards.

The Short-horned Bull

The animal next in order of popularity was the short-horned bull seen on seals 308-26, Character of 487, 536, and 557b. There is, fortunately, no doubt whatever about this animal, which bull. is also very commonly represented in pottery, sometimes roughly made by children, sometimes exceptionally well made, presumably for votive purposes. It is remarkable that in all its representations, both on the seals and as pottery figures, the head is always lowered and twisted slightly to one side, as if the animal were just about to charge. The fact that the bull is always shown in angry mood suggests that this aspect of it was significant. Possibly the animal may have been the emblem or vehicle of a god of war or destruction.

In most cases the heavy wrinkles on the shoulder of the bull are shown with fidelity, Wrinkles. and sometimes the dewlap also. The fact that these wrinkles somewhat resemble those on the unicorn's neck and head lends some support to the view that in the latter animal also wrinkles and not garlands are indicated. On several of the seals, Nos. 310, 312, 316, 318, etc., the animal wears an ornamental collar or garland around the neck.

In every case there is a low manger (?), flat-based and with concave sides. This manger Manger. is distinctive, and though the bull itself is duplicated in the art of the surrounding countries, yet the unusual shape of the manger is characteristic of the art of the Indus Valley civilization. The point is stressed because the occurrence of the same form of manger on a cylinder-seal of bone found at Susa 2 leaves no doubt, I think, that this seal either came from India in the first instance, or, as is suggested by its very rough workmanship, was engraved for an Indian visitor to Susa by an Elamitic workman.

At first sight the attitude of the animal suggests that he is about to eat from the manger; but that his head is really intended to be lowered in anger seems to me indicated by the pottery figures of the same animal being obviously made to represent him in angry mood (Pl. XCVII, 23-6).

The manger appears in most cases to have been of some such material as pottery, but Materials. No. 536 suggests that it was sometimes made of basket-work. The manger on this particular seal seems unmistakably to be made of reeds, or a similar material.

The bull represented in seal No. 542 is differently portrayed from the other bulls on The head is not lowered as if to charge, and a kind of cup is substituted for the the seals. usual manger.

A most interesting seal found by Mr. Woolley at Ur 3 bears the device of this type of bull with head lowered exactly like the bulls on seals 308-26 from Mohenjo-daro. The curious thing about this seal is that the inscription upon it is in cuneiform characters,

1 There can be little doubt that the animal in question is the Indian bison or Gaur (Bos gaurus), of which the attitude portrayed on the seals is a most striking characteristic.—[ED.]

² Catalogue des cylindres orient., Musée du Louvre, vol. i, pl. xxv, fig. 15. See also J. de Morgan, Prehistoric Man, P. 261, fig. 171; Mém. Dél. en Perse, t. ii, p. 129.

3 Sidney Smith, Early History of Asseria, p. 50, fig. 3; The Antiquaries' Journal, vol. viii, pl. xi.

and not in the script of the early Indus Valley, but the syllabic values of the signs are uncertain. From the forms of the signs upon this particular seal, it can be dated to the pre-Sargonic period. It is not outside the bounds of possibility that the language used on this seal is an Indian one and that the seal belonged to an Indian trader who was residing at Ur. For business purposes he naturally preferred to use a script on his seal that his Babylonian customers would understand. At the same time, the figure of the bull with its manger was retained, perhaps to show that the trader was an Indian.

To whomsever this seal belonged and whatever its inscription, it is of especial value because it confirms our dating of the Indus Valley civilization. The posture of the bull, together with its manger, proves it to have belonged to a man who was acquainted with Indian culture, and its inscription shows that that culture was existing at or before the time of Sargen the Great.

Buffalo (Bos bubalis)

Characteristic attitude.

This animal is rare and only appears on three of the seals (Nos. 304-6). On all three it is in a very typical attitude, with nose up sniffing the air. In fact, like most of the buffaloes of the modern Indian village it appears to be in a belliance to be in a be

of the modern Indian village, it appears to be in a belligerent mood.

On two of the seals, there is exactly the same form of manger as in front of the bulls, but on the third (No. 304) this feature is missing and there is nothing—there is no inscription either—to take its place. This seal, however, appears to be unfinished. The portrayal of the animal is exceedingly natural, and we can only regret that the workmanship of these three seals does not approach the level of some of the others. The manger on seal 306, again, appears to be made of basket-work.

Brahmanī Bull (Bos indicus) 3

Careful delineation.

We have certain proof in Nos. 327-40, and possibly No. 542,4 that this type of bull was known in India in very early times. The characteristic hump on the shoulders allows of no doubt whatever. Fortunately, the majority of the seals on which this animal is represented are well preserved. Indeed, rather more care seems to been have taken with the portrayal of this animal than with some of the others. No. 337 is marvellously well engraved and finished; in feeling and in the careful portrayal of the muscles it will compare favourably with early glyptic art anywhere. The heavy wrinkled dewlap is especially well done, as is the case also with the bulls of seals 333 and 339. On seal No. 337 a band or garland of some kind has been thrown over the bull's shoulders; and on seal 333 the shoulders together with a portion of the hump appear to be draped with some material. It is possible that in the latter case the seal cutter has made a slight mistake; for, if rolls of skin are intended, the hump should have been left round and smooth. There is no cult object of any kind represented in conjunction with these bulls. Apparently the Brahmani bull

Garlands.

^{1,} See pp. 406, 412, and 413 infra.

² Compare the setting of the heads and horns of these buffaloes with the method of portrayal on Sumerian scals, as for instance, the seal said to have belonged to Sargon of Agade. Peake and Fleure, Priests and Kings, p. 55, fig. 24.

³ The humped bull is more fully dealt with in Chapter XVIII, on Figurines and Model Animals.

⁴ I regard the animal on this seal as being of the humped variety with short horns.

does not appear on any of the seals or pottery of either Sumer or Elam.1 It first appears in Babylonian art about the time of Gudea on a limestone bas-relief.2 It is also shown on a painted sherd from Nal in Baluchistan.3

· Rhinoceros (R. unicornis)

This animal also rarely appears on the seals, Nos. 341-7 being the only examples that Great Indian we have as yet. In every case it is the single-horned animal that is represented, probably rhinoceros. the great Indian rhinoceros which was formerly found along the base of the Himālayas as far as Peshāwar, where it was hunted by the Emperor Babar.

This animal's thick hide is well represented on seal No. 345, where the wrinkles and Excrescences on folds of skin are very true to life. Rough excrescences on the skin are indicated in hide. some of the examples by means of holes made with a fine drill. In others hatched lines are employed. In every case the animal is rendered with extreme fidelity, even to the wicked pig-like eye.4 From this, I think, it can safely be affirmed that the animal was very well known to the people of Mohenjo-daro; in ancient times it was probably very common in Sind and perhaps still further west. It does not appear on any of the seals from Elam or Mesopotamia.

The rhinoceros is, curiously enough, provided with the same kind of manger-more Manger. probably a cult object—as the short-horned bull.

The animal represented on a fragment of a seal (No. 354) is difficult to identify. At first glance it seems to be a rhinoceros, especially as the fore and hindquarters bear drill-marks similarly arranged to represent roughnesses as on the other rhinoceros seals. The legs of the animal, however, are much too thin for those of a rhinoceros; they resemble father the legs of a bull or ox.

The rhinoceros was very commonly modelled in clay and was a favourite with the Clay models. children. It must, therefore, have been very well known to them (Pl. XCVII, 8-11).

Tiger (Felis tigris)

That the animal on seals 349-53 and 355 is the tiger is proved, I think, by its being Existence in. striped. This animal is now extinct in Sind, though it is found in most of the wilder parts Sind. of India. Unfortunately, some of the seals upon which the tiger appears are badly broken. In two (Nos. 350 and 351) the animal is very quaintly represented with a manger before it of identically the same pattern as provided for the short-horned bull and rhinoceros.6 Two Tiger and man. • seals in this group are of especial interest (Nos. 353 and 355). On both a man is seated in

- ¹ It appears, however, carved on archaic bitumen vessels from Susa. Mém. Dél. en Perse, t. xiii, pl. xxxiv. See also Scheil, Recueil de signes archaiques, p. 11.
 - ² King, History of Sumer and Akkad, p. 69, fig. 21.
- 3 See Pl. XCIII, 30 of this work. Also Mem. Arch. Surv. Ind., No. 35, pl. xvii. [It should be added that it is a very common motif on the Mehi-Kulli ware of Balūchistān. See pp. 98-9 supra.—ED.]
- 4 Seals Nos. 342-5 are good examples of this fidelity. The great Indian rhinoceros is characterized by the skin of the sides of the body being thickly studded with large rounded tubercles and also by the great folds of skin which surround the back of the head like a coif. Lydekker, Game Animals of India, p. 28.
 - ⁵ The last specimen was killed in 1883.
- 6 A seal in the Louvre bearing the device of a tiger standing over a manger is illustrated in Revue d'Assyriologie, xxii, 99. M. Thureau-Dangin, who published it, suggests that it came from Telloh.

a tree with a tiger below regarding him attentively. In each case the man clasps the tree with one hard; the other he is holding out as if he were apostrophizing the animal. As this scene occurs on two of the seals it seems that it was not entirely an unusual one. The nearest analogy we have to it is a scene on a limestone cylinder seal of the neo-Babylonian period from Kish. In this, a man is seated in the same attitude in a tree, with a hyena at its base.

Elephant (Elephas maximus)

Careful portrayal.

This animal figures on fifteen of the seals, Nos. 362-76. In fact, it may be said to rank next in order of popularity to the bull. On most of the seals it is carefully portrayed, in some cases even to the wrinkles along its back. On one seal only (No. 369), the same low manger or cult object is placed before the animal as on the seals representing the short-horned bull. In some cases the elephants appear to belong to the present sole existing species in India, but in others (Nos. 369-72) the back has a pronounced slope which recalls the African variety. The comparatively small ears, however, are against any connection with the African elephant. The animal is no longer found in Sind, but it occurs wild in places along the base of the Himālayas as far west as Dehra Dun. It is not certain whether trappings are represented on seals Nos. 369, 370, and 373, or the vertical folds of skin at the junction of the limbs. This animal is sparsely represented in pottery. For an example see Pl. XCVI, 10, where, however, the trunk is broken and missing.

Rarely represented in pottery. Trunk recalls African species.

Lydekker remarks that one of the differences between the Indian and African elephant is that the former has a finger-like process on the front edge only of the tip of the trunk, whereas the African species has two such processes, on the front and hind margins respectively.² In seals 367, 371, 372, 534, and 535 two processes are definitely shown, though the animals portrayed belong to the Indian species, as shown by the smallness of their ears, the flatness of their foreheads, and the profile of their backs. It may be, however, that the animals seen on these seals represent a species of elephant that is now extinct in India. The presence of two processes on the trunk on no less than five seals can hardly be regarded as a mistake on the part of the seal-cutter, though that mistakes were sometimes made is shown by the wrongly placed eye on seals 372 and 534, and the absurd ear, if it is an ear, on seal 369. Possibly the elephant was not so well known to the inhabitants of Mohenjo-daro as we thought at first. It may never have been wild in Sind and have been used by a few people only for purposes of state.

Mistakes in carving.

Gharial (Gavialis gangeticus)

Fish-eating crocodile.

The reptile shown on three of the seals (Nos. 359-61) and on two of the sealings (Pl. CXVI, 14 and 20; Pl. CXVIII, 10) is the fish-eating crocodile which still inhabits the Indus and other rivers of India. It can be readily identified by its very elongated, thin snout. On both seals and sealings a fish is generally represented between its jaws. On No. 360 the scales are represented by hatching, but in No. 361 holes were drilled to indicate the scaliness of the creature. If this animal was sacred, it must have been selected for some other attribute than ficrceness; for it is harmless to man.

1 In the Ashmolean Museum, Oxford.

o 2 Game Animals of India, p. 10.

Antelopes are very rarely represented on the seals of Mohenjo-daro (Nos. 302-3), Rarely whereas the motif is very common on the Sumerian seals.

That the animal portrayed on Seal No. 302 is an antelope is suggested by the shortness of its tail. In general appearance, however, it resembles the so-called unicorn, with the difference that it clearly has two horns. This seal is also unusual in having two characters in front of the animal.

That No. 303 definitely portrays an antelope is shown by the long curling horns. The little shrub in front of the animal is characteristic of many of the archaic Sumerian seals, where also it occurs in conjunction with an antelope. The animal wears a collar, apparently Collar. made of some woven material, with a pendant in front which may possibly be a bell.

MYTHOLOGICAL CREATURES

Of these, Seals Nos. 356, 357, and 358 represent human or partly human forms. • The Enkiduhuman figures in No. 356 occur on the two ends of Seals Nos. 227 and 230, which bears an inscription together with an animal on each of its larger faces. These human figures have the hoofs, horns, and tail of a bison, and the left arm of each is raised above the head while the right hangs down by the side. Both these figures closely resemble Enkidu, the companion of Gilgamesh, whose head, shoulders, and arms were human, but with the addition of a pair of bison's horns.

The same figure appears again on Seal 357, where he is struggling with a fabulous beast, Wrestling with the greater pant of which is tiger-like. On seals and other objects from Sumer, Enkidu is mythological always shown struggling with a lion and his companion Gilgamesh with a bull, but it is possible creature. that at Mohenjo-daro the tiger was substituted for the lion, which animal never appears on The treatment of the tree behind the hero is extremely realistic, both in its very careful drawing and its pleasing irregularity. One feels that such a tree could be found almost anywhere in the east, cropped by animals and broken down by man. The horns on the head of the animal, whose stripes show it to be a tiger, do not resemble those of any particular beast; without them, this would be an exceptionally good representation of a tiger, for the mouth is open and the canine teeth are showing.

The man in No. 358 is probably not mythological at all. He is evidently engaged in Shadoof. working a shadoof, whose counterpoise is seen at the end of the pole above and behind

The aninal on Seals 376 (upper figure) and 377-81 appears to be a ram, with the horns Composite of a bull, a human face, and the trunk and tusks of an elephant. That the body of this animal. composite beast is a ram's body is indicated by the long locks of wool on its fore-quarters. The hind-quarters and hind-legs are, however, those of a tiger. On those seals where the face is not broken away, it appears to be human, and the eyes, like those of the statues, are very elongated and slit-like.

In No. 381 the beast has three ornamental collars. In Nos. 378, 380, and 381 it Tail armed with has its tail straight up in the air and in No. 378 this tail is armed with pincers.2 This fabulous pincers.

The horns are certainly those of a bison (Bison bonasus or Bos gaurus). See on this subject, Ward, Cylinder Seals of Western Asia, pp. 426-7.

² Compare this animal with the creature described by Ctesias called Martikhora. It was said to be as large as a lion, with a human face, and to shoot stings out of the end of its tail.

beast closely resembles the stone figure of the ram illustrated in Pl. C, 9, but, unfortunately, in the statue the head is very badly broken and we are unable to say whether the resemblance is complete in all respects. The elephant's trunk is, however, clearly indicated in the statue.

Seal 384 is very badly weathered, but on the right side the two horns of an animal and a portion of its head can be traced. The horns somewhat resemble those of the composite

animals just discussed.1

Three-headed beast.

The three-headed beast on seal 382 appears to be a composite of three animals. The heads and horns seem to be those of antelopes and the body that of a unicorn. The heads have been joined to the body very carefully. One is eating, the second looks straight ahead, and the third is looking backwards in apparent alarm. If any two of the heads were removed and the tail shortened, quite a normal animal would be left. From the way in which the heads are arranged, it is probable that the seal-cutter carved the central head and the body of the animal first and then added the extra heads.

Arrangement of horns.

Owing to insufficient room, the horns of the lowest head are rather different from the others; they resemble a bull's horns rather than those of an antelope. Again owing to lack of room, the horns on the middle head, though obviously an antelope's, are reversed in position. Judged by the shape of the body, the markings on the necks and the trappings over the withers, it seems evident that the animal, except for the horns, was intended to be the so-called unicorn.

Triskillion.

The design on No. 386 is most complex. The animals appear to be tigers whose three bodies cross one another in the centre. In archaic fashion, every available space on the ground of the design is occupied by pictographs.²

On the broken seal, No. 383, the heads and necks of six animals radiate outwards from a ring-like motif. Of the four unbroken heads, one is a unicorn's, another a short-horned bull's, the third an antelope's, and the fourth a tiger's. The remaining two heads were probably those of a rhinoceros and an elephant.

Mythological beast.

The fantastic creature on No. 385 is unique. The drill marks on the body are apparently intended to represent spots, and the long horn just above the nostrils is evidently taken from the rhinoceros.

PLANT-FORMS

Pipal tree.

The representation of plant-forms on the seals is rare; they occur only on twelve seals, Nos. 22, 126, 167, 303, 340, 352, 353, 355, 357, 382, 387, and 527. On only two seals is a plant-form the central motif (Nos. 387 and 527). The plant on the former has been identified as the pipal tree,3 which in India is the Tree of Creation. The arrangement is very conventional and from the lower part of its stem spring two heads similar to those of the so-called unicorn. The very conventionalized arrangement of the leaf-stems is not only decorative; it enables the whole ground of the seal to be filled up by the stems and leaves without confusion. The lower portion of the seal is filled in with pictographs. It may be the babul or the jhandi tree, that is represented on four other seals (352, 353, 355, 357). They are the commonest trees of the neighbourhood of Mohenjo-daro at the present day,

² Compare the designs with some seal impressions of the Persian Period, dated about 464-404 B.c., found at Nippur. Legrain, Culture of the Babylonians, pl. lv.

This linking together of the ram, elephant, tiger, bull, and human form may be an attempt at the fusion of several deities; it is perhaps a step on the road to monotheism.

³ Ficus religiosa. The leaves of this tree constitute a common motif on the Nal pottery (Pl. XCIII, 2 and 3). It does not appear on the pottery of Mohenjo-daro. Sec Pl. CLIV, Fig. 9.

and are rather straggling in growth, with small leaves.1 That it was intended to represent trees and not shrubs is proved by there being a man in the tree on two of the seals.

Out of 387 soals bearing non-fabulous animals, the unicorn appears on no less than Order in 312, showing the great popularity of this animal. The short-horned bull is a poor second, popularity. appearing as it does on twenty-two seals. There are seventeen examples of the elephant and fourteen of the Brahmanī bull. The rhinoceros and the tiger come next with seven representations each. The buffalo and the gharial appear three times each, but of the antelope there are only two examples, excluding the heads on Nos. 382 and 383.

It is a curious fact that the lion is not represented on any of the seals, the more so; as it Lion. appears repeatedly on the archaic seals from Elam and Sumer. In the early seals from Kish it was one of the most frequently portrayed animals. It was generally represented as attacking a herd of antelopes, showing that the herdsman in early Babylonia was perhaps better acquainted with the beast than he desired. The lion though extinct in Mesopotamia is still found, it is said, in remote parts of Persia. In India it is now rare, but in the early historic period it extended over a great area of northern and central India. On the seals of Mohenjo-daro the tiger takes the place of the lion, though, it is true, it is but rarely represented.

Another significant feature is the rarity of the antelope on our seals, though, as before- Antelopementioned, it appears very frequently on the seals of Elam and Sumer. The short-horned bull is common to the seals of Mohenjo-daro, Elam, and Babylônia, especially on the seals . of the latter countries. The Brahmanī bull, elephant, gharial, and rhinoceros are not to be found, to my knowledge, on any but the seals of the Indus Valley civilization.

These facts are of considerable interest as they tend to show that the fauna of ancient Sind was radically different from the fauna of both Elam and Sumer. If this be granted, we can safely say that the physical nature of these countries must have been just as different. The lion and antelope, for instance, inhabit rocky and sandy wastes, and are not to be found in a country of forests. On the other hand, the tiger, the elephant, and the rhinoceros live chiefly in forest country and in high grass near water.2 These facts would also argue that the climate of Sind was entirely different anciently from what it is at the present day; at least that portion of it in the vicinity of the Indus river, which even now cannot truly be called a desert. That the rainfall west of Sind, i.e. in Balūchistān, was by no means negligible in very early days is proved by the observations of Dr. Vredenburg, who found in southern Balūchistān ample evidence of a greater rainfall in ancient times, which he suggests may have been modified by forest denudation.3 Sir Aurel Stein is also of the opinion that desiccation can alone account for the depopulation of southern Balūchistān. The very numerous city and village sites in that part of India prove that in ancient days the population must have been very considerable.

The presence of what seems to be a feeding-pan in front of some of the animals on the Captive seals suggests that they may have been kept in captivity as sacred animals. This manger animals. was always placed before the buffalo, the short-horned bull, the rhinoceros, and sometimes even the tiger and elephant. The keeping of animals in captivity as emblems of various deities is especially well known to us from ancient Egypt, where this was an established religious practice. If it be admitted that the animals represented on the seals were captives.

1 The babul = Acacia arabica; the jhanai or kandi, as it is otherwise known = Prosopis spicigera. - [ED.].

² We have been struck by the number of antlers and bones of the Sambur deer that have been found at Mohenjo-daro. This deer is a forest-loving animal and does not frequent the arid or semi-arid plains.

³ Mem. Geol. Surv. of Ind., vol. xxxi, part 2, pp. 179-302. See also Pumpelly, Explorations in Turkestan, Expedition 1903, pp. 300-15.

the additional fact that some of them are provided with trappings suggests that they were open to the inspection of visitors, and regarded as sacred animals.1

Temple models

On the other hand, it is within the bounds of possibility that models of these animals were kept within the temples, either together or each in a temple devoted to a particular deity. The existence of the curious composite animal with ram's body and elephant's trunk, etc., of which we have found more than one example in stone, suggests that something of this kind was done. The people of Mohenjo-daro may have believed that the god occasionally look up his abode in the animal itself and that at stated times offerings were required to be placed before it.

Again, models of animals to which reverence was paid might easily alter in appearance as time went on. Figures of this description would require replacements, and as each was made, some slight change would creep in. For instance, the one-horned beast, which is not far removed from an actual animal, might easily have assumed, from constant copying, the form that we now see on the seals, the animal itself having become rare or extinct.

Animal bones.

In Chap. XXXI on the animal bones recovered during the excavations at Mohenjo-daro, which has been contributed by the Director of the Zoological Survey of India, it will be seen that amongst those of other animals which are not pictured on the seals, the bones of the following animals that do appear on the seals, were found, namely, of the gharial, the Brahmanī bull, and the elephant.

It will have been noticed that the majority of the animals on the impressions of the seals, from which the photographs were made, face to the right. On the actual seals, the direction is, of course, the reverse. There are only ten exceptions to this rule (Nos. 112, 167, 272, 302, 304, 307, 341, 352, 376, and 382). Of these there are only three amongst the many "unicorn" seals. Two are buffaloes, one a rhinoceros, one a tiger, and one an antelope. One is an unknown animal and one a composite beast.

Animals used in script.

It is remarkable how few animals are used as characters in the inscriptions. We can identify the jungle-fowl, the duck, the fish, and the man. Two of the signs above the bull on seal 338 almost certainly represent jungle-fowl, their long legs and turned-up tails unmistakably marking them as such. We do not yet know whether this bird was domesticated or not. It also appears in seals 36, 207, 228, and 237.² On seal 93 there is a delightful sign representing a duck (shoveller?) in a pool of water. This is drawn with great fidelity, even to the turned-up end of the beak. A pea-fowl is perhaps represented in seal No. 144.

Guat.

A goat, as shown by the short and uplifted tail, appears on one seal (No. 150); and an animal that may be a scorpion on seal No. 262.

It is likely that the animals portrayed on the seals represent a decadent totemism and

that they gradually passed into the religion and became deities, though still retaining their animal form. They appear on the seals of rich and poor alike, as well as in figurines. These latter might perhaps be explained as being due to conservatism; the seals, however, were for use and, in consequence, had to be understandable by even the poorest person, who would recognize the animal, even if he could not read the writing.

Bow and arrow.

In some of the inscriptions a man appears to be holding a bow and arrow in one hand (Nos. 12, 15, 60, 65, 69, 70, 92, 400, and 406). On other seals he holds a bent stick or some other object (Nos. 37, 42, 43, 116, 118, 343, and 348). In some cases he carries his bow

of On the trappings of sacred bulls in Crete and Cappadocia, sec Arthur Evans, Palace of Minos, iii, pp. 204-6, and figs. 139 and 140 a and b.

The jungle-fowl only appears on Mesopotamian seals at a late period. For a good example see Ward, Seal Cylinders of Western Asia, p. 339, fig. 1126. It was probably well known in that country long before. In Egypt this typical Indian fowl is shown on an ostrakon dated to the eighteenth dynasty. See Jour. Eg. Arch., vol. ix.

on his back (Nos. 18,038, 101, 111, 116, 478, and 496), and his arms are drawn up to the breast, as in the figure on the ivory tablet pictured in Pl. CXXXII, 10.

SEAL IMPRESSIONS

In addition to five seal impressions on jars, thirty impressions have been found on tablets of various shapes found at Mohenjo-daro, twelve made of faience and the remainder of baked clay. As, with one or two exceptions, they are not perforated, it is possible that, like some copper tablets, they were used as amulets.

These impressions, which are illustrated in Pls. CXVI and CXVIII, can conveniently Grouping.

be divided into four groups for description, namely, impressions on :-

- (a) Rectangular or Square Tablets.
- (b) Triangular Prisms.
- (c) Round Tablets.
- . (d) Impressions on Pottery Vessels.

(a) Reclangular or Square Tablets

There are altogether eighteen examples in this group which vary slightly in shape, the majority being well made, with flat ends and sides. Others, have slightly rounded faces, and one with a flat base has a highly rounded back. The members of this group vary somewhat in size, as will be seen in the detailed list below.

Only one is perforated, probably by the owner, who apparently tried at first to drill a hole Perforations. through the side and gave it up when he realized that it was quicker and safer to make holes through the face. The two that he made disfigure both sides of the impression; and,

moreover, they are cut obliquely (Pl. CXVI, 1).

No. 1 on Pl. CXVI; Pl. CXVIII, 7 (B 426). Grey-coloured paste. Size 0.8 by 0.77 by 0.35 in. On the obverse is a row of six nude human figures in the upper register, standing side by side with the arms held close to the body. It is impossible to determine whether these figures are male or female. In the lower register is a kneeling figure on the left holding a broad-bladed object in one hand. In front of him is a goat, before which is a partly defaced object that looks like a tree. In the centre of the tree is a human figure. The reverse has exactly the same scene, but it is not so distinct.

Two small holes irregularly placed and running obliquely through the amulet probably served to attach it to the clothing. Level, 8 feet below surface. Room 17, Block 3,

Section B, DK Area.

The interpretation that I incline to place on this most interesting scene is that a priest Tree worship. is about to secrifice a goat to a tree-spirit. In most parts of India at the present day, offerings and occasionally animal sacrifices are made to certain trees to placate the spirits that dwell within them. The cult of the tree was also common to most ancient religions throughout the world. For example, we have the Dryad and the Hamadryad of Greek mythology, and Hathor who dwelt in the sycamore fig-tree of ancient Egypt.2

The leaves of the tree on the sealing are not unlike those of the pipal,3 a very sacred Pipal tree. The tree itself appears also on seal 387 in tree in India in past and also present times.

a conventionalized form.

Particularly pipal and banyan trees.

² Tree spirits also frequently appear in Buddhist art.

Ficus religiosa. For an illustration of the leaf of this tree, see Pl. CLIV, 9.

Several examples of this figure in a tree appear on sealings from Harappā, but without the accessory figures. This sealing from Monenjo-daro is the only one of its kind that has been found on that site. The nearest approach to this motif in Babylenian art is shown on a seal in the Louvre, where a goddess is pictured beneath a tree that has its top bent over to form a canopy.

Composite arimal.

No. 3 on Pl. CXVI (SD 1923). Pottery. Formerly coated with a red slip. 1.7 by 0.47 by 0.3 in. Same design on both sides; two signs on the left and an animal on the right, which appears to be the same as the fabulous beasts on seals 377-81. Its tail is straight in the air and it appears to have an elephant's trunk. Level, 6 feet below surface.

Rhinoceros.

o'63 by o'15 in. Indistinct characters on one side and a rhinoceros on the other. Level, 6 feet below surface. From Room 76, House XIII, VS Area.

Unicorn.

No. 6 on Pl. CXVI (E 232). Pottery. Size 1.2 by 0.75 by 0.5 in. Face flat; the rounded back and sides of the impression have been carefully smoothed with the fingers. Five characters above a "unicorn". This impression was made with a large seal, but from the way the seal was used, it appears that only the inscription was required. Level, 5 feet below surface. Trial Trench E, DK Area.

No. 10 on Pl. CXVI (HR 1056). Pottery. Coated with a smooth, red slip. Size 1.55 by 0.62 by 0.3 in. On both sides of this impression there is the same scene as on No. 11. Level, 2 feet below surface. Chamber 9, House II, HR Area.

No. 11 on Pl. CXVI (VS 3513). Pottery. Coated with a red slip. Size 1.5 by 0.6 by 0.2 in. Both sides alike; a rhinoceros facing to the right and two signs enclosed in brackets (?). Level, 9 feet below surface. From Room 30, House I, VS Area.

No. 12 on Pl. CXVI (VS 928). Faience. A fragment only. Characters on one side.

Level, 5 feet below surface. Room 11, House XVIII, Block 4, VS Area.

No. 13 on Pl. CXVI (HR 4275). Pottery. Coated with a red slip. Size 1.55 by 0.65 by 0.2 in. The same scene on both sides as on Nos. 10 and 11. Level, 2 feet below surface. Chamber 25, House XV, Block 3, Section B, HR Area.

No. 15 on Pl. CXVI (HR 4505). Faience. Size 0.95 by 0.4 by 0.15 in. Six very clean-cut characters impressed on one side only. Still bears traces of original colour, either green or blue. Well made and shaped. Level, 3 feet below surface. House XLVIII. Block 6, Section B, HR Area.

No. 16 on Pl. CXVI (HR 5971). Faience. Size 1.8 by 0.55 by 0.3 in. Inscribed on both sides with clear characters. Each inscription is bounded on either side by a band of three vertical lines. Exceptionally well made. Level, 8 feet below surface. Room 87, House IX, Block 2, Section B, HR Area.

No. 19 on Pl. CXVI (E 1449). Faience. Size 1.0 by 0.7 by 0.15 in. Both sides inscribed; four characters visible on one side, other side illegible. Level, 10 feet

below surface. Trial Trench E, DK Area.

No. 20 on Pl. CXVI (E 2500). Pottery. Size 1.55 by 0.45 by 0.3 in. Slightly rounded ends. One face flat and the other rounded. A gharial, or fish-eating crocodile, on the rounded face, with a fish between its jaws. On the reverse a svastika on the left, followed by a tree and three characters. Level, 2 feet below surface. Trial Trench E. DK Area.

Rhinoceros.

Gharial.

¹ A seal illustrated in Pl. XII, 18 and recently found at Mohenjo-daro bears practically the same device.

The goat-like animal is not intended to be a sacrifice in the new seal. It is a deity of some kind, for it has a human face.

Ward, Seal Cylinders of Western Asia, pp. 149 and 150.

No. 22 on Pl. CXVI (HR 165). Faience. Size, 1.2 by 0.5 by 0.4 in. Both sides are slightly rounded. Four signs on obverse. Reverse blank. Traces of original glaze still remain. Level, 1 ft. 6 in. below surface. Southern end of Deadman Lane, HR Area.

No. 26 on Pl. CXVI (HR 2289). Pottery. Formerly coated with a red slip. Size, File of animals. 1.75 by 0.65 by 0.3 in. A row of eight characters on one side and a file of animals on the other, the latter very indistinct. Level, 12 ft. 8 in. below surface. Room 127, House X,

No. 27 on Pl. CXVI (DK 1323). Faience. Yellow paste inside. Size, 1.2 by 0.3 by 0.35 in. Inscribed on both sides with characters which are now undecipherable. Jevel, 3 feet below surface. Room 18, Block 4, Section B, DK Area.

No. 29 on Pl. CXVI; Pl. CXVIII, 11 (VS 210). Faience. Size, 1'3 by 0'6 by Figure in yogī 0.35 in. On the obverse is a seated figure on a dais, flanked on either side by a kneeling attitude. worshipper. Behind each worshipper is a cobra in a vertical position. On the reverse there are five or six characters, some of which are partly obliterated. Level, 2 feet below surface. Lane 5, House XXVII, VS Area.

Not illustrated (HR 3959). Faience. Fragment only. Inscribed on both sides. Still shows traces of blue glaze.

(b) Triangular Prisms

Five impressions of this shape have been found, one in faience and the remainder in Pottery. In four of the examples, all three sides are used for inscriptions or for scenes. Included in this class of sealing are two of slightly different shape.

No. 5 on Pl. CXVI (HR 1443). Pottery. 1.15 inches long, sides 0.36 in. wide. Ensign bearers. A single row of characters fills up two of the sides of this prism, the upper half of the row being impressed on one side and the lower half on another side. The third side contains a most interesting scene of four men in file, each carrying a standard. Unfortunately, we cannot see what is on three of the Standards, but the central Standard appears to show the well-known "unicorn". This particular scene is certainly Egyptian in feeling; indeed, if it had been Egyptian infound in that country probably no particular attention would be paid to it. Level, 10 feet character. below surface. Room 14, House III, HR Area.

No. 8 on Pl. CXVI; Pl. CXVIII, 9 (HR 1546). Faience. 1'15 inches long with Prism sealing. two sides each o.5 in. wide, and one side o.25 in. wide. This prism bears identically the same scene as occurs on No. 5, but it is rather clearer. Evidently both impressions were made from the same seal. Apparently the object carried on the standard behind the one with the unicorn is the basket-like object that always appears in front of this animal. Both these triangular prisms were too small for the seal used upon them, with the result that much interesting detail has been lost. Level, 7 ft. 6 in. below surface. Found in the area between Houses III and VI, in HR Area.

No. 14 on Pl. CXVI; Pl. CXVIII, 10 (Mus. 4). Pottery. Average size of each face, 1.6 inches long by 0.35 in. wide.

(a) On one face, from left to right, there are an elephant, a rhinoceros, a tiger Animals in file. or leopard, and another cat-like animal. Above these animals, which are en file, is a fish on the left, followed by a gharial with a fish in its mouth.

¹ The position in which this figure is sitting is typically Indian.

(b) From left to right, a file of animals: a unicorn, what seems to be a cow, a shorthorned bull, and a rhinoceros. Above the file there appear to be a jungle-fowl and a gharial, but these figures are somewhat indistinct.

(c) From left to right, there are two goats eating from a tree, a jungle-fowl, a man apparently pushing a goat or similar animal along, and finally, an antelope-like animal with

two heads, similar to those on the copper seals.

A hole, 0.3 in. deep, at each end of this object, suggests that it was used as a kind of revolving bezel. The animals are too close to the ends of the impression for it to have been capped with metal,

Pentagonal impression.

No. 17 on Pl. CXVI (HR 5713). Faience. 1.05 inches long. This impression is five-sided, but only one side bears an inscription, which is entirely illegible owing to weathering. Level, 6 feet below surface. Room 43, House LXIV, Block 8, Section B, HR Area.

No. 21 on Pl. CXVI (E 1260). Pottery. 1.65 inches long with sides 0.38 in. wide. On one side there is a row of eight or nine characters; the other sides are blank. Trial Trench E, DK Area.

Quadrilateral sealing.

No. 23 on Pl. CXVI (E 1517). Light-grey pottery. 1.25 inches long by 0.4 in. thick. This prism was evidently first intended to be triangular, but in the removal of waste material in the process of shaping it, it acquired four unequal sides. On three of the sides there are inscriptions in small, fine characters which are difficult to make out. Level, 10 feet below surface. Trial Trench E, DK Area.

Tiger, unicorn and bull.

No. 25 on Pl. CXVI ; Pl. CXVIII, 12 (HR 3766). Pottery. Coated with a red slip. 1.3 inches long with sides 0.5 in. wide. Level, 10 feet below surface. House XIV, Block 3, Section B, HR Area.

(a) On the left, a tiger, standing over a manger; three signs on the right.

(b) From left to right, a unicorn and three signs.

(c) On the left, a short-horned bull standing over a manger; on the right two signs.

(c) Round Tablets

Only six seal-impressions were found on rounded tablets, all varying slightly in detail. No. 7 on Pl. CXVI (C 696). Pottery. 1 inch in diameter and 0.4 in. thick. side of the object has been stamped with a square seal, and more care was taken to secure the impression of the characters than of the animal. The other side was stamped with a seal of somewhat indefinite design. Level, 8 feet below surface. Chamber 17, Block 12, Section C, DK Area.

No. 9 on Pl. CXVI (E 1450). Yellow sandy paste. 0.7 in. in diameter and 0.32 in. thick. Of the roughest make. Characters on one side, and an animal that cannot be identified on the other. This object seems to have been made in the same mould as No. 24. Level, 10 feet below surface. Trial Trench E, DK Area.

No. 24 on Pl. CXVI (E 1451). Faience. 0.7 in. in diameter and 0.3 in. thick. Roughly shaped and stamped on both sides with a seal. There is an animal that looks like a bear on one side, and a row of five characters on the other. Level, 10 feet below surface. Trial Trench E, DK Area.

Impression of

No. 28 on Pl. CXVI ; Pl. CXVIII, 8 (HR 1051). Pottery. 1.5 inches in diameter unusual shape and 0.7 in. thick. This impression was carefully made in a mould. It is globular in shape with a projecting ring around its equator. On one side is a short-horned bull,

and on the other a rhinoceros. There is a manger in front of each animal. The inscriptions above the animals are not the same. See also Pl. CII, i and j. Level, 6 feet below surface. From Deadman Lane, HR Area.

No. 30 on Pl. CXVI (E 444). Pottery. 1.55 inches in diameter and 0.6 in. thick. Pottery Very roughly made. The rounded face has been stamped with a square seal. The signs impression are clear, but it is evident that no trouble was taken to secure a good impression of the unicorn, which can just be seen below the characters. Level, 3 feet below surface. Trench E, DK Area.

Not illustrated (Mus. 11). Yellow sandy paste. 0.7 in. in diameter and 0.3 in. thick. On one side is an animal which it is impossible to identify; on the other, there is an inscription in four characters which are very faintly marked.

(d) Impressions on Pottery Vessels

A rectangular seal bearing characters only was used in stamping some of these impressions (e.g., Pl. CXV, 558, 559, and 560). For the impression shown in Pl. LXXVIII, 3, a square seal was evidently employed, but more care was taken to impress the inscription than the animal. The same inscription occurs on two potsherds (Pl. LXXVIII, 3, and Pl. CXV, 560), but it is evident that the same seal was not used for making both impressions. No. 558 (HR 275) in Pl. CXV comes from Courtyard 18, House I, of HR Area, and No. 560 (VS 2269) was . found 3 feet below the surface of the ground in a pit dug to the south of House XX, Block 3, VS Area.

Unclassified Impressions

No. 2 on Pl. CXVI (C 2105). Grey pottery. This is a fragment of an impression which is so broken that it could not be placed in any particular group. It is a portion of an inscription in well-preserved characters. Chamber 1, Block 8, Section C, DK Area.

No. 13 on Pl. CXVIII (Mus. 5). Bronze. A cast of a seal impression measuring Bronze 1.8 inches long by 0.25 in. thick. Of very rough work with no attempt whatever at finish. impression. The reverse is blank. Perhaps experimental.

That the impressions on baked clay and faience were regarded as talismanic seems likely, Talismans. . though they may also have been ex-votos. One tablet stamped with a seal impression is pierced with very roughly made holes (Pl. CXVI, 1), with the evident purpose of securing it to something, possibly to the clothing. Moreover, all of the tablets which are stamped on one side only have smooth backs, which shows that they had never addered to anything and, therefore, were not labels for merchandise. Again, many of the objects stamped with seal impressions were inscribed on more than one side, which would be suitable in an amulet but could serve no other purpose. Also some were coated with a red slip, which is never present and would be useless on sealings.

If they were not used as amulets, it is perhaps possible that the objects that have been Votive objects. described were votive offerings. . Or they could have been used for either purpose. The fact that no less than three of these objects bear the same impression in addition to being made in the same mould rather suggests their being votive objects. They may have been given by the priest to visitors to a temple, or, as seems more likely, they were bought from the priest as a proof that the visitor had fulfilled certain religious duties, like the embossed cake of sacred earth that is carried away from Kerbela by all devout Shias. Such an object would doubtless be carried on the person.

398

The fact also that many of the impressions are in faience proves that they were not ordinary sealings. Faience requires a very considerable heat to fuse its glassy coating, which could not, of course, be applied, if it were attached to merchandise.

Animals in file.

It is interesting to find that a file of animals is a feature of some of the seal-impressions, for this motif is very common on the archaic Mesopotamian and Susian seals. In place, however, of the antelope and lions that almost invariably figure on the latter seals, we find on the seals of both Mohenjo-daro and Harappā the unicorn, the rhinoceros, the gharial, the short-horned bull, elephant, and tiger.

Prism sealings.

The seal impressions on triangular and other prisms are especially interesting as nothing at all similar has been found in Babylonia or Elam. The nearest approach is a triangular seal with figures on all three sides, which was found in the south Kurgan at Anau, and dated to Culture III. Three-sided scals are, of course, well known in Crete and Cappadocia.²

COPPER TABLETS

Curious flat pieces of copper, either rectangular or square in shape, have been found in

most parts of the Mohenjo-daro site, chiefly belonging to the Later Periods.

Sizes.

The rectangular pieces are of various sizes, ranging from 1.2 by 0.5 in. to 1.5 by 1.0 in. The square pieces, which are rarer, average 0.92 by 0.92 in. in size. These tablets vary greatly in thickness, from 0.07 in. to 0.12 in. One especially substantial tablet (HR 4799) measures 0.85 in. square by 0.23 in. thick.

Owing to the salty nature of the soil of Mohenjo-daro, a large number of these copper tablets are in bad condition, and it has been found impossible, even after cleaning, to make

out the animals or the signs upon some of them.

Incised designs.

On most of the tablets there is the figure of an animal on one side, and on the other three or more signs forming an inscription. The figures and signs were in every case carefully cut with a burin, but, except in a few cases, corrosion has entirely filled up the incisions with cuprous oxide, making the figures and inscriptions only legible in a reflected light. For this reason none of the tablets could be satisfactorily photographed and only a selected few were sufficiently clear to be drawn. The best preserved are illustrated in Pls. CXVII and CXVIII.

Finish.

The majority of the tablets are well made, and all seem to have been cast first and hammered smooth afterwards. In some cases they were trimmed remarkably true, with smooth faces, sides, and ends. In other cases they are rough and jagged at one end, which suggests that they were snapped off from a longer piece. In rare instances the ends are slightly rounded.

Classification.

The tablets fall into two classes :-

- (a) Those with an animal or human figure on one side and an inscription on the other.
- (b) Those with an inscription on each side.

Class (a) are the more numerous and, moreover, are usually of rougher make.

Out of a total number of eighty copper tablets found, forty-seven belong to class (a) and nine to class (b). Twenty-four tablets are more or less illegible, but there is certainly an inscription on one side, whatever the other side may contain.

¹ Pumpelly, Explorations in Turkestan, vol. i, p. 169, No. 400.

² Evans, Palace of Minos, vol. i, pp. 68-9. They are found as early as F.M. I. In shape they resemble the prisms from Mohenjo-daro, but it must be noted that the latter are in every case unrerforated and are sealings, not seals.

The animals on the tablets always face to the right, except the antelopes, which are represented as looking backwards over their shoulders.

Below is a list of the animals on the legible tablets with the numbers found, up to the List of animals.

present, of each :-

			Exan	aples.
Elephant				6
Antelope				5
Hare .				5
Rhinoceros				4
Buffalo (?)				4
Short-horned	bull			4
Human figure	е .			3
Goat .				2°
Brahmani bul	1			2
Tiger .				2
Two-headed	anima	1		2
Composite an	imal			ſ
Monkey (?)				I

The animals with long tails and curly horns have been provisionally classed with The three tablets with human figures are similar to that illustrated in Pl. CXVII, 16. One tablet seems to bear the figure of a monkey, but this was too indistinct to be drawn. The above list shows that most of the animals that appear on the seals are also represented on the copper tablets. There are, however, several additional animals, viz. the hare, a double-headed animal, and the monkey, if indeed the last is what it seems to be.

The addition of the hare is somewhat surprising, as most of the animals are large and Hare. powerful, and therefore the more likely to have developed into divinities. The addition of the hare, however, suggests that, as in ancient Egypt, the lesser animals also were objects

The hare is always drawn in a crouching attitude with a small tuft of grass in front of it, as if it were feeding (Pl. CXVII, 5 and 6). The hare is not worshipped 1 in India to-day, but it is one of the animals into which Buddha entered in one of his previous existences. One of the black spots in the moon is termed a hare in India and China, although the animal is not associated with lunar worship. No. 6 was found in Block 2, Section C, DK Area. Level, 6 feet.

There is a composite animal on one tablet only (VS 3590). It has the hind-quarters Composite of a rhinoceros and the fore-quarters of a leopard or tiger. It also has the unicorn's horn, animal. and a manger stands before it (Pl. CXVIII, 2).

A very curious animal on two of the tablets appears to have the body of an antelope with a head at either end. The fact that more than one example has been found of this animal proves that it is not a vagary of the engraver (Pl. CXVII, 3).

The tablet bearing the figure of a man dressed in what seems to be a costume of leaves Hunter. is exceptionally interesting (Pl. CXVII, 16). He is apparently a hunter armed with a bow and arrow, and he is clearly thus attired to enable him to get close to his quarry.2 Another tablet (E 2215), which is, unfortunately, in a very bad state of preservation, bears the same

> 1 Cf. p. 71 supra.—[ED.] ² The horns on his head indicate that he is a divine hunter. See supra, p. 67.—[ED.]

design, but it is not certain whether the garment here is of leaves. The first tablet was unearthed from Room 1, House XVIII, VS Area, and the second comes from 3 feet below the surface in Trial Trench E, DK Area.

Monkey.

As stated above, there appears to be a monkey on one of the tablets, but the latter is in such a bad condition that the question of the animal represented must be regarded as uncertain. The monkey, however, is represented in several models in faience, pottery, and paste (Pl. XCVI, 11, 12, and 13).

Antelope.

The antelope appears on five of the tablets, represented in a typical attitude with his head turned to look behind him (Pl. CXVII, 1 and 2; Pl. CXVIII, 1). This attitude is very common in Elamitic art, 1 especially on the pottery and seals. The position is also well known on both the archaic seals and pottery of Mesopotamia.

Elephant.

For the present, the elephant appears to take first place amongst the animals on these copper tablets. An excellent example is seen in Pl. CXVII, 11, of which the original was found at a depth of 1 foot below the surface in House XXVI, VS Area. Figures of the elephant are always roughly executed, unlike the careful carvings on the steatite seals, even though there mistakes were sometimes made in their portrayal.

Bull.

The short-horned bull is rarely depicted on these tablets, but one particularly good example is shown in Pl. CXVII, 13. This tablet was unearthed from Chamber 22, Block 4, of the L Area, and is dated, like the rest of the tablets, to the Late Period. The humped bull, but with short horns, is pictured on tablet No. 14 in the same plate. This last comes from Structure XXXIX, Block 5, of the HR Area, and was found at a level of 3 feet below the surface of the ground.

Tiger.

The tiger is only twice represented. The best example of this animal is shown in Pl. CXVII, 4. The position of the pictographs above the animal is very unusual for an inscription on these copper tablets. This particular tablet comes from Chamber 27, Block 4, of L Area.

Unknown

The exceptionally powerful-looking animal with long curling horns (Pl. CXVII, 8 and 12, and Pl. CXVIII, 4 and 6), and with a manger placed in front of it, does not appear on any of the seals. The long tail of the animal with a tuft at the end is carried well in the air, as if the creature were about to charge. Tablet 8 in Pl. CXVII was found in Room 107, House XVI, VS Area, and tablet 6, Pl. CXVIII, comes from the pillared hall, Block 4, of the L Area. Tablet No. 12 was recovered from Court 39, House XVII, Block 3, of HR Area.

The rope pattern on the obverse of Tablet No. 5 in Pl. CXVIII is unique at Mohenjo-daro.² This tablet was unearthed from Room 30, House I, VS Area.

Inscriptions and animals.

The fact that all of the tablets bearing the representation of a hare have the same inscription on the obverse (Pl. CXVII, 5 and 6), and that the animals with long curling horns and long tail 3 also bear the same inscription—different, however, from the inscription on the hare tablets (Pl. CXVII, 8 and 12)—suggests that in some cases at least the inscription on the tablet refers in some way to the animal on the tablet. Of three tablets, each with an elephant engraved upon it, all bear the same inscription (Pl. CXVII, 11), and lastly, those

1 Mém. Dél. en Perse, t. xiii, p. 43, figs. 143, 144.

² Compare this pattern with one on an Egyptian vase of predynastic date. Ancient Egypt, 2928, pt. iii, p. 69, fig. 2. Cord designs were frequently used by the early Sumerians on their seals, especially in the archaic period. Oxford Editions of Cunciform Texts, vol. vii, pl. xxix.

³ It is difficult to identify this animal. The Director of the Zoological Survey of India suggests that it may be a buffalo (Bos bubalis). It, however, bears no resemblance to the undoubted buffalo that is represented on three of the steatite scals (Nos. 304-6).

with the figures of antelopes looking backwards over their shoulders all have the same characters on the reverse (Pl. CXVII, 1 and 2; Pl. CXVIII, 1).1

Some, if not all the animals on the copper tablets were possibly dedicated to certain Captive gods. As on some of the seals, we find a manger placed before certain of them, as, for instance, animals. the unicorn, the rhinoceros, antelope, and Brahmani bull. This suggests that these animals were kept in captivity, and, if so, it is likely to have been for religious purposes; a rhinoceros is obviously quite useless for any domestic purpose. A manger is placed before the composite animal on the tablet illustrated in Pl. CXVIII, 2, despite the fact that such an animal could never have existed.2

It would be difficult to use these tablets as seals on account of their being so thin, and not Use of tablets. deeply enough incised. Moreover, none is perforated for threading on a cord. They were probably used as amulets, wrapped up in some material and worn round the neck or wrist, or sewn to the clothing. This would account for the rough finish of some of them, for if worn in this way they would not have been exposed to view. It is possible that the possession of one of these amulets placed the wearer under the especial protection of the deity whose particular animal was engraved upon it. On the other hand, the animals may not have been regarded as sacred, but simply as possessed of a special attribute of which the wearer hoped to avail himself. For example, the hare has the quality of great speed, and the wearer of a copper tablet with a figure of this animal upon it perhaps thought himself more speedy for that reason. Even at the present day in India, mothers who think their children lack certain qualities provide them with amulets to overcome the defect, and these amulets are frequently worn through life. On the whole, however, it seems more probable that the animals on the copper tablets were definitely symbols of certain deities, and that the wearers of these emblems wished for the patronage of the particular deity symbolized thereon.

¹ The second sign in the tablet illustrated on Pl. CXVII, 2, may possibly be incorrect. The artist had great difficulty in making out the signs on this particular object.

² Unless this badly drawn animal is meant to be a rhinoceros!

7	1	T		terials :	and			-	7	0	Ma	terials Colour		
Size in Inches.	Level below Surface.	Туре.	Steatite.	Faience.	Pottery.	Site and Serial No.	Plate No.	Size in Inches.	Level below Surface.	Туре.	Steaute.	Faience.	Pottery.	Site and Serial No.
	4 2 2 3 7 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	B. B	Wh.			HR 4161 E 1187 VS 823 HR 582 HR 3336 HR 164 HR 743 C 1895 HR 4601 C 194 C 187 C 187 C 187 C 187 C 187 C 187 C 188	71 72 73 74 75 76 77 78 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 96 97 98 99 100 101 102 103 104 105 106 107 108 109 110 111 112 113 114 115 116 117 118 119 120 121 122 123 124 125 126 127 138 139 130 131 131 132 133 134 135 136 137 138 139 130 131 132 133 134 135 136 137 138 139 130 131 131 132 133 134 135 136 137 138 139 130 131 131 132 133 134 135 136 137 138 139 130 131 131 131 131 132 133 134 135 136 137 138 139 130 131 131 131 131 131 131 131	1.15 × 1.15 1.1 × 1.1 1.1 × 1.1 1.1 × 1.1 1.1 × 1.1 1.1 × 1.1 1.1 × 1.1 1.1 × 1.1 1.1 × 1.1 1.1 × 1.1 1.2 × 1.25 1.2 × 1.25 1.2 × 1.25 1.3 × 1.3 1.15 × 1.15 1.0 × 1.0 1.2 × 1.25 1.2 × 1.25 1.2 × 1.25 1.3 × 1.3 1.15 × 1.15 1.3 × 1.3 1.25 × 1.25	1' II" 3' 0" 0" 0" 0" 0" 0" 0" 0" 0" 0" 0" 0" 0"	B.B.B.B.B.B.B.B.B.B.B.B.B.B.B.B.B.B.B.	Wh.			BJ

	1			10 - 100 ADMINISTRA	erials and)				⁹ Ma	terials	and	0 ,
Plate No.	Size in Inches.	Level below Surface.	Туре.			Fortery.	Site and Serial No.	Plate No.	Size in Inches.	Level below Surface.	Туре.	Steatite.			Sites and Serial No.
141 142 143 144 145 146 147 148 149 150 157 158 159 160 161 162 163 164 165 167 171 173 174 175 177 178 179 180 181 182 183 184 185 186	in Inches. 1.0 × 1.5 1.35 × 1.35 0.8 × 0.8 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.8 × 0.85 0.8 × 0.85 0.8 × 0.85 0.9 × 0.9 0.8 × 0.85 1.15 × 0.35 0.9 × 0.9 0.85 × 0.85 1.15 × 0.35 0.9 × 0.9 0.85 × 0.85 1.15 × 0.95 0.9 × 0.9 0.85 × 0.95 1.05 × 1.0 0.95 × 0.95 0.9 × 0.95 1.05 × 1.0 0.95 × 0.95 0.9 × 0.95 1.05 × 1.0 0.95 × 0.95 0.9 × 0.95 1.05 × 1.0 0.95 × 0.95 0.9 × 0.95 1.10 × 1.10 0.10 × 1.10 1.10 × 1.10 1.10 × 1.10 1.10 × 1.10 1.10 × 1.10 1.10 × 1.10 1.10 × 1.10 1.10 × 1.10 1.10 × 1.10 1.10 × 1.10 1.10 × 1.10 1.10 × 1.10 1.10 × 1.10 1.10 × 1.10 1.10 × 1.10	below Surface. 5' 6" 6' 0" 2' 6" 2' 6" 2' 6" 3' 1" 3' 6"	B. B	Wh.	Cologr. •	3.	Serial No. HR 1950 DK 3054 HR 4057 HR 5076 DK 2971 E 845 DK 221 VS 1961 HR 4384 C 3155 HR 5995 HR 5995 HR 5995 HR 2522 VS 1666 DM 50 E 1809 HR 4291 VS 3389 HR 398 C 206 HR 4635 HR 5311 HR 3791 C 810 E 2053 HR 5703 VS 2372 HR 4994 HR 3277 VS 1558 E 96 VS 2541 E 1521 SD 1553 C 3133 SD 1731 C 2394 HR 4873 E 2006 E 1008	211 212 213 214 215 216 217 218 219 220 221 222 223 224 225 226 227 228 229 230 231 232 233 234 235 237 238 239 240 241 242 243 245 246 247 248 249 250 251 261 261 261 261 261 261 261 261 261 26	in Inches. • 1.0 × 0.6 0.7 × 0.7 0.8 × 0.85 0.85 × 0.85 0.85 × 0.85 0.85 × 0.85 0.85 × 0.85 0.85 × 0.85 0.85 × 0.85 0.85 × 0.85 0.85 × 0.85 0.85 × 0.85 0.85 × 0.85 0.85 × 0.85 0.85 × 0.85 0.85 × 0.85 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.9 × 0.9 0.85 × 0.85 0.95 × 0.95 0.85 × 0.85 0.95 × 0.95 0.85 × 0.85 0.95 × 0.95 0.85 × 0.85 0.95 × 0.95 0.85 × 0.95 0.95 × 0.95	below Surface. 2' 0" 2' 0" 2' 0" 2' 6" 0" 2' 6" 0" 3' 6" 0" 0" 1' 6" 0" 1' 0" 3' 6" 0" 0" 1' 0" 3' 0" 0" 0" 1' 0" 0" 3' 0" 0" 0" 0" 0" 0" 0" 0" 0" 0" 0" 0" 0"	B. B	Whi. W.			Sites and Serial No. HR 4585 C 2692 HR 5594 HR 5057 E 1154 HR 5057 E 1154 HR 5789 DK 1519 E 653 HR 6098 HR 5656 HR 1955 VS 2262 HR 4872 L 323 HR 4436 DK 1892 DK 1861 HR 3792 HR 1365 HR 5516 HR 1673 HR 3792 HR 4386 HR 5648 L VS 505 BJ R 5310 HR 3595 BJ C 2327 VS 2582 HR 5699 HR 2596 HR 4492 DK 160 HR 3010 HR 4112
186 187 188 189 190 191 192 193 194 195 196 197 198 200 201 202 203 204	1.15 × 1.15 1.05 × 1.15 1.05 × 1.05 0.95 × 0.95 1.0 × 1.05 	3' 0" 3' 0" 3' 0" 3' 0" 3' 0" 6" 3' 0" 6" 2' 0" 6" 2' 6" 4' 0" 4' 6" 4' 6"	B. B	Wh. Bl. Wh. Wh. Wh. Wh. Wh. Wh. Wh. Wh. Wh. Wh			E 2217 HR 4519 C 2023 C 3024 VS 235 VS 272 DK 744 C 2114 HR 4622 DK 925 C 3202 E 1912 C 2863 HR 1451 HR 4400 HR 5607 HR 5261 C 435	257 258 259 260 261 262 263 264 265 266 267 268 269 270 271 272 273 274	0.4 × 1 0.8 × 0.8 0.85 × 0.85 1 × 0.85 1 × 0.85 1.0 × 0.3 0.65 × 0.65 0.5 × 0.65 0.6 × 0.6 0.5 × 0.5 0.6 × 0.6 0.6 × 0.6 0.5 × 0.5 0.6 × 0.6 0.6 × 0.6 0.6 × 0.6 0.6 × 0.6	7' 0" 0" 3" 5' 0"	B. B	Wh.			HR 5772 HR 5251 DK 2027 DK 91 E 268 C 3201 HR 2912 L 661 E 2484 HR 4409 E 2094 C 162 B 650 C 2372 B 434 L 316 DK 2294 C 1863
205 206 207 208 209 210	0.85 × 0.85 0.85 × 0.85 0.75 × 0.75 0.9 × 0.9 0.95 × }	4' 3" 4' 0" 3' 0" 4' 0" 4' 6"	B. B. B. B.	Wh. Wh. Wh. Wh.		-	D 289 HR 5596 HR 4124 HR 5597 VS 3359 BJ 10	275 276 277 278 279 280	0.6 × 0.2 0.6 × 0.6, 0.55 × 0.55 0.65 × 0.70	3' 0" 1' 0" 9' 0" 2' 0" 4' 0"	B. B. C. B. B. B.	Wh. Wh. Wh. Wh. Wh.			L 899 HR 4244 E 250 VS 2518? DK 1510 HR 5589

-		,	-	1			1	-			9			. 0	
		0			terials Colour.			·					terials Colour.	and	
Plrte No.	in Inches.	Level below Surface.	Type.	Steatite.	Faience.	Pottery.	Site and Serial No.	Plate No.	Size in Inches.	Level below Surface.	Туре.	Steatite.	Faience.	Pottery.	Site and Serial No.
308 309 310 311 312 313 314 315 316 317 318 319 319 320 321 322 323 324 325 326 327 328 329 330 331 332 332 333 334 335 337 338 339 330 331 331 332 332 333 334 335 336 337 338 339 330 330 331 331 332 332 333 334 335 336 337 338 339 330 330 330 330 331 331 331 331	0.8 × ? 0.75 × 0.25 0.75 × 0.25 0.75 × 0.75 0.77 × 0.77 0.77 × 0.77 0.75 × 0.75 0.75 × 0.75 0.75 × 0.75 0.75 × 0.75 0.75 × 0.75 0.75 × 0.75 0.75 × 0.75 0.75 × 0.75 1.1 × 1.1 0.7 × 0.7 0.75 × 0.75 1.1 × 1.1 0.7 × 0.7 0.75 × 0.75 1.1 × 1.1 0.7 × 0.7 0.75 × 0.75 1.1 × 1.1 0.7 × 0.7 0.75 × 0.75 1.1 × 1.1 0.7 × 0.7 0.75 × 0.75 1.1 × 1.1 0.7 × 0.7 0.75 × 0.75 1.1 × 1.1 1.15 × 0.35 1.2 × ? 1.1 × 1.1 1.15 × 0.35 1.2 × ? 1.1 × 1.1 1.15 × 0.35 1.2 × ? 1.1 × 1.1 1.15 × 0.35 1.2 × ? 1.1 × 1.1 1.1 × 1.	3 5 2 5 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	B. B	Wh.			E C HR 4054 HR 4035 HR 6066 HR 1793 HR 4364 HR 4387 HR 4364 HR 5949 HR 1793 HR 4364 HR 4387 HR 4364 HR 5949 HR 1793 HR 4364 HR 4387 HR 4364 HR 5949 HR 1793 HR	351 352 353 354 355 356 367 368 369 370 371 373 374 375 376 377 378 380 381 382 383 384 385 386 387 378 389 390 391 392 393 394 405 406 407 407 408 409 407 407 408 409 409 409 409 409 409 409 409	1.0 × 1.0 1.0 × 2 0.75 × 0.8 1.05 × 1.05 0.9 × 0.9 1.6 × 1.6 1.2 × 1.2 0.65 × 0.35 0.55 × 0.55 1.2 × 1.2 0.55 × 1.1 0.8 × 0.8 0.75 × 0.75 0.30 × 1.2 1.15 × 1.15 0.45 × 1.3 1.3 × 1.3 1.3 × 1.2 1.5 × 1.15 0.95 × 0.95 1.15 × 1.15 0.95 × 0.95 1.15 × 1.15 1.15 × 0.65 1.15 × 0.65 1.15 × 0.65 1.15 × 0.65 1.15 × 0.65 1.15 × 0.65 1.15 × 0.65 1.15 × 0.65 1.15 × 0.65 1.15 × 0.65 1.15 × 0.65 1.15 × 0.65 1.15 × 0.65 1.15 × 0.65 1.15 × 0.65 1.15 × 0.65 1.15 × 0.65 1.15 × 0.65 1.15 × 0.65 1.15 × 0.45 0.7 × 0.45 0.7 × 0.45 0.7 × 0.45 0.95 × 0.45 0.95 × 0.45 0.95 × 0.45	5' 6" 0" 0" 0" 0" 0" 0" 0" 0" 0" 0" 0" 0" 0"	B. B	Wh.			C 427 HR 4469 D 392 L 860 DK 2869 L 323 VS 1574 DK 797 C 310 D 417 DK 2340 E 1651 D 104 VS 2876 HR 1965 HR 4055 VS 3450 C 675 C 353 HR 5611 C 2053 HR 1696 HR 5972 HR 4355 VS 1816 HR 4212E E 1277 HR 2596 HR 4952 VS 1753 L 384 E 1886 E 1432 SD 2172 C 2896 B 63 VS 3094 D 171 DM 72 C 2896 B 63 VS 3094 D 171 DM 72 C 51 VS 2049 HR 3130 C 3158 VS 1190 HR 5676 VS 3227 C 1814 BJ 9 HR 3005 HR 2023 HR 6187 D 262 VS 3546 HR 1050 DK 1398 VS 1681 D 288 E 2039

No.		0	9	. Ma	terials Colour			0				Materials and Colour.			
Plate N	Size in Inches.	Level below Surface.	Туре.	Steatite.	Faience.	Pottery.	Site and Serial No.	Plate N	Size in Inches.	Level below Surface.	Туре.	Steatite.	Faience.	Pottery.	Site and Serial No.
474 475 476 477 478 479 480 481 482 483 484 485	1.45 × 0.45 0.95 × 0.45 1.2 × 0.4 0.95 × 0.8 1.55 × 0.4 1.65 × 0.6 1.15 × 0.4 1.65 × 0.7 1.2 × 0.75 1.3 × 0.55 1.2 × 0.75 1.3 × 0.55 1.3 × 0.55 1.3 × 0.55 1.3 × 0.55 1.5 × 0.45 1.3 × 0.55 1.5 × 0.45 1.5 × 0.45 1.5 × 0.65 1.5 × 0.65	36'15'6'2'4'3'9'6'1'4'2'5'3'3'1'8'5'5'3'1'2'5'3'6'1'6''3'3''5'6''3''3''8'5'5'3''1'2'5'3''8'5'5''3''8'5'5''3''8''5''5''8''5''8''5''8''5''8''8''8''8'		Wh.			VS 1082 HR 6210 C 2056 D 207 HR 2780 HR 1574 DK 2732 VS 1681 E 2475 HR 1121 HR 5260 HR 4125 VS 1694 A 148 HR 5264 HR 3732 HR 4434 VS 3454 C 1095 DK 1638 A 148 HR 5248 HR 3732 HR 4434 VS 3454 C 554 C 656 VS 2289 HR 6177 DK 597 C 8860 VS 2289 HR 6177 DK 597 C VS 880 VS 2289 HR 4373 C VS 3553 SD 1962 VS 208 VS 2846 HR 4373 C VS 3553 VS 208 VS 2846 HR 4291 HR 4373 C VS 3553 HR 4109 VS 208 VS 2846 HR 4291 HR 2240 HR 3767 VS 953 HR 4109 VS 208 VS 2846 HR 4285 HR 4285 HR 3689 HR 4237 HR 2240 HR 2237 HR 4394 HR 4394 HR 4394 HR 2939	527 528		2' 6' 6' 6' 6' 6' 6' 6' 6' 6' 6' 6' 6' 6'	B. B. F. B. E.	Wh. Wh. Br. Bl. Wh. Wh. Wh. Wh. Wh. Wh. Wh. Wh. Wh. Wh		4	E 894 DK 595 VS 880 DK 844 DK 595 VS 880 DK 2363 DK 2363 D 234 HR 5572 L 209 HR 5593 DM 7 HR 6147 HR 4503 HR 6163 HR 5628 HR 5657 E 1723 VS 1960 HR 1989 HR 6207 VS 1278 DK 1298 VS 928 B DK 1278 DK 1298 VS 958 DK 1278 DK 1298 VS 958 DK 1543 VS 955

CHAPTER XXII

SIGN-LIST OF EARLY INDUS SCRIPT

1. SOME EXTERNAL FEATURES OF THE WRITING

[From p. 406 to p. 411 this chapter expresses the joint views of Messrs. Smith and Gadd. From the bottom of p. 411 to p. 414 it expresses the views of Mr. Gadd only, and from p. 415 to p, 422 those of Mr. Smith.]

HE accompanying list of signs used in the inscriptions upon seals found at Harappa and Mohenjo-daro is offered for the use of those who may in the future devote themselves to the study of this writing. It is published as a contribution, indeed, to that study, but rather as a tool ready to the hand of scholars when time may have brought the possibility of further achievement, than as a finished production in itself. For the aim of such study must naturally be the decipherment of this script, and it is proper, therefore, to state at the outset that we have not succeeded in reading anything of it; there was, in fact, very little hope, in the complete absence of any kind of clues which might lead to some trustworthy inference. Hope for the future most probably rests in Mesopotamia. It is known for certain that seals and sealings of this class were carried thither by trade from the Indus valley in ancient times,1 and one such seal has already been found (at Ur) with a cuneiform in place of an "Indus" inscription,2 There is consequently reason to hope that some day a bilingual record may be discovered, and very few data of this kind would probably suffice to reveal the secret. Meanwhile, all that can be done is to prepare the material to which the

solvent may ultimately be applied.

Indus seals found in

Mesopotamia:

Script not

deciphered.

Difficulty in

Even for the modest purpose indicated we are sensible that the list we have compiled is far from perfect. Its faults arise partly from the inherent difficulty of classifying signs classifying signs. simply by their outward appearance, but partly, too, from the nature of the copies which we have used. These have been photographs, showing sometimes the original seals, sometimes the impressions, and hence the order of the signs may now and then have been unintentionally reversed; if this has occurred, however, the attentive student, once familiar with the writing, will probably detect and allow for it. A more serious defect will doubtless be found in the making of distinctions between signs which are differently drawn in certain instances but are actually identical, or, conversely, in the neglecting of actual distinctions between signs which are very similar in appearance. As an example of the first, CCXLII and CCXLIV may be quoted (these two are probably not different), and of the second, the number of "barbs" on signs of the class CCLXIV may sometimes have been incorrectly given, and here a real distinction may have been observed—though it is perhaps not very likely. Faults of this

² Mr. C. L. Woolley in Antiquaries' Journal, 1928, p. 26 and pl. xi, 2.

¹ They have been recovered from at least four sites, the ancient cities of Kish, Lagash, Umma, and Susa; see the article by Mr. E. Mackay in Journal of the Royal Asiatic Society, 1925, pp. 697 f. and pl. x, and also that of M. Thureau-Dangin in Revue d'Assyriologie, xxii, 99 for another specimen and further references.

kind arise, of course, from the first-mentioned difficulty, that of dealing with a script purely from outward appearance, without knowledge wherewith to control eye and hand.

The form and material of the seals, their archæological character and context, will be Device and found fully described in the preceding chapter; preliminary accounts of them have already legend been given in periodicals. All that need be said here is that there seems to be no direct unconnected. connection between the device engraved upon the seal (usually an animal) and the inscription, the same animal being found in company with completely different inscriptions. The devices

may be presumed to have religious significance, and perhaps some amuletic value.

As concerning the signs themselves, the number listed here is 396, which must be considered only a very approximate measure of the signary of this writing, both because the material is still, no doubt, far from complete, and because of the slight uncertainty of distinction mentioned above, but also because of the great resources of modification and combination of signs which this writing possessed, the extent and ingenuity of which is perhaps its most striking feature. The signs are pictographs, as in all other early scripts. They are Signs are carefully drawn as faithful representations of their originals in all cases where the original pictographs. can be identified, and the same may therefore be presumed of the much more numerous cases where the original is doubtful. That is to say, the writing remains in what may be called, on Egyptian analogy, the hieroglyphic state; it has not degenerated nor been worn down by use, to conventional summaries like the Egyptian hieratic, the Babylonian cuneiform, or the Chinese writing. This is certainly due in great part to the material upon which these inscriptions are found, since pictographs always preserve their form best when they have to be sculptured on stone, but tend to lose it when they are employed cursively on soft substances like clay, papyrus, or parchment. Whether the Indus people wrote upon more perishable materials, and what form the signs then assumed, there is nothing to show, but the scratched characters found upon potsherds and copper utensils suggest a more extended usage.

Clearly as the signs are drawn it is a remarkable fact that few can be identified. This Objects difficulty is familiar in other early scripts also, but it is generally due rather to imperfect imperfectly representation than to actual uncertainty of the object intended; this applies particularly to represented. the archaic Sumerian signs, which, while often suggesting the original, very seldom portray it unmistakably, and often seem very doubtful representations of the objects which their known meanings presumably indicate. Among the Egyptian hieroglyphs only a few still resist identification. No doubt further study of this "Indus" writing will reveal more of the objects represented, but at present the list is surprisingly short. The following are some additions or alternations to the very tentative proposals made by us in the Illustrated London News of 4th October, 1924, p. 614.

Numbers.		Possible Identification.
I to XVIII		Strokes, representing numbers.
CCCL XIX to CCCXCVI		Men in various attitudes.
CCCLXX		Man standing.
CCCLXIX		Man raising arms.
CCCLXXVII		Man with staff.
CCCLXXVIII	•	Man with bow and arrow (or, more probably,
		defending himself with a shield), in any case,
		a warrior.
CCCXCVI		Man with staff raised.
CCCLXXIX f.		Man holding up three or five fingers.
CCCLXXXV		Man holding yoke (possibly abbreviation of the
		following picture).

Possible Identification

1	Numbers.	(Possible Identification.
CCCLXXXVI .			. 0		Man carrying on a yoke two water-skins (ligature of above and No. CLIX).
CCCLXXXVII .					
CCCXXXI to CCCL	1				Fish, with various additions and insertions.
CCLV ff					Hand, with different numbers of fingers outstretched.
CCLXI					Hands (?), indicating the number 13 (?)
CCCLI ff. A .					Birds and animals; among which CCCLXIV seems
					to be a drake, and CCCLIX a bat.
ECLI f., CCCLXVI f.,	and perhaps	CCX	XXVI	III	Plants.
CXXXV ff					Mountains (?)
LXV					Heart (?)
CLIX					Spear.
CCCXIX					Chair,
CCCXXII					Table.
CCCXXIX					Parasol (cf. CCCLXXIII).
CCLXXXIII					Road.
CCXLVII ff					Foot.
LII ff					Insects.

Parts of human body.

"Fish" signs

Indus signs compared with Sumerian.

doubtful.

Apart from the apparent numbers, which will be considered later, there are a few remarks to be made on the foregoing list. It is rather noticeable that, whereas men in various attitudes are well represented, there are few parts of the body among the signs; seemingly the only exceptions are the hand and foot, if, indeed, Nos. CCLV, CCXLVII are correctly so interpreced. Among the "man" signs No. CCCXCVI gains certainty from the object published in Times of India, 22nd January, 1928,1 which shows on a larger scale a man standing in exactly the position which the sign depicts in miniature. That Nos. CCCLXXIX f. really indicate a number of fingers held up is suggested by the circumstance that they follow, in the inscriptions, three and five strokes respectively. The pictures of the man carrying the yoke, and the two water-skins or sacks hanging from it look quite unmistakable, and equally clear seems the nature of the composite signs CCCLXXXVI f., particularly as these occur in positions where CLIX and CCXXXVIII are expected. The suggested "fish" signs are more puzzling, since the modifications to which the original (?) CCCXXXI is subjected are not particularly natural as indicating different kinds of fish, and it is by no means certain that a fish is intended at all, but the comparison suggests itself at once, and it is hard to find a better. That CCLV and the like represent the hand with different numbers of fingers extended must be considered a very doubtful possibility, since there are instances in which more than five digits are shown, although, on the contrary, there is the very suggestive case of the man (No. CCCLXXX) who seems to hold up five fingers while he stands next to five strokes, and these "fingers" with his forearm, have much the appearance of the "hand" signs. In the Illustrated London News (loc. cit.) we formerly proposed a comparison between these "hands" and the archaic Sumerian form of gal; outwardly, this is still striking, but if the "Indus" sign really represents a hand this comparison would have to be abandoned, since, although the original of the Sumerian sign is uncertain, there is no reason to connect it with the hand. The elaborate character No. CCLXI is perhaps to be explained as the fingers of one hand twice outspread, and three of the other hand held up, the whole indicating the idea of "thirteen". Instructive comparisons with this sign are Nos. CCLX and CCXXXII, but

1 Cf., Pl. CXXXII, 10.

whether favourable to the "hand" supposition or not it is not easy to decide. The birds Birds and and animals are more obvious, but it is impossible to be more precise as to their kinds save in animals the cases of the drake and the bat. Nearly all of the plants must be pronounced doubtful, identified. though No. CCLII seems a clear instance; it would be something if No. CCXXXVIII, by Representations far the commonest sign of all, could be identified as a plant, but actually it is very questionable. of plants "Mountains" are simply an analogy from the Sumerian sign kur; the analogy is perhaps doubtful. quite illusory. The same remark applies to No. CCLXXXIII "(cross) road", and to No. LXV "heart", especially to the latter, which has further modifications tending to show that the "heart" form is merely an oval with one segment (instead of four) cut out from it. Other objects. Finally, the "table", "spear", and "parasol" have to rely only upon their outward form, though the last is seen over the head of a man in No. CCCLXXIII. Doubtless several more suggestions will occur to any user of this list; we have confined ourselves to such as seemed most obvious to a purely outward view.

The extensive use which this writing makes of modification and combination of signs has already been mentioned and it is, indeed, one of its most striking peculiarities. While it is difficult to give any conspectus of the modifications, a rough principle at least may be observed by dividing them into "additions" and "enclosures". By the first we mean the Modifications small strokes, generally vertical, and standing beside the top of the sign modified, but some of signs. times also oblique, in which case they are contained within the sign (as indeed are the vertical Strokes in a few cases). "Enclosures" are signs which stand in the midst of a varying number, usually of vertical strokes, but occasionally within a kind of parenthesis. Groups of this latter kind are, naturally, of rather similar composition to the combined signs, and the distinction between the two is based principally on the use of simple strokes (nearly always) in the "enclosures", whereas the combined signs are coalitions of two entirely different individuals. The "additions" are:—

"Enclosures" are constituted by the following:-

The principal combinations are given in the following table:-

Combined Sign.

CXLIX. CL.

XLVIII in a number of combinations.

LXXVIII f.

CXXIV f.

CCCLXXIX f.

CCCLXXXVI f.

CCCLXX in a number of combinations.

LXXIII and CCXXXII.

LXXIII and CLII.

XLVIII and CCLXXXIII.

CXII and CCXXXII. CCCLXX and CCLV f.

CCCLXXXVI with CLIX and CCXXXVIII.

CCXXXII and CCLX.

Next to the signs themselves the direction in which the writing runs is to be considered. First, however, it must be repeated, as M. Thureau-Dangin has already observed, that the impression produced by the seal, not the seal itself, gives the true order of the inscription. Direction of This may be shown best by turning from the seals (upon which, of course, most of the Writing. inscriptions occur) to the other objects, pottery or metal, upon which signs have been scratched; for there the legend is naturally to be read as it is written. A pottery fragment from Harappa,

¹ Revue d'Assyriologie, xxii, p. 100.

Position of Signs.

Clay, labels on bales.

Signs face to the right and left.

No. 2779, is inscribed with two completely preserved signs, the one on the spectator's left being No. XCIX of our list; in the pot-inscription, the opening of this sign faces to the right. As an example of the same sign upon a seal we may quote the inscription given as No. LXXIV, H. 40, in the list. Here it is found in the second place from the right, and with the opening again facing to the right. But the inscription as there copied is from an impression of the seal; a photograph now before us of the seal itself naturally shows this sign with its opening towards the left. But since the pot-inscription gives the signs in the position in which they were meant to be read, it follows that the sign in question is properly placed with its opening facing to the right; that is, the impression, not the seal, presents the inscription in its true form. An exactly similar experiment can be made with the copper dagger-blade from Harappa, No. 2777. Here also the inscription is obviously meant to be read directly, and the sign furthest to the spectator's right is No. XXXI, with its "loop" on the left. Now this sign is found also upon the seals, of which No. XXXI (H 31) may be taken as an example. A photograph of this seal (not its impression) shows, as before, the sign reversed, i.e. with its "loop" on the right; hence again the impression gives the correct form, not the seal. There is no need to multiply examples, since these two suffice for proof, and indeed the proposition that seals are made for the purpose of reproducing a device, not to be looked at theinselves, flows so directly from the nature of seals, and is so supported by all analogies that it might seem almost self-evident. However, it can be formally established in the present case, as shown above. Perhaps also it may be well to mention that at least one ancient impression of an Indus seal has already been published,1 showing that these marks were affixed to clay labels upon bales of goods, in precisely the same way as the Babylonian seals were rolled over the clay "dockets", or the Egyptian seals impressed upon the clay stoppers of wine-jars.

The correct way of looking at the inscriptions having been settled it remains to take up the original question—in which direction does the writing run? An answer which we believe to be right, though based on quite insufficient evidence, has already been given by M. Thureau-Dangin 2: "les inscriptions sont à lire de droite à gauche, comme le montre l'un des signes du no. XV, représentant un oiseau de profil à droite." The number referred to is No. CCCLXIV of our list, and it is true that in the impression of this seal the bird enclosed in a ring (it seems to be somewhat carefully marked as a drake) faces to the right. It is, of course, a well-known rule of the Egyptian hieroglyphs that the inscription is read from the side to which the figures face. But it is easy to show that this is no safe indication for the "Indus" writing; for while most of the "men" signs face to the right (cf. Nos. CCCLXXIV to CCCLXXX in the list), there are several birds and animals (cf. Nos. CCCLIV to CCCLVIII) which face to the left! Some other criterion must therefore be sought, but is not altogether easy to find. First it will be noticed that in nearly all cases the bull or other animal which forms the main subject of the seal faces to the right, and there is consequently a presumption that the inscription begins from its head. There is, nevertheless, at least one exception to this stance of the animal, for in the impression of the Seal No. 341 a rhinoceros faces to the left. This may be an inadvertence, but it s u ces to warn us against relying too much on the usual position of the animal as indicating the beginning of the inscription. Another small indication may be found in the usual manner of writing the sign composed of seven strokes (|||) in which the lower three are nearly always placed level with the right end of the upper four. A very significant example, too, is a seal

¹ By Father Scheil in Revue d'Assyriologie, xxii, p. 56.

² Ibid., p. 100.

from Harappa (No. 5629) which makes it evident that the engraver has been cramped for space, and that in consequence not only were his signs closely bunched together, but the ., space remaining on the left side was not sufficient to take another sign, which has therefore been dropped below the line. The inference that the inscription began from the right is almost irresistible. But there is a final instance which puts this conclusion boyond doubt. The seal H 173 found in the excavations of 1926-7, is peculiar in having no animal device, but a long inscription which occupies two whole sides of the square and most of the third side. Now (in the impression, of course), this inscription occupies all the top side, all the left side, and most of the bottom, thus , the signs being turned 90 degrees at each corner in such a way that their tops always follow the edges. It is manifest, therefore, that the inscription was read turning the sealing round in the hand, and the position of the second and third sections shows that it was turned over towards the right; in other words, that the reader began from the right of the first and longest section, turned the sealing through 90 degrees, read the second section again from right to left, and similarly the third. Proof Reading from that these inscriptions are to be read from right to left seems herewith complete.1

• Up to this point it has been possible to write with some assurance upon certain outward characteristics of the "Indus" script, but whatever is now added must concern its actual mechanism and reading, and must therefore, in the absence of any advance towards decipherment, be largely speculative. Perhaps, indeed, it would be prudent to stop entirely here, but there are a few observations that may still be advanced, and cannot, at least, do any harm provided the reader be amply cautioned that they are no more than tentative suggestions,

which time may well prove completely erroneous.

First, then, something ought to be said about the possible affinities of this script. Being at that time in possession of very little evidence we once ventured to comment on a few resemblances between certain "Indus" signs and certain archaic signs of the Sumerian syllabary. This hint was on the one hand taken up with exorbitant enthusiasm and regrettable results, on the other rejected with an emphasis which mistook a suggestion for an affirmation. Few resem-We need not dwell upon this longer than to remind the over-rigid that conjecture has its blances most legitimate place where other resources are lacking, and has played a brilliant part in between Indus former decipherments of unknown scripts; nor is it likely to be otherwise here. But, for and Sumerian the question in hand, we shall admit without hesitation that further experience has not tended signs. to confirm our faith in any direct connection between the writing of Sumer and the Indus. The list which we gave could not now be much extended, some of the comparisons are doubtless fortuitous or occasionally far-fetched, and it is not improbable that a similar list could be constructed with the aid of other early scripts, such as the Minoan, which indeed affords some striking analogies. When it is reflected how many totally different scripts are known to have been employed within areas smaller than that which divides the Tigris from the Analogies of Indus, no surprise will be felt that connection in this case cannot be established. Contact Indus and between the two peoples certainly existed; we think even that they shared certain cultural Minoan script. influences, but the presence of common elements in their mode of writing cannot be proved.

What is likely to be the nature of this script? That it is not an alphabet must be obvious from the number of its signs; such a notion cannot seriously be taken into account. • On the other extreme, it can hardly be a pure picture-writing in which every sign represents a word, Script not an since a very short search will reveal groups of signs which frequently appear in the inscriptions alphabet. in different contexts and often with the insertion of one or more varying signs. While no great certainty can be felt about this matter, it remains true that the general impression derived

right to left.

¹ On this subject, see pp. 40 (with footnote) and 427-8.

Signs probably from the study of these inscriptions is that the signs are probably syllabic, with the admixture of some "ideograms", and perhaps determinatives; in short, that the system is perhaps not very much different from that of the cuneiform writing. It would be possible to produce some slight support for this conclusion, but nothing which would amount to substantial evidence, or deserve the trouble of critical examination. The use of determinatives, moreover, is far from certain. Perhaps the most likely examples are those in which a man holds up five or three fingers, standing next to those numbers of strokes respectively, and certain other of the "man" signs may also be of this class.

Inscriptions probably Names and Titles.

The contents of the inscriptions must evidently be a matter of simple conjecture, so long as they are not read, but, in view of their being mostly found upon seals, it must occur immediately to anyone that they include names, very probably of the owners. Many, perhaps, especially of the shorter inscriptions, may be regarded as names alone, but others seem to addequalifications, which may be titles. This is particularly suggested by some of the two-line inscriptions, of which Seal 12 will serve as an example. Here the upper line seems to consist of two words, each ended by the common ending sign CCXXXVIII, while the lower line has only three signs, of a very "ideographic" appearance, headed by one which might well be a determinative. Such a group has a very decided appearance of an appendage to the upper line, and of expressing a qualification or title. Other examples may be found in LXXXIX, 99; VII, 209; CCCXXXI, 321; CCCXXIX; and elsewhere. There is, however, a different hypothesis as to the contents of these inscriptions, which is strongly suggested by several examples, namely, that they are, or at least contain, references to quantities or numbers of objects. Since it is known that these seals were sometimes affixed to bales of cloth and packages of goods, in precisely the same way as the Babylonian seals, such an inscription might be very appropriate; the Babylonian practice was, of course, to inscribe a note of the contents upon the clay "docket" with the ordinary stilus, and to confirm the whole by impression of the seal. Particular instances can be found very favourable to this supposition; they are those in which the number-signs (collections of plain strokes) accompany only one or two other signs, and the whole consequently appears to signify "x objects" (see especially No. CCXIX, which very commonly stands alone with, 2, 3, or 4 strokes, but similar arrangements are found, as may be seen under Nos. I to XVIII). In spite, however, of these very remarkable appearances, there are reasons, both general and particular, which tell strongly against the idea that the inscriptions are concerned mainly with notes of quantity. In general, then, there is a prima facie unlikelihood that a seal should be cut in a permanent material to mark a quantity, since in commerce such quantities must have been multifarious, and thus a separate seal would have been required for each, a most cumbrous contrivance. Further, it is possible to quote the unique seal recently found at Ur (see p. 406 above), the cuneiform inscription upon which, though indistinct, certainly has nothing to do with numbers or quantities. But of more weight than these generalities is the evidence of the inscriptions themselves, i.e. the manner in which the apparent number-signs are involved. First, it should be observed that to extract a numeration-system from these writings seems impossible. Counting strokes, the only numbers found are 1, 2, 3, 4, 5, 6, 7, 8, and 12,1 and even these occur in different sizes and arrangements of unknown significance. Nine, ten, and eleven cannot be identified though there is a possibility that they are denoted by a different kind of signs; thirteen is, it may doubtfully be suggested, system doubtful. represented by No. CCLXI. With so restricted a range of numerals, even admitting the

Numerical

¹ The "treize bâtonnets" mentioned in Revue d'Assyriologie, xxii, p. 101, are composed of the usual 12 and the modifying mark I attached to the preceding sign.

possibility of others not identified, it is hard to believe that a complete numerical-system exists in these inscriptions. Again, very little inspection of the text will reveal examples in which the apparent number occurs near to the beginning, or in the middle of a longish inscription, followed by several signs which have no obvious numerical value. Even if it be assumed that preceding signs are in some way higher "powers" of numbers, there is no such explanation for what follows, and the mere presence of a seemingly numerical sign in a long inscription is insufficient ground for assuming that the inscription conveys a note of quantities. Furthermore, not a few examples are found in which two numerical signs stand side by side, as || || , or || ||, or || || ||, and it is very hard to understand why so peculiar a form is adopted, if they are really numbers. Finally, to conclude the examination of this question, it will be interesting to take two or three individual cases. The first two inscriptions in the list are not uninstructive; the second might be interpreted "two men, one water-bearer", but the first has only the second part of the inscription, with a qualifying sign added. Even so it would still be possible to interpret this as "|----water-bearer", but it is then to be noted that the added sign CCXXXVIII can itself follow "numbers", so that it can hardly have been a mere qualification. Even more difficult is No. H 149, where if both | and | are numbers, the whole must be a plain number, and that incomprehensibly expressed. Also, what should be the difference between U and V or Allill and Allil, all of which are found? Lastly, if the sign XV be consulted, it will be found that this "number" occurs almost exclusively before one or two special signs; there should be no reason for this if the group really denotes the number seven. The general conclusion is that these collections of strokes, though obviously containing a certain number of units, are not here used in a numerical sense, but Strokes most probably with a phonetic value, which is perhaps derived from the native words probably not expressing the respective numbers.

The peculiar and at present (it seems) hopeless difficulty in the way of decipherment is the complete lack of exterior evidence. The finds in the Indus valley have been the first revealers of an Indian civilization of high antiquity, which appears to have left no traditions of itself. What may have been the race and language of this people is a question of pure conjecture. We must end where we began, with the hope that Mesopotamia, which has already revealed so infinitely much of ancient history, here also will not fail. The appearance at Ur of an "Indus" seal with a cuneiform inscription is full of hope; its three signs are all, Indus seal found unluckily, indistinct, but the reading is perhaps Sak-ku-shi or ka-lu-shi,1 probably a name at Ur. indeed, but whether characteristic of the Indus population we do not know. One other interesting reminiscence of these seals may be mentioned; there are certain devices and punch-marks on coins from N.W. India which have a strong apparent likeness to Devices on these ancient pictures. We may refer to the new British Museum "Catalogue of the coins from N.W. Coins of Ancient India", where the feeding rhinoceros on No. 70 (p. 16), the bull with India similar to the "symbol of Taurus" before him, No. 16 (p. 18), and some of the devices described ancient Indus on pp. 120 ff. seem not very far removed if not direct descendants, from the pictures engraved pictures. on the seals of Harappa and Mohenjo-daro.

The following note may be completely neglected by those who object to licence in speculation, as it may also be decisively exploded even by those willing to try heroic measures. First, then, a series of assumptions will be made, for which there is no proof, and next

numerical

¹ Ka-Ku-wa, equally possible, might be compared to such names Kakia, already, known as used east of Tigris and in Asia Minor.

414

A Conjectural Reading. to no evidence; the third will be rejected at the outset by the best-informed opinion.

Nevertheless let them be made:—

(a) That the writing is, at least in part, syllabic.(b) That the seal-inscriptions are, in general, names.

(c) That these names belong to an ancient Indo-Āryan language.1

These are the general assumptions; what likelihood the first two may have is considered above. The third, as already observed, would be denied by most Indologists on the ground that Aryans were not present in India at the period (before 2600 B.C.) to which these seals presumably belong—the date itself is, of course, not satisfactorily ascertained. Since, however, we are admittedly guessing, we shall not even pause to make any attempt (which

must be unsuccessful) to meet these objections.

From which these values would be ascertained :-

$$\bigcup = p(u), \quad ||| = tr(i), \quad \uparrow = a$$

Could these be established it would follow that the principle of akrophony had some application in this writing, and further that the not uncommon examples of inscriptions ending with the above group would be patronymics. Unhappily there seems to be nothing whatever by which the above pleasing speculation can be tested. The reader who has persevered so far may take it that I am fully conscious of many objections which it would not even be worth while to formulate here, since they could not possibly be answered out of a simple conjecture.

1 On the subject of the Vedic Aryans see pp. 109-11.

² For the present purpose it makes no difference that in Sanskrit the form used is "N's son M", not "M son of N".

THE MECHANICAL NATURE OF THE EARLY INDUS WRITING

The writing found on seals and other objects from Mohenjo-daro and Harappa was Script used intended to be read from right to left ; it cannot be purely alphabetic in character; and it is in third probable from the seals found at Susa and Kish, and from the analogy of a seal found at Ur, millennium that it was in use in the first half of the third millennium B.C.

No help is to be derived, so far as an understanding of the inscriptions is concerned, from the Intaglios on the seals; just as the same device may occur with different inscriptions, so the same inscription can occur with different devices.

It is believed that the inscriptions on the small, stone rectangles from Harappa belong to an earlier period than the inscriptions on the large seals. . Early inscriptions frequently present more complications than later ones, so far as questions of phonetic reading and interpretation are concerned; the "mechanical" nature of early writing is generally more

By the "mechanical" nature of writing is meant the manner in which the signs are used. Mechanical Of those writings which are not purely alphabetic it may be said that signs fall into one of nature of three classes, syllables, ideograms, determinatives. In any one inscription a sign can only writing. belong to one of these classes, but it may in different inscriptions belong to all three. If a sign is used with a syllabic value, it may in different inscriptions have different syllabic values. If a sign belongs to the last class, it may determine meaning, in which case it has no bearing upon the sound of the word, or sound, in which case it generally marks the first or last sound in a syllable, or the first or last syllable in a polysyllable. A determinative of sound is usually called a complement, and is particularly useful when ideograms permit of variant readings.

In this sense the "mechanical" nature of the writing does not include the "material" Material nature nature. The complications of the "material" nature of the signs arise from two main of writing. features of the script, modifications, whether internal or external, and combinations. The modifications, when simple, consist of a stroke or strokes in various positions, sometimes placed inside, sometimes adjoined, sometimes separate. In rare cases the constant addition of modifications transforms the appearance of a sign, see Nos. CCCIV to CCCIX. Combinations may be effected by interior adjustments or by simple ligature. It seems probable that at any rate in certain cases the ligature has the same sense as the two signs in juxtaposition, see Nos. CVIII and CII. In Sumerian and Egyptian, parallels could be cited for such modifications and combinations; the Indus writing differs from them in its frequent use of these compound signs, and by its use of the two together, to judge from the series Nos. CXL-CXLIV. The "material" nature of these signs suggests an extremely ingenious invention, dependent upon the use of certain fixed principles; but it does not throw any light on the "mechanical," use of the signs. Whether combined or modified signs retain their separate significance or acquire new phonetic values and meanings depends upon an examination of the "mechanical" use of the script.

The object of such an examination must be to divide the signs into classes, of the three Division of kinds mentioned. Such a division of these signs presents insuperable difficulties. This signs. examination must commence by a recognition of three fairly obvious classes of signs, (a) the "end" signs, (b) the "beginning" signs, (c) the "numeral" signs. Of the "end" signs, the commonest has not been separately entered in the present list, for obvious reasons. sign occurs nearly always at the end of inscriptions. When it occurs in the middle it can generally be proved that it there marks the end of a word or group. A favourable instance

"End" signs.

of this kind may be found under sign No. CCLXXXIII. The form of the inscription (No. 12) in which the two first signs are repeated after the first occurrence of the "end" sign, and the first line of the inscription closes with the "end" sign, is sufficient to illustrate this point. But there are some peculiar cases. Sign No. CLIX appears so constantly at the end of inscriptions, or at the end of groups in inscriptions, that it clearly belongs to the class of "end" signs; yet it can appear at the beginning of such inscriptions as H 208 and 329, which consist entirely, it should be noted, of signs which belong to the "end" class. These instances are sufficient to prove that this sign No. CLIX is not a peculiar form of a phonetic sign used only at the end of words. There must be some peculiarity in the sign which demands that it should ordinarily stand at the end, and which allows only of other "end" signs appearing after it. It is improbable that the sign denotes a syllable, for it should appear then in more varied positions; or, on the other hand, if it represents a syllable of such a peculiar kind that it can only appear at the end of a word, the instances in which it appears at the beginning cannot be accounted for. There is a general probability that sign No. CLIX is an independent and self-contained unit, that it possesses a meaning in and by itself. In the inscription H 266, it occurs with a single stroke before it; and the similar inscriptions listed under sign No. 1 hardly permit any doubt that here this sign must have a meaning complete in itself.

Granted that sign CLIX does not form a syllable of a word, but is a separable element, and that it has upon occasion a meaning in itself, it is still impossible to be sure whether this "end" sign is an ideogram or a determinative in most inscriptions. The obvious comparison suggested by inscription No. 287 which has the other "end" sign, No. CCCLXXXVII, does not assist; but it is interesting to note that sign No. CXXVII, with which a comparison is suggested by inscription H 52 can certainly stand alone, as it does in inscription 292. On the whole, it seems possible that sign CLIX is some separate word, at least in most cases.

Inside this group of "end" signs it seems possible to distinguish grades of strength, as it were; and yet no very firm rules can be distinguished. Thus sign CLIX is occasionally followed by other signs; thus by No. CCXCII in inscriptions 554, 387, and 534,1 by No. CCLXIX in H 250 and 173. An examination of sign No. CCXCII in the list favours the view that this sign represents a word, or at any rate a meaning, in itself; for the form of inscriptions Nos. 550, 386, 355, and 341 points to that conclusion. Similarly, a reference to No. CCLXIX proves that this is another "end" sign, which appears not only after No. CLIX, but after the commonest "end" sign. According to this line of argument inscriptions often end in one or more signs which have separate meanings and do not form part of the preceding words. But it is still possible for these signs to be ideograms, determinatives, or separate elements of personal names, and no aid is obtained for the classification of signs.

"Beginning" signs.

An examination of the "beginning" signs results in the same observation. A remarkable group of "beginning" signs consists of signs modified by two short perpendicular strokes. The signs without the modification can generally vary their position in inscriptions, as in the case of Nos. LXV and LXXIII; but when modified, in the forms LXVI and LXXV, they occur only at the beginning of inscriptions. But it is necessary to note that sign LXXIII is able to stand by itself; it therefore means something. Similarly, a comparison of inscription No. 133 (under sign IX) with inscription 76, and a consideration of the form of the inscription No. 126 leads to the opinion that the modified sign LXXV has a meaning by itself. Of the modified sign No. LXVI it may be affirmed with confidence from H 255 that it has a meaning by itself; but the question whether LXXV has such a meaning does

¹ Erroneously listed under CCXC.—[ED.]

not at present allow of a certain answer. Now the modified signs LXVI and LXXV are almost always in the initial position. The cases in which they are not in that position allow of a special explanation. If they were ordinary syllables, it is difficult to see why these signs must always be in the initial position; the simplest explanation seems to be that these signs retained in the long inscriptions the separate sense we know they would have. But it remains as difficult to assign these "beginning" signs to one of the three classes as proved to be the case with the "end" signs.

There is a peculiar characteristic of the mechanical use of some of the modified signs which must be associated with the nature of the "numeral" signs that have yet to be Numeral signs. considered. The commonest, unlisted, "end" sign, when modified in the forms show? by Nos. CCXXXIX to CCXLVI becomes capable of occupying a medial or initial position, while e.g. the modified," beginning "sign CXV can only occupy an initial position as against the medial, initial, or end position of the simple sign CXIV. This mechanical characteristic of the modified signs, which throws them into a forward position as compared with the simple signs, must probably be explained in the same way in both cases. Otherwise it would be plausible to believe that the modification which enables the "end" sign to occupy a medial or initial position represents a vowel, though this would involve the abandonment of the reasoning which has led to the view that the "end" signs represent words in themselves. But this explanation of the modification as a vowel does not serve to explain why a sign which can occupy any position must occupy the initial position when modified.

It is fairly clear that the modification is in itself an entity. That seems the only reasonable explanation of inscriptions Nos. 65 and H 54, listed under sign No. CCCLXXVIII. In these cases the inscription begins with two strokes, in H 54 in the small form that is common as a modification, in No. 65 in the large form which naturally leads to an association with the "numeral" sign; the consecution of signs leaves hardly any doubt that the two forms are identical. The same inscriptions prove that the modifications consisting of one and two strokes are similar in their "mechanical" effect, though not identical. Since one, two, or three small strokes are used as modifications, it is natural to inquire whether their use in this manner is not immediately derived from the sense

of the "numeral" signs.

The "beginning" signs modified by two small strokes are often followed by one of the "numeral" signs; it does not seem to matter which of the "numeral" signs is used in this connection. There is a parallel between this collocation of modified "beginning" signs and numeral signs, and the collocation of "numeral" signs, either in repetition or with one another. When the "numeral" signs are in such collocation, it is often, but not always, found that one of the "numeral" signs is written smaller than the other; but no rule has been distinguished in the collocation of "numeral" signs that governs the orders large, small, or small, large, that seem to be used alternatively. It is possible that the "mechanical" nature of the modification, e.g. by two small strokes, is the same as that of "numeral" signs when written small, and this view is rather favoured by inscription No. 113 under sign XV. The question then arises, what is the difference between the small and large writing? It Small and large has already been seen that inscriptions Nos. 65 and H 54 show that the difference can only be, signs. if one may use the phrase, in intensity; they can hardly differ considerably in "mechanical" nature. If the "numeral" sign consisting of two strokes is a syllable, then the small two Strokes are also a (similar) syllable; if the "numeral" sign is not read, but has some determining function, so has the other, and so forth.

The question of the "mechanical" character of certain "beginning" signs may, then, depend upon a consideration of the "mechanical" nature of the "numerical" signs. The signs composed of strokes are here called "numerical" as a convenient description of their

"material" nature, not because they denote numbers. These "numerical" signs consist of strokes of different lengths, at different angles, arranged in different ways. It would be conceivable that these differences are due to differences of meaning, were it not that an examination of the inscriptions leads to the opinion that this is probably not so. Thus in the case of the arrangement of the strokes, the single example in which the sign with five strokes is not written with the strokes side by side, listed as sign XII, is surely to be compared with inscriptions 301 and 441 under sign XI; the additional element is the "beginning" sign, a separable and distinct part of the inscription that we know can have a meaning by itself. Similarly, the four strokes arranged in two sets of two occur in a connection in X No. 130, which clearly offers a comparison with the four strokes side by side in IX No. 133 and No. 395. These instances do not amount to a logical proof that there is no difference between signs XI and XII, or between signs IX and X; but it must be admitted that, if there was a difference, then that difference must frequently have led to confusion in view of the similarities pointed out, and that it cannot be due to any "mechanical" difference in the nature of the sign. Or again, in the case of the difference between perpendicular and sloping strokes, an inspection of the last inscription listed under VII should show that it must be the same as the last three signs of VI No. 3. Similarly, we may compare VII No. 170 and VI No. 65. It is not easy to believe that there is any difference at all between signs VI and VII of meaning or nature.

Perpendicular and sloping strokes.

It is difficult to explain why these "numerical" signs can change, as is probable, their angle, or, as is possible, their internal arrangement, unless they are numbers. In those scripts where numeral signs can have syllabic, or even word, values, for instance Sumerian, the forms of the signs are not variable, but as fixed and unchangeable as all other signs with syllabic values. Numerals, however, which have no phonetic value, like the Egyptian, can and do shange their position in very much the way that these "numeral" signs from the Indus valley do. Analogies of this kind may be extremely misleading. But the changing form of the Indus valley "numeral" signs is a feature which favours the interpretation of these signs as numbers.

Signs for numbers.

Certain of the inscriptions seem most easily explained by the interpretation of these signs as numbers, more especially the shorter inscriptions from Harappā. Under sign No. CCXIX may be found an instance in which the same sign can combine with "numeral" signs containing 2, 3, or 4 strokes and the position of the "numeral" sign varies, being sometimes before, sometimes after sign No. CCXIX. Let it be granted, for argument's sake, that these inscriptions contain words, and that the two signs in these inscriptions form, in the six different cases, one word. The assumption leads to a strange coincidence. It is peculiar that, if the syllable represented by two strokes can be combined with the syllable represented by sign CCXIX in two ways to form two intelligible words, the syllable represented by three strokes should have the same power; it is almost incredible that the syllable represented by four strokes should have the same power. The easiest explanation, the explanation which immediately presents itself, is that in this particular series we have a formula x2, x3, x4, or 2x, 3x, 4x. It is true that even so the indifference shown to the position of the numeral is peculiar. But it may well be that the alternation is a purely graphical one, of the kind sometimes found in our own conventional writings, e.g. £3 or 3£.

Small Harappa signs are older.

The small Harappā inscriptions may well be in a different class from those on the larger seals. They belong to an earlier stratum than the large inscribed seals. Granted that it is possible or probable that in certain cases in the Harappā inscriptions the "numeral" signs may represent numbers, it is not necessary to assume that they always do so. Some arguments against considering them numerals have already been stated. The most important seem to be that the most natural interpretation of inscriptions on seals is that they are names, and that

the regular occurrence of the signs containing 3 and 7 strokes with certain other signs points to a natural sequence of sounds. It must be remembered, however, that these arguments themselves contain assumptions, and need testing before it is admitted that we have any ground

for attempting an interpretation of these inscriptions as personal names.

The final result of the examination of the "mechanical" nature of the "nunleral" signs is then as inconclusive as that of "beginning" or that of the "end" signs; there is only the probability that in certain cases the "numeral" signs denote numbers, and that the significance of the stroke modifications of some "beginning" signs is closely connected with the corresponding "numeral" signs. There is a further parallel between the modifications and the "numeral" signs that may be of importance. A comparison of the signs CCXQIV and CCXLV with GCXLII and CCXLIII seems to show that there is no important difference in the meaning of these signs, or in other words that the modifications can in certain cases be

perpendicular or aslant, as is true also of the "numeral" signs.

It is impossible to be certain of the character of these inscriptions until we know whether they consist of one or more words, and of that there is no indication. But a "mechanical" analysis tends to point to certain conclusions; the typical series of instances listed under sign No. CCCXXXI will provide an example of the kind of analysis meant. H 3570 seems to show that the sign can in itself mean something. It can combine with the "numeral" signs with six or seven strokes to mean something. With two strokes in front and the separable Strokes at "end" sign after, it forms a significant group in H 152. When sign No. XXVIII intrudes beginning or before the "end" sign into this group, it is permissible to infer that another separable element end. is present in inscription No. 120, an inference much favoured by considering the inscription No. 5 listed under sign XXVIII, since the intrusive sign and the "end" sign make a significant group. The most natural, though not demonstrable, conclusion is that in inscription No. 120 there is a series of signs which retain their separate characters; in other words, the inscription consists of a series of intelligible expressions. If the whole is a personal name, then on this reasoning it contains four separate ideas. Similarly, in inscription No. 19 we have "beginning" sign + 4 strokes + fish + "end" sign, again conveying four separate ideas. But in those inscriptions where "numeral" signs occur before the fish, 2, 3, 4, 6, and 7 strokes are to be found. So far as we know at present, the non-appearance of the other "numeral" signs may be accidental; in any case the "numeral" signs appear to be significant in themselves.

If we now consider inscription No. 314 we shall find that it consists of at least Analysis of an five elements that seem to have a separate significance, possibly six. There is the "end" inscription. sign, preceded by the fish, with six strokes in front of it; before these, as the second sign, comes sign No. CCLX, with the "modifying" element of two short strokes already discussed. Of sign No. CCLX it may fairly be assumed, from a comparison of inscriptions Nos. 268, H 21, and 372 that it has a separate value in itself. The first sign in inscription 314 is sign No. CXXXIX, and about this sign there is a curious observation to be made. It occurs upon a broken pot, and it is therefore not absolutely certain that it stood above; it may have done so. The sign also occurs on pots from the Aegean region, of the kind called "Urfirnis" ware, see e.g. Hall, Civilization of Greece in Bronze Age, fig. 68, dating from about the middle of the second millennium, but is to be seen on much earlier ware, ibid., fig. 31. It also appears commonly on the "Dipylon" ware from Attica of about the ninth century. The usual interpretation of its appearance on Aegean ware is that it is used as a decorative motif to fill in blank spaces. It is not necessary to deny this interpretation, but it is to the point to remark that in certain cases it appears in a connection in which it seems to have a particular meaning. Thus on the "Dipylon" pots illustrated in Cambridge Ancient History, pl. i, p. 282, it is placed in many blank spaces of a scene depicting a naval battle in a manner that suggests an

Sign depicting some material.

Cretan sign.

Many signs rarely used.

Signs as ideograms.

positions.

interpretation; the signs may denote objects carried in the boat as articles of commerce, and emptied out when the crew were thrown out. The most natural interpretation of the sign on pots would be that it denoted the stuff they contained, or the measure they could contain. Curiously enough, this sign, placed sideways, appears in the Sabæan alphabet as the letter zayin, the meaning of which is much disputed; the older interpreters believed the word meant a kind of weapon, but more recent authorities have advanced widely divergent views. There is a Cretan sign which closely resembles the Sabæan zayin, but there is an important difference in that a small horizontal stroke is attached to the centre of the sign in such a manner that it is reasonable to see in this Cretan sign a representation of the double-axe. The shape of the sign is peculiar, though the opinion that the sporadic occurrences are due to accident rather than borrowing will doubtless appeal to some.1 But at least a possible interpretation of all this evidence is that sign No. CXXXIX depicts some material commonly contained in earthenware vessels, which was carried far and wide over the ancient world, even by sea, for very many centuries; this interpretation does not impose itself, but is to be borne in mind as a possibility.

It may be, then, that inscription No. 314 consists of a series of five signs, each having a separate meaning. An analysis of longer inscriptions would show that they contain an even larger number of elements. But it is first necessary to mention a very important fact in this script, namely, that the greater number of the signs in this list occur only once or twice, and a considerable increase in the number of inscriptions would result in an increase in the number of these rare signs. The form of the inscriptions in certain cases proves that these signs are capable of standing alone; a clear case may be found under Nos. CL and CLI. It is extremely probable that these signs are for the most part ideograms. In many cases they occur alone immediately before a "beginning" sign or after an "end" sign. Two typical instances will serve to illustrate this, listed under sign No. CXV, viz. inscriptions Nos. 324 and H 148. The first, No. 324, consists of a group of three signs and an end sign, preceded by a "beginning" sign, which also occurs in H 148 but with a different "end" sign. In front of the "beginning" sign in both inscriptions there are other signs. That which appears in No. 324 occurs in one other inscription, also as the first sign. The second sign in H 148 occurs also in one other inscription, at the end, in a group of three Signs in various signs of very rare occurrence. The first sign in H 148 is sign No. CLXXX which is probably identical with sign CLXXXI; it occurs five times, in various positions, sometimes before or after an "end" sign, inscriptions No. H 164, H 146, and 106. There is no logical proof to be adduced in this matter; but there is a strong impression that these signs are separate and distinct from the groups which follow them; in other words that they are ideograms. As to the signs which follow the "end" sign in H 148, the inscriptions listed under sign XLIII are sufficient to show that the penultimate sign has a sense in itself, since it appears alone before the "end" sign, and has a sense which frequently requires it to appear after the "end" sign. As to the last sign, it belongs to a group of signs consisting of strokes with a varying number of small strokes attached, the ideogrammatic nature of which is fairly clear; an observation of such cases as inscriptions Nos. 339 and 116 points to this inference for the group.

There seems a vague, and indemonstrable, probability that a not inconsiderable proportion of these signs are ideograms; but even so there are many difficulties to be considered. For instance, the sign which seems to resemble a table with a cloth on it, No. CCCXXII, appears at the end, sometimes after the commonest "end" sign, of all the listed inscriptions save one, No. 440. In that case the signs exactly reverse the order of the last three signs in No. 435. Were it not for inscription 440, the explanation of

¹ The sign occurs at Selima in the Libyan desert, Antiquity, 1928, p. 283.

sign CCCXXII as an ideogram would fit. But if inscription 440 were reduced to three ideograms to accord with this, inscription 435 would necessarily be reduced to the first two signs, and three ideograms, thus severing the sign with seven strokes from sign No. CCCIV. But this seems inadmissible, because the sign with seven strokes is very closely connected with this sign, as in inscriptions Nos. 211, 113, H 11, and H 8, a connection thal cannot be accidental if sign No. CCCVIII be considered as a development of No. CCCIV. There is a mass of material of this kind in these inscriptions, and until certain proof is forthcoming it will remain very problematical whether any sign is certainly an ideogram. But the expression of a purely personal opinion may be allowed, namely, that the evidence points to Suggested

inscription 435 being a succession of separate words.

If this view is not altogether mistaken, then it has a certain relevance to the assumption on inscription. that these inscriptions contain proper names. It must, under this assumption, be granted that the inscriptions do not all contain only personal names; there must be other elements as Not only Secondly, it will be evident that in certain cases the name is expressed by one single personal names This may be seen from the two inscriptions listed under sign No. CXXIII. In the on inscriptions. first, of these, the form of the inscription clearly shows that the sign belongs, in its "mechanical" nature, to the class tentatively considered ideograms. In the other inscription there are only two signs; and unless we are to assume that the ideogram which apparently forms a description of the name in one class can with the same or a different sense be part of a personal name in the second—which is possible, but unlikely in view of its comparative rarity in this large number of inscriptions—the personal name is reduced to a single sign. Thirdly, some of these names include rather peculiar ideograms. One of the most obvious pictograms in this script is the chair (No. CCCXIX). It is true that this is not beyond all doubt an ideogram, but a glance at the first three inscriptions listed under No. LXXX is sufficient to show the possibility that it is such. Now a chair may naturally, as an ideogram, represent very diverse meanings, but it is of rare occurrence, and it seems most probable that a rare pictogram would retain one meaning closely allied with its origin. If this formed part of a personal name, then that name must belong to a language which must be classed in this respect with a very limited group. One inevitably thinks of certain English and German personal names; the mere comparison is instructive because it shows how limited this type of name is. If on the other hand, the chair represents a prefixed title, the group of languages concerned is again probably a small one. Again, in certain cases very obvious pictograms, e.g. of a bird, are repeated. One expects the repetition in such a case to denote a plural (or at least a dual). Men are often called by the names of birds or fowls, but the plural seems unsuitable for a personal name.

A fourth consideration must involve the difficult question of the longer inscriptions, Long of the kind exampled by No. 400, listed under sign No. LXXV. This consists of three lines, inscriptions of which the first and second each have as the last sign a common "end" sign; and there is discussed. nothing in either line separately to distinguish them from single-line inscriptions with the same "end" signs. We should expect two personal names on a seal either to be joined by the word or words "son of", or by some grammatical inflection which should denote that relation. Yet in all these inscriptions it is impossible to single out any constantly recurring sign or group the position of which "mechanically" points to such a meaning. Certainly the third line of inscription, No. 400, might be so interpreted; but it presents no striking analogy to groups in other long inscriptions, and therefore such an interpretation would not be probable. Much could be written of a speculative nature on this subject; thus it might be suggested that the grammatical relation of the first and second "names" is expressed by the very same grammatical form as that in which the names appear. If, for instance, the language possessed a genitive, then it is conceivable that the second name is a genitive after the first

separate words

name, and that all the names appear in the genitive, owing to some unexpressed idea like "property of". Nevertheless, these long inscriptions are a very considerable difficulty for any "mechanical" explanation of these inscriptions as personal names, or even as personal names and titles. It does look as if these long inscriptions were lists of words, or wordgroups; and some other hypothetical explanation than that of personal names would suit the case better.

The attempted examination of these signs so far has led to the conclusion that most of them have meanings by themselves, and that some are probably "ideograms", in that they convey a word as an idea, and are therefore not used with syllabic values. Are there any that can be shown to have syllabic values? That unfortunately is beyond the limited means of analysis at our disposal. Those signs which are constantly found in recognizable groups may well be syllabic, but it is at present impossible to be sure that the extraordinary permutations and combinations possible for a sign like No. CCCLX (a bird of some sort) really prove that it is such. Indeed, this variety of order that is possible renders one extremely doubtful of such an explanation in the case of the "fish" sign and its modifications.

Division of Indus signs into classes difficult.

At present, as has already been said, the difficulties of dividing these Indus signs into classes are insuperable. There is a general probability that most of them could have a meaning by themselves and that some are pure ideograms. Were it possible to be sure that these inscriptions were personal names, more might be said, for an examination of the inscriptions proves, to the present writer, that those names were marked by a series of peculiarities which must be very rare. But there could be no more dangerous hypothesis at present. The arguments that have been adduced against considering the "numeral" signs as numbers can at least be countered by the observation that in certain cases they almost certainly do represent numbers; and the assumption that they are numbers might even be reconciled with the hypothesis that the inscriptions contain personal names—which would be of considerable importance, for we know a language that not infrequently contained numbers in the personal names. But it is safer to believe that these inscriptions may in fact have an import quite other than personal names. The analogy of the devices of certain Indian coins to the devices of these seals has already been mentioned. It is fitting to note that certain themes in these signs may be compared to the punch-marks on those coins; thus, for example, the little man who brings along two hooks, if the description may be allowed, is strikingly similar to the little man of the punch-marks, who holds a hook in either hand. It is disappointing, but wise, to admit that these inscriptions may in fact mean, on the present evidence, almost anything. An open-minded consideration of the evidence led, in 1924, to the conclusion that the similarity of some of these signs in form (not in use or meaning) to Sumerian signs showed an early connection between Sumer and the Indus valley. connection has since been conclusively proved to have existed. An open mind may equally find very close and remarkable similarities between some of these signs and the marks (wasm) of Arab and African tribes; such signs have also been found at Selima in the Libyan desert. Some will certainly hold that the resemblances are accidental. They may equally be due to a traditional use of certain trading marks which has lasted until a comparatively recent period.

Arab and African signs similar to those of the Indus.

N.B.—In the Sign Manual on Pls. CXIX-CXXIX, the letter II attached to the reference number of an imorription signifies that the inscription in question comes from Harappā, and that the seal or other object on which it occurs is not illustrated in this work. All other inscriptions come from Mohenjo-daro and, with very few exceptions, are reproduced in Pis. CII-CXVI. The exceptions referred to are distinguished by the letter S.

The following corrections should be made in the Sign Manual:—Pl. CXXV, Col. 4: delete Sign CCLXVII; ibid., Sign CCLXX: delete Inscr. H 329, the correct reading of which is as shown under Signs CCLXIII and CCLXVI; Pl. CXXVI, Col. 3, Sign CCXC: the clast sign of Inscr. 534 is No. CCXCII, not No. CCXC. The

latter eign should therefore be deleted .- [ED.]

CHAPTER XXIII

THE INDUS SCRIPT

FOREWORD

N this study of the inscriptions of the early seals of the Indus Valley I have definitely Indus writing stated that the early Indian alphabet, known as the Brāhmī script, is derived from the original of the ancient Indus pictographic writing, and I have identified the origin of many Brahmi script. Brāhmī characters with confidence. In my Sign List the phonetic values of the derived alphabetic characters have been inserted, but I do not wish to convey the inference that these are the correct values of the original ideograms, any more than the phonetic values of the Phænician alphabet represent the values of the Egyptian pictographs from which they are It is highly improbable that the signs of the Indus script have reached the syllabic stage, that is, a consonant + vowel, as in the Brāhmī alphabet. Many of them may possibly be so used, and used as phonetic elements in the writing of the words, as many Sumerian pictographs are in the oldest known Sumerian texts. If the roots of this unknown language are mainly biconsonantal, as in Sumerian and Indo-Germanic languages, then it follows that? the syllabic values, such as ba, ta, ga, etc., of the derived Indian alphabet, have lost a final consonant, and may have been bad, bag, ban, etc., tad, tag, tab, etc., gal, gan, gab, etc. It is Transliteration no more possible to transliterate the Indus signs from the derived Brāhmī alphabet than to of the Indus operate in the same manner upon Egyptian hieroglyphs with the derived Phænician alphabet. script from the Here we have, already from the seals, a sign list approaching 300 numbers 1; obviously Brahmi not the initial consonants of a very restricted proportion would be known, even in the successful possible. identification of all the forty-five Brāhmī characters.

The proper names and names of professions on these seals do not supply sufficient material for successful decipherment. It is not possible to separate word and sign groups; the declensions and verb inflections cannot be detected here, and the pronouns are entirely absent. Until longer inscriptions of a literary and historical character are discovered, not much advance in the interpretation can be expected. A good many important facts can be determined, however, to clear the ground for more satisfactory research. In the first place Indus script this script is in no way even remotely connected with either the Sumerian or Proto-Elamitic unconnected signs. I have compared some of the signs with the signs of these scripts. For the references with Sumerian. to the Sumerian pictographs, or the earliest forms of the Sumerian signs,2 I have referred the reader to the numbers of REC. (Thureau-Dangin, Recherches sur l'Origine de l'Ecriture

It should be noted that at the time of writing this chapter (it was finished in April, 1927) Professor Langdon did not have access to all the inscriptions utilized by Messrs. Sidney Smith and C. J. Gadd in the preparation of their sign manual.—[ED.]

² But see the Postscript (July, 1928).

Indus signs resemble Egyptian hieroglyphs Cunéiforme), and for the Proto-Elamitic signs to Professor Scheil's "Textes de Comptabilité Proto-Élamites", in vol. xvii of Mémoires de la Mission Archéologique de Perse, pp. 31-66. This series is commonly cited as Dél. Per. (Délégation en Perse). The Indus inscriptions resemble the Egyptian hieroglyphs far more than they do the Sumerian linear and cuneiform system. And secondly, the presence of detached accents in the Indus script is a feature which distinguishes it from any of these systems. Although vowels must be inherent in all the signs, nevertheless some of the signs and accents must be pure vowel signs. For this reason alone it is necessary to resign further investigation to Sanskrit scholars. If future discoveries make it possible to transliterate the signs, and the language proves to be agglutinative, it will then be a problem for Sumerologists. I am convinced that all attempts to derive the Brāhmī alphabet from Semitic alphabets were complete failures.

Indus seals found in Mesopotamia and Elam. This study of the script of a pre-Sanskrit civilization of the Indus Valley is made from the material supplied by 541 impressions of small press seals. Five hundred and sixteen were supplied to me in photographs by the Archæological Department of the Government of India, together with photographs of several more which are not inscribed. The remainder consists of photographs of seals (not of the impressions), published by Sir John Marshall in the Illustrated London News, 1924, pp. 624 ff., and 1926, p. 346; in Cambridge History of India, vol. i, pl. xi (two seals); and in the Archæol. Survey Report. 1923-4, pl. xix, 15 (one seal). Three seals found at Harappā (1872, 1885, 1886) were published by J. F. Fleet in the Journal of the Royal Asiatic Society, 1912, pp. 699 ff., and five have been found in Mesopotamia. Since the archæological criteria for dating prehistoric monuments in Mesopotamia and Elam are much more secure than in India, they constitute the most valuable evidence for dating the early civilization of the Indus Valley.

One of these five seals is a bone roll cylinder found at Susa, apparently in the same strata as that of the tablets in Proto-Elamitic script of the second period of painted ware. Scheil, in Délégation en Perse, vol. xvii, assigns this group of tablets and painted pottery to the period of Sargon of Agade, twenty-eighth century B.C., and some of the tablets to a period as late as the twenty-fourth century.² The cylinder was first published by Scheil in Délégation en Perse ii, 129, where no precise field data by the excavator are given. The text is there given as it appears on the seal, and consequently the text is reversed. Louis Delaporte in his Catalogue des Cylindres Orientaux . . . du Musée du Louvre, vol. i, pl. xxv, No. 15, published this seal from an impression, which gives the proper representation of the inscription. it will be noted that the style of the design is distinctly pre-Sargonic: witness the animal file and the distribution of the text around the circumference of the seal, and not parallel to its axis as on the seals of the Agade and later periods. See the pre-Sargonic seals of Lugalanda, Revue d'Assyriologie, vi, 105-25, by Col. Allotte de la Fuÿe; seal of Eniggal by the same scholar in Documents Présargoniques, pl. ix; Delaporte, Cat., ii, pl. lxx, No. 3. It is certain that the motil one of the design known as the animal file motif is extremely early in Sumerian and Elamitic glyptic; in fact it is among the oldest known glyptic designs.

Animal file motil one of the oldest designs.
Two-horned bull not known in Sumer.

But the two-horned bull standing over a manger was a design unknown in Samerian glyptic, except on the small round press seal found by De Sarzec at Telloh and published by Heuzey, Découvertes en Chaldée, pl. xxx, fig. 3a, and by Delaporte, Cat. i, pl. ii, t. 24.

¹ This title no longer appears on the title page of the official publications, which are now called Mémoires de la Mission Archéologique de Perse.

² See my review of Scheil's latest study of the Pr3to-Elamitic script in FRAS. 1925, p. 169.

The Indus seals frequently represent this same bull or bison with head bent towards a manger. See Seals 317, 318, 319, etc. Two archæological aspects of the Susa seal are disturbing. The cylinder roll seal has not yet been found in the Indus Valley, nor does the Sumero-Elamitic animal file motif occur on any of the 530 press seals of the Indus region. It seems evident, therefore, that some trader or traveller from that country lived at Susa in the pre-Sargonic period and made a roll seal in accordance with the customs of the seal-makers of the period, inscribing it with his own native script, and working the Indian bull into a file design after the manner of the Sumero-Elamitic glyptic. The Susa seal clearly indicates a period ad quem below which this Indian culture cannot be placed, that is, about 2800 B.C.

On a roll cylinder it is frequently impossible to determine where the inscription begins and ends, unless the language is known, and that is the case with the Susa seal. However, I have been able to determine a good many important features of these inscriptions and

I believe that this text'should be copied as follows:—

Pictograph of Indus seal from Susa.

宁!!!! 中門第一

The last sign is No. 194 of my list, a variant of No. 193, which is a post-fixed determinative, denoting the name of a profession, that is "carrier, mason, builder", and

invariably stands at the end. (The script runs from right to left.)

As to the small circular press seal found by De Sarzec at Telloh (Lagash), a site in the extreme south of Sumer, which has furnished monuments anterior to 3000 B.C., here again no archæological data have been preserved concerning the stratum in which it was found. The text here follows the upper circumference, and for similar round and oval seals from Harappä and Mohenjo-daro see Seals 309, 478, and 527. It is extremely probable that this seal also belongs to the pre-Sargonic period, and it is regrettable that no exact information is available from the field notes of the excavator. The material is a "soft grey greenish" stone. The text is:—

\$ " Y8V

The postfix No. 87 has here a more archaic form than on any of the seals from the Indus

Valley.

A small square press seal of steatite of the usual Indian type has been acquired by the Louvre and published by Dr. F. Thureau-Dangin, Revue d'Assyriologie, xxii, 99. He suggests that it came from Telloh also. The text is:—

発りり 414

The last sign is No. 195, a postfixed determinative of a profession. The fourth sign may be nothing more than No. 219, the accretions being due to defects on the surface of the seal. The animal on this seal is the Indian tiger with head over a manger, facing right, as in Seal 351; cf. Seals 350, 353, and 355.

The impression on clay of a similar seal was found at Djokha (Umma) near Telloh, a site which has supplied no antiquities later than the twenty-fourth century B.C., and many

¹ The cylinder seal has since been found at Mohenjo-daro.—[ED.]

² This motif occurs, however, on the sealings, e.g., Pl. CXVIII, 10.—[ED.]

³ Published by Delaporte, Catalogue des Cylindres, Louvre, i, pl. ii, t. 24.

of the greatest antiquity. This seal has the usual horned bull 1 over a bowl-shaped stand surmounted by a box as in Seals 40 and 115. The reverse of this clay tag from Djokha is impressed with another seal bearing the same simple design of a surface ruled in small squares as found on the Indian seals; see Revue d'Assyriologie, xxii, 56, and compare Seals 524, 525, 526, and 528. Professor Scheil, however, thinks that this is only the impression made by a coarse cloth. The inscription on the Djokha seal is:—

RYRD A

Here the text ends with the postfix No. 96.

Of the four Indus Valley seals found in Mesopotamia, that excavated by Mr. Mackay in the temple of the war-god Ilbaba at Kish is the only one concerning which exact field records exist. It came from a chamber in the temple beneath the Samsuiluna pavement and is described as found lying in the débris used to fill up the foundation of the chamber. A plaster copy is published by Mr. Mackay in the Journal of the Royal Asiatic Society, 1925, pl. x. It was originally covered with a blue glaze. The text is:—

分录回Ⅱ

The postfixed determinative No. 182 shows that the text bears the name of a person,

or profession.

Indus seals of Mesopotamia are pre-Sargonic.

Racial connection between Indus and Sumer unlikely.

Cunningham on Indian pictographic writing. Bühler's theories. However these five seals may have arrived in Mesopotamia and Elam, it is obvious that they are pre-Sargonic, that is, earlier than the twenty-eighth century, and consequently the Civilization of the Indus Valley may be as old as that of Sumer and Egypt. I make no comment on pottery as inadequately known to me, but the statuette published by Sir John Marshall in the Illustrated London News, 1926, p. 343, is so entirely un-Sumerian that any close racial connection must be dismissed at once. The familiar design of a bull, buffalo, elephant, rhinoceros, and tiger before a manger or sacred symbol is also unknown in Sumerian and Elamitic glyptics. The survival of the svastika design on Seals 500 to 515, a religious symbol characteristic of India, suggests that perhaps other survivals may be found, which will enable us to interpret the script also. For I hardly believe that there can be any doubt concerning Sir A. Cunningham's brilliant suggestion of an early Indian pictographic system as the origin of the Brāhmī alphabet.²

The origin of the Brāhmī monumental script of the Asoka Edicts has been the subject of numerous theories. They are summarized by Georg Bühler, On the Origin of the Indian Brāhma Alphabet (1898), and in his standard German work Indische Palæographie, p. 10 (1896).

Cunningham's suggestion was the first one put forward as an explanation of the origin of the Sanskrit Nāgarī alphabet. It has been derived from the Phænician alphabet by Weber and Bühler, from the Sabæan-Himyaritic alphabet by Isaac Taylor and from the cuneiform syllabary of Assyria and Babylonia by Deecke. The comparisons of individual signs of the Brahmī script of early Indian epigraphy, which dates from 350 to 220 B.C., with the letters of the Phænician alphabet on the one hand, or with those of the Himyaritic alphabet on the

Only one horn is shown on the design, which is merely a usual method of glyptic common to Sumerian seals also; one horn is hidden behind the other. See Revue d'Assyriologie, xxii, 100, n. 1. See, however, pp. 68 ff. supra.—[ED.]

² Corpus Inscriptionum Indicarum, i, 52.

other, do not inspire much confidence in those theories. Their advocates claim "obvious connections" between certain syllabic signs of the Brahmi script and certain letters of the

two Semitic alphabets with an enthusiasm altogether unwarranted.

In approaching an epigraphical and linguistic problem so difficult as that presented by the new script of the Indus Valley, the chronology and nature of the script must first be settled. The evidence for a minimum date, twenty-eighth century B.C., has been stated above. Is it then reasonable to suppose that this pictographic script of ancient India survived without any archæological evidence of its existence during the long interval between the age of the seals of Harappa and Mohenjo-daro and the age of Asoka in the third century B.C.? Obviously the geographical and historical aspects of the problem favour an ancient Indian pictographic system as the origin of the alphabet finally adopted by the Āryans of India.1

In my sign list I have compared some of the signs with early Sumerian and Egyptian pictographs, and a few comparisons with Himyaritic-Sabæan letters have been made. I do not wish the reader to infer that I believe in any actual connection between the signs thus compared. The similarity is due to pure hazard, such as is bound to occur in pictographic The script as represented by the Indian seals is more like the Egyptian pictographic system than any other known script. As in the case of the earliest Egyptian inscriptions, this Indian script is already standardized; a large number of the original pictographs have been reduced to neat monumental forms, which indicates a long period of evolution. It will Great antiquity be seen in the subsequent pages that the writer believes that the early syllabic alphabet of of Indus picto-Northern India, known as the Brāhmī script, from which all later characters were derived, is graphs. most probably a survival of the early pictographic system of the Indus Valley. But even though future discoveries confirm this thesis, it does not follow that the language of the early Brahmi script Indus Valley seals is Indo-Germanic; the Babylonians borrowed the Sumerian ideographic derived from and syllabic script for writing their Semitic language and the same circumstance may have Indus writing. obtained in India.

from right to

The Indus script runs from right to left. The Sumerian pictographic writing also ran from right to left. Nothing can be determined in this respect about the Proto-Elamitic writing; for it has been preserved in lists of objects only, and consequently its signs are written in columns. The direction of the writing of the Indus script from right to left is Indus writing proved by the following facts 2:-

1. All the pictographs face to the left with the sole exception of the homo-signs left. Nos. 189, 196b, 201, 204, and there is certainly some good reason for this. These signs convey some such sense as "retreat, defence, ward off, backward, behind". For signs facing left, see Nos. 74, 165-74, 250. It is curious that the fish-signs, 175-80, and most of the homo-signs are drawn en face in the old perpendicular style.

The determinative No. 87 Internal 2. But even more conclusive is the internal evidence. stands at the left end of a large number of the lines. Now if the left were not the end evidence. of the line, how can we explain a text like that in Seal 52, where the material is too much for one line, and runs over into the second line by one sign? This is the postfix No. 87 and stands immediately below the left end. If the line began on the left this sign would stand at the left end of the line. Again, compare the text of Seal 554, where No. 30 stands just below the left end, and Seal 355 where it again stands below the line. That this sign is the ending is made certain by Seals 386, 387. The text on Seal 302 is interrupted by the

¹ Indian tradition, at any rate, places the invention of writing as early as the end of the fourth millennium B.C., 3101, and ascribes it to the creator Brahmā. See Fleet's edition of Bühler's Indian Palæography, p. 1.

² Cf. also Mr. Gadd's observations on this subject in the preceding chapter.—[ED.]

bull's head and continued below with Nos. 57, 87. It is certain from the repeated occurrences of No. 87 at the left ends that it is either a prefix or a postfix. But were it a prefix and the writing to be taken from left to right, clearly it must stand where No. 237 is there placed. It will be observed that, when a line is broken by the design, it is continued below on the *left* side; see Seal 167. Finally, compare Seal 101 with Seal 247. Here is a clear case of boustrophedon, the second line *returning* in the order Nos. 43-87, as it appears on Seal 101.

3. When the text contains one line and a second incomplete line, the second line runs from left to right or boustrophedon. A good example was cited above by comparing Seal 101 with Seal 247. For No. 99 at the end of a one-line text, see Seals 101, 102, 396, and 413. Compare Seal 126 with Seal 340; No. 214 stands next to the last line in Seal 126; but on the two-line text in Seal 340, the second line of which has only two signs, No. 214 stands first, which indicates boustrophedon. On the other hand, a text having two or more complete lines is not boustrophedon. See Seals 12 and 321, where No. 220b stands at the left end of line two, and compare Seal 397, where this sign ends the word. The longest text is that of Seal 400, where line two ends with the usual postfix 87, and line three with No. 153, which also has the last place in Seal 471; and often at end with postfix 87. But Seal 329, on which the three signs in line two are a continuation of line one, is probably boustrophedon, No. 237 standing at the right end in the last place as in Seal 302. No. 126 comes first in Seal 139, line two, and note that this sign usually comes first on one-line texts. It is also certain that if (which is very probable) Seals 435 and 440 are parts of one and the same text, the Seal 440 is boustrophedon of Seal 435, from the position of No. 98c, always last, and of No. 5, usually first.

ACCENTS

Accerts in Indus writing. Signs syllabic, writing phonetic.

Analysis of accents.

A. ('S.) The most extraordinary feature of this script is the accents added to a large number of letters, and the simple accents are invariably at the left side, which shows that the ideogram or syllable ended on the *left* in the pronunciation. I am of opinion that most of these signs are *syllables* and that the writing is phonetic, with the exception of certain determinatives. The accent ('S) is added to Nos. 87, 88, 97, 118, 124, 153, 154, 233, 264, that is, to the signs which most frequently occur at the end of words, and elsewhere. Since its doubled forms (" or ;) suggest the sibilant *Visarga* of the Sanskrit, it is tempting to compare this accent with the Sanskrit *Anusvāra* 1 or nasalization of a vowel ending.

Since the accent ('S) occurs with so few signs in the Indus script, it can hardly be the common accent for nasalization. But it is curious that this short stroke, when added to the Brāhmī characters for A and I, indicates the long vowel; and note that this same stroke may be added to signs Nos. 47 (50); 125 (130), attached and not standing free from the sign.

No. 47, especially the form 48, is so similar to the Brāhmī syllable sign ma, mo that they may be identified.2

B. ("S or "S.) By doubling the accent A the most frequently employed inflection of a syllable or ideogram (") is obtained. It is found with Nos. 47, 68, 87 (89, written inside), 95, 113 (114), 120, 126, 129, 131, 149, 153, 167, 187, 199b, 200, 232, 233, 234, 238, 264; also 72 is probably an example, cf. 89.

1 Placed over the sign.

² My references to the Brāhmī characters are taken from Georg Bühler, *Indische Palæographie*, Tafel 11 with Umschrift. It is possible that Nos. 47, 48 are different signs and consequently only No. 48 can be compared with ma, mo, No. 32 of Bühler's list.

No. 87 is probably the Brāhmī sign la, B. 351; No. 113 is B. 23, ta; No. 125 is B. 30, ba; Nos.º 126 and 232° are modifications of this sign and so perhaps No. 11. Now No. 11 resembles B. 30, bo, and No. 6 B. 30, $b\bar{a}$; No. 129 without accent B. 30, $b\bar{i}$; these accents would then be not vowel prolongations, but something in the nature of the dot over a letter indicating nasalization, and the sign: (Visarga). In other words, one stroke added to the simple sign ba would produce $b\bar{a}$, and two strokes added produce bo, $b\bar{u}$; in this case ba = 125(simple sign); $b\bar{a} = \text{No. 6}$; bo, $b\bar{u} = \text{No. 11}$; $b\bar{\imath}$ would be produced by adding three strokes, 129 (= 26).

In case of the sign for ma 47 and 48, No. 50 should be mā, corresponding to B. 32 VI, XIX, XX. No. 49 is made by adding two strokes one above and one below, producing a straight line, and this is B. 32 XXII + XXIV mo, and B. 32 VII mo, where the two strokes are added at the right. I would therefore read No. 87 la; 88 lā; 89 lū, lo; 90 lī, No. 224 Suggestions for should then be $b\bar{a}$. But how then should bi, bu, be (short) be expressed if the simple sign is reading. ba? No. 132 is surely B. 8, vowel o, and No. 133 may be the same sign reversed. In that case Seal 195 would end in la-o, assuming that this script had reached a purely syllabic stage. If it had not, then different signs may have stood for ba and be, etc., as in Sumerian, and the suggestion that strokes are added to signs for vowel prolongation is entirely erroneous, this being a principle of the derived Asoka script only. No. 6, for example, may resemble B. 30 XI $(b\bar{a})$ by accident only. I am inclined to believe that this suggestion is not on the right track, and that the signs 6, 11, 26, 129, for example, have no connection with Nos. 125 and 219 as base forms.

The detached accents, however, are clearly not all vowel prolongations; for several Detached vowel signs of the Brāhmī script are obviously derived from the Indus script, and these are accents. probably employed for vowel prolongation in this ancient writing, as the same vowels are employed in Sumerian, or for a final elided letter, or for indication of case and mood. Vowel o,

B. 8, has been identified with Nos. 132-3. Vowel i, B. 3, is clearly No. 269b; vowel e, B. 7, is most likely 219; and the character given as doubtfully ī, B. 4, is No. 274b. The Brāhmī character for a, B. 1, I suggest, comes from the homo-signs 193-4, turned 90° to the right.

C. ("S".) Accent B may be placed on each side of a letter, which I take to be one of the glides, , or h, see under D. It occurs with No. 1 (see No. 25) (between two signs).

D. (1.) Several signs are accompanied by this detached accent which is A doubled perpendicularly and resembles the sign Visarga. It occurs with No. 156c, and the fish-sign, No. 175, is followed by D + B on Seal 373.

E. (S ..) Much more frequent is the accent D placed before and after a sign, representing probably the on and off glide, which according to the nature of the spoken language may be the "check" on and off glide (,), Aleph of the Semitic languages, the sonant glide (1) Aying or the fricative rough on and off glide (h), hē. This does not assume that a syllable or word represented by a sign so accented begins and ends with a vowel only. It may occur with liquids and nasals, spirants and explosives. See Sievers, Grundzüge der Phonetik, pp. 150-8. This accent occurs with Nos. 163 (Standing between two signs), 175b (at end), 176b (between two signs), 178b (at end and between two signs), 220b (always last).

F. ("S".) Accent C doubled perpendicularly on both sides of the sign, which suggests the vowel 1, No. 274b. On Seal 74, No. 153, would be preceded by i and followed by i. Since No. 132 is probably B. 18 (ta), the Seal 296 would read i-ta-i-la, or if No. 162 in the original script had a final consonant, ita (?) ila, assuming that the Brāhmī alphabet is taken from the first consonant or vowel of a word represented by an ideogram. This accent

(or sign preceded and followed by vowel i?) occurs with Nos. 96d (at beginning), 102 (at

beginning).

G. ("S.) The accent C doubled perpendicularly, only at end of the sign, with 232c. It will be noted that No. 232 occurs with accents B and G. I take B for an off glide, and G for the vowel i. These forms occur repeatedly at the beginning of names and are probably prepositions or determinatives.

H. (Y or Y.) Accent A after slanted line. With Nos 47 (at beginning), 99, 118,

131, 153, 160b, 233d, 240 (264b, I do not understand this form).

I. (Ŝ.) The circumflex accent placed over a sign occurs with No. 96b, which I identify with B. 12, gha, but the effect of the accent is entirely obscure. Also over No. 177 and combined with accent E, No. 177b, No. 181.

J. (S.) This superimposed accent occurs with Nos. 1 (25), 53, 98, 120, and 120

is also accented, J + B and J + E.

DETERMINATIVES

Determinatives probably not pronounced. There are certain signs which are obviously determinatives, and as such are naturally not accented; for, as in Sumerian, they were probably not pronounced. They may stand either before or after the name. Since the seal inscriptions are surely names of persons or professions, or both, the material now at our disposal contains only a small number of the determinatives, which must have existed, such as the signs for "stone", "metal", "garment", etc. It is due to the special character of these texts that the signs from which a number of the Brāhmī characters were derived have not been found.

The following determinatives occur on the seal inscriptions:—

1. No. 68 is probably a sign for a place name, or gentilic. Postfixed.

2. No. 124, which see for citations.

3. No. 130, prefixed and postfixed. This I take for the word "city". It should be noted that when Nos. 130, 131 stand as prefixes, the sign 87 ends the line, wherefore No. 87 may be a gentilic ending.

4. No. 182, simple sign for "man", is a postfixed determinative showing that the name is that of a person or profession, precisely as the Sumerian pictograph for "man" (galu)

precedes the names of professions.

5. No. 87 is clearly a possifixed determinative, usually followed by the inflections A or B.

6. No. 190, postfixed, see this number.

7. Nos. 193-5, postfixed determinatives for a profession.

8. No. 198, prefixed determinative meaning "warrior", "soldier".

9. Nos. 204-5, prefixed determinative for prince, high official.

Under Nos. 264-78 I have entered a number of signs, which appear at first sight to be numerals, but I am convinced that they are syllables, or at any rate, numeral signs used as syllables in the phonetic pronunciation of the names. For it is certain that seals, on which the engraver patiently engraved such fine designs, could not have been used ad prasens et pro hac vice, for the passing purpose of sealing a document with an account of a fixed quantity of some commodity. These inscriptions contain names of men and professions, as the determinatives prove. Moreover, No. 264 is probably the origin of the Brāhmī sign B. 34 (ra). And it should be noted that Sumerian signs for the numerals are often employed as phonetic syllabic elements of words.

In the table which follows I have drawn up a list of those signs, from which some of the Table of Brāhmī characters appear to be derived. A notable parallel to this evolution of a pictographic Brāhmī and script into an alphabet is the Phænician alphabet, which is undoubtedly based upon the Incus Egyptian pictographic writing. It is true that the agreement there has the additional characters. advantage of agreement in the direction of the writing; for the Egyptian writing also runs from right to left? The Brāhmī and derived characters are written left to right, whereas the Indus script undoubtedly runs from right to left. Moreover, the Kharosthi script, contemporary with the Brāhmī, was borrowed from the Aramaic, and followed its parent in the direction of the writing. Why, then, if the Brāhmī was taken from the Phœnician alphabet, did it not follow the same principle? If one can depend upon the small five letter inscription on the Eran coin, the Brāhmī script did run from right to left as its parent, the ancient pictographs of the Indus Valley.1 The Greeks borrowed the Phænician alphabet and altered its direction to suit their own purposes, after having retained the order (right to left) of the parent Semitic writing for a short period after the borrowing. Obviously the same circumstances may have obtained in India.

If one studies Bühler's detailed defence of a Phænician origin of the Brāhmī script in his On the Origin of the Indian Brahma Alphabet, and his table on pl. i, he will find only two letters which warrant anything like a satisfactory comparison, Gimel and Teth. Now ga of B. II is even more like No. 100 of the Indus characters than the Phænician Gimel, and tha, B. 24, which Bühler derives from Phænician Teth, is much more similar to No. 224 than Phænician Teth. In fact, I am unable to see how anyone can even tentatively hold a resemblance between the Brāhmī alphabet and the Phænician, and the positive assertion of the correctness of this theory is entirely unwarranted. Undoubtedly the great lapse of time between these seals of the Indus Valley and the age of Asoka will be regarded as a fatal objection. But the epigraphical material may be found, and the evolution of the old pictographic writing into the late Indian alphabet will be traced. Obviously a large number of signs were discarded and only the necessary ones chosen; precisely the same procedure provided the Phœnician alphabet. If the excavations in the Indus Valley supply us with inscriptions which contain consecutive sentences and not mere proper names and titles, perhaps the key to the interpretation of this script may be discovered. Working with the present material, I suggest to Sanskrit scholars that they choose the names of a few mythical heroes Suggestions for and of deities, and with the few identifications here made attempt to separate the constantly decipherment. recurring groups of signs and compare them with these names. The principles of ancient Indian nomenclature are only vaguely known to me. It is of course possible that this is not an Indo-Germanic language. So early a date (3200-2800 B.C.) for the existence of an Aryan civilization in India is confidently asserted to be pure legend and the dream of a national

In all this widely spread epigraphical material, ranging from the upper to the lower parts of the Indus Valley, and to ancient Sumer and Elam, there is not a single text which differs in archaic style from the others. The epigraphist has no scope for studying the evolution of the script. It represents a standardized and advanced stage even at this early period, and the existence of the accents reveals the astonishing care and knowledge of phonetic principles which would hardly be conceded to the scribes of this remote period. But the archæological. evidence of the mounds in the Indus Valley is said to admit of no doubt in this matter. The seals come from strata far below the earliest Buddhist monuments. With the epigraphical

¹ Fleet, Indian Antiquary, xxxiii, p. 3 (Bühler's Indian Palæography), argues that this coin cannot be depended upon for the direction of the writing.

Archæology decisive in dating Indus script.

Aryans in India earlier than history admits. Mesopotamian seals are also decisive on the problem of the chronology. Lagash and Umma disappear from history before 2000 B.C., and three of these seals were found there. If inscriptions of no other type are found in the excavations of the Indus Valley, then we must suppose that the history of this fine civilization ends with these monuments, and the vast expanse of years between that catastrophe and the invasion of the Āryans is filled with uncertain traditions. If, however, this script was preserved and finally issued into the alphabet of the Buddhistic period, it proves that the Āryans must have had intimate contact with these founders of culture in India. In any way we may look at the problem, the Āryans in India are far more ancient than history admits. Their migration across Anatolia, where traces of them are found in the inscriptions of the Hittite capital, as early as the seventeenth century, is an hypothesis entirely contradictory to the new situation revealed by these discoveries in the Indus Valley. Far more likely is it that the Āryans in India are the oldest representatives of the Indo-Germanic race.¹

1 On this subject see supra, p. 112.—[ED.]

TABLE OF BRĀHMĪ CHARACTERS DERIVED FROM THE INDUS SCRIPT

Bühler Pl. II.	o Syllabic Value.	Number of the Indus Sign	in my List.
ì	`, a	185, 193, 194, turned	to right.
o3 o Or	i	2696.	0
4 0 0	ī	2746.	,
8 Z		132.	,
9	, ka :	1 or ,2.	
Pl. IV,	7.		
11 /	ga	100.	,
12	ģa, gha	96.	
14 do do	cha	, 223.	
15	ja	66.	,
18 (E	ţa, ţā	162.	
23	ta	113.	
24 🔘	tha	224.	
28	pa,	70.	
30 .	ba	125.	
32 ° 8	ma	48.	
33 4	ya	75-	,
. 34	ra	264.	
35	, la	87 (?).	,
36 Å b	• • • • • • • • • • • • • • • • • • • •	* 244.	

Nota Bene.—There are many other characters of the Brāhmī script which are strikingly similar to signs of the Indus script, but to avoid misleading material for future research they are omitted.

SIGN LIST OF THE INDUS SCRIPT 1

6; 179; 180 f. ILN. 1924; for accented forms, see No. 25. 267, twice as last sign. Value Ka. 16. 233; 4; 155 f.; RA. xxii, 99; CHI. i, pl. xi, 22; 81. 155. 388 f.; 440 f.; 373 with accent B; 340; 90 f.; 388 f.; 448, preceded by No. 269. 211. Cf. Proto-Elamitic sign, No. 236. 388; 40; 81, preceded by No. 270; 222; 265 f.; 418; 430; 539 f.; 388; 404; 52. Accent E 478; 292. 580, identical with Sabæan letter for Samekh. 337; 18 l.; 389 l.; 49, followed by accent B; ILN. 1924 L; ILN. 1926. 463 l. Cf. No. 6. ILN. 1924, followed by accent B. JRAS. 1912, 700 B. 253; 130; 201; in all cases followed by No. 119 and termination No. 87. 101 l.; 342, preceded by No. 265; 237 f. 262 f. 328. 32; 469; 277; 198; 50. 1 32; 277; and 198 followed by No. 175 and terminal sign No. 124. 540 between fish signs. 494 l.; 360; 341; 234. Delaporte, Cat. i, pl. xxv, No. 15 f. Del. Per. ii, 129 = Delaporte, Cat. i, pl. xxv, No. 15. 17 142. 329; 309 l. 19 161; 176. 从 497.

¹ Positions of signs in the text are indicated by f = first; l = last.

21	III		552, twice at end; so also 542; twice at beginning on 159; 180, twice after No. 1.
	-		On 253, line 2, after numeral III. 282 l. Stands alone 242; 121 f. These are apparently identical signs, and employed indifferently for No. 22. The first of them is identical with Sumerian LU (dib), to seize. REC. 456.
22	#		334; 101, twice at end; 16, twice at beginning as on 437; 4, alone at twice at end. 175, twice. Same form as Sumerian GID, LIL, reed mat, REC. 425. The most probable comparison of Nos. 21, 22, and 27 is Egyptian \$10-1\$, district, determ. for province.
24	1		450. Cf. Proto-Elamitic sign, No. 327,
25	Q	0	Accent form of No. 1. 536.
-,	-4		Accent form of No. 1. 39.
	. 50.0	11111	
26	"		391 f. Same as 129.
27 .	H.		424, twice at end. Probably same sense as No. 21. The form is identical with Sumerian LU (udu), sheep, REC. 454. That the sign is No. 21, is proved by comparing 424 with 437. Hence the script does not distinguish between DIB and LU as in Sumerian.
28			ILN. 1924, twice at beginning.
286	0		471 l.
29	8		324 f.
30	8	0	387 l.; 122 f.; 554 l.; 386 l.; or read No. 30 as second sign? 355 l.
31			341.
32			2; 421.
33			306 f.; 38 f.; 337.
34			34 f.
35	XX		550; 139.
36	田		444.
37	M	•	89.
38	M		58.
39	M		438.
40		•	18; 406.
406		#	465, a word in itself with prefix No. 2326 and postfix No. 87.
41	D		191. Cf. No. 56.
42	4.		206.

MOHENJO-DARO AND THE INDUS CIVILIZATION 436 65; ILN. 1924. ILN. 1926. 438; 444. 346. 46 Preceded by a numeral sign, 282; 456; 47 l.; 269; 96; all have this sign after No. 178 and before terminal sign No. 68. 110; 579, with No. 48, which indicates two different signs. At the end this sign is usually followed by the ending No. 68. 121 with ILN. 1924 f. accent B. 188; 412 f.; 170 f.; 199; 420; 23 f.; 107; 458; 447 f.; 139; 134. At the end this sign is usually followed by the ending No. 87; cf. 247 boustrophedon, with 107, etc. Value ma, mu. 19, 5 f.; 29, 9 f. 245; CHI. i, pl. xi, 23 f., 190. 33; 35 f. Ligature with No. 219. 350; 180; 447, in all cases followed by No. 68, as is its cognate No. 47, and preceded by 50 the fish-sign. It is probably No. 47 with A accent. 33; 335. 51 319. 420; 215; 6. 53 Accented form; 405. 389. 54 426. 55 336; 1917; 72. 56 302; 329. 321. 52. 59 434. 142; 340; 77; 396. Bow and arrow? See No. 198. JRAS. 1912, 700 C. 62 84; 14; 99; 557; 553; ILN. 1924; 20.

```
325.
                             343.
 65
                            °54 f.
                             173; 343; 336; 204 l.; 70 l.; 163 l.; 138 l.; 580; 116 l.; 110 l., twice; 227 l., twice; 138 l. This is certainly a possifix occurring after the homo determinative,
                                  as No. 87. Cf. 116, with 339, and 227. Value ja.
                             This sign occurs repeatedly in the Jemdet Nasr script, but is unknown in Sumerian. See
666
                                  OECT. vii, Sign List, No. 408.
                             545, twice.
67
                             Apparently a terminal sign, or postfixed determinative. 456 l.; 238 l.; 319 l.; 269 l.;
68
                             .96 l.; 75 l.; 180 l.; 158 l.; accented form, 51.
This is the Sumerian sign for "plough", value apin, pin.
                10 B
                             444 l. Probably = No. 68.
69
                             403 at end followed by postfix 87.
                             477; 165 f.; 212 l.; 578 f.; 476 f.; 206 l. Identical with Sabæan letter Beth inverted.
                                  The sign seems to be an inflectional ending or postfix. Value pa. ILN. 1926; l.,
                                 on two texts.
                            ILN. 1926.
                            209 f. Probably accented form of No. 70.
                            99; 544.
                            413; 131.
                             131; 150.
                             142; frequently followed by numbers, ILN. 1924. Value ya.
75
                             557; 425; 202; 142; 147; 170; 389; 340; 30; 544; 90; with accent B, 310.
                             128. No. 75 is clearly ya, B. 33.
756
                            463; JRAS. 1912, 700 B; 3; 464 f.; 8; 38 l.
                            61.
77
                            ILN. 1926.
78
                            ILN. 1924.
788
                            420.
                            286; 336; 47; 367.
80
```

438 MOHENJO-DARO AND THE INDUS CIVILIZATION 115; 816; 81. 81 22. Compare Egyptian pictograph for "papyrus bush", Erman, Grammatik, 215, No. 42. ILN. 1924; 1926. Undoubtedly a plant pictograph. See Delaporte, Cat. i, pl. ii, No. 8. 83 286. 86 The most frequently employed sign of the script, and certainly either an inflectional ending or determinative. 245 l.; 120 l.; 188 l.; 222 l.; 178 l.; 432 l.; 211 l.; 385 l.; 122 l.; 21 l.; 466. 325 l.; 351 l.; 339 l.; 142 l.; 369 l.; 459 l.; 296 l.; 160 l.; 253 l.; 231 l.; 226 l.; 305 l.; 81 l.; 99 l.; 557 l.; 174 l; 95 l.; JRAS. 1912, 700 B. 66; 553; CHI. i, pl. xi, 22; 412; Delaporte, Cat. i, pl. ii, No. 8 l. Within the text 286; 418; 139; 448; 122;262; 160; 553; 119. As first sign, rare. Value la? Accented form. 122; 347. Accented form of No. 87; 234; 179; 253; 222; 442; 155; 395 f.; 99. 88 329. Accented form of 88? 888 490 l. 88c Accented form of No. 87; 535; 29; CHI. i, pl. xi, 23 f.; 247. Accented form of No. 87; 469; 548; 420; 21; 461; 70. ILN. 1924. 393. 429. See 264b. 402. Same sign as 89? 434. Same sign as 90? 49; ILN. 1924. 233; 237. 494. 178; 142; 97; 294; 374. 415. 52. See No. 149.

```
Apparently an inflection or postfix. RA. xxii, 36 l.; 7 l.; 361 l.; 207 l.; 76; 537; 35; 395; 80; 159. Commonly after number-signs. It is similar to the Sabæan letter Hhā.) Value gha. This sign is found scratched upon vacant spaces of inscribed
                                 tablets at Kish' of the Fara period, circa 3200 B.C.
                             Accented form, 51 l.; 397.
                             150; 60; 48.
                             130.
                             Same sign as No. 96, or accented form of it. Cf. No. 15.
                             RA. xxii, 99; ILN. 1924, after numeral at end; 40; 580; 246 at end after numeral,
                                  as 418; 6; 449; 448; 439; 411; 220; 25.
                            If No. 113 (cf. 448) is a numeral, 410 belongs here.
                             For this sign within the text, 539, after No. 6. See No. 230. Accented form 309.
                             179; 209 l.; 203. Identical with Sabæan letter Tau, and Egyptian sign for "divide,
                                  count", Erman, Grammatik, 228, No. 7.
986
                             Accented form, 393. Cf. No. 130.
980
                             Accented form 53 l.; 136 l.; 435; 440.
                             13; 193. Probably same sign as No. 99; 21; 412; 413.
                            398. Sign defaced.
                             100 f.; 321; here it begins a word within the text; in both places with accent 1.
                                 101 l.; 370; 102 l.; 33; 87; 396 l.; 413 l.; 101 l.
                X
                            Accented form; 149; 195; 100 f.; 321; 12. 106 f.; 390 f.; 149 f.; 95.
     'IX
                            ILN. 1926.
                            355; 321; 373; 404; 283. Value ga.
                A
                             391. A accented form, 262.
                             32.
                             527.
                             242 f.; 155 £
                             Accented form, 400 f. on line two.
                             427 l. .
                             132.
```

MOHENJO-DARO AND THE INDUS CIVILIZATION 440 383. 105 309. 106 47; 33 (with accent B). 107 Compare Egyptian pictograph psd, back, spine. 108 397; 357; 400. 109 319. Accented form of 109. 69. IIO 357-III ILN. 1924. II2 Apparently two forms of the same sign. Cf. No. 97, and 410 with 285; 448; 538; 149. 113 544 f.; RA. xxii, 56; 90 l.; 242; 110; 211; 130; all before fish-sign. 265 l. After No. 266, on 425; 127. Value ta. Accented form of 113, 349. 21. 115 51; ILN. 1924; 401; 436, 116 JRAS. 1912, 700. C.L.; 185 f. Accented form 108. 8; 29; 69; 539; ILN. 1924. Accented form 67. Accented form 186. Cf. Sumerian KUR, mountain range, REC. 287; 555; 197; 459, after No. 120 with which it forms a ligature in some texts; 160; 420; 201; 54; 247, before No. 47. Followed by postfix No. 124 on 197; 459; 160; or by the postfix No. 87, on 201; by accented postfix No. 89 on 420; by No. 88 on 420. Similar sign in Egyptian means "foreign land" (\$3-\$1-1), which is also the original Sumerian meaning. 130, followed by No. 87; 186; 495. Ligature of Nos. 119 and 120; 416; 5266, both followed by No. 87. AMA 537; 66; 123. Cf. Proto-Elamitic sign, Scheil, No. 839.

1206 Accented forms, 367; 49; 540; 274 182. Sign defaced, 66 f. Cf. Sumerian zu, to know. 90. B 471. 321. A postfix, determinative or ending; see No. 119. At end with No. 175; 32; 41; 277; 103; 198; 534, followed by No. 266, at end with No. 178; 347; 324. At end after 266; 147; 170; 8; 3; 168; 345. At end with No. 176; 380; 583 f.; 286 1.; 225 1. Within the text, ILN. 1926. See No. 226. 30. Within the text after No. 175, ILN. 1926 (). 556 after No. 175. ILN. 1924 f. 111. Same sign as No. 219. Resembles Sabæan letter Fā. Identical with Sumerian sign for DUG "good", REC. 206; Proto-Elamitic sign, 720 + 865. Same sign as No. 232? 305; 94 f.; 215 f.; 67. The Sumerian ideograph for "heart", REC. 255, is obviously not this sign; see the early forms, ibid. 78 f.; 139 f., on line two. Accented form 494 f.; 340 f.; 433 f.; 246 f.; 115 f.; 326 f.; 369 f.; 97 f.; 181 f.; 127 f.; 57 f.; 80 f.; 476 l.; 477 l. Within the text, 426; 97. On 386 this sign 1266 stands at the beginning of the name of a profession, or N. Pr. 551 f. 183. Cf. the Sumerian sign Sargadu, REC. 215. 329. 362 l. Ligature of 125 and 96. Note that 96 is also an ending. 128 99, independent sign standing beneath the text as No. 217. 1286 ILN. 1926 f. Same as No. 26. 129 Accented form of 125, 360 f. Cf. No. 99, and Proto-Elamitic sign, No. 726. 227; accented form of No. 125. Cf. No. 98. 1300 Same sign as No. 234. 285 f. before No. 113; 432; 338 l. This sign probably means 1306 "city" as does the corresponding Egyptian determ. for city; Erman, Grammatik, 217, No. 1. It is totally different from the Sumerian pictograph for "city", REC. 358. 1-18 f. Accented form, 416 f. See No. 234. Accented form, 387 f.

```
MOHENJO-DARO AND THE INDUS CIVILIZATION
                         195 l. Value o, u.
132
                         370; 267.
133
                         549; 13; 27; 87; all after the hare-sign, No. 168, as also 370.
                         107 f.; 494.
134
                         195 f.; 475 f.; 279 f.; 27; 295; 28; 20; 426; 23.
135
                         306.
136
                        ILN. 1924 l.
137
                        Delaporte, Cat. i, pl. ii, T. 24 L. See No. 87.
138
                        Delaporte, Cat. i, pl. ii, T. 24. Cf. No. 83.
139
                        Delaporte, Cat. i, pl. ii, T. 24. The sign is not very clear on the impression, and its form
                             is to be restored from 309.
                        RA. xxii, 56 f. It is possible that the Brāhmī character sa, B. 39, is derived from this or
                             No. 142.
              8
                        RA. xii, 56; Delaporte, Cat. i, pl. ii, T. 24. Cf. the Egyptian sign determ. for "to bind", if.
                        ILN. 1924.
                        RA. xxii, 56.
                        214 f.
                        540 f.; 464; 226.
145
                        340.
                        426 f.
                        Accented form 474.
                        ASR. 1923-4, pl. xix, 15.
                        574, in two places.
                        172 f.
                        12; 58; 139; 265; 211 f. See No. 95.
                        315; 395; 52.
```

```
ILN. 1924 f.; followed by No. 68.
150
                           1446. Partly obliterated. Probably to be restored as No. 151.
1506
                            464; 446 f.; CHI. i? pl. xi, 22; cf. No. 212.
151
                            ILN. 1924.
                            36; at end followed by suffix 87; 188; 460; 311. 11; 72 before and after homo-sign
                                473 f. and l. 472 f.; 471; l. on A after No. 264. 108 f.; 185. Identical with
                                Sabæan letter Rā. It has also the same form as No. 162 with opposite position. No.
                                162 is also identical with the Sumerian sign SUS, REC. 257, which indicates the fraction
                              2 1/6 and the Proto-Elamitic sign, Scheil, No. 127, 3, which indicates 1/5 there. 257 l.
                                on line 3.
1536
                            41 f.; 160°f.
                            321 ·f.
1530
                           444 f., after prefix 233; also 20.
                            321. Before fish-sign.
153d
                            403. Before fish-sign. 212 f.
                            At end followed by postfix 87; 23; 499; 540, and cf. No. 265 also in same posizion which
                                seems to indicate an identity of No. 153 with 264 and 154 with 265. 461 l.; 221 f.
                                after prefix 233b, and compare 114, which again indicates 154 = 265. 421 in text;
                                397 after? But 540 has 265-154-87, which excludes the identification suggested;
                                see also 42.
1546
                            21 f.
                            72, after No. 155.
156
                            At end followed by suffix No. 87; 120; 351; 224; 5, which seems to prove the identity
                                of Nos. 156 and 154.
                            439 f., followed by No. 87, 11 followed by No. 153.
1566
                            Delaporte, Cat. i, pl. xxv, No. 15 f.
156c
                            373.
                            43; 434 f.
157
                 見
1576
                            289.
                            42; followed by postfix No. 87. Certainly two signs, Nos. 156 + 265.
158
                            74. This is hardly an accented form of No. 153. See No. 2696 and 2746.
159
                            186 f.; 457 f.; 302 f.; 161; 100. Cf. No. 161 pictograph of a shield
160
                            Accented form, 361 f.; 29 f.; 160 f.; 469 f. 24 f.; 469 f.; 24 f.
1606
```

MOHENJO-DARO AND THE INDUS 444 225 f. Cf. No. 160.4 457. 161 162 16 l.; 403. But used with No. 153 to enclose signs. See Nos. 167, 171, 201, 175c. Accented form, 296. Value ta. See remarks under No. 153. 163 164 194, after hare-sign, No. 168. 8 f. 1650 166 431. 167 6. 4 77; 306. 168 262; 370; 27, followed by No. 133; 194 f. This seal has hare, fowl, and a bird with deployed wings. Pictograph of a hare. For some reasons these signs have been turned 90 degrees to the left. 1686 115; 49. 1680 549; 67. Cf. 370 with 549, where this sign and No. 168 are followed on both seals by Nos. 133-99-87. 1684 No. 168d on 87 is apparently identical with No. 168g. 168e 101; 12, followed by Nos. 133-99-87; 179. Compare 12 with 13, same text? 168f 13, followed by Nos. 133-99-87. 21. 168g The bird signs Nos. 169-72 indicate various kinds of birds as do the corresponding Egyptian pictographs 228. 36; 338, twice at beginning. 219 f. Bird with deployed wings. 194. 207 followed by No. 267 and postfix No. 96. ASR. 1923-4, pl. xix, 15. This sign clearly suggests the emphatic or gunu form of the Sumerian sign for bird. For the bird sign in Sumerian, see Thureau-Dangin, REC. 33, and especially Revue d'Assyriologie, vi, 142, Rev. ii, 3, and Rev. i, 1, Sign MUD "bird with egg" according to Genouillac, RA. vi, 160; almost identical with this sign. Dél. Per. ii, 129.

1750 175d 1766

182

Probably intended for a fish, but the resemblance to the Sumerian sign HA is not very close.
41; 277, at end with postfix No. 124; also 32; 198, often combined with No. 178;
175-178 on 47; 324 (+ No. 124); 14; 79, Nos. 176-175 only on 455.

Nos. 178-175 on 53; 534; 88; 313.

Not combined with a fish-sign, ILN. 1924; 1926; JRAS. 1912, 700 A.
81; 110; 188; 32; 211; 142; 130; 120; 104; 365; 254; 23; 261; 19; 87, before hare-sign; 75 f.; before No. 212.

Accented form 177 l.

148.

Accented form, JRAS. 1925, 697.

Accented form, 211.

95; 170; 380, after No. 177; 455, before No. 175; CHI. i, pl. xi, 22 f. After No. 177; 380; 350.

156, after No. 175. Accented form.

Accented form of No. 175. 540; 40 f. Often with No. 178 in the order 177-178; 400; 544; 21; 404; 379; 87; 109; with No. 175 in order 177-175; 350; 321; 470; ILN. 1924 f. with No. 176 q.v. Not with a fish-sign; 420; 349; 418 f.; 269; 202; 580; 283; JRAS. 1912, 700 C.

Accented form 425 f.; 48 l.; 66; 403; 316, only sign on this seal. 156, after No. 175; 147.

Probably also a fish-sign. With No. 175 in order 178-175; 534; 79, etc. See No. 175. With No. 177 in order 177-178; 400, etc. See No. 177.

Not with another fish-sign; 198; 347; 557; 351.

Accented form, 535 l.; 36.

Not same sign as No. 176. 370 f.; 308, after No. 176. Cf. 370 with 549, same text?

75 f.

415 f.

4. The unaccented form is found on a seal in ILN. 1924 L.

395.

The homo-sign. A large number of variant forms occur and there is not complete consistency in regard to its direction. It occurs (1) en face, (2) facing right, (3) facing left. They are given in this order. This is the only pictograph which does not consistently face to the left, as do the numerous homo pictographs of Egyptian. The Sumerian pictograph for man faces right naturally, but its early form is not known, REC., 289. It is clear that these forms of the homo-sign express some special aspect of human activity, as do the Egyptian forms. En face 336 l., after No. 87; 386, after No. 87, followed by No. 30; 225, followed by 124. 214 l., after No. 87; so also 115; 536; 295; 109. This sign is undoubtedly a postfixed determinative indicating that these are

321, line 2. Faces left.

198 Man with bow and arrow. In Egyptian this figure is kneeling and in act of shooting, there determ. for "foe", and as noun afti, "foe." 12 f. on line 2, 70 followed by No. 66. 406, probably beginning of a title. 15; 400, line 3, ideograph in N.Pra. 142 f.; 305 f.; 92 f.; 69 f.; 142 f.; within text 190; 60. When this sign is a determ., it usually stands at the beginning. 403 f. Man with boomerang. 43 f. 199 42 f. 1996 165 f. A ligature of 70 + 182? 575 f. On this seal the two signs, 2016 followed by No. 175, seem to be enclosed in the 201 parenthesis sign. 2016 449 f. Compare the Egyptian pictograph for "pass over, go beyond", Erman, Grammatik, 202 p. 208, No. 100. 203 307 l. The inscription is not clear and this sign is not entirely certain. 348 f.; 301 f., followed by No. 268 and postfix No. 96, 331 at end followed by No. 87. 204 101 f.; 373 f.; 339, after No. 266 f., and before No. 184 f. and No. 87 l. Same text on 116, but No. 183 in third place. 266 after No. 268. 151 f. 555 f. Same sign as No. 204, facing left. 482, only sign on the seal. 206 A plant pictograph, 537. Palm leaf, 42 The Egyptian sign im3, determ. for "tree", is similar. 207 473. 208 200 473. 191. Probably sign No. 204. 200. 75, followed by postfix No. 68. 161 at end followed by postfix No. 87. 126 at end followed by postfix No. 87, 340.

RA. xxii, 99 f.

MOHENJO-DARO AND THE INDUS CIVILIZATION 448 320 f. at end followed by postfix No. 87. 216 Defaced sign on 16, standing alone beneath the text. 536. 188. On 325 an independent sign beneath the text; 278 f. on line 2, boustrophedon. 219 253 f. 398 f. 235 f.; 369; FRAS. 1912, 700 A; 536; 215; ILN. 1926 (in all places followed by 220 No. 265). 552 preceded by No. 265. 315 f.; 99; 257. 2206 Accented form, 321 l.; 12 l. on line 2; 397 l. 22 I 80 at end followed by postfix No. 96. 409; 467, at end, followed by No. 97 (96). 325, text A; followed by Nos. 268 and 188 (187), 50 f.; 37; 303 followed by No. 268. Value cha. 221 l.; 421. Cf. the Sumerian sign TEMEN, REC. 217, value te. 478; 236 f. 0 400, line 3. Value tha. 349 f. No. 124 inserted in 219. 292 l., and note that No. 124 usually comes l. 226 142; 105; ILN. 1924, at end followed by No. 137. 227 389; 35. 28. 77, same sign? No. 96 inserted in No. 219. 217 f.; 173 f.; 224 f.; 49 f.; 45 f.; 540; 126. This 230 sign is here either in the first position or it immediately follows the initial sign. 95 at end followed by postfix No. 87. 161 f.; 430 after initial sign; 164; 6; 66; 467 f.; 445 l. 2306 204 twice before postfix No. 66. 552; 84. One of the most frequently recurring signs; and usually at the beginning. See No. 126. ILN. 1924 f., followed by No. 118, 245 at end followed by No. 87. 351 f.; 36 l. 232 Stands alone on 486. Apparently variant of No. 232. 147 f. ILN. 1926 f., followed by No. 178; 32 f.; 372 f.; 424 f.; 537 f.; 232 f.; 96 f.; 22 f. 553 within text. 19 f.; 554 f.; 88 f.; 317; 393 f.

334 f.

```
131 f.; 39 f.
                            547 l.; 110 f.; followed by No. 47, and at end followed by No. 666. 186 at end followed
233
                                by No. 96. ILN. 1924, at end followed by No. 66b. 490 twice f.; 406. ILN.
                                 1926 l., 266; 444 f.
2336
                            Accented form, 221 f.; 438 f.; 61 f.; 88 f.
                            Accented form. 79 f.; 76 f.; 178 f.; 10 f.; 400 f.; 105 f.; 344 f.; 327 f.; 104 f.; 148 f.; 468 f.; 498 f.; 407 f.; 126 f.
                           Accented form. 134 f.; 335 f.; 192 f.; 543 f.; 345 f.; 189 f.
                            478. But see 264c.
                            445 f.; 59 f. See No. 130.
                            83 f. twice; 15 l.; 47 f.; 319 f.
                            Sign defaced, 3.
237
                             52 f.; 302; 121; 20 f.; 175; 329; 336.
                            330 f.
238
                            203 1.
239
                            174 f.
240
                            276; 421 1.
241
                            544.
                            209 l.
242
                            252 f.
243
                            553; 67 f.; 55. Value va.
                            574.
                            182 f.
                            46 f. Probably a musical instrument.
                            Delaporte, Cat. ii, pl. xxv, No. 215.
                A
                            253.
                            Goose in circle. ILN. 1924; stands between two vegetation signs, No. 91 (on either side).
```

Accented form; 66. Probably two signs, 441. Apparently two signs, 113.

429 Ligature.

2641

389, sign defaced

265

48 after No. 96c; 218 f.; before No. 182; 120 f., before No. 175; 278 l. after No. 96; 552 f.; 81 f. and between 816-175; 120 f.; 369; 536 before No. 87. 23; 549, before No. 175. 215; 77; 42; 541; 146; 263 at end before No. 87. 222 after No. 876. 357 l.; 14 f.; after prefix No. 2326, as on 82, both before fish-sign; see also same series in the text, 324; and 468 f.; 114; 79 where prefix is No. 2336. 342 f. 48; 47 (second and fifth signs); 8; and in text apparently beginning of a second word. 406. 205 f. and third signs. 65 f.; 266 l. On 551 f. after prefix 1266 before fish-sign, same sense as 14; 82; 432 after vowel sign i, No. 2696.

266

429 after No. 75, before No. 264b; 425 before No. 113; 253 l.; 326 l.; 147; 65; 94; 105; 68; 3; 168; 345; 170 at end followed by postfix No. 124; and 30 followed by 124b. 77 f.; 414; 429; 456; 431. 400 f. on line 3. 54î; 104. The combination of Nos. 266–124 occurs on 251 with postfix No. 66. It will be seen from these citations that No. 265 is usually followed by the postfix No. 87, and No. 266 by the postfix No. 124 at the end of a word.

2666

Doubled sign; 539; 54.

266c III II

No. 265+266, two signs, 191.

267

574 f. and l. on both A and B. 126 followed by No. 96. At end with No. 96, 395. 321 f. on line 2.

268

325 f., before No. 223. 6, 16; 13, 2; 50 after No. 223, in all places before No. 188 or 187. 54, etc. See 266b.

269

Accent on No. 109.

2696

Accent? on No. 241. But on 448 f.; 432 f.; 366 f.; 257 f.; Delaporte, Cat. i, pl. ii, T. 24; this is clearly a sign. See No. 159.

270

41; 372; 361 at end followed by No. 96; 339 f.; 365 f.; 411; 220; 91 with No. 96. 116 f.; 282 f.

271

207 at end with No. 96; also 449; 246; 229; 418; 159; 143; 441; 31; 346; 133. 453. 321 l. on line 2. 471. C., 19.

272

301 between homo-sign and No. 96. 460 f. 92. 51 f. 6. 311, with No. 96; 402; 418.

273

66 between No. 120 and No. 87.

274 (пиц)

253 f. See No. 162. 123 between No. 120 and No. 87; also 466.

1745 II

74 at end, followed by No. 87; 296 f.; 130; 400, line two; 131; 39. See accents F and G.

275

439, followed by No. 97; also 35; 227; 243; 249. 314 before fish-sign.

276

273 f. followed by No. 265; 548 f.; followed by No. 87.

MOHENJO-DARO AND THE INDUS CIVILIZATION

548 f.; 156; 414, at end followed by No. 87. 3; 79; 404. 470 f. 105 f. after prefix No. 233c. 415.

278 III 211; 442; 553. 146 f.; after prefix No. 232b, also 344. 25 with No. 96. 435 f.; after prefix No. 48.

2786 Delaporte, Cat. i, pl. xxv, No. 15; 478 l.

This is a hapax and there is no similar combination, 535. Perhaps a prefix like No. 233d +

No. 264 is to be understood. Cf. 189.

580, sic! Cf. No. 66.

281 LKILL 382.

82 \$ 426.'

283 Zr 144 f.

284 W000

452

285

286

287

. 288

POSTCRIPT

Since the preceding study of the Indus Valley script was made over a year ago I have, in the interval, completed my study of over 200 tablets in the most archaic Sumerian script, excavated at Jemdet Nasr, 17 miles N.E. of Kish, in 1926. These tablets supply an almost complete corpus of the most archaic Sumerian signs, and, as they were found with a mass of painted pottery akin to the painted ware of the Indus Valley, which accompanied the Indus Valley seals, it is obviously necessary to comment upon the relation between the two scripts. In the following study I shall refer to the new early Sumerian sign list based upon the Jemdet Nasr tablets as PI = Pictographic Inscriptions from Jemdet Nasr, Oxford Editions of Cuneiforms Texts, vol. vii, Herbert Weld Collection of the Ashmolean Museum. In the Jemdet Nasr tablets we possess the earliest large collection of tablets made by the people who invented the originally pictographic script used by the Sumerian people.

As to the racial character of the people who invented the Sumerian script, as it appears in its earliest known stage of development on the Jemdet Nasr tablets, and on a certain few archaic stone tablets of the same period from Nippur, Kish, and other unknown sites, I express the opinion that they are Sumerian. In any case the language of these texts is Sumerian, although the grammar is in such primitive state that the verbal system of Sumerian had not yet been attained. The signs have the same sense as in the later Sumerian texts. A few god names, which are Sumerian, such as the great trinity An, heaven god, Enlil, earth god, Enki, water god, and lamma, the divine protecting genius, appear in these texts, but the determinative for god and in fact the entire system of determinatives of the later Sumerian are almost entirely absent. A good many new signs, unknown in later Sumerian, are present in this archaic script, and some of them are identical with signs of the Indus Valley script.


There is, then, definite linguistic evidence that the Jemdet Nasr and contemporary civilization of the Mesopotamian Valley at the time when the painted pottery was made, On the Zoological side there is from the Jemdet Nasr texts the definite conclusion that the buffalo, Bos bubalis (No. 128 of PI.), is the well-known prehistoric animal (represented by the Sumerian pictograph DUN) which disappeared in Mesopotamia about 2600 B.c. The archaic period represented by the painted pottery and tablets comes down to about 3500 B.C., and goes back to an indefinite period, certainly as early as 4000 B.C. There is also the astonishing fact revealed by the Jemdet Nasr tablets that the horse was in use then; for the ideogram for horse (ausu-kur) "ass of the mountain" occurs as a pictograph here Of the important mammals occurring on the Jemdet Nasr tablets, viz. the ox (Bos primigenius), the buffalo, and the horse, one certainly occurs on the Indus Valley seals, the Bos primigenius (VS 3503, etc.); the bison (VS 3026, HR 2657, DK 2137, HR 4348 et passim) is also characteristic of early Sumerian art (Hilzheimer, Die Wilrinder im alten Mesopotamien, 10-13).1 As to the animal most characteristic of the Indus Valley seals, with thin long nose, long forward protruding horns, and smooth body, I suggest that the forward protruding horn is stylistic, and that this is the buffalo, so characteristic of early Sumerian art, and the DUN, so common in the domestic life of the Sumerian people from the most archaic period until this animal disappears about the time of Sargon of Accad.2

² The buffalo (bos bubalis) is illustrated in seals 304-6 and appears quite distinct from the unicorn commonly figured on the seals.—[ED.]

I am sorry to dissent from Professor Langdon regarding these identifications, but seal VS 3503 (= No. 312) appears to me clearly to depict the Indian bison (Bos gaurus), as do all the seals from No. 308 to No. 326. Similarly, the seals VS 3026 (= No. 333), HR 2657 (= No. 335), DK 2137 (= No. 339), and HR 4348 (= No 329) seem to me just as clearly to portray the Indian humped bull (Bos indicus). So far as I am aware, the bos primigenius is not represented on the seals. See p. 70 supra.—[Ed.]

It is, however, on the epigraphical side that I wish to emphasize more definite connection between the most archaic Sumerian script and the Indus Valley script than I was disposed to admit in my preceding study. The entire method of writing Sumerian pictographs in the upright and natural position exists on extremely few monuments which have survived, notably on the earliest of all known survivals of writing, the pictographic stone tablet of Kish (Langdon, Excavations at Kish, vol. i, pl. xxxi). The great mass of archaic Sumerian texts already represent the signs turned 90 degrees to the left. This was done to facilitate rapid writing from left to right, whereas the original pictographs were written from right to left in perpendicular position. In the new system every sign lies on its left side. Now the Indus Valley system, which still retains many traces of its pictographic origin, remained true to its original principle; the writing still runs from right to left and the signs still retain their upright position. Obviously any comparison of the Sumerian signs with the Indus Valley signs must be made after turning each Sumerian sign 90 degrees to the right, thus bringing it into its original upright position. By utilizing the new material in PI., which provides far more ancient and extensive material than in REC., employed by the author in his preceding study, the following list of signs can be compared :-

- 1. No. 15 = PI. 84, " gal, " large," " great." No. 16 is, therefore, gal-gal, plural of No. 15.
- 2. No. 2 = PI. 35, + maš, "half."
- 3. No. 8 = PI. 6, na, za, ia, "stone," "jewel."
- 4. No. 33 = PI. 246, gug, "beans" or "peas".
- 5. No. 29, cf. PI. 360,
- 6. No. 37 = PI. 293, M, disappeared in later Sumerian.
- 7. No. 63 = Sum. ug, "to die," "dead."
- 8. No. 66 = PI. 408, so in secondary position. Very common in J-N, but disappeared in later Sumerian. Value unknown.
- 9. No. 68 = PI. 125, picture of a plough, values apin, pin, engar, uru.
- 10. No. 70 = PI. 44, \int , disappeared in later Sumerian.
- No. 71. This sign is so nearly identical with the form of TUM in its secondary position, PI. 338, values ib, tum, that the forms may be identical.



- 12. No. 83; cf. PI. 144, possibly the pictograph of the date palm, values sag, gisimmar.
- 13. No. 98 = PI. 12, /, disappeared in later Sumerian.
- 14. No. 100 = PI. 270, A, value lal, "lacking," "missing," "to weigh," "bind."
- 15. No. 113, perhaps Sum. A bad, "open."
- 16. No. 264 = PI. 1, values as, rum, dil. Cf. value ra, suggested from Brāhmī.
- 16. No. 265 = PI. 41, tab, "double," "pair."
- 17. No. 266 = PI. 57, &, three. Used as a syllable, not as numeral, in Indus script and usually so in PI.

- 18. Ng. 276 = PI. 64,
- 19. Nos. 277-8, cf. PI. 75-6, 1111 and 11111
- 20. No. 283 = PI. 192, hu, mušen, pag, dar.

Among the identifications above, (2) has the value mas, but the Brāhmī value ka; (14) value lal, la, but Brāhmī ga. If the two main hypotheses be assumed as true, (1) the identity of the Sumerian and Indus signs, (2) the derivation of the Brāhmī characters from the Indus signs, then it must follow that the Āryan Sanskritists gave values derived from their own language to these characters. In other words they knew the ideographic meanings, translated them into Sanskrit, and derived the syllabic values from the Sanskrit words.

The connection of this script with Sumerian is favoured by the many similar or identical signs noted in the sign list and in the new comparisons above. There is also the extraordinary fact that both Sumerian and Indus Valley scripts freely employ numerical ideographs as syllables and that the two both read from right to left.

OXFORD.

13th July, 1928.

CHAPTER XXIV

HOUSEHOLD OBJECTS, TOOLS, AND IMPLEMENTS

HE objects described in this chapter have all been found in houses and buildings at Mohenjo-daro. Those whose uses are obvious come at the beginning of the chapter and those of uncertain or unknown use at the end. In each section stone objects are described first, followed by objects of pottery and other materials.

Querns (Pl. CXXX, 16 and 17; Pl. CLVII, 54)

Proof of Agriculture.

Judging from the very large number of saddle-querns found, the only form of quern apparently used at Mohenjo-daro, agriculture must have been in a flourishing state at that place. As far as we know at present, wheat was the principal corn that was grown. Samples of this cereal have been found in several parts of the site, badly carbonized, but otherwise sufficiently well preserved for the species to be identified. No samples of barley or other forms of grain have yet been found, but it is quite possible that barley or rice was grown as a food for the lower classes.

Materials.

The better made querns are almost invariably made of basalt; in one case grey granite was used. They are all very much worn, the depression in some of them being as much as 5 inches deep, so that only the end of a stone muller could have been used. The grain appears, therefore, to have been pounded rather than rubbed.

Dimensions.

The average size of these querns is 21 by 9 inches. The nullers, one of which is shown lying on its quern (Pl. CXXX, 16), are usually natural pebbles averaging 11 inches long by 4 inches in diameter. Only the ends of these mullers seem to have been used, to judge from the bruising of the stone. Sometimes blocks of red sandstone or quartzite were used as querns; and from the frequent irregularity of their bases one must suppose that they were intended to be partly sunk in the floor of the house or courtyard. The upper surface of a new quern was roughly dressed flat and then by much use was worn into a deep groove.

None of the querns can be dated to any particular period by either their shape or the

Stone of which they are made, and they are found at all levels.2

¹ The circular revolving quern does not occur in either Mesopotamia or Egypt until late times. It is known in India from about the second century B.C.

Similar saddle-querns are known in both Egypt and Mesopotamia and at Anau, where they date from very early times. They are always worn into a deep concave shape by the rolling of a long stone to and fro. They are also common in the historic period in India.

No. 16 in Pl. CXXX (VS 1925) is really a large natural pebble of basalt, 17.5 inches Descriptions. long by 9.5 inches wide by 4 inches high, whose centre has been very much worn down. Six feet below surface. House XXV, VS Area.

No. 17 in the same plate (VS 790), which measures 19 inches long by 11.5 inches wide by 6 inches high at the ends, is a very roughly dressed pebble of sandstone. Two feet below surface in House XVIII, VS Area.

No. 54 in Pl. CLVII (HR 742), which is of basalt, is somewhat better made. It has roughly fashioned feet for use on a brick pavement. Five feet below surface. Southern end of Chamber 3, House II, Block 2, HR Area.

Pumpelly's suggestion that the similar querns found at Anau were made by cracking Mode of apart a small quartzite boulder and rubbing together the two new surfaces till they became manufacture. flat seems likely to be correct.1 Most of the querns found at Mohenjo-daro have curved bases, which were roughly dressed. It was probably found that the natural surface of the two halves of a boulder allowed of too much rocking and that it was necessary, in consequence, to roughen the surfaces.

Palettes (Pl. CXXX, 11 and 31; Pl. CXXXI, 39 and 40; Pl. CXXXIII, 4-6)

Stone palettes of good workmanship are not often found at Mohenjo-daro. Four examples, in slate, of especial interest are described below:—

No. 11 in Pl. CXXX (VS 416) measures 12.3 by 8.8 by 0.8 inches. It is beautifully Descriptions. made and one side shows evidence of much rubbing, but no trace of colour is left. Level, 3 feet below surface. House XIX, Block 3, VS Area.

No. 31 in the same Plate (VS 1853) measures 11.5 inches long by 4.3 inches at its widest part by 1.2 inches thick. At first sight it appears to be a stone adze, but it has no edge. It is slightly irregular in shape, especially at the rounded end, and neither side shows any trace of rubbing. Level, 4 feet below surface. House XXV, VS Area.

A fragment of stone (VS 2894) found in the same area must have been part of a palette very similar to No. 31. It measures 4.85 inches wide and 1.45 inches thick; the length cannot be determined owing to breakage. Level, 3 feet below surface. Room 65, House XVII, Block 2, VS Area.

Another palette found in the SD Area (SD 2577), made of dark grey slate, measures, 4.7 by 4.25 by .95 inches. Both faces show signs of very considerable use, the centres of each being very much worn down on both sides. This palette seems originally to have been considerably longer, for a fracture at one edge has been partially rubbed down. There is a trace of red pigment on one side. It was found in Chamber 18 of the Great Bath at a level of 7 feet below the surface.

These palettes are all made of a very dark coloured slate, with the exception of SD 2577, Material and which is somewhat lighter in colour. They were probably used for rubbing down hæmatite use. and other colours for cosmetics or for painting pottery. We have not found the mullers that were used with these palettes, but these also were probably made of slate.

Ordinary flat pebbles, as shown in Pl. CXXXI, 39 and 40, were also used as palettes, Use of flat and even neatly shaped rectangular pieces of sandstone (Pl. CXXXIII, 4-6). Some of the pebbles. latter show evidence of much wear, and as the majority were found in houses they were robably used in the preparation of eye-paint and other pigments.

¹ Explorations in Turkestan, vol. ii, p. 477.

Flint Implements (Pl. CXXXII 1-19)

Flakes and cores.

No short flakes.

The flint implements found at Mohenjo-daro are of the simplest description, most of them being long flakes that were probably used for cutting up meat and for other household purposes. Both the flakes and the cores from which they were struck are found in nearly Indeed, it is probable that flakes were struck by the servants of the household whenever an implement of this kind was required.

No specimens of the short flakes, both notched and unnotched, that are so common in the early periods of Babylonia, have been found at Mohenjo-daro, nor any traces of pottery sickles; and it is evident that flint was not used in the manufacture of sickles as it was in both Sumer and Elam. Nor are the well-finished lanceolate and leaf-shaped flint arrow-heads, that are such a feature of the earliest periods of Sumer and Elam, found at Mohenjo-daro, though they are known in other parts of India. We do not yet know what lies hidden in the Early strata of Mohenjo-daro, but from the Intermediate and Late strata it is evident that in those periods metal working was in an advanced state and flint implements were no longer in great demand. The art of working flint had, however, by no means languished, for we find this and allied materials in almost universal use for the manufacture of beads and The latter, especially, are beautifully made, being first flaked into shape and then ground.

The form of flint most used at Mohenjo-daro was a brownish-grey chert which was

often mottled. Neither flakes nor cores show any trace of patina.

Besides being used for striking flakes from when required, the flint cores found had in some cases been used as rubbers, e.g., No. 13 in Pl. CXXXI (DK 774), whose edges near its point have been rubbed down and slightly polished. This core is 4.15 inches long and comes from Space 7, Block 1, Section C, DK Area, 4 feet below the surface. The tip of No. 14 (E 80), which is 4 inches long, has been rubbed down to a rough edge and may have been used as a burnisher. This last was unearthed in the street between Houses I and II, Trench E, M, DK Area. Level, 4 feet below surface.

The sides of two flint flakes (HR 1821 and DK 2361) had evidently been used as

polishers and in consequence were greatly worn down.

Three flint implements have been found which may have been used for agricultural purposes; they seem too big to have been used as weapons of offence or defence and are too unfinished to be any kind of tool. They are rectangular in shape and very roughly flaked. The cutting edge has two sloping sides and the long sides of the implement are square cut. Nos. 17 and 19 have slightly convex faces, but those of No. 18 are plane, or practically so. In conception these implements are not unlike the shoe-last celts of the Danubian culture, except that they are not ground and lack the plano-convex appearance of the Danubian specimens.1 In fact the examples found at Mohenjo-daro appear never to have been used; they give the impression of being unfinished, and it may have been intended to grind their surfaces.

No. 17 in Pl. CXXXI (VS 1218) is 10.2 inches long by 4.3 inches wide at the edge and 3.2 inches at the butt; it is 2.1 inches thick. Roughly made of light grey and brown mottled chert; neither in finish nor in the quality of the stone does it approach No. 18. Level, 3 ft. 6 in. below surface. House VIII, Block 2, VS Area.

No. 18 (B 728) is 9.9 inches long by 4.15 inches wide at the edge and 3 inches wide at the butt; it is 1.4 inches thick. It has been carefully chipped into shape from chert of good

Polishers.

Descriptions.

¹ These were used as hoes, and it is possible that the examples from Mohenjo-daro were employed as ploughshares.

'quality and is dark grey in colour. Level, 6 feet below sulface. Street between Blocks 2 and 3, B Section, DK Area.

No. 19 (VS 2079), which is broken, is 9.3 inches long by 3.5 inches wide near the edge, and an average thickness of 1.75 inches. It is made of coarse brown chert and unfinished. Level, 5 feet below surface. North-western corner of House XXV, VS Area.

Dish-Borer (Pl. CXXX, 35)

This is the only stone drill (VS 256) that has been found at Mohenjo-daro. From its Egypt. shape it must have been used to fashion the interiors of stone bowls and dishes. implement is made out of a hard, greyish-black stone resembling a fine-grained basalt. It measures 7.4 inches long. The upper side is slightly concave, the bottom convex, and the two ends are very strongly bevelled. This drill was worked by means of an upright forked stick that fitted the recesses in the sides. It is not known whether the movement was circular or to and fro, but either way would be quite effectual. A very similar drill has been found in Egypt, but its date is uncertain. Level, 4 feet below surface. House XXIV, Block 3, VS Area.

Burnishers (Pl. CXXX, 10, 32, and 36)

Nos. 10 (HR 4612) and 32 (L 514) are spindle-shaped objects of highly polished chert Triangular with the ends tapering to blunt points. They are triangular in section, but with the angles shape. rounded off. No. 10 was found 2 feet below the surface in House LIV, Block 7, Section B, HR Area; and No. 32 was unearthed at the level of 2 feet below the second pavement in Chamber 30 of L Area, and belongs to the Late Period. A portion of each is unfortunately missing.

No. 36 (C 1853) measures 7 inches long and is 0.65 inch thick in the middle. It is made of polished chert. It resembles in every way the two burnishers just described. Level, 3 ft. 9 in. below surface. Chamber east of Room 25, Block 11, Section C, DK Area.

These burnishers could have served several purposes, but from the very hard stone Used on metals. of which they are made and the care with which they were polished, it is probable that they were used on metal. The last especially is a fine specimen of the lapidary's art.

Mace-heads (Pl. CXXX, 1-3; Pl. CXXXIV, 25-30)

Mace-heads of stone were certainly used as weapons by the inhabitants of Mohenjo-daro; Materials. they have been found in sufficient numbers to show that they were in common use. They were made in alabaster, sandstone, cherty-limestone, and also in a hard, green-coloured stone somewhat resembling slate.

Three distinct types occur, namely, (a) pear-shaped, (b) lentoid, and (c) of the shape Types. shown in Pl. CXXXIV, 27.

Type (a) (Pl. CXXXIV, 25 and 26).—The mace-heads of this type closely resemble specimens that have been found in Elam, Mesopotamia, and Egypt from the earliest times.

No. 25 (VS 679) is well made and shaped, of a hard black stone 2 which is highly polished. Pear-shaped. It was found at a depth of 6 ft. 6 in. below the surface, and is of Intermediate date. House XXI, Block 3, VS Area.

No. 26 (HR 4625) is of alabaster. It was found quite fortuitously by a basket-boy just outside the HR Area.

> 1 Petrie, Tools and Weapons, pl. lii, fig. 73. ² Hornblende (?).

Lentoid.

Type (b) (Pl. CXXX, 1-3 Pl. CXXXIV, 28-30).—No. 28 in Pl. CXXXIV (DK 2862) is made of well-burnt pottery and there is, therefore, some doubt whether it really is a macehead. It certainly resembles one in shape, but the hole through it is the same diameter throughout. East of Room 5, Block 2, Section B, DK Area. Level, 4 feet below surface.

No. 29 (VS 2393) is made of a hard olive-green stone with a smooth, but unpolished surface. Its hole is very regular, but the circumference of the mace-head is not a perfect circle. It was found 6 feet below the surface of the ground and is of Intermediate date. Western side of House XIII, VS Area.

No. 30 (HR 4078) is of sandstone with a smooth, but unpolished surface. It, too, is irregular in shape, but has a well-drilled hole. It was found 3 feet below the surface in Section B, Block 5, House XXVII, Room 31, of the HR Area, and is of the Late Period.

Nos. 1-3 in Pl. CXXX are illustrations of the same type of weapon:—

No. 1 (VS 1957) is 4.2 inches in diameter and 1.8 inches thick, and made of a compact cream-coloured limestone. The hole is .65 inch in diameter at the surface on either side and slightly smaller in the middle of the stone. Level, 6 ft. 6 in. below surface. Room 113, House XVII, Block 2, VS Area.

No. 2 has no catalogue number; it was picked up outside the area of excavation. It is made of grey granite and measures 2.85 inches in diameter by 1.35 inches thick. The hole through its centre is 1.1 inches in diameter at each end and 0.65 inch in the middle.

No. 3 (VS 3046), which is of a dark-coloured slate, is 4.4 inches in diameter and 1.65 inches thick. The hole through its centre is 0.8 inch in diameter throughout. Level, 4 feet below surface. Room 66, House XVII, Block 2, VS Area.

VS 74 (not illustrated) is a mace-head of alabaster, which measures 4.05 irrches in diameter and 1.1 inches thick. Its hole is also of the same diameter throughout, namely, 0.6 inch. Alabaster is a very soft material for a weapon of this kind, and it is doubtless for this reason that this mace-head is rather badly damaged. Level, 1 foot below surface.

Effective weapon.

There is no doubt that the lentoid-shaped mace-head was a very effective weapon, even though the edge-like ridge around the middle was rarely sharp. Most of these heads were carefully made and they were, no doubt, valued possessions.

Elam and Egypt.

The lentoid type of mace-head is found in both the Intermediate and Late levels at Mohenjo-daro, and has also been found at Susa made in limestone.^{1,2} It does not seem to occur in the ancient sites of Mesopotamia, but a disc-shaped mace-head is found in the middle predynastic period of ancient Egypt. The latter, however, differs in some respects from the Mohenjo-daro type.³

Partially perforated.

Type (c) (PI. CXXXIV, 27).—The only specimen of this type (HR 5035) is made of alabaster and has been badly weathered. Though the shape is very unusual—especially the beading around the hole at the base—the same type has been found at Harappā, but made in copper or bronze. The hole by which it was fixed to the shaft does not pierce through the head; it only extends about three-quarters of the way through. This macehead, which is of Intermediate date, was found 6 feet below the surface in Section B, Rlock 3, House XVI, Room 31 of the HR Area.

¹ Mém. Dél. en Perse, t. i, p. 194, fig. 420.

² De Morgan, La Préhistoire Orientale, t. iii, p. 101, fig. 1a.

³ The lentoid form is, however, known in pre-dýnastic Egypt. See Brunton and Caton-Thompson, The Badarian Civilization, pl. liii, fig. 9.

The same kind of beading as around the base of the above mace-head is to be found in several mace-heads from Anau 1; the shapes of these are, however, entirely different.

The form of the holes through these mace-heads is the same in all but those of Type Biconical holes. (c), which in shape also is radically different from the others. Similar biconical holes are known in the mace-heads of ancient Egypt, Mesopotamia, and Elam. They are thought to have been bored with the aid of wet sand and a hollow reed,2 the boring being certainly done from both ends.

The pear-shaped mace-head is a very common type all over the ancient world, especially Pear-shaped in very early times. It was used by the neolithic Cretans, in early Thessaly, by the people mace. who occupied Sardinia in the chalcolithic period, and by the peoples of the Caucasus and Danube regions. It was common in pre-dynastic Egypt as well as in the early dynastic period, and it was extensively used by the early Sumerians.3

Mace-heads were probably not used bare, but lashed all over and thus firmly secured Method of to a'shaft. The latter was probably made of wood or, as Professor Petrie suggests, of hide,4 securing to which had a certain amount of spring; and care, therefore, had to be taken that the head was shaft. firmly secured to it. And it is likely that the lashings were of raw hide, which if applied green, would have become taut on drying. The mace-head is not used in Sind at the present day, but it still survives amongst the tribesmen of Mesopotamia, where, made of bitumen and pear-shaped, it is carried by nearly every man on even quite short journeys abroad.

Weights (Pl. CXXX, 25, 26, and 34; Pl. CXXXI; 20-35; Pl. CXXXIII, 9)

The large number of weights that have been found at Mohenjo-daro, in small houses as well as large, suggests that the housewife realized the necessity of checking the weights of the goods she purchased. These weights range from large examples that had to be lifted with a rope or metal ring to very small ones which were probably used by jewellers for weighing precious metals. The majority are cubical in shape, quite unlike those used in Babylonia. We have as yet found no scales; probably these were of very simple pattern, and if they were made of wood, as seems likely, they would have perished long ago.

The large number of the weights found is remarkable. I do not think any ancient site outside India has produced so many. They are not found in any special place, which, might be a manufactory, but are well distributed all over the city. The careful way in which they are made and the hard stone of which they are composed suggest that the authorities had some surveillance over their manufacture; it may be that the use of false weights was a penal offence.

All the weights found at Mohenjo-daro have been examined and weighed by Mr. Hemmy, formerly Principal of the Government College, Lahore, whose results are given in Chapter XXIX:

According to their shape the weights can be conveniently divided into seven types:-

- (a) Cube-shaped.
- (b) Spherical with flattened base and top.

1 Pumpelly, Excavations in Turkestan, vol. i, pl. 167, fig. 390.

- ² Childe, Dawn of European Civilization, p. 24.
- 3 Mackay, Sumerian Palace and "A" Cemetery at Kish, Field Museum, Chicago, pl. xxxvii, No. 3.

4 Petrie, Prehistoric Egypt, p. 22.

Division into types.

- (c) Cylindrical with flat base and top.
- (d) Weights with hole for suspension.
- (e) Barrel-shaped.
- (f) Cone-shaped.
- (g) Hemispherical.

Type (a): Cube-shaped Weights (Pl. CXXXI, 20-35).—Cube-shaped weights were by far the most commonly used. Sometimes the cube is perfect, sometimes one measurement is smaller than the other two. The smallest weight that has been found of this type (DK 140) measures 0.3 by 0.25 inch, and the largest (B 165) 6.8 by 6.0 by 3.8 inches.

Material.

Weights of this type were always made of chert, which is often beautifully banded or mottled. They were first roughly flaked into shape and then ground, and finally carefully polished. An unfinished weight (VS 3210) has been found that had only passed the stage of being flaked into shape (Pl. CXXXIII, 9). This specimen measures 4 inches square by 3 inches high, and was found 8 feet below the surface in Room 113, House XVII, Block 2, VS Area.

Descriptions.

Type (b): Spherical weights with Flattened Base and Top (Pl. CXXXI, 60 and 61).—Only six weights of this type have been found up to the present. The smallest of these (DK 2032), which is made of chalcedony, measures 0.7 inch in diameter at its equator and is 0.55 inch high. The flat top and base are 0.45 inch in diameter. Level, 4 feet below surface. From the street east of Block 4, Section B, DK Area.

The dimensions of the next in size (C 2974), which is made of flint, is 0.74 inch in diameter at its equator and 0.5 inch in height. The top and base are 0.5 inch in diameter.

Its weight is 6.7 grammes. Level, 6 feet below surface.

DK 1265 is 1.1 inches in diameter at the equator and 0.9 inch high, with the top and base 0.7 inch in diameter. It is made of chalcedony and is unfinished; there is no trace of polishing. Level, 2 feet below surface. Room 22, Block 4, Section B, DK Area.

DK 2255 is 1.1 inches in diameter at its equator and 0.9 inch high. The top and base are 0.65 inch in diameter. It is made of agate and weighs 27.2 grammes. Level, 1 ft. 6 in.

below surface. Room 17, House VIII, Block 3, Section B, DK Area.

The two weights illustrated in Pl. CXXXI, 60 and 61, are both of large size. No. 60, the first and larger (VS 1821), is beautifully made in a hard, yellow limestone and measures is inches high. It weighs 5.556 kilograms, and was found 1 foot below the surface of the ground. House IX, Block 2, VS Area.

No. 61 (VS 1173) is made of cherty-limestone and is unfinished. It bears pickmarks all over its surface which it was perhaps intended to remove. It stands 4.35 inches high. The weight of this object is now 2.792 kilograms, but if smoothed down it would have weighed considerably less than this. Level, 2 feet below surface. Between Houses

XVIII and XXXIII, VS Area.

With the exception of DK 1265 and VS 1173, these six weights were very carefully made. The rarity of specimens of this type suggests that they were used for some special purpose. They have not been found in Mesopotamia and are unknown in Egypt.²

Type (c): Cylindrical Weights with Flat Base and Top (Pl. CXXXI, 41).—The weight that is illustrated (HR 19) is the only example of its type that has been found up to the present.

1 It should be noted, however, that this particular weight is practically half that of VS 1821, which leads one to suspect that no further finish was intended.

² A weight of this type, from Aphrodisias in Caria, is in the Ashmolean Museum, Oxford. The type is said to occur also in Palestine.

Rarity of type.

It measures 1.8 inches in diameter by 1.4 inches high, and was found close to the surface of the ground.

Type (d): Weights with Hole for Suspension (Pl. CXXX, 25, 26, and 34).—Three heavy Perforated conical stone objects with holes bored in their tops for a cord were probably used as weights. weights. Their careful finish and great size make it unlikely that they were used as loom-weights.

No. 25 (HR 4618) is made of green slate and has a carefully smoothed surface. It is 8 inches high and its flat, semi-polished base is 5.8 inches in diameter. Holes, each 0.95 inch in diameter, bored diagonally downwards on either side of the apex, meet in the middle of the top of the stone. Level, 4 ft. 5 in. below surface. The weight could not be determined satisfactorily owing to the stone being badly chipped. Room 11, Structure L, Block 7, HR Area.

No. 26 (DK 3079), which is of grey limestone with a roughly finished surface, is 9.9 inches high. Its smooth, but unpolished flat base is 5.5 inches in diameter. is a V-shaped hole through the apex, as in No. 25. Its weight is 10.262 kilograms. Level, I ft. 9 in. below surface. Room 2, House I, Block I, Section B, DK Area.

No. 34 (VS 1899), made from light green slate, is 5.9 inches high, and its slightly concave base, which shows the polish of much wear around the edge, is 7.1 inches in diameter. The V-shaped hole through the apex is 0.85 inch in diameter. The weight is 6.903 kilograms. Level, 6 feet below surface. From Room 15, House VIII, VS Area.

These three weights were probably slung on a rope or metal ring. If the latter, the ring Handles. must have been included in the weight, and the weights, therefore, without such rings, would in consequence be only approximate. With such heavy objects as these, one would have expected to find evidence of a great deal of wear at the edges of the base where they were presumably dragged along the ground. No. 34 alone shows traces of this kind

A weight, which is similar to these in every respect, has been found, in conjunction with Nal. painted pottery, at Nal in southern Baluchistan. Weights of this shape are also known at Harappā in the Panjāb and are still in use in India. I can find no evidence of their occurrence outside India, despite their simple and somewhat obvious shape.

Type (e): Barrel-shaped Weights (Pl. CLIV, 5 and 7).—Only three examples of this type of weight have been found at Mohenjo-daro, though more specimens are known from

No. 5 (HR 1115) is made of a dark-grey slate with an unpolished surface. It is slightly **Description**. chipped at one end, and measures 1.92 inches long by 0.55 inch in diameter in the middle and 0.3 inch at the ends. Weight 14.019 grammes. Level, 2 ft. 6 in. below surface. Court of House VII, Block 3, Section A, HR Area.

No. 8 (VS 2509) is 2.18 inches long by 0.79 inch in diameter in the middle and 0.4 inch at the ends. It is made of a hard black stone,2 and weighs 33.553 grammes. Perfect and moderately polished. Level, 5 ft. 6 in. below surface. House XII, Block 2, VS Area.

C. 315 is made of a hard black stone similar to VS 2509. It is 3.3 inches long by 0.85 inch in diameter in the middle and 0.5 inch at the ends. As this weight was in places very badly chipped, it was not weighed. Level, 6 feet below surface. Chamber 14, Block 12, Section C, DK Arga.

This type of weight was used in Egypt, where it was frequently made of hæmatite. It Known in is found in considerable numbers in Mesopotamia, where in early times (pre-Sargonic) it Egypt.

¹ Mem. Arch. Surv. Ind., No. 35, pl. xv (b), 78.

² Apparently hornblende.

was made of limestone and even alabaster, and in the later periods of hæmatite. Weights of this shape were also common in early times in Elam, where they were made of limestone, marble, granite, and other stones.

Various.

Type (f): Cone-shaped Weights (Pl. CLIV, 6).—No. 6 (DK 3131) is a conical object of hard black stone that may possibly be a weight. It measures 0.95 inch high with a flat base 0.72 inch in diameter, and is 15.264 grammes in weight. It is well made and carefully polished. Level, 3 feet below surface of ground. From street between Blocks 1 and 2, Section B, DK Area.

A piece of lead of conical shape (L 418) found in Chamber 104 of the L Area is thought to be a weight. Unfortunately, it was so corroded that its weight could not be ascertained with accuracy. It measures 1.4 inches high and has a flat base 0.7 inch in diameter. From its level it can be dated to the Late Period.

An object that may possibly also be a weight is seen in Pl. CXXXIV, 21. It is made of a hard black stone and stands 2 inches high. As at first it was thought not to be a weight, it was not put on the scales.

Type (g): Hemispherical Weights.—A limestone object (DK 7056), which is hemispherical in shape, 0.85 inch high and with a flat base 1.05 inches in diameter, is thought to be a weight. It weighs 26.5 grammes.

Weight of Indefinite Type.—VS 467 is a piece of limestone, weighing 13 grammes, which is slightly irregular in shape with a flattened top and base. Though irregular in shape, there is reason to think that it may have been used as a weight. Level, 5 feet below surface of ground. Room 4, House XXI, Block 3, VS Area.

Net-Sinkers (Pl. CXXXIII, 21; Pl. CLVII, 61)

Grooved stone.

This curious object (Pl. CLVII, 61, DM 285), of Intermediate date, appears to be a netsinker. It is made of limestone and measures 2.5 inches high; its flat round base is 1.4 inches in diameter. A shallow groove, 0.15 inch wide by 0.1 inch deep, cut entirely round the stone, even across the base, was doubtless intended for a cord. Level, 7 feet below the surface.

Lend object.

A large circular piece of lead (L 394), measuring 6.7 inches in diameter and 1.4 inches high, was found just below the surface of the ground in Chamber 88 of L Area. It is flat one side and slightly rounded on the other, and there is a roughly bored hole through the centre which, being almost square, seems to have been made with a chisel. From the flat base two holes were bored diagonally, one on each side of the central hole, which they joined in the middle of the object. Judging from the roughness of its surface, this net-sinker was cast in sand. The illustration in Pl. CXXXIII, 21, shows the underside of this object.

Whetstones (Pl. CLV, 8)

A considerable number of stone objects that have been found at Mohenjo-daro appear to have been used as whetstones. But the great majority of them are natural pebbles of slate or sandstone, and no attempt was made to bore or groove them so as to hang them on a cord, or to shape them in any way. Only the hone or rubber, which is illustrated and which is made of sandstone, was cut into a more or less regular shape. It was found at a level of 4 ft. 6 in. below the surface.

Ayvils (?) (Pl. CXXX, 24)

Two objects of hard sandstone, both very carefully shaped into an animal form somewhat Stone animals. resembling a mongoose, seem much too heavy to have been children's toys. It is suggested that they were perhaps used as anvils for fine metal work. That shown in Pl. CXXX, 24 (D 457), measures 6.5 inches long by 2.1 inches high. The round eyes are very slightly in relief, and the legs short and rudimentary. Level, 5 ft. 6 in. below surface. Western end of Trench D, DK Area.

The second object (HR 2592), which is not illustrated, is 3.1 inches high and is very similar, though not so well made as the first. Level, 3 ft. 6 in. below the surface. Court of House VII, Block 3, Section A, HR Area.

Lattices (Pl. CXXXI, 43 and 46; Pl. CXXXIII, 10 and 11; Pl. CLVIII, 14)

No. 10 in Pl. CXXXIII (VS 2540) is a fragment only and measures 7.1 inches long by Bevelling. 0.9 inch thick. It is of alabaster, and well made and cut. The straight edge of this latticework is slightly bevelled, doubtless for the purpose of securing it in place. Both surfaces are perfectly flat. Level, 6 feet below surface. House XIII, Block 2, VS Area.

No. 11 (VS 2766) in the same plate is made of the same stone as the above, but is badly weathered. It now measures 4.8 inches long by 0.95 inch thick. Level, 7 ft. 6 in. below surface. Room 76, House XIII, Block 2, VS Area.

These two fragments of lattice-work do not belong to one another; they were probably Windows. used for covering windows. Their design coupled with the natural translucency of the stone of which they were both made must have made them effective window ornaments.

A few fragments of pottery have been found at Mohenjo-daro that also appear to have Pottery been gratings. They are all flat pieces of pottery made of a porous clay, light red in colour gratings. and containing a little lime. The baking is rather harder than usual.

No. 46 in Pl. CXXXI (DK 1462), which is 0.95 inch thick, is typical of many other The incisions were roughly cut with a knife. Level, 3 feet below surface. Space 13 between Blocks 14 and 15, Section C, DK Area.

The fragment (C 160) illustrated in No. 43 of the same plate is rather more elaborate in design, and is further decorated with roughly scratched lines. Level, 4 feet below surface. Room 8, Block 12, Section C. DK Area.

A grating illustrated in Pl. CLVIII, 14, differs from the others just discussed. This object (HR 6148), which is made of some soft white paste and measures 2.32 inches long by 1.5 inches wide by 0.21 inch thick, was made in a mould and now bears no sign of having been glazed. In all probability it once formed one of the sides of a small box. Level, 8 feet below surface. From Courtyard 39, House XVII, Block 3, HR Area.

OBJECTS MADE OF POTTERY AND OTHER MATERIALS

Ballista Balls (?) (Pl. CXXXI, 44 and 45)

A number of large round balls of baked clay or roughly chipped stone have been found Clay and stone. in various parts of Mohenjo-daro. Similar objects in roughly baked clay, found in Mesopotamia, chiefly at the bases of city walls of the early periods, are thought by many to be ballista balls,2 though there is no direct evidence that the large catapult was used in Sumer in early times.

1 The paste, however, of which it is made is so soft as to have needed the protection of a glaze, which seems to have entirely disappeared. ² Banks, Bismya, p. 336.

No. 44 in Pl. CXXXI (2D 2199), which is somewhat irregular in shape, averages 2.6 inches in diameter. Found at a level of 3 ft. 3 in. below the surface in constructions (Block 4, No. 4) south of the Great Bath buildings.

No. 45 (SD 2310), which averages 2.6 inches in diameter, is also slightly out of shape.

Recovered from Block 4, Southern Buildings Section. Level, 7 feet below surface.

Both these balls were roughly shaped from a coarse light grey chert by bruising the face all over, presumably with another stone. But it is possible, of course, that they were themselves used as hammer-stones to crush grain or even harder materials.

A number of egg-shaped objects of badly baked clay found in the SD Area average 3.75 inches long by 2.5 inches in diameter. They were found 4 feet below the surface inside, not outside, a building.

At the northern end of Chamber 45 in L Area, fifty or more of these egg-shaped lumps of badly burnt clay, averaging 4 inches long and 2.5 inches in diameter, were found carefully stored in a large pottery vessel. Further south in the same area quite a number of large pottery balls were found lying in confusion upon the ground outside a very thick enclosure wall. Their shape, material, and the spot where they were found certainly lead us to regard them as weapons of offence or, rather, of defence.

Sling Balls (Pl. CXXX, 4 and 5)

We are on surer ground with regard to the sling-balls of which so many have been found at Mohenjo-daro, and it is clear that in ancient times the sling was known and used in the Indus Valley, as in Sumer and Anau in Turkestan.

Two types of sling-pellets are found at Mohenjo-daro; one round and about the size

Types of sling-pellets.

Reason for shape.

of a large marble, the other, which is more rare, ovoid in shape and averaging 2.5 inches long by 1.6 inches in diameter. No. 4 (L 730) and No. 5 (L 642) in Pl. CXXX illustrate the ovoid form; this type occurs at all levels. Both types were made by hand with varying degrees of finish. In all cases they were baked. The round pellets may have been propelled by a sling of ordinary type or by means of a bow such as is used in Sind at the present day for killing small birds. No. 4 was found in Chamber 9, Block 5, and No. 5 in Chamber 65, Block 2, of the L Area. There must have been some reason for making the ovoid form of bullet; perhaps this shape imparted a spin to the projectile and made it more accurate in its flight. The form would also, I am told, lead to a certain amount of ricochet and thus increase the chances of a hit. On the other hand, it should be remembered that the original sling pellet was doubtless a water-worn pebble, which is much more commonly ovoid in shape than round. There is no doubt that in ancient times the ovoid form of sling-pellet was preferred in some countries, for it is commonly found made both of baked clay and dressed

Foreign connections.

stone.

Both ovoid and round sling-pellets have been found in early Sumer 2 and Turkestan,3 as well as in India. No specimens have been found at Susa,4 as far as I am aware, but Herzfeld has recently unearthed ovoid sling-pellets in neolithic settlements on the Iranian

.

Oviform

objects.

¹ The same kind of thing has been found in a large pre-Sargonic building at Kish (P.). Those lumps, however, were of unbaked clay.

², I have found them at Jemdet Nasr and their use extended down to neo-Babylonian times. Mackay, A Sumerian Palace, pt. ii, pl. xliv, fig. 3. Also Hall and Woolley, Ur Excavations, vol. i, p. 53.

³ Pumpelly, Explorations in Turkestan, vol. i, p. 164, fig. 364.

⁴ Since this was written I have found a specimen from Susa illustrated in Mém. Dél. en Perse, t. xx, p. 108, fig. 11. This is dated to the Second Period.

table-land; he dates them prior to the First Period of Susa. Further west, the sling was certainly in use in later times in both Palestine and Syria, but not in Egypt, where it was introduced at a still later period.2 Petrie has pointed out that in twelth dynasty scenes in which the sling is represented the weapon is only carried by Syrians.3

The sling probably originated in a stony country where ammunition would be plentiful. Sling. When its use extended to alluvial countries the pellets would naturally have been made of pottery. It is essentially a weapon for open country, and in the hands of a skilled man is a formidable weapon.4 Quite possibly it was introduced into India from the west; and at a very early period, as the specimens from Mohenjo-daro prove.

. Flesh-rubbers (Pl. CXXXIII, 13-17)

A very unusual barrel-shaped object of pottery (VS 3612) must certainly be a fleshrubber. It is pictured in Pl. CXXXIII, +4, and measures 8.8 inches long by 3 inches in diameter in the middle and 1.15 inches in diameter at each of the slightly rounded ends. The clay of which this object was made was heavily mixed with angular grains of sand with the result that the surface is very rough; indeed, the sand is so plentiful that there was only just sufficient clay to bind it together.

A flesh-rubber such as this would probably have been used for ablution purposes, and Use for as it is hollow, it was light enough to be easily held in the hand. Found in Chamber 37, ablutions. House I, VS Area, at a level of 3 feet below surface.

No. 13 in Pl. CXXXIII (D 368) measures 7.4 inches long by 3.5 inches in diameter in its middle. One end is pointed and the other flat. The rasp, which is hollow, is made of a light red clay plentifully mixed with sand. It shows evidence of much use on one side, which in consequence has become slightly flattened. Level, 10 feet below surface. Trench D, DK Area.

Of this form of rasp quite a number have been found, mostly in a broken state, showing that their use was extensive. It is found in both the Late and Intermediate Periods.

Another form of rasp (HR 3121), shown in Pl. CXXXIII, 15, is of quite a different Second type. Though also barrel-shaped and elongated, measuring 3.2 inches long by 0.85 inch in diameter in the middle, one side is flattened and made rasp-like by pricking it all over. This type of rasp was easily and cheaply made of such a material as pottery; but it was liable to be worn smooth, as, indeed, happened to the specimen described, which was found at a level of 7 feet below the surface in Room 49, Structure V, Block 2, Section B, HR Area.

No. 16 (also HR 3121) is 3.25 inches long and 0.6 inch thick. It has a rounded back and slightly concave surface, and is hand-made and hard-baked. Level, 7 feet below surface. Room 136, House X, Block 2, Section B, HR Area.

No. 17 (HR 966) measures 4.1 inches long and 1.95 inches broad. The back is rounded and the slightly concave face has been roughened in more or less regular lines. roughening became smooth through regular use and the rasp was discarded on this

1 Illustrated London News, 25th May, 1929.

² According to Sir Arthur Evans, there is "no evidence of Minoan use of slings", but he remarks that "this form of missile (sling-stone) had an early vogue on the Maipland side". See Evans, Palace of Minos, vol. ii, pt. i, p. 345.

4 Judg. xx, 16.

³ Petrie, Tools and Weapons, p. 36. Note, however, the slings of plaited linen thread recently taken from the tomb of Tutankhamen. As, however, these slings were found in a play-box, they may possibly have been looked upon as playthings or curiosities only. Illustrated London News, July 20th, 1929.

account. Hand-made, of superior clay and hard-baked. Level, 4 feet below surface. Chamber 125, House X, Section B, HR Area.

Heavily fired.

Rasps of the shape just described are fairly common at Mohenjo-daro. Some of them have been almost vitrified in the kiln in the attempt to make a more durable article, but the teeth have in every case been entirely worn down. Practically all the specimens found have a slightly concave face, doubtless in order that they might more easily fit the surface of an arm or leg, while rubbing it down.

Rubbing the body with a rough substance to cleanse it is practised in India at the present day, fine sandstone being used wherever it can be procured. And rasps of pottery, to be used for this purpose, can be purchased in most bazaars. The same method of cleaning the body seems to have been customary in Mesopotamia in pre-Sargonic times, for we found in a cemetery at Kish that almost without exception a piece of fine white sandstone was buried with the dead, though it occupied no particular position in the grave.

Spindle-whorls (Pl. CXXXI, 62-71; Pl. CLVI, 8-10; Pl. CLVII, 36, 40, 41, and 47)

Weaving.

Spindle-whorls are found in such numbers at Mohenjo-daro that the art of weaving must have been practised extensively. We know for a certainty that cotton was one of the materials used for this purpose, and there can be no doubt that wool was also employed as the sheep was well known, being one of the many animals portrayed in clay. Whether flax was grown we do not at present know, but there is a strong probability that linen was used also for garments, as was the case in early Sumer and Egypt.

Spindle-whorls were mostly made of pottery, but there are some of shell and many of faience. The pottery whorls are of three types:—

Materials.

- (a) With a single hole in the middle.
- (b) With two holes in the middle.
- (c) With three holes in the middle.

Types of spindles.

The spindle used with the first type of whorl was a plain wooden stick, as shown by the size of the hole that it fitted. With the two-holed type a partially cleft stick must have been used, and the fact that the holes are invariably small suggests that the two separate ends of the stick were sharpened to fit them. It is uncertain whether or not a stick was used with the three-holed type of whorl, but there would be no difficulty in splitting the end of a wooden spindle into three parts to fit into the holes.

Two-holed whorls.

No spindle-whorls, except of the first type, were found at Jemdet Nasr, but the two-holed type has been found by Campbell Thompson at Abu Shahrein in Mesopotamia,³ and also in early Elam ⁴ and Turkestan.⁵ The three-holed type seems peculiar to the Indus Valley civilization.

Spindle-whorls of the first type are very common and generally indifferently finished, if in pottery. In some cases they were actually cut from broken potsherds and more or less roughly rounded. They vary considerably in size, ranging from 1.25 inches to 2.1 inches in diemeter. The top is generally rounded and the base flat, but sometimes the base is slightly concave.

- 1 Of practically identical shape.
- 2 Report on the Excavation of the " A" Cemetery at Kish, Field Museum, Chicago, p. 15.
- 3 Archæologia, vol. lxx, pl. x, b.
- 4 Mém. Dél. en Perse, t. i, p. 118, fig. 203.
- 5 Pumpelly, Explorations in Turkest in, vol. i, pl. xli, fig. 21.

Some of the two and three-holed whorls have a deep groove, averaging o 1 inch wide by Grooved edges. 0.15 inch' deep, around the edge. The reason for this groove is difficult to fathom. could hardly have been used for winding thread, as it would take but little. It is, however, possible that the thread was drawn along it to consolidate the fibres, though it could not be said that the grooves of any of the whorls show any signs of wear.1

The spindle-whorls made of shell (Pl. CLVI, 8-10) are somewhat rare. They range in Shell whorls. size from 1.5 inches to 1.85 inches in diameter and the single hole in the centre averages 0.18 inch in diameter, which suggests that a metal and not a wooden spindle was used with them. Shell spindle-whorls are all slightly out of the true owing to the curvature of the shell

from which they were cut.

Two strange objects, both of which are made of pottery and seem akin to the pottery Unknown whorls just described, are shown in Pl. CLV, 9 and 10. The first has a slightly concave objects. base and a small hole running through it vertically, but the top is almost dome-shaped, instead of being gently rounded. The second is very similar in shape, but is of especial interest in that it is perforated by seven vertical holes, of which five are roughly, in line. These holes are curiously enough not all the same size; the largest hole is in the middle and the smaller holes, four at the opposite poles, are near the edge.

Both these objects are of light red clay, and No. 10—which is so well made that it looks as though it had been shaped in a mould—was originally covered with a red slip. No. 9 is of rougher workmanship and is thickly covered with a white slip, upon which lines, that have now nearly all disappeared, were painted in red. Both these objects have a groove round the edge, which in No. 10 is 0.07 inch wide and 0.25 inch deep. The small size of the holes through them suggests the use of metal spindles, but it is doubtful whether they are spindle-whorlo at all, despite their resemblance to the whorls with three holes. No. 10 was found in Courtyard (2), House LVI, Block 8, HR Area.

Spindle-whorls of faience are also rare. In each the very small size of the one hole again **Faience**

suggests that they were fixed to a metal rod.2

No. 36 (SD 2040) in Pl. CLVII is 2.9 inches in diameter by 0.3 inch thick, with a flat base and slightly rounded top. The central hole is 0.15 inch in diameter. It is made of vitreous white paste with a circle of light blue and both the latter and the outer ring of white are delicately fluted. Level, 4 feet below surface. Outside western wall of Block 7, Southern Buildings Section.

No. 40 (DK 2948) is 1.4 inches in diameter by 0.3 inch thick, with the base slightly concave and the top rounded. The hole is 0.2 inch in diameter. The two glazes used on this object are now white and blue.3 The outer ring is blue, then comes white followed by a narrow ring of blue, then a narrow ring of white, and the centre is blue? These colours were probably originally blue and green. Level, 3 feet below surface. From space between

Blocks 1 and 2, Section B, DK Area.

No. 41 (SD 1894) is 1.4 inches in diameter and 0.4 inch thick. The hole is 0.15 inch in diameter and the base flat. The rounded upper surface is decorated with fluted radii, and the whorl was made of a soft white paste coated with a glaze which is now light blue in colour. It was found in the clay packing between the two brick piers on the northern side of the Great Bath, at a level of 6 feet below the surface.

No. 47 (SD 1231) is 1.4 inches and its hole 0.15 inch in diameter. The base is flat

² Metal rods were also used in Sumer. Report on the "A" Cemetery at Kish, pt. i, pl. xviii, 17.

³ This blue is probably due to cobalt.

whorls.

A similar shallow groove is cut around the edge of a whorl from Susa. This object, however, has only one hole for the spindle. Mém. Dél. en Perse, t. vii, p. 111, fig. 368.

and the rounded upper surface decorated in the same manner as No. 41. The soft white paste is coated with a light blue glaze, which has probably changed from a darker shade. Found in one of the cells on the eastern side of the Great Bath. Level, 6 feet below surface. Nos. 41 and 47 were evidently made in the same mould.

Type found at Kish.

Small faience spindle-whorls very similar to those just described have been found in pre-Sargonic graves at Kish. One found in a grave of that period was mounted on a copper shaft.

Needles (Pl. CXXXII, 1-3 and 5; Pl. CXLIII, 20, 21, and 36 (?))

Bronze and copper.

Both awls and needles are somewhat uncommon at Mohenjo-daro. The needles are made of either bronze or copper and, owing to their thinness and the salinity of the soil, they have become barely recognizable—if they have survived at all. The badly corroded, wire-like pieces of copper and bronze that are constantly found possibly once were needles.

No. 1 on Pl. CXXXII (HR 300) no longer has a point, and now measures 1.95 inches long. It was cut from a piece of sheet copper and is rectangular in section, 0.15 inch wide by 0.05 inch thick. The eye, which is oval and 0.1 inch long by 0.05 inch wide, was made by drilling a number of small holes close together and breaking away the intervening metal. Level, 3 feet below surface. Outside south-east corner of House I, Block 1, Section A, HR Area.

No. 2 (DM 187) is 1.81 inches long by 0.5 inch in diameter, and is made of bronze or copper. The eye appears to have been made in the same way as in the needle above. Level, 9 feet below surface. Stūpa Section, SD Area.

No. 3 (HR 5127). Bone. It is possible that this object may be a needle, for it has a suspicious groove at the top, a portion of which is missing. It is very roughly made and is not completely round. It measures 5.07 inches long. If a needle, it must have been used in sewing a very soft and loosely woven material. The point is much polished. Level, 6 feet below surface. Room 50, House XXX, Block 5, Section B, HR Area.

No. 5 (DK 430) is 3.1 inches long by 0.1 inch in diameter. The point is fine, but rather abrupt. The head of the needle has been badly damaged by corrosion, but there are indications that the eye was formed by bending the head over, as in some of the pre-Sargonic needles at Kish, rather than by drilling a number of holes.² Level, 1 ft. 9 in. below surface. Room 5, Block 9, Section C, DK Area.

Awls (Pl. CXXXII, 4, 6-9, 11, and 12)

Metal.

No. 4 on Pl. CXXXII (L 340) is of copper or bronze, and measures 4.12 inches long and 0.12 inch in diameter. It has a blunt point at one end and a graduated one at the other. Level, 4 feet below surface. Space 91, Block 9, L Area.

No. 6 (SD 2511) appears from its colour to be copper. It is 3.52 inches long and o.1 inch in diameter at its thickest part. It has a point at each end, the lower one being very fine and sharp. Found in Court 4, in the constructions south of the Great Bath, at a level of 3 feet below the surface.

No. 7 (VS 851). Bone. Measures 2.85 inches long. Round in section with one side slightly flattened. Good polished point at one end. From the rough nature of the other end this awl would seem to have been set in a handle. Level, 3 ft. 6 in. below surface. Between Houses XVIII and XXII, Block 3, VS Area.

1 Perhaps also matting?

2 Report on " A" Cemetery at Kish, pt. 1, pl. xix, 11.

Bone.

Pone.

No. 8 (HR 5765). Bone. Point broken and missing. Now measures 4:43 inches long and o 31 inch in diameter at widest part. Evidently made to be set in a handle. Shows a polish due to much use. Level, 7 feet below surface. Room 50, House XXX, Block 5, Section B, HR Area.

No. 9 (HR 6041). Bone. 4.25 inches long. Diameter at thicker end 0.37 inch. Blunt point. Very much polished. Level, 9 feet below surface. Room 87, House IX,

Block 2, HR Area.

No. 11 (HR 4398). Bone. 2.6 inches in length with a rounded top, Level, 2 feet

below surface. Room 37, House XXIX, Block 5, Section B, HR Area.

No. 12 (DK 4563). Bone. Rectangular in section, rounding to the point. 2.93 inches long and 0.25 by 0.21 inch at its broken butt. The rectangular end is decorated on each side with two incised circles set one within the other. This object may once have been of the same nature as the objects depicted in the lower part of Plate CXXXII and then converted into an awl. Level, 9 feet below surface. Room 9, House I, Block 10, DK (g) Area.

Ladles (Pl. CLVI, 26-9)

The four ladles illustrated in Pl. CLVI are all made of shell. They vary considerably Shell.

in size, the largest being 6.8 inches long.

Each ladle was made from a single piece of shell and its size, therefore, was in a measure governed by the size of the shell from which it was cut.1 These objects are naturally irregular in shape, but are otherwise well finished and finely polished. Very similar ladles were used in Mesopotamia in very early times.

No. 26 (HR 2528) measures 2.58 inches long and is well preserved. It was found at the northern end of the main street (HR Area) at a depth of 4 ft. 3 in. below the surface of

the ground.

No. 27 (SD 2617) is 3.55 inches long.

No. 28 (SD 1407) measures 4.65 inches long, and was unearthed from a depth of 11 feet in Room 15, Block 4, Southern Buildings Section.

No. 29 (SD 951), measuring 6.8 inches long, came from Chambers 5 and 6, Block 3, Southern Buildings Section, where it was lying at a depth of 4 feet below the surface of the

ground.

It is possible that these spoon-like utensils were used for oblations and also for drinking Ritual use. from, especially the smaller sizes.2 An exact copy of one (HR 5673) in baked clay was found in the HR Area (Pl. CXXXIII, 12). This copy is rather larger in size than the usual shell Pottery metal. ladles, but it is doubtful whether one so large could have been made of shell for want of a shell of sufficient size.3 The pottery model measures 6.5 inches long, including its handle, and is made of a well-kneaded clay, now light red in colour, that contains a little lime in the form of small particles. Even the slight thickening present on the edges of the shell ladles has been imitated in this pottery model. Found 6 feet below the surface in Passage 20, House XVIIL Block 4, HR Area.

Shell ladles are found in both the Intermediate and Late levels at Mohenjo-daro, and they will probably be found to occur in the Early levels also."

1 Murex (chicoreus) ramosus, Linn. (Red Sea, Indian Ocean, etc.)

² They are used by Hindus at the present day in sacred ceremonials. The Sanskrit name for these dippers

³ Since writing this I have ascertained that some shells of this species attain a length of over a foot.

" Handles (Pl. CXXXII, 14-18)

Faience.

No. 14 (HR 1546) measures 2.2 inches long by 1.0 inch in diameter at its thickest part and has a hole 0.32 inch in diameter through the centre. It is made of faience, which is now a light green colour, and is decorated with three grooves, each 0.1 inch wide by 0.1 inch deep. Each of these grooves contains a black substance that looks like bitumen. Level, 7 ft. 6 in. below surface. From between Houses III and VI, Section A, HR Area.

Ivory.

No. 15 (VS 2651) measures 2·15 inches long by 0·65 inch in diameter at its widest part. The upper portion of this specimen is missing, but the lower has a hole 0·25 inch in diameter. This handle, which is made of ivory, is well carved and shows a polish due to much handling. Level, 3 feet below surface. From Chamber 76, House XIII, VS Area.

Jaisalmir stone. No. 16 (HR 5655). Inside this handle, which is made of yellow Jaisalmīr stone, there still remains traces of the copper or bronze tool to which it was once attached. The hole is 0.15 inch in diameter. This handle, which shows the polish of much use, measures 2.1 inches long by 0.95 inch in diameter. Level, 4 feet below surface. Room 8, House XXXVI, Block 5, HR Area.

Incised decoration.

No. 17 (HR 5409) is decorated in the same manner as No. 15, and, like it, is made of ivory. It measures 2.3 inches long by 1.45 inches in diameter at its widest part. It has a round hole, 0.2 inch in diameter, right through its centre longitudinally. The top of the handle is flat and somewhat roughly finished, suggesting that it was once capped with metal. The incised decoration upon it is divided by grooved lines into four registers, each containing a wavy line. The handle was first made upon a lathe. Level, 4 ft. 6 in. below surface. House XVIII, Block 4, Section B, HR Area.

Inlay.

No. 18. In design this handle is similar to No. 14, but the greater part of its inlay is still in place. The upper portion is missing and the handle is now 1.32 inches long and 0.8 inch in diameter. There is a hole at the top of the handle, now 1.15 inches deep and 0.21 inch in diameter. This hole once extended through the base of the handle, but has been stopped up with the same coloured paste as forms the inlaid bands around it. The handle is made of a hard paste, grey-green in colour. The inlay is of a softer paste and cream-coloured. There is now no trace of glazing on the outside.

Small size.

The small size of all these handles is remarkable; it suggests that, like the modern inhabitants of Sind, the people who used them had very small hands. It is very probable that the handles of the majority of knives and other implements were made of wood and that it is for this reason so few have survived to the present day.

Comparisons with Kish.

These inlaid handles are not unlike some made of faience that have been found at Kish; dated there to the pre-Sargonic period. The main difference between them is that the bands on the Sumerian examples are mainly spiral.²

Cake Moulds (Pl. CXXXIII, 7 and 8)

No. 7 in Pl. CXXXIII (E 946) is 4.25 inches in diameter and 0.7 inch thick. Depth of convolutions 0.5 inch. The base is flat and there are indications that the object was made on a piece of matting. There are traces of a cream slip. Trench E, DK Area. Level, 9 feet.

No. 8 (DK 1924) is 5 inches in diameter at its widest part, but is not entirely round. It is 0.7 inch thick and the depth of its convolutions is 0.5 inch. Though, like the first, this

¹ Compare this handle with one of pre-Sargonic date found at Kish. See Mackay, A Sumerian Palace, pt. ii, pl. xliii, No. 10.

² Mackay, Report on the Excavation of the " A" Cemetery at Kish, pt., i, pl. xviii, fig. 21.

object is a copy of a shell, it was not moulded from one, as the slight irregularity of the convolutions show. Coated with a cream slip. Level, 4 feet below surface. Chamber 1, House II, Block 2, Section B, DK Area.

Both these objects are made of a clay that has burnt a light red in colour. They are Cake moulds. exceedingly well fired. It is suggested that they were used as moulds for fancy bread or for shaping sweetmeats.1 They cannot be described as rare, as quite a number of fragments have been found, though only one whole specimen, which is illustrated, has been unearthed so far. A square object allied in conception to the objects illustrated is also known. square-shaped ridges filling up its interior instead of a spiral one.

OBJECTS OF UNCERTAIN USE

The objects that fall into this division are unfortunately many, and it must be left to the imagination of the reader to interpret their meaning. Those objects that are made of stone are described first, followed by those made of pottery and other materials.

Stone Rings (Pl. XXXVIII, f.; Pl. CXXX, 7, 9, and 30; Pl. CLV, 1; Pl. CLVII, 59)2

No. 1 in Pl. CLV is an alabaster ring which seems too large to have been used as a mace- Find of stone head. It was found 3 feet below the surface of the ground and seems to be of the same type rings. as the stone-rings described below. The stone-ring pictured in Pl. CLVII, 59 (HR 2184a), which was found in Court 6 of House II, Section A, HR Area, is very similar in shape but of small size, measuring 3.5 inches high by 6.3 inches in diameter. The central hole is 2.85 inches in diameter. The best examples, however, are illustrated in Pl. CXXX, 7 and 9. These two massive rings of stone were found with many others in Section B, Block 2, House 5, Find-spot. Room 49, of the HR Area, at a level of 3 to 6 feet below the surface of the ground. The walls of the chamber in which they were found are of Intermediate date, but it is not certain whether the rings themselves are of the Intermediate or Late Period.

The dimensions of No. 7 (HR 5925) are 10 inches high and 16.7 inches in diameter Dimensions. at the widest part; No. 9 (HR 2810) is a little larger. These two rings, together with the fifteen others that were found with them, are made of limestone and each has a hole bored through the centre, varying from 4.6 to 8.2 inches in diameter.

On one side only No. 7 has two small dowel-holes, each 0.5 inch in diameter and 1.0 inch deep, on opposite sides of the large central hole. There also are two slots, each o-9 inch long and deep, alternating with the dowel-holes; these slots are cut on the edge of the large central hole. Only three stones out of the seventeen found in the cache were found to be provided with these slots (Pls. CXVIII, 17; CXXX, 7 and 9).

The presence of these dowel-holes and slots suggests that it was intended to fasten the stones provided with them to something that was passed through their central apertures. The very large size of the latter in ring No. 7—it is 4.6 inches in diameter—indicates that the material to which the stone was fixed was either wood or stone, and it may be inferred that a dowel-perhaps a metal one-was passed at right angles through this wooden or stone stem, so that its ends engaged the slots in the ring and prevented the stone from either sliding down or from turning on its support.

As these stone-rings were found in a heap and vary in size as well as in the bore of the central hole, it seems evident that they do not belong to one another, but had been gathered

¹ Cake-moulds of exactly the same pattern but made in metal are, I am told, in use at the present day in parts of the Madras Presidency.

² For these and other ring-stones, see Chap. V, pp. 61-3.—[ED.]

together for some unknown purpose. The dowel-holes suggest that such stones were placed on top of one another to form a kind of pillar, each being fastened to the one above or below to prevent twist. Unfortunately for this theory, only nine of the stones have dowel-holes, and no two stones are uniform.

However this may be, the presence of these dowel-holes in some of the rings proves to my mind that these stones served some architectural purpose; they could, for instance, have been used as capitals for wooden columns.¹ It is also suggestive that with them was found the capital pictured in Pl. CXXX, 22.

Eight of the stones' have small circular pittings placed closely around the edge of the central hole (Pl. CXVIII, 16). It is possible that these once served as identification marks. If this be so, the markings may imply that the stone ring upon which they appear had a definite

allotted place with regard to other stones marked in the same way.

There is no doubt that being of different sizes the stone rings that were thus found together in the HR Section had been collected for some other than their original purpose. Many were badly broken and weathered before they were gathered together, which suggests that it was not intended to apply them again to their original purpose. It is possible that they were to be cut up and made into something else.²

Rings with Wavy Tops and Bases (Pl. CLVI, 2-5; Pl. CLVII, 56 and 57)

Rings of wavy

Five objects found at Mohenjo-daro, two of shell and three of alabaster, are difficult to identify. They range in size from 1.05 inches to 2.5 inches in diameter, but at Harappā both small and large stones of this shape have been found, of which the latter, usually made of grey or yellow limestone, are as much as 2 ft. 9 in. in diameter (Pl. XIV, 6 and 8). These stones seem to be allied to the large stone rings that are common to both Mohenjo-daro and Harappā, which have been described above. In fact, they only differ from them in the wave-like surface of the top and base.

Descriptions.

No. 56 in Pl. CLVII (HR 257) is made of alabaster. When complete, the hole running through its centre was 1.35 inches in diameter. The ring is 1.05 inches high by 0.75 inches thick, and is well made but unpolished. Level, 5 feet below surface.

No. 57 (HR 326) is a small fragment. Its central hole was originally 1.3 inches in diameter and it is 1.2 inches high and 0.8 inch thick. Like the first it is of alabaster. Level, 3 feet below surface. Court 18, House I, Block 1, Section A, HR Area.

Another broken specimen in alabaster (L 834) was found 2 feet below the surface of the ground in Court 69 of the L Area.

A fourth example (HR 4891) measures 1.1 inches in diameter and 0.65 inch high, with the central hole 0.5 inch in diameter. Found in lane between Houses L and LV, Block 7, Section B, HR Area, 3 feet below the surface.

Somewhat allied to the above, but made in shell, are a pair of objects, one of which is illustrated in Pl. CLVI, 3. Each measures 0.62 inch in diameter by 0.51 inch high. They closely resemble the stone examples except that they are not perforated in any way. These two specimens may be unfinished, but otherwise they are well cut and highly polished. They were both found together at a depth of 4 ft. 6 in. below the surface, and their serial numbers

The possibility may be admitted, though it seems a remote one, in the case of the large plain ring-stones, but not in the case of the large undulating ones; nor, obviously, in the case of the smaller ones which are sometimes not more than an inch or two in diameter. For a fuller discussion of these ring-stones, see Chap. V, pp. 61-3.—[Ed.]

² The inference here drawn by Mr. Mackay seems questionable. The room where the ring-stones were found may have belonged to a temple, and they may have been deposited there as cult objects.—[ED.]

are VS 2187 and VS 2182. They are more fully described in Chapter XXVIII on Ivory, Bone, Shell, and other objects.

Though they presumably belong to one another, these two specimens do not exactly Comparisons fit together. Possibly they alternated with similar objects made of paste or some other with Kish material. If so, they recall the curious rods made up of alternate sections of shell and objects. bituminous limestone threaded on a copper rod that I found at Kish, belonging to the pre-Sargonic period, and that are also known at Susa and Musyan.1

Mace-like Objects (Pl. XIII, 11 and 12; Pl. CXXX, 6; Pl. CLVII, 55, 58, and 60)

No. 6 in Pl. CXXX (VS 3175) is a curious object made of alabaster, which at first sight Objects of appears to be a mace-head, but evidently served some other purpose. It measures unknown use. 1.95 inches high and its flat base is 2.35 inches in diameter. It is rounded at the top where four grooves at right angles radiate outwards from a vertical hole through the centre. This hole is slightly irregular in bore, the average diameter being 1.05 inches. There is also a horizontal hole in the side of the object near its base, measuring 0.75 inches in diameter and only 0.6 inch deep, so that it does not meet the vertical hole. The illustration of this object in Pl. CXXX, 6, shows it from above. Level, 5 ft. 3 in. below surface of ground. Room 62, House XXVII, Block 6, VS Area.

Nos. 55 and 60 in Pl. CLVII are two views of another object of alabaster (HR 1123), Descriptions. which also in some ways resembles a mace-head. This object is conical in shape, 2.75 inches high, with a flat base 2.75 inches in diameter. A hole, 0.95 inch in diameter, bored through its centre is smooth throughout and shows no particular wear. There is another hole, 0.5 inch in diameter and 0.6 inch deep, in the side of the object at a distance of 0.75 inch above the base." This second hole is at right angles to the central hole, but does not meet it." The top of the object is divided by deep grooves into four portions. It was found 4 feet below the surface of the ground. Chamber 5, House I, Section A, HR Area.

No. 58 in Pl. CLVII (HR 4943) measures 2.5 inches high and 3.1 inches in diameter at its widest part. The vertical hole that runs through it is I inch in diameter. The horizontal hole is 0.7 inch in diameter and 0.6 inch deep, but does not meet the vertical hole in the middle. The material is a very soft variety of alabaster. Level, 6 feet below surface. Room 102, House XII, Block 2, HR Area.

VS 2507 is another object of the same type and material, but is not illustrated. 2.5 inches high and 3.1 inches in diameter at the base, which is flat. The hole through its centre, 1.6 inches in diameter, is much larger than the others described above. This object also has a horizontal hole, 0.75 inches in diameter, but in this case the hole is continued right through to the centre. Level, 5 feet below surface. Room 76, House XIII, Block 2, VS Area.

Of VS 1530, which again is of the same material and shape, only a fragment remains. Level, 5 feet below surface. South-east corner of House XXII, Block 3, VS Area.

What these objects were used for it is difficult to determine. The broad flat base Possible cult suggests that they were meant to stand on something rather than to be supported by a stick objects. through the middle. And that they were not to be subjected to very much wear is proved by their being made of very soft material. They could hardly have been intended to have revolved on a stick, as none of the vertical holes through their middles show any evidence of wear, and yet the presence of the smaller horizontal hole near the base suggests that a stick

was used to turn the object round on a pivot. It is, of course, possible that these objects were connected with some cult. Similar objects, but made of pink limestone, have been found at Harappa.

Conical Stones (Pl. CXXX, 8) 1

Stone cones

No. 8 in Pl. CXXX (HR 2783) is a conical mass of white limestone, measuring 15.65 inches high, somewhat roughly made with an uneven base 7.5 inches in diameter, whose edge is slightly rounded. Level, 2 ft. 3 in. below surface. From First Street, HR Area.

HR 2079 is a very similar mass of cherty limestone, 8.3 inches high, with a smooth but unpolished surface. The flat base is 9 inches in diameter. The top of this cone is polished in places as if by constant friction of the hand. Level, 2 ft. 6 in. below surface. From the constructions south of Chamber 29, House I, Block I, Section A, HR Area.

HR 587 is also a conical mass of cherty limestone, 6.5 inches high, whose flat and polished base is 5.7 inches in diameter. It is only roughly dressed and has pick-marks all over it. There is no sign of any polish except on the base. Level, 3 feet below surface. First Street between Sections A and B, HR Area.

Conical Stones with Heads (Pl. CXXX, 27-9 and 33)2

Cones with heads.

No. 27 (SD 207) is made of roughly dressed limestone, but the head shows signs of polishing, especially at the extreme tip and around the base. It measures 10.5 inches in height and its flat base, which also shows a considerable degree of polish, is 9.2 inches in diameter. Level, 2 feet below surface. From Chamber 1, Block 6, of Southern Buildings Section.

No. 28 (HR 201) is made of cherty limestone and carefully finished. This cone is 6.4 inches high with a flat base roughly 3.7 inches in diameter; there is a shallow vertical hole 0.37 inch in diameter in the top of the cone. Although it is now badly chipped, its surface was formerly very smooth, though there are no signs of ancient polish. Level, 8 feet below surface.

No. 29 (SD 1567) also is made of a cherty limestone. It stands 11 inches high and has a very smooth base, 8.3 inches in diameter. It is only roughly dressed with a pick, except for the head which is polished. Found in the lane between Blocks 4 and 5 of the Southern Buildings Section, at a depth of 7 feet below the surface.

No. 33 (VS 2321) is similar to the others, but its apex has been badly knocked about. It is made of limestone and measures 13 inches high with a smooth flat base, 8.5 inches in diameter. It was found at a depth of 6 ft. 6 in. in Room 13, House XVII, of the VS Area.

In many respects these stones resemble the phallic object (linga) of the Hindus. The fact that nearly all of them are more or less polished at the top 3 suggests that they were constantly fingered; possibly they were repeatedly anointed with butter as is the custom at the present day.

Small Cones with Pointed Tops (Pl. CXXXI, 47-55; Pl. CXXXIV, 8-20; Pl. CLVI, 19)

Clay cones.

A striking feature of the excavations at Mohenjo-daro is the great number of small cones that have been found, made principally of baked clay, but also of shell and in one case of lead. These pottery cones occur in most of the rooms of both the Late and Intermediate periods.

1 For the meaning of these stones see Chap. V, p. 59-60.—[ED.]

2 No. 28 of Pl. CXXX seems to belong to a different class from Nos. 27 and 29.—[ED.]

3 This polishing has not been caused by ordinary handling. The tip of the con has as much or more polish as its lower part.

They are baked very hard and in some cases they are almost vitrified. One of the commonest forms is shown in Pl. CXXXIV, 11, 12, and 18. They average 2.75 to 3 inches in height, and have a small rough projection at the base, on account of which and in connection with their general shape, our basket-boys call them "carrots". Some of these cones are decorated -always at the base-with spiral lines of pittings, which show no trace of having been filled in with white or any other colour. Nos. 9 and 10 in Pi. CXXXIV are of shell and both came from the L Area. The first was found in Court 121, Block 6, and the second in region 128, Block 8. Both belong to the Late Period.

Another common form is the cone with a flat base (Pl. CXXXIV, 13 and 15), which Flat based unlike the "carrot" type, readily stands up. In this variety of cone, the base is but seldom variety. decorated with pitted lines. When, however, this form of cone is decorated, the base is scored with from three to six horizontal lines, as in No. 13, or with spiral lines, as in No. 15. This type frequently has a small shallow hole in the centre of its base, averaging of 15 inch in diameter and 0.03 inch deep. No. 13 was found outside the western wall of Block 7, SD Area, at a level of 4 feet below the surface.

Round-based cones (Pl. CXXXIV, 14), which average from 1.6 to 2.5 inches in height, Round-based are also found in large numbers. Sometimes the base is quite plain, sometimes it is scored cones. with a spiral line. Occasionally there is a shallow hole in the centre of the base.

No. 16 (VS 6178) in Pl. CXXXIV is a very curious form of cone. It is hand-made, with a small flat base, and is unusual in having a spiral line scored around the middle of the body.

No. 17 (DK 3090), which is made of light red pottery, is coated with a brown slip. Its receding base is uncommon in shape, and the hole in it is unusually long, measuring 0.6 inch in depth and 0.2 inch in diameter. Outside south-east corner of Block 2, Section B, DK Area. Level, 3 feet below surface.

No. 20 (SD) in Pl. CXXXIV is also of unusual type. It is hand-made with its base decorated with vertical lines of pittings that meet circular lines below. There is a shallow hole in the projection from the base, 0.15 inch deep and 0.2 inch in diameter at the surface.

The purpose for which these cones were used has not yet been gathered. It is very Broken points. rarely indeed that one is found with the point unbroken, and it is probable that this part of the cone was essential to its use and that breakage of the point led to the cone being thrown aside. In the rare cases in which the point is intact, it sometimes shows signs of having been, carefully trimmed with a knife in the course of manufacture, which suggests that the point was used for boring.1 On the other hand, it is very unusual to decorate tools and implements, yet most of these cones are decorated in some way, even to the extent of coating them with a smooth red slip—a finish which hardly seems necessary in the case of a simple tool.

These pottery cones were sometimes hand-made, and sometimes made on a wheel. In Make. the former case, they were so carefully finished that it is often difficult to distinguish them from the mechanical articles. Those which were decorated with scored lines, whether horizontal or spiral, were usually made on a wheel, and in some cases the scoring was done with a comb.

In colour the cones range from light red, sometimes coated with a dark-red slip, but more frequently left plain, to a dark-brown colour which almost approaches black. Many of the latter are made of a special clay of a very compact nature, and have been so heavily fired in the kiln that they are almost vitrified. This is especially the case with the "carrot" type of cone.

⁻¹ Small clay cones from Jemdet Nasr were treated in a similar way.

478

Holes in bases.

It is difficult to explain why there should be a hole in the centre of the base of some of these objects. In most cases it is much too shallow for the cones to have been fixed to any kind of handle. It is possible that these holes fitted a peg on the wheel on which the majority of the cones were turned, enabling the potter to finish off the base of the cone before removal from the wheel. But there is a possible objection to this in that some of the hand-made examples have a similar hole. In the latter case, however, a wooden peg stuck in the base of the cone would help in rolling it into shape and it would, of course, disappear when the cone was baked.

Use of in game (?)

It is possible that these cones were used in some form of game and that they were thrown with the idea of making their apices point in a certain direction. If this were so, it would explain the existence of so many of them with broken points, and the fact that some of them were decorated would also point to this conclusion. It is certainly open to doubt whether such comparatively blunt points as those of Nos. 11, 12, 14, and 19 in Pl. CXXXIV would be of any use for boring.

Foreign comparisons.

Pottery cones very much like those illustrated, but undecorated, have been found at Jemdet Nasr in Mesopotamia. Like the Mohenjo-daro examples they are associated with painted pottery and all of them had very carefully trimmed points. They most closely resemble in type No. 11 on Pl. CXXXIV, but are without the projection at the base.

Cones of various sizes have been found in other places in Mesopotamia. At Ur, for instance, they have been found in plenty. The use of some pencil-like varieties found on that site have not yet been satisfactorily explained. Mr. Campbell-Thompson found a great many at Abu Shahrain, and these, like the Ur examples, are of very early date and generally associated with painted pottery.

Shell cones.

Nos. 8, 9, and 10 in Pl. CXXXIV and Pl. CLVI, 19, are made of shell—the only ones found at Mohenjo-daro—and on account of the hardness of this material their points have not been broken off. They are all somewhat roughly made, and the bases of two are rounded, the third flat. The cone illustrated in Pl. CLVI, 19 (HR 900) is 3.2 inches long; it was found inside the south-western corner of House I, Block 1, Section A, HR Area, at a level of 3 feet below the surface.

Small Cones with Rounded Tops (Pl. CXXXIV, 22-4; Pl. CLVI, 7)

Gamesmen (?)

A small number of very carefully made cones with rounded tops were made of shell or pottery. The three illustrated in Pl. CXXXIV were all found together, 4 ft. 4 in. below the surface of the mound in Section B, Block 3, House 14, Room 11, of the HR Area. Each measures 2.2 inches high by 1.5 inches in diameter and is made of a light red ware whose surface is uncoated with a slip. The use of these three objects is uncertain. They are perhaps too large to be gamesmen.

No. 7 in Pl. CLVI (HR 5539) is one of a group of three, all beautifully made in shell. They were all found together, 3 ft. 3 in. below the surface in Section B, Block 8, House LXII, Court 36, of the HR Area, and average 1.9 inches in height and 1 inch in diamet the base, which is flat. All the cones of this group are of Intermediate date.

Cylindrical Objects of Pottery (Pl. CXXXI, 42)

Pottery cylinders. Three very curious objects (HR 5751), pottery cylinders with flat ends, were found together in the HR Area at a level of 11 feet below the surface of the ground. They are of

- See Dr. Hall's remarks on these objects in *Ur Excavations*, vol. i, pp. 48-50. It is out of the question that the Mohenjo-daro examples were used for wall decoration.
 - ² Campbell-Thompson, Archæologia, vol. lxx, pl. x (b).

different sizes, one being 4.4 inches in length by 1.9 inches in diameter, another 4.05 by 1.8 inches, and the third 4.6 by 1.8 inches. A fourth object of the same kind, measuring 5 by 1.75 inches, was found at a level of 8 feet below the surface on the eastern side of the Stupa buildings, i.e., it belongs to the Late Period, whereas the other three are apparently of Intermediate date. The three cylinders were found in Room 74, House V, Block 2, Section B, HR Area.

These four objects were all roughly made by hand and somewhat indifferently baked. Mode of The clay seems to have been rolled on a flat stone and then squarely chopped off in lengths. manufacture. They have no slip and show no signs of wear at any particular spot. They were possibly used for rolling dough, but they seem rather short for this purpose.

Shell Caps (Pl. CLVI, 13, 16-18)

No explanation has at present been found of the shell objects illustrated in Pl. CLVI, Shell objects. 13, 16-18. They are always in two pieces which fit more or less correctly together, according to the skill of the carver, but two halves have never been actually found together. decoration is always the same, namely, a deeply scored line around the edge of the rounded upper surface and quartering by means of three parallel lines. The lower surfaces of the two halves always show the convolutions of the shell and apparently no attempt was ever made to smooth them down.

When the two halves are placed together there is a natural hole between them; and this, coupled with the fact that the top shows traces of a slight flattening, suggests that a small metal plate was placed on the top with a wire passed through it for a handle. Possibly a metal plate once covered the base; if so, this would account for the lack of finish in this part ofthe object. These objects may have been used as jar covers.

No. 16. The two pieces of this cap do not strictly belong to one another (DK 2991 Descriptions and DK (?)). When set together, they measure 2.85 inches in diameter and 1.02 inches

high. Level, 18 inches below surface. House I, Block I, Section B, DK Area.

This illustration shows the appearance of the inside of one of these caps, made up of pieces DK 2899 and DK 2927. The two measure 2.4 inches in diameter and are 0.85 inch high. Levels, 3 feet and 2 feet, respectively, below surface of ground. Room 3, House I, Block I, Section B, DK Area.

No. 18 (HR 324 and DK 3114). 2.4 inches in diameter and 0.7 inch high. DK 3114 was found 18 inches below the surface in Room 5, House I, Block 1, Section B, DK Area.

No. 13 is a rare example of three pieces of shell being used to make one of these caps. Two of these pieces belong together (HR 2465), but the third (HR 3198) is part of another cap. This type of cap is rare for the reason that it must have necessitated considerable labour to fit three pieces 'accurately together. Levels, 14 feet and 2 ft. 4 in. below surface."

These objects are found in both the Late and Intermediate levels.

Pedestal (?) (Pl. CXXXIII, 18)

This is an alabaster object (VS 2648) rounded on its upper surface and with a flat base Stand. 5.6 inches in diameter. Its height is 1.9 inches. In the centre of the upper surface is a shallow depression, 2.7 inches in diameter by 0.2 inches deep. The exact use of this object is doubtful; it may be that it is a pedestal of some kind. Level, 5 ft. 4 in. below surface. From House IX, VS Area.

Roundel (Pl. CLVIII, 12)

Steatite ornaments

This curious object (HR 5463) is 1.9 inches in diameter by 0.3 inch thick, and is made of steatite. One side has been cut to a flat edge. In the centre is a heart-shaped design similar to the inlay of Nos. 39-44 in Pl. CLV. Close to the edge a number of lunar-shaped depressions have been cut. The use of this object is quite uncertain. It is too thick for inlay, and, as it is unbored, it cannot have been used either as a bead or a pendant. Its reverse is quite flat and unornamented. Level, 4 feet below surface. Room 87, House IX, Block 2, HR Area.

Pottery Tablets (Pl. CXXXI, 56-9)

Rough pottery objects.

The use of the four pottery objects in Pl. CXXXI, 56-9, has long been a puzzle. Similar specimens have been found in various parts of Mohenjo-daro, belonging to various periods. They vary considerably in size, ranging from 1.5 inches to 3.7 inches across one side. In thickness they vary from 0.7 inch to 1.3 inches, according to their size.

These curious objects are flat on both sides and always roughly made. In some specimens straw was mixed with the clay of which they are made. Most examples are of triangular shape with more or less rounded corners; a few, however, are circular, but these are rare. There are no indications on their upper or their lower surfaces to guide us as to their use; neither are these surfaces particularly well finished.

I was at first inclined to think that these pottery plaques were used as stands for pottery in the kiln, particularly as one has been found in the interior of a kiln. On the other hand, they are always so badly baked that they would seem never to have been exposed to any great 'degree of heat. Provisionally, I venture the theory that they represent model loaves, either as votive offerings or intended for burial use. They closely resemble the triangular loaves portrayed on tomb walls in Egypt.

Models of loaves (?)

No. 58 in Pl. CXXXI (VS 1025) measures 3.7 inches along each side and is 1.2 inches thick. House XXVI, Block 7, VS Area. Level, 4 feet below.

CHAPTER XXV

COPPER AND BRONZE UTENSILS AND OTHER OBJECTS

PART I

SOURCES AND METALLURGY OF COPPER AND ITS ALLOYS

HE excavations at Mohenjo-daro have shown that the metals known to the early Metals of the inhabitants of the Indus Valley were gold, silver, lead, copper, and 'tin as an Indus people. ingredient of bronze; iron was altogether unknown to them. Of these, copper was the earliest and the most useful metal at their disposal for general purposes, and objects Copper of this metal, which have been found here in abundance, comprise domestic utensils, axe- abundant. heads or "celts", daggers, knives, lance-heads and arrow-heads, sickles, statuettes, bangles, finger-rings and ear-rings, amulets, wires, rods, etc.

It is well known that pure copper is a comparatively soft metal and unfit for tools and weapons requiring a keen, hard edge. This was early understood by the Indus people who doubtless felt the need of a harder metal for their weapons as well as for their works of art. Whether they invented bronze independently or learnt the art from some foreign nation it is not at present possible to decide; but it is certain that they became acquainted with this alloy at a very early period. Bronze objects discovered at Mohenjo-daro comprise Use of bronze. utensils, tools and weapons, statuettes and jewellery. Most of these were evidently made by casting, but some had to be shaped and finished by hammering. Therefore, it is obvious that their makers were quite familiar with the property of bronze, that enables it to be forged at a temperature just below redness. The chemical composition (vide infra) of the bronze objects leaves no doubt that the tin, 4.5-13 per cent, is not accidental, but was added intentionally to produce an alloy suitable for cutting tools or other purposes. Some of these objects are in a completely oxidized state, consisting of a substantial core of white stannic oxide enveloped in a layer of red cuprous oxide, thus affording a visible proof of the use of a high-grade bronze. These facts lead us to the conclusion that at the time these objects were produced the Indus people had passed much beyond the experimental stage and had Advanced acquired a very good knowledge of the properties and working of bronze. In spite of this, knowledge of however, it is noteworthy that pure copper tools and weapons persisted alongside with those brenze. of bronze even in the uppermost strata, where many fine specimens of bronze (e.g. saws, chisels, and vases) have been unearthed. The only possible explanation of this simultaneous use of copper and bronze is that the supply of bronze was limited and its use, therefore, was confined to objects of a special nature, e.g. tools, razors, jewellery, or ornamental vases for those that could afford them. Later on we shall see that the Indus people were handicapped in their efforts to develop the use of bronze, on account of the scarcity of tin in India and the Tin scarce. difficulty of procuring it from abroad. We must also bear in mind that precious objects such as these were likely to have been passed on from one generation to another and to have been

Another alloy, composed of copper and arsenic (vide infra) and comparable with a low alloy.

Copper-arsenic

eventually carried away when the city was abandoned.

grade bronze in hardness, is also met with at Mohenjo-daro. How it originated and when precisely it came into vogue, we do not know. It is possible that the addition of arsenic (2-4.5 per cent) was intentional, but it is more probable that some mines of arsenical copper ore were found to yield a very hard and yellowish metal which was much prized for tools, before the introduction of bronze in the Indus Valley. Objects of this alloy have also been found in early Egypt and at Anau.

Copper and bronze in Egypt, Sumer, and other countries.

In Egypt copper came into use very early in predynastic times, and there is evidence of a sporadic use of bronze during the Old Kingdom period, the earliest known object of this alloy being a rod found at Meydum, in a third dynasty tomb, containing 9-1 per cent tin. At the result of a careful survey, Montelius 1 comes to the conclusion that full tin bronze (9-10 per cent) came into use in the eleventh or twelfth dynasty, but according to Petrie it did not come into regular use until the eighteenth dynasty (c. 1580 B.c.).2 Copper was commonly employed by the Sumerians from the earliest times, and copper casting was practised by them even before the reign of Ur-Nina (c. 2900 B.C.). Chemical analyses of the objects found at Tello, Eridu, and Al 'Ubaid have shown that tools of copper unalloyed with tin were in use even in late Sumerian times.3 However, bronze objects have been found at Ur and Erech ranging from the second half of the third to the end of the second millennium. Recently several careful analyses by Dr. Desch of authentic specimens from Kish, Ur, and Al 'Ubaid have been published, which leave no doubt that bronze was employed by the Sumerians earlier than circ. 3000 B.C.4 It is obvious that both copper and bronze were simultaneously in use in Mesopotamia before c. 3000 B.C. and that subsequently the alloy was employed sparingly even for tools, as in the Indus Valley. As we have stated above, this paucity of bronze was due to the scarcity of tin, and there is some documentary evidence also in support of this view. A record which is earlier than Sargon of Agade States that "five minas of pure tin" had been received at Lagash. Sayce informs us that tablets from Kara-Euyuk also refer to tin which was "a rare and precious metal in Babylonia at the time (c. 2500-2200 B.C.)." It can hardly be doubted that the introduction of bronze in the Indus Valley and Babylonia was approximately contemporaneous, on account of the close commercial relations that must have existed between them. Copper appears in the earliest strata at Susa. At Anau, copper has been obtained in the later phases of Culture I and weapons of the pure metal were in use in Cultures II and III, with occasional bronze in the latter period.6 In Crete, the Bronze Age begins even earlier than in Egypt, in the early Minoan I Period. In Cyprus, the Copper Age continued down to c. 2200 B.C., when the Bronze Period followed. Copper was in general use in the first settlement at Hissarlik, and bronze in the Second City which flourished probably much earlier than 2000 B.C.7

The discovery of numerous prehistoric copper implements (e.g. celts or axe-heads, swords, harpoons, etc.) at various sites in Northern India and the Central Provinces indicates that copper was extensively worked in India at a very early period. The most important find was that made at Gungeria in the Bālāghāt District of the Central Provinces, which included 424 hammered copper implements and 102 silver laminæ, weighing 828 and 20 lbs. respectively. This has been described by Sir John Evans as the most important discovery of instruments of copper yet recorded in the Old World. Formerly the earliest date assigned to the prehistoric copper implements of India was c. 2000 B.C., based on arbitrary comparisons

Early, utensils of copper in Central India.

¹ I.' Anthropologie, i, p. 27. 2 Flinders Petrie, "Metals in Egypt": Ancient Egypt, i, 1915.

³ King, Sumer and Akkad, p. 73; Hall and Woolley, Al 'Ubaid, pp. 34-5.

⁴ Harold Peake, "The Copper Mountain of Magan": Antiquity, Dec. 1928, pp. 452-7.

⁵ Man, Nov., 1921.

Pumpelly, Explorations in Turkestan, 1904, p. 53. Cambridge Anc. Hist., i, p. 103.

with European examples. (It was also believed that the prehistoric Indians were not acquainted with the art of manufacture and properties of bronze, and bearing in mind the fact that only seven specimens of prehistoric bronze, with a very irregular chemical composition, were known, it is not perhaps surprising that the existence of a Bronze Culture was denied. However, the discovery of similar celts, but of superior workmanship, in the Indus Valley points to a much greater antiquity for the Northern specimens. The presence of copper at Mohenjo-daro and Harappa, even in the earliest stratum yet reached, indicates that copper must have come into use in India at a very early period, but no definite date can be assigned to it as yet. In the light of the various bronze objects that have been discovered at Mohenjo-daro, it is obvious that the Indus people were also well acquainted with the metallurgy and properties of bronze, and extended its use to the manufacture of tools, weapons, utensils, statuettes, jewellery, etc., but they failed to replace copper effectively for such purposes simply on account of the limited supply of tin. At Mohenjo-daro bronze objects have been Bronze known found in the earliest stratum yet reached, and on the basis of the chronology adopted in this by Indus work, we may assume that bronze was known in the Indus Valley even earlier than people before This may be taken to imply the existence of commercial relations, direct 3000 B.C. or indirect, with some region where the invention of bronze took place—a region, probably, where deposits of copper and tin ores existed in close proximity to one another.

Copper ore is unknown in Sind and the nearest deposits are situated in the countries Sources of bordering on the west of the Indus Valley. In Baluchistan, rich copper ore occurs at Shah Copper. Bellaul and at Robat, where large heaps of copper slag indicative of ancient smelting have been observed. Deposits of copper ore also occur in the Rās Kūh and Kojak Amrān range. Rich veins of the ore exist in the Shah Maksud Range in Afghanistan as well as at Kaleh Zeri (Kerman) and Anarek in Persia, at both of which places there is evidence of ancient working • on an extensive scale. The nearest copper mines in India proper are those situated near Ajmer, in Sirohi, Mewar, and Jaipur States, notably those at Khetri and Singhana, which have been worked from very early times. The presence of small quantities of sulphur and the absence of tin in the copper lumps point to the use of the sulphide ore, which abounds in these mines, for the extraction of copper. The presence of lead in some of the copper objects (1.58 and 3.28 per cent in two of the specimens analysed) is noteworthy, as it throws some light on the source of the metal. As copper ores associated with lead occur in Afghānistān

these countries, but it should be added that copper ore associated with lead occurs also in Rājputāna and Hazāribāgh.2

The source of the tin which is an ingredient of bronze is difficult to locate. Tin ore is Source of tin. scarce in India proper and unknown in Balūchistān. The only Indian deposits, worth mentioning, exist in the Hazāribāgh District, and appear to have been worked in ancient times. Tin occurs in the Kārā Dāgh District in North-Western Persia. Strabo mentions that tin was found in Drangiana in the south-west of the modern Afghanistan, and ancient tin mines have been discovered by Van Baer in Khorāsān, between Astrābād and Shāh Rūd.3 The rick deposits of cassiterite ore which occur in the Malay Peninsula and the neighbouring

and Balūchistān, it seems probable that some of the copper, at any rate, was obtained from

1 Vincent Smith, "On the Copper Age and Prehistoric Bronze Implements of India": Indian Antiquary, 1905. pp. 229 ff.; ibid., 1907, pp. 53 ff.

² As some of the Indian copper ores (e.g. in Rājputāna and Singhbhum) contain nickel in appreciable quantities, the occurrence of nickel in the Mohenjo-daro specimens does not imply that the Indus people depended for their supply of copper on Oman or any other foreign source. Noteworthy, also, is the high proportion of arsenic in these specimens, which distinguishes the Indian from the Sumerian metal.

³ Gowland, "Metals in Antiquity": J.R.A.I. vol. xlii, 1912, p. 252.

islands, that form the principal source of tin in the present age, do not appear to have been worked in early times. Moreover, a regular supply from this area, which involved a long and perilous sea voyage, must have been impossible in those remote ages. The possibility of a supply from Hazāribāgh must also be discounted, as the deposits are so meagre that they could barely have sufficed to meet local demands, and this assumption is amply justified by the scarcity of prehistoric bronze in the Gangetic Valley. Moreover, Hazāribāgh was isolated by deep forests from Northern India down to historic times. It is, therefore, more than probable that the sources of tin or bronze lay towards the North-West. It is a noteworthy fact that the ancient tin mines mentioned above were accessible from the busy and ancient highway that traversed North Persia and Western Afghanistan and afforded communication by way of the Bolan Pass between the Indus Valley and the Western World. As copper was extensively worked in these regions in ancient times, it is not unlikely that the discovery of the alloy of copper and tin, by the accidental smelting together of the ores of these metals, also took place somewhere in North Persia, and thence found its way to the Indus Valley. In this connection it is a significant fact that the daggers and knives discovered in the Indus Valley resemble some of the weapons found at Susa, Anau, and in the South-West Caspian area.

Typical analyses of the specimens of copper and bronze found at Mohenjo-daro are given below:—

CHEMICAL ANALYSES OF COPPER AND BRONZE FOUND AT MOHENJO-DARO
(Analyses by Mohammad Sana Ullah)

Serial Number.	Specimen.	Copper.	Tin.	Antimony.	Arsenic.	Iron.	Nickel.	Lead.	Sulphur.	Oxygen (by difference).	Remarks.
I.	Copper lump .	96.67	0.00	0.88	0.12	0.03	1.27	0.02	0.98	_	Unaltered core.
2.	Copper lump .	97.07	0.00	tr.	0.98	0.49	0.31	tr.	1.15	_	Unaltered core.
o 3.	Copper lump .	96.42	0.00	-	0.00	0.00	0.35	€.09	0.36	2.78	Partly oxidized.
4.	Copper lump .	92.49	0.37	tr.	1.30	1.51	1.06	tr.	2.26	1.01	Partly oxidized.
5.	Fragment of seme implement.	95.80	0.00	0.72	0.74	0.13	0.25	1.58	0.61	0.18	Unaltered
6.	Celt	94.76	0.09	_	4.42	0.12	0.14	0.26	_		metal. Unaltered and
7:	Copper chisel (?)	92.41	0.00	0.10	3.42	0.59	0.12	3.58	0.05	_	very hard metal. Unaltered
8.	Bronze rod .	91.90	4.21	1.15	1.96	0.12	-	0.17	0.16	_	portion. Unaltered core.
*9	Bronze buttons .	88.05	8.22	2.60	tr.	0.29	tr.	0.00	0.84		Completely oxidized.
*10.	Bronze chisel .	86.22	12.38	0.35	-	0.35	, 0.00	0.70	_	-	Completely oxidized.
11.	Bronze slab	82.71	13.51	0.33	1.17	0.42	0.56	0.11	0.00	1.49	Partly oxidized.
12.	Bronze chisel .	85.37	11.09	tr.	0.07	0.18	0.16	tr.	0.11	3.02	Partly oxidized.
13.	Bronze lump .	83.92	12.13	tr.	0.00	0.00	0.17	0.17	0.00	3.61	Metallic core, partly oxidized.

^{*} Note.—Complete specimen, along with the adhering incrustations, was taken for analysis and the original composition of the alloy has been recalculated from the relative proportions of the metals found therein.

Neither copper ore nor any remains of a smelting furnace have so far been recovered at Mohenjo-daro, and it is highly probable, therefore, that the reduction of ore was carried out at the mines. Lumps of crude copper plano-convex in shape, 6 to 9 inches in diameter and I to 1½ inches thick in the centre, have been found, which were evidently produced by the smelting operation in a primitive furnace consisting simply of a concave depression in the ground. The crude metal was re-melted for refining in clay crucibles, which were broken up for the recovery of the purified metal. A fragment of such a crucible with the slag sticking to the edges, is illustrated on Pl. CXLII, 9. No specimen of pure tin or its ore has been found, so far, at Mohenjo-daro.

These analyses indicate the occurrence of four distinct varieties of copper and its allows at Mohenjo-daro: (a) Crude copper, (b) refined copper, (c) copper-arsenic alloy, (d) copper-tin

alloy or bronze.

(a) Specimens Nos, 1, 2, and 4 represent the crude product of the smelting furnace. They are too rich in sulphur to be worked up by hammering and are suitable only for

casting heavy or plain objects.

- (b) Specimens Nos. 3 and 5 are good examples of refined copper in general use. Specimen No. 3 is well suited for the raising of vessels of elaborate shapes on account of its remarkable purity and consequent ductility. The presence of over 3 per cent of foreign metals in No. 5 renders it suitable for obtaining sound castings in closed moulds. Such small amounts of arsenic and antimony will also impart appreciable hardness to copper although not comparable to that produced by tin. There is no doubt that these elements have not been added intentionally but were derived from the original copper ore with which they were associated.
- (c) Spesimens Nos. 6 and 7 represent a copper-arsenic alloy which is as hard as a low Copper-arsenic grade bronze. In these cases it is difficult to decide whether the arsenic was added alloy used for intentionally, in the form of a flux, or was derived from an arsenic bearing copper ore. In hardening. this connection it is interesting to recall the occurrence of löllingite (a natural mineral composed of arsenic and iron) at Mohenjo-daro, and it may be questioned whether this mineral was intended for the preparation of this alloy. It is a noteworthy fact that a similar alloy of copper and arsenic was also in use in Egypt, the composition of No. 6 being almost identical with that of a copper strip of the twelfth dynasty. It is therefore quite possible that this alloy was obtained from the same source, both for the Indus Valley and Egypt. Petrie makes the interesting suggestion that arsenic was the earliest hardening element for copper in Egypt, and it may be that this alloy was employed for tools in the Indus Valley also, before the advent of bronze.
- (d) Specimens Nos. 9 to 11 represent the various qualities of bronze in use. The percentage of in is 4.51 in No. 8; 8.22 in No. 9; but in the last four, varies between 11.09 and 13.21. It is obvious that 11-13 per cent tin alloy was popular and had come into general use during the period under review, although lower grades were also employed to some extent. The preference of the high grade alloy well suited for sharp-edged tools, with a fairly regular proportion of tin, leaves hardly any doubt that the addition of the white metal was intentional and not the result of mere accident. It is obvious that this stage in metallurgy had been reached after prolonged experimentation and experience with copper and its alloys with arsenic and tin. These specimens are also contaminated with appreciable proportions of antimony and arsenic, which would add further to their hardness.

1 On the subject of löllingite see p. 684 f.—[ED.]

² Garland and Bannister, Ancient Egyptian Metallurgy, p. 66.

The proportion of lead in the bronzes is trifling, which shows that the Indus people, had not discovered the valuable property of this metal in rendering the alloy more fusible and more fluid, that is, more suitable tor casting. This partly accounts for the absence of bronze castings of any appreciable size at Mohenjo-daro. The Egyptians also remained ignorant of this fact until quite late, in the Saitic period.

Analyses of copper and bronze specimens made for the Sumer Committee of the British Association by Prof. C. H. Desch, F.R.S.

Specimens from Mohenjo-daro: Season 1926-7

The specimens were completely oxidized, and contained sand and earthy matter mixed with the oxide and carbonate. Sulphur was usually present, but it is not certain whether this was in the metal originally or derived from the earth. A microscopical examination will be made to throw light on this point. The table is arranged to show the proportion of tin and nickel in the metallic part, excluding the sulphur, but the sulphur content is added in a separate column. The sulphur figures refer to the crude oxidized material. The tin and nickel figures are calculated as if the remaining metal were only copper, except where other metals were detected. In most specimens other metals were certainly absent.

					Tin.	Nickel.	Lead.	Sulphur
	SD	1405			_	0.17	0.36	6.78
	SD	1932			_	9.38	tr.	1.73
	L	3767			-	3.34	0.30	7.77
	SD	2683	(A)		_	tr.	present	
	SD	2683	(B)		-	_	_	_
	SD	2683	(C)		_	tr.	_	2.63
	L	III	2		_	1.04	_	2:40
	HR	oI 152			_	0.39	_	0.32
	E	602			14.4	tr.	_	_
	HR	1472			_	1.49	_	0.23
	VS	1572			19.0	0.23	_	0.43
	VS	1416			-	0.09		0.28
	DK	542		•.	_	0.30	_	0.34
	DK	1679			_	tr.	present not	0.05
0	DK	2155			_	0.53	estimated	0.03
						Balance	copper.	

Specimens from Mohenjo-daro: Season 1927-8.1 As before, the tin and nickel have been calculated back to the metallic contents, other metals having been determined to be absent:—

No.	Mark.	Tin.		Nickel.
I	DK 3479	_		_
2	,, 4585	10.5		-
3	" 4378	_		_
4	,, 3833	_	0	_
5	,, 4568	10.3		tr.

¹ It is due to the courtesy of Mr. E. Mackay that I am able to include the analyses of these specimens in the present work.—[ED.]

No.	Mark.	Tin.	Nickel.
6	DK 4588	14.6	_
7	» a 3735	_	• tr.
8	,, 44035	_	faint tr.
9	,, 4005	_	faint tr.
10	" 37·3 I	_	0.22
II	" 3939	_	faint tr.
12	,, 3992	_	tr.
13	» 3955	_	• tr.
14	,, 3914	•	
15	,, 39568	ss <u> </u>	tr.
16	,, 3935	_	tr.
. 17	,, 3849	_	tr.
18	,, 3843	_	faint tr. Much lead.
19	,, 3756	_	0.68
20	,, 3748		tr.
21	,, 4128		0.86
22	,, 3846	_	faint tr.
23	,, 4185	_	tr.
24	,, 4173	_	0.21
25	,, 4059		0.12
26	,, 4087	_	0.56
27	,, 4068	10.7	tr.
28	,, 4041	_	tr.
29	,, 3648	_	
30	,, 3760	(Lead, cont	raining 0.007% silver)
31	,, 3612		tr.
32	,, 3630	11.6	tr.
33	26	_	0.14
34			0.24
35	1500		0.01
36	1600	5.6	0.04
37	1226	, ,	0.02
38	1100		
39	126-	10.1	0.07
40	1166	(Lead cont	tr.
41		(Lead, Coll	taining 0.036% silver)
42	,, 4451		Ginter
	,, 4303		faint tr.
43	» 4431		
44	,, 4565		tr.
45	,, 4586		faint tr.
46	,, 4330		tr.
47	,, 4384		
48	" 4260	/T 1	
49	I. 1208		taining 0.02% silver)
50	L 1226	(Lead, cont	taining 0.008% silver)
51	DK 3566		0.81
52	,, 4642	-	-

Balance, copper except where marked as lead specimens.1

¹ All these specimens come from Late Period levels.

Specimens obtained by St. Aurel Stein in Balūchistān. Received Sept., 1928.

- 1. Copper from bracelet. Jiwanri iii, xvi f. Too small for analysis.
- 2. ,, spear-head. sh.T. vii. 12d.
- 3. Bronze. Zangiān. i, v. Tin, 23.1; nickel, faint trace.
- 4. Disk. Shāhī-tump. xiv. " 5.3.; " trace.
- ii. " 6.0; " nil.
- 6. Vessel from Gatti. ,, 27.0; ,,- nil.

Ditto, received Oct., 1928.

				Tin.	Nickel.
I.	Plate. Dwelling, iv, c.			nil	1.77
2.	Beads. Surface of Mound, Dash	t.		21.4	nil
3.	Rod. Tāke-dap			18.0	nil
4.	Cup. Gate-dap, Kolwa .			23.9	nil
5.	Fragment from Tumpak, Makran			6.4	tr.
6.	Fragment from Shāhī-tump .			6.2	nil
7.	Spiral wire from Mehī, Mashkai			11.4	faint tr.
8.	Plates found with mirror, ii, 2			nil	tr.
9.	Bowl from Mehī-damb, Mashkai			nil	tr.
10.	Plates, from surface, Mashkai.			24.4	nil
II.	Plates, from Bit-damb, Bāghwāna			32.5	tr.
12.	Curved Plate. Siāh-damb .			11.7	nil
13.	Fragments from surface, Kolwa			19.3	nil
14.	Rod from Segak mound, Kolwa			8.7	tr.
	Nos. 5 and 14 contained	traces	of	lead.	

Of the above specimens, those from Jīwanrī, Zangiān, Gatti, and Tāke-dap belong to the historic period; those from Shāhī-tump, Mehī, Siāh-damb, and the Segak mound to the prehistoric period. The age of the other specimens is uncertain, but it is seems probable that those which exhibit an exceptionally high percentage of tin are posterior to the prehistoric age. It should be noted that very little nickel occurs in the copper from Balūchistān.—[Ed.]

PART II

TECHNIQUE AND DESCRIPTION OF METAL VESSELS, TOOLS, IMPLEMENTS, AND OTHER OBJECTS

Technique.

It is not easy to determine the technique employed in the making of many of these utensils. It would be a simple matter to raise all the copper vessels from sheet metal, as their shapes are simple. But in the case of the bronze vessels there are two methods that could have been employed: Firstly, beating them out of sheet bronze which, however, would call for constant annealling to prevent the metal from cracking; or, secondly, the process that is called *cire perdue*. But the latter process is exceedingly difficult for large and thin castings owing to the risk of flaws and crevices that would render the vessel made in this way non-watertight. The varying thickness of the metal of some of the bronze vessels certainly suggests that the *cire perdue* process was used; but, on the other hand, it is possible that this inequality may be due to corrosion—the majority of the bronze pieces and some of the copper pieces could not be chemically cleaned owing to their very bad condition. I am

inclined myself to the opinion that some of these bronze vessels were raised from sheet metal which, being unrolled, would in the first place not be of equal thickness throughout.1 The fact that a second piece of metal was used to form the base of the utensil shown in Pl. CXLI, 6, I think, corroborates this view, unless we are to suppose that this vessel when cast had a faulty base and had subsequently to be repaired.2

The use of bronze instead of copper for utensils indicates a great advance in metal Bronze. working. Copper is an ideal material for making household utensils owing to the metal being so ductile; but unless it is fairly thick it is apt to bend and dent, especially if the temper produced by hammering is destroyed by heat, as, for instance, when vessels are used for cooking purposes. Bronze has the disadvantage of being considerably less ductile, but a finished vessel of this material is considerably stronger and less liable to damage.3

On reference to the pottery plates it will be seen that many of these utensils have their Counterparts counterpart in pottery. For instance, Nos. 7 and 18 in Pl. CXL are obviously of the same in pottery. type as the pottery jar illustrated in Pl. LXXXVI, 22. The two silver vases seen in Pl. CXL, 1 and 2, are of exactly the same shape as Nos. 55-8 in Pl. LXXXI. And other comparisons can easily be made.

I have already pointed out in the chapter on the pottery that ribbed ware is very rarely Ribbed ware. found at Mohenjo-daro. It is, therefore, satisfactory to have among our metal vessels one type shown in Pl. CXL, 18. Ribbing of this nature was, however, not primarily intended to strengthen the jar; it is a copy of the very old method of making a pottery vessel in two portions which were subsequently fitted together before firing, the rib being caused by the projecting edge of the lower portion being lapped over the upper portion of the jar. Only those metal vessels which were difficult to shape were made in this way, and the vessel under discussion, which is obviously a copy of the older pottery pattern, was without doubt shaped from a single sheet of metal.

The reason of the scarcity of metal utensils at Mohenjo-daro can only be that, when the Metal vessels city was deserted, the inhabitants had sufficient time to remove their most valued possessions. rare. Even at the present day copper vessels are of considerable value in the East and are bought by weight rather than by size. If a vessel of this metal be accidentally crushed out of shape, it can easily be restored by a coppersmith. It is only when it is badly holed that it must be replaced by a new one; and then the weight of the metal in the old vessel is credited towards the cost of the new one.

Nos. 4 and 5 in Pl. CXL prove to us that the art of casting bronze was a well-established Casting. industry at Mohenjo-daro. Both the dishes and their covers are cleanly made; so much so, that they must have been either carefully rubbed down or trued up on a lathe. No lathemarks are visible, but these could have been removed by subsequent honing and polishing. The fact that the handles of the covers were made separately from the lids themselves is difficult of explanation, for the two could easily have been cast together in a not too complicated mould. In describing No. 5, I have mentioned that the handle was secured to the cover not only by a rivet, but also by pouring molten metal around the base of the rivet for additional security; this process is known as "running on", and is one which requires skill to perform.

1 Mr. Mackay's view is not shared by Mr. Sana Ul'ah, who emphasizes the difficulty of raising such vessels from sheet metal and quotes Garland and Bannister, op. cit., p. 65.—[ED.]

² Casting by the cire perdue process was, however, practised in Egypt as early as, if not before, the Third Dynasty. See Garland and Bannister, Ancient Egyptian Metallurgy, p. 35. It has not yet been definitely decided whether the same process was used in early Sumer. See Hall and Woolley, Al 'Ubaid, pp. 34-5

Possibly, as Childe suggests, tin was added to copper not to harden it, but to lower the melting point. Dawn of European Civilization, p. 33.

490

Bases.

As these utensils were used on floors of hard brick or mud, the majority have flat or semi-flat bases. Those with rounded bottoms were probably kept either on wooden stands, which have perished, or on the circular pottery rings of which we find so many at Mohenjo-daro.

Rims.

It is curious that no attempt should have been made to strengthen the rims of these metal vessels by turning the metal down a little all the way round. The rim of a metal jar or dish is always its weakest part and likely to suffer damage, unless it be properly thickened. Some slight advance towards this method is shown, however, by the flaring of the rims, which undoubtedly produced a certain amount of stiffness. Why the process should not have been carried further, it is difficult to say, as a turned down or beaded rim is ornamental as well as protective.

Copper and bronze found together.

We have sufficient proof that copper and bronze were in use at the same time from various groups of vessels that were found together.

Group I consists of three vessels (C 1978), two of which are of copper and the third of bronze (Pl. CXL, II, 14, and 17). With these were found discarded tools, some broken and bent, made in bronze as well as in copper. The depth at which they were found (2 feet) would date them to the Late Period.

Group 2 (E 2044), shown in Pl. CXL, 4, 5, 9, and 18, consists of two bronze vessels

and two of copper, also belonging to the Late Period.

Group 3 (HR 4212a) comprises two silver jars and one of bronze, shown in Pl. CXL, 2 and 3, and Pl. CXLI, 13. With these were associated a number of copper and bronze implements of various kinds, described further on in this chapter.

Description of Copper, Bronze, and Silver Utensils

Copper and Bronze Vessels

Plate CXLI.

Detailed descriptions.

No. I (C 100-1). See also Pl. CXL, 6. Bronze vessel with slightly projecting flat base. Badly bent and with pieces missing. Plain rim with edge 0.09 inch thick. The metal thins towards the base to 0.04 inch in thickness. Despite corrosion, hammer-marks can still be seen in places. Height, 5.75 inches. Level, 5 feet below surface. Room 9, Block 12, Section C, DK Area.

Nc. 2 (C 100-1). See also Pl. CXL, 20. Large well-made bronze jar; badly broken and pieces missing. Small flat base that appears to have been lapped on. Plain edge, 0.18 inch thick. The metal of this jar is of unequal thickness, which suggests that it may have been cast, though unequal corrosion might possibly account for variation in thickness. Height, 10.5 inches. Level, 5 feet below surface. Room 9, Block 12, Section C, DK Area.

No. 3 (C 95). See also Pl. CXL, 7. Base missing. Shows traces of having been hammered. Thickness of metal fairly equal throughout, and averages 0.04 inch. Plain bent-over rim. Material copper. Height, 4 inches. Level, 4 feet below surface.

Room 9, Block 12, Section C, DK Area.

No. 4 (C 1978). See also Pl. CXL, 14. Base and other parts of jar missing. Plain rim measuring 4.6 inches across. Of copper of unequal thickness, varying from 0.15 inch at rim down to 0.05 inch towards the base. Height, 9 inches. Level, 2 feet below surface. Room 14, Block 8, Section C, DK Area. In this jar were found several copper implements which are illustrated in Pl. CXXXV, 2; Pl. CXXXVI, 1 and 4; and Pl. CXXXIX, 11. These are in a good state of preservation owing to having been protected in a measure from the soil.

Copper imple-

No. 5 (E 2044). This object appears to be the stem and base of a censer similar in shape Censer. to the offering-stands of pottery, from which the pan has disappeared. The copper base, which is incomplete and broken off the stem, is decorated with a fluted pattern not unlike that on the pan or base illustrated in Pl. LXXXVII, 3. The flutings are hollow on the inside; and the rim is bent over slightly and has a raw edge decorated with three rows of indented markings which can just be seen in the illustration.

The stem was fluted, horizontally and fairly regularly, by means of hammer-work, Fluting. whose marks still show in places; it was once a single piece of metal with the base. The knob at the top of the stem is a solid bronze casting and very heavy. That it is of bronze is proved by its being considerably lighter in colour than the stem and base. A circular mark upon it suggests, that it was given a final finish on a lathe. There would seem to be also traces here of a rivet, by which the pan was affixed to the stem. Estimated height, 6.65 inches. Diameter of base, 6.75 inches. Level, 4 feet below surface. This object was found in the large copper vessel illustrated in the same plate (No. 12). Room 1, House I, M, Trench E, DK Area.

No. 6 (E 2045). See also Pl. CXL, 12. Badly broken and bent. Has a plain flared Base lapped on. The projecting base, as the photograph shows, was roughly lapped on, the turned-over edge being very unequal in places. The metal of this vessel is unequal in thickness; half-way down it is 0.15 inch thick and at the rim 0.1 inch. This may be due to unequal thickness in the sheet from which the vessel was made, or perhaps to corrosion. Material, bronze. Height, 8 inches. Level, 4 feet below surface. Room 1, House I, Trench E (M), DK Area.

No. 7 (HR 5627) is a piece of copper shaped like a mussel-shell. It has a hole 0.08 inch in diameter pierced through it near one edge, and this edge is thicker and more raised than the opposite one. This object may have been used as a dipper and hung up by a cord when not in use; or it may have been affixed to a handle, though one would expect two holes if . the object had been riveted to anything. It measures 3.75 inches long by 2 inches wide. The thickness of the metal is 0.1 inch. Level, 4 feet below surface. Area to east of Structure XXXIX, Block 5, HR Area.

A similar object (HR 3941), which is not illustrated, is also the shape of a musselshell. It measures 3.2 inches long and 2.03 inches wide by 0.05 inch thick. There is also a hole 0.2 inch in diameter near one edge. Level, 2 feet below surface. Both these objects were purposely made this special shape; they are not pieces of metal cut haphazard out of copper sheet. Room 9, House VIII, Block 2, HR Area.1

No. 8 (HR 5725) is a twisted piece of copper which was probably the handle of some Handle. utensil. Its present length is 3.3 inches. The portion to be gripped has been bent into a rough tube with slightly overlapping edges. The rest is broken and incomplete. Level, 6 ft. 4 in. below surface. Room 40, House LV, Block 7, HR Area.

No. 9 (E 188). See also Pl. CXL, 8. Small vase, wide mouthed and with plain rim. The base is heavy compared with the thin sides. Thickness of metal at rim 0.15 inch, at middle height 0.09 inch, at base 0.2 inch. Its unequal thickness may be due to corrosion. A curious sunken band around the base of the jar measures 0.8 inch wide and 0.2 inch in depth. This vessel has the colour of pure copper, though it is made of bronze. Height, 4 inches. Level, 2 ft. 6 in. below surface. Trench E, DK Area.

No. 10 (C 100-1). See also Pl. CXL, 13. Bronze bowl of very thick metal, which seems to have been cast. Plain rim 6.34 inch wide, rather roughly finished and uneven. Rounded base. Diameter 12.75 inches. Height, 4.4 inches. Level, 5 feet below surface. Room 9, Block 12, Section C, DK Area.

A number of these objects of exactly the same shape have since been found.

No. 11 (C 1978). See also Pl. CXL, 14. This is another illustration of Pl. CXLI, 4, to show its contents when found. Level, 2 feet below surface. Room 14, Block 8, Section C, DK Area.

Ribbing.

Contents.

No. 12 (E 2044). See also Pf. CXL, 9 and 18. Both vessel and cover are of copper. The thickness of the metal at the level of the beading is 0·15 inch, and at the base 0·1 inch. The rim of the vessel is plain and lapped over slightly to stiffen it. The surface is too corroded to show the technique used in making this jar, but undulations of the surface suggest hammerwork. This vessel was not made in two pieces and joined together at the ribbing, as one at first would suspect; the whole was made from one sheet of metal. The ribbing was formed from the inside by beating the metal on a round-edged anvil. The cover was not made to fit the vessel, as is seen in Pl. CXL, 9. It was found adhering to the top of the jar, and it has not been found possible to remove it. This vessel contained the fine girdle of carnelian beads, and bronze and other gold and silver ornaments illustrated in Pl. CLI, b, and also the incomplete metal censer shown in Pl. CXLI, 5. Height, including cover, 12 inches Level, 4 feet below surface. Found in the north-western corner of Room 1, House I, Trench E (M), in the DK Area. (See Pl. LXV.)

No. 13 (HR 4212a). Bronze vase of graceful form. Small flat base and plain flared rim. Broken and repaired. Appears to have been cast. Height, 7 inches. Level, 6 feet below surface. This vessel was found with the two silver jars illustrated in Pl. CXL, 2 and 3, in Poore & House VIII. Plack at HP. Area

in Room 8, House VIII, Block 2, HR Area.

Plate CXLII.

Cast bronze.

No. I (E 2044). See also Pl. CXL, 4. Dish and cover of cast bronze. The dish is of very heavy metal, well finished and with a smooth surface. The cover fits very closely to the dish and has a slight projection on the inside, made by thinning the edge, to prevent its sliding off. The two fit so very closely together that there is practically no play at all. The handle is a separate piece riveted to the top of the cover, as can be plainly seen on the inside. There are indications, too, on the inner surface of the cover that it was cast in a sand mould. The dish measures 6.55 inches in diameter and 0.95 inch high, and the cover is slightly more in diameter. The two together stand 2.6 inches high. Judging from the very careful way in which the cover was made to fit the dish, it is possible that they were made for some commodity of value, perhaps a scented fat which was volatile. Level, 4 feet below surface. Room I, House I, Trench E (M), DK Area.

Nos. 2 and 3 (E 2044). See also Pl. CXL, 5. A dish and cover similar to the last, but not so well preserved. They are of slightly larger size, the dish measuring 7.4 inches in diameter. The bobbin-like handle was riveted on, and a patch of rough metal that now partly hides the rivet suggests that molten metal was run over it to help secure it. Level, 4 feet below surface. Bronze. Room 1, House I, Trench E (M), DK Area.

No. 4 (E 190). See also Pl. CXL, 19. Small vessel of beaten copper. Base projects a little and is slightly concave. Hole in centre of base, 0·18 inch in diameter. Rim plain, slightly flared and 0·07 inch thick. Height, 2·5 inches. Level, 2 ft. 6 in. below surface. Room 6, House II, Trench E (M), DK Area.

No. 5 (C 1978). See also Pl. CXL, 17. Bronze bowl of same type as No. 3, but smaller. 3.75 inches in diameter and 0.5 inch high. Level, 2 feet below surface. Room 14, Block 8, Section C, DK Area.

No. 6 (E 190). See also Pl. CXL, 16. Bronze flask, 3.05 inches high. Evidently

¹ Such dishes were commonly used to cover metal vessels.

cast. Surface not particularly well finished, but the working of the flask may not have been completed: Very thick, solid metal. Level, 2 ft. 6 in. belowsurface. Chamber 6, House II, Trench E (M), DK Area.

No. 7 (E 2044). Jar-cover beaten from very thin copper sheet, 0.02 inch thick. In Punchorder, apparently, to stiffen the edge, this cover was stamped all round inside the edge with markings. a row of punch-marks, which, however, do not show through the metal. At the top of the cover the metal has been raised up to form a projection, 0.47 inch in diameter and 0.22 inch high. This could only have served as a handle, especially if it was once capped, as appears likely. Passing through this projection there are the remains of a strip of copper, 0.21 inch wide, which was bent into a loop; the ends after being passed through the projection were twisted back on either side. Diameter, 2.57 inches. Level, 4 feet below surface. Room I, House I, Trench E (M), DK Area.

No. 8 (E 2044). Bronze cover. Similar in shape and make to Nos. 1 and 2 in the same plate. Diameter, 4.9 inches. Height, 1.1 inches. Level, 4 feet below surface. Room 1, House I, Trench E (M), DK Area.

No. 9 (No. ?). Possibly portion of clay crucible, with slag slicking to its sides.

No. 10 (DK 1621). See also Pl. CXL, 10. Very thick copper pan, measuring 11.3 inches across the rim, which is plain, and 1.42 inches high. Thickness of metal at rim 0.15 inch. Level, I foot below surface. Room 25, Block 2, Section C, DK Area.

No. 12 (E 189). Simple copper bowl with plain edge, o 1 inch thick. Height, 1.75 inches. Diameter, 4.75 inches. Level, 3 ft. 6 in. below surface. Room 6, House II, Trench E (M), DK Area.

Plate CXL.

No. 11 (C1978). Copper pan, half of which is missing. Shallow and with flat base. Diameter, 8.7 inches. Height, 1.1 inches. Level, 2 feet below surface.

Silver Vessels

Plate CXL.

No. 1 (DK 1341). See also Pl. CXLVIII, b. Silver vase and cover measuring Silver vase. 8.25 inches high. Cast. Level, 3 feet below surface. Room 2, Block 16, Section C, DK Area.

This fine vase was found to contain the gold and silver jewellery illustrated in Jewellery Pl. CXLVIII, a, which are described in Chapter XXVI devoted to "Personal contents. Ornaments". In order to extract this jewellery, it was found necessary to saw away part of the cover which owing to corrosion had become firmly fixed to the vase.

No. 2 (HR 4212a). Small silver vase made by casting. Height, 2.7 inches. Level, 6 feet below surface.

No. 3 (HR 4212a). Vase raised from a sheet of silver (?). Flat base and of simple make. Height, 3.8 inches. Cover 1.85 inches high. Level, 6 feet below surface.

Both these two last vases contained a quantity of gold ornaments and stone beads, Associated a great part of the former being merely scrap metal. This jewellery is illustrated in vessels. Pls. CXLIX, CL, and CLI, a, and is described in the chapter on "Personal Ornaments". The larger silver vase (No. 3) was found with its cover upside down, and considerable difficulty was experienced in removing the cover to get at the contents of the vase. With the two vases there was also found the bronze vessel pictured in Pl. CXLI, 13, and associated with the three were a number of implements illustrated in Pl. CXXXV, 5, 12, and 13; Pl. CXXXVII, 1, 4, 8, 9, 10, and 12; and Pl. CXXXIX, 6, 7, and 8. From Room 8, House VIII, Block 2, HR Area.

Blade-axes

Blade-axes.

The blade-axes illustrated in Pls. CXXXVIII and CXXXIX could have been used either in war or for ordinary purposes. For war and hunting they were probably set in a split handle, at right angles to it and secured by lashings of raw-hide. For carpentry they may have been hafted differently. It is possible, that the implement shown in Pl. CXXXIX, 5, was used as an adze, for it has a true chisel-edge, whereas the cutting edges of the other implements of this group are sloped both sides, the slope being gradual and flowing so that there is no abruptness.

In every case these implements are of substantial make and there was no skimping of metal. Few of the butts have the corners more than slightly rounded off. In one weapon (Pl. CXXXIX, 5), both ends of the tool are sharp-edged, and three blade-axes (Pl. CXXXVIII, 1, 2, and 6) have blunt edges at the butt, which suggests that this end also

could be sharpened and utilized if required.

As would be expected at this early period, copper is more commonly used for making blade-axes than is bronze, there being only three made in the latter material, not including a non-illustrated specimen (C 1978), which has all the appearance of being of bronze.

It is probable that these simple axes were first cast in open moulds and then hammered to give them the requisite hardness. There are ridges on the edges of several copper axes from the famous Gungeria hoard of 424 copper implements found in the Central Provinces, some of which are in the British Museum, which suggest that they were cast in a closed mould.¹ Copper is, however, difficult to cast in this manner, and there seems to me but little advantage in doing so with weapons of simple shape, except that the resulting castings would perhaps be cleaner. We do not, however know, the age of the Gungeria implements; they may be of later date than those of Mohenjo-daro and a more advanced technique may have been employed in their manufacture.

The absence of hammer-marks on all our examples except one suggests that they were carefully rubbed down after being hammered. Their straight cut sides and butts and only slightly rounded angles indicate some such treatment; for these features, which were probably also present in the mould, would have been destroyed in the process of hammering.

The bronze blade-axes would have required very much the same treatment, though cleaner castings could be obtained with this alloy and, therefore, not so much hammering would be required to harden them. Their tin content served this latter purpose.

The greatest thickness of the blade-axes of Mohenjo-daro is at about two-thirds down them, which gave weight at that part of the blade where it was most needed. It is uncertain whether the blades were cast with this special thickness here; it is more probable that the castings were originally flat slabs of more or less equal thickness throughout, and that when they were beaten to harden them little was done to the centre of the implement, but more attention was paid to the edges which were thinned out. The blade-axe in Pl. CXXXVIII, 6, distinctly shows that the hammering was started from the centre lightly and that the blows became more pronounced as the edges were approached; the latter have been beaten comparatively thin.

In certain respects the short type of axe is not unlike some of the copper axes found in the Bijnor district and now in the Lucknow Museum.² And certain of the Gungeria implements resemble those of Mohenjo-daro, while others are entirely different in type. Some of the blade-axes of Mohenjo-daro have an incipient shoulder (Pl. CXXXVIII, 3 and 6,

1 V. Smith, "The Copper Age and Prehistoric Implements of India" in The Indian Antiquary, vol. xxriv, p. 238.

2 Ibid., pl. i, fig. 12.

Copper more common than bronze.

Mode of manufacture.

Finish.

Thickness.

Comparisons.

and Pl. CXXXIX, 3 and 4), a feature which is also found among the Bijnor and the Gungeria axes, but is far more pronounced. This feature, however, is not confined to Indian weapons, for it is found in Hungary and Western Europe in both the Copper and Bronze Ages.

The blade-axes of about 3100 I.c. from Kish have rounded or semi-rounded tops and almost straight edges.1 They all belong to a long and narrow type. But some very early blade-axes from Susa,2 with but slightly splayed edges and straight sides and butts, approach very closely to the Mohenjo-daro blades of Type 1. This is perhaps what we should expect, for numerous connections between ancient Elam and the Indus Valley civilization are now known to us. The short and wide blades of Type 2, some of which have distinct shoulders, are not exactly paralleled in either Sumer or Elam, though very similar weapons are known in the Copper Age of Europe.3

For easy reference the axes found at Mohenjo-daro are grouped into two types, as below:

Type 1. Long and narrow. Type 2. Short and broad.

The first type is perhaps the more common, but owing to their more substantial make the blade-axes of the second type are invariably in a better state of preservation.

Type 1. Long and Narrow Axes (Pls. CXXXVIII and CXXXIX)

Plate CXXXIX.

No. 1 (VS 1450). See also Pl. CXXXVIII, 1. 8.9 inches long by 0.24 inch thick. Descriptions. Edges at both top and bottom. Bottom edge rounded and 2.3 inches wide.

Level, 5 feet below surface. Room 11, House XXX, Block 5, VS Area.
No. 5 (L. 383). 7.15 inches long by 0.23 inch thick. Width of chisel-like edge 2.8 inches. Butt square with sharp edge. Sides cut square with slightly rounded edges.

Copper. Level, I foot below surface. Room 104, Block 8, L Area.

No. 7 (HR 4212). Portion of a long blade-axe. Part of edge missing, but width is estimated at 2.38 inches. Edge sharp and gradually sloped both sides. Sides cut square. Bronze. Level, 6 feet below surface. Room 8, House VIII, Block 2, HR Area.

No. 8 (HR 4212). Portion of a long blade-axe, 0.22 inch thick. Edge straight (a rare feature) with a sharp slope on either side; 1.9 inches wide. Appears to be bronze.

Level, 6 feet below surface. Room 8, House VIII, Block 2, HR Area.

No. 10 (C 1978). Fragment of blade-axe, 2.5 inches wide and 0.2 inch thick. Both sides of cutting edge slope abruptly. Bronze. Level, 2 feet below surface. Room 14, Block 8, Section C, DK Area.

Pl. CXXXVIII.

No. 7 (HR 6056). 4.82 inches long by 0.2 inch thick. Sides and butt cut square. Wide butt. This blade is unusual in that the butt end, which is 1.32 inches wide, is of greater width than the edge. Both sides of edge slope. Copper. Level, 6 feet below surface. Room 87, House IX, Block 2, HR Area.

Non-Illustrated Specimens of this Type.

C 1978. 1 Very roughly made blade, 5.8 inches long by 0.21 inch thick. Blunt rounded

1 Mackay, Sumerian Palace and " A" Cemetery at Kish, Field Museum, Chicago, pt. ii, pl. lxi.

3 Petrie, Tools and Weapons, pl. i, figs. 26-8.

² Mém. Dél. en Perse, vol. xiii, pl. i, figs. 11 and 12. See also a specimen from Nagada, Egypt, dating from the Second Predynastic Culture. Childe, The Most Ancient East, p. 89, fig. 32.

edge, 1.8 inches wide. Very battered and bent, and seems to have been used for some other purpose. Appears to be bronze. Level, 2 feet below surface. Room 14, Block 8, Section C, DK Area.

Type 2. Short Broad Axes (Pls. CXXXVIII and CXXXIX)

No. 2 (VS 1450). See also Pl. CXXXVIII, 5. 6.95 inches long and 0.33 inch thick. Width at edge 3.55 inches. Edge rather blunt, very rounded, and has very slight suggestion of splay. Butt slightly rounded. Copper. Level, 5 feet below surface. Room 11, House XXX, Block 5, VS Area.

No. 3 (VS 1450). 7.5 inches long and 0.37 inch thick. Edge 4.2 inches wide. Butt, 2.9 inches wide. Sides slightly concave. Edge very rounded and slightly splayed, sharp, and gradually sloped on both sides. Butt cut square and flat. A very handsome implement. Copper. Level, 5 feet below surface. Room 11, House XXX, Block 5, VS Area.

No. 4 (VS 1450). See also Pl. CXXXVIII, 3. 5.95 inches long and 0.39 inch thick. Edge very sharp, rounded, sloped on both sides, 3.5 inches wide. Distinct shoulders present. Sides and butt cut square. Copper. Level, 5 feet below surface. Room 11, House XXX, Block 5, VS Area.

No. 6 (HR 4212). Portion of blade-axe, 0.35 inch thick. Edge is slightly splayed, 3.7 inches wide, and steeply sloped on both sides. The edge is badly corroded. Bronze. Level, 6 feet below surface. Room 8, House VIII, Block 2, HR Area.

No. 9 (VS 3185). A broken casting, 6.2 inches long and 0.45 inch thick. Both the projecting edges in the lower portion of the illustration are sharply sloped on both sides, and once formed the edges of a large blade-axe. Copper. Level, 10 feet below surface. It is possible that the casting was found to contain a flaw and in consequence it was broken up for remelting. Room 10, House XXXIV, VS Area.

Pl. CXXXVIII.

No. 2 (VS 1450). 8.25 inches long and 0.35 inch thick. Width at edge, 4.03 inches. Edge blunt and gradually sloped on both sides. The square butt also has a blunt edge. Sides cut square with slightly rounded edges. Copper. Level, 5 feet below surface. Room 11, House XXX, Block 5, VS Area.

No. 6 (VS 1450). 6.25 inches long and 0.3 inch thick. Rounded edge sharply sloped on both sides. Butt end is also fined to a blunt edge. This implement was hammered from the centre towards the edges, which are all slightly thinned. Copper. Level, 5 feet below surface. Room 11, House XXX, Block 5, VS Area.

Specimens of same type not illustrated.

VS 1450. 8.45 inches long and 0.4 inch thick. Edge sharply rounded and slightly splayed. Butt cut straight with corners carefully rounded off, 2.8 inches wide. A fine heavy implement, very carefully made. Sharp edge sloped on both sides, 4.25 inches wide. Incipient shoulders. Copper. Level, 5 feet below surface. Weight, 2 lb. 1 oz. Room 11, House XXX, Block 5, VS Area.

C 1978. 5:75 inches long and 0.35 inch thick. Abruptly rounded edge with double slope, 3.2 inches wide. Butt, 2.2 inches wide, cut square with corners slightly rounded. Sides cut square with distinct shoulders near edge. Copper. Level, 2 feet below surface. Room 14, Block 8, Section C, DK Area.

HR 4212a. 6.05 inches long and 0.28 inch thick. Edge rounded, slightly splayed,

Bronze.

Hammermarks. and 2.25 inches wide. Butt cut square with sharp corners and 1.7 inches wide. Edge sharp and sloped both sides. Appears to be bronze. Level, 6 feet below surface. Room 8, House VIII, Block 2, HR Area.

3.25, inches long and 0.22 inch thick. Slightly rounded edge, sharp C 1978. and sloped both sides, 2.05 inches wide. Butt, 1.6 inches wide. Sides and butt cut square. Copper. Level, 2 feet below surface. Room 14, Block 8, Section C, DK Area.

Spear and Lance-heads (Pls. CXXXV and CXXXVI)

It is with some hesitation that the weapons about to be described are called spear-heads. The possibility of their being knives used for a special purpose, such as flaying, is precluded, I think, by the total absence of rivet holes by which they could be secured to a handle.¹ It is unfortunate that no traces now remain of the wooden handles or shafts in which these heads were once fixed. Their complete disappearance proves them to have been of wood, and the unkindly soil of Mohenjo-daro accounts for their non-preservation.

These spear and lance-heads are peculiar for the width and thinness of their blades. Unsulstantial Some, indeed, are so thin that, unless they were reinforced in some way, they would have make. doubled up with even moderate pressure. It seems likely, therefore, that these blades were strengthened down their axes. Wood was most likely employed for this purpose; but how it was fastened to the blade is not clear, seeing that there are no rivet holes. It is probable that the shafts in which these blades were fitted were of a hard stiff wood, and that the portion that took the blade was sawn down longitudinally instead of split, so that the sides of the bifurcation might grip snugly along the blade, acting as a kind of mid-rib on either side. A wood such as bamboo with its tough exterior would serve this purpose Whether a cement was also used is not known, but shellac, it should be remembered, was probably a product of Sind in ancient days as now.

The thinness of these spear-heads and their being made of copper seem strange in view of the weight and heavy nature of the blade-axes. True, the latter implements require weight to be effectual, but this is also required in spear and especially in lance-heads. Seeing that metal was not spared in the manufacture of the blade-axes, we must conclude that it was not for reasons of economy that so little metal was used in the making of the spear-heads.

I venture to suggest that these large thin spear-blades were not made by the inhabitants of Mohenjo-daro, but that they were trophies captured from a people of inferior civilization. It is difficult to believe that the people who built Mohenjo-daro used such inferior weapons; on the other hand, there may have been a less civilized people living in Sind at the same time, such as the Bhils, Gonds, and other tribes who inhabit India at the present day. It is such people as these who would have made such primitive spear-heads; their poor resources would have compelled them to stint the metal in them as much as possible.2 The habit, even at the present day, of keeping weapons of strange make as curiosities might also have held among the people of the Indus Valley civilization.

The blades seem to have been made from a rod of metal but little thicker than the tangs. Metal rods. There does not seem any possibility that they were cast in their present shape, although the rods from which they were made were probably cast. The greatest thickness is at or close to the tang, and the hammering to shape seems'to have commenced from about

¹ The flaying knives, however, from Egypt which are illustrated by Flinders Petrie, Tools and Weapons, pls. xxiii, K, I, and xxxi, 2, etc., are without any rivet holes.—[ED.]

² The fact, however, that these weapons have been recovered from all parts of the site and from various levels, and that similar weapons have been found at Harappa, necessarily militates against Mr. Mackay's hypothesis.—[ED.]

this point. A little extra thickness was allowed for on the axis of the blade, but it gradually fines down towards the point. There is no attempt at a mid-rib.

Use of hone.

Judging from a slight irregularity (concavity) in the edges of some of the blades, it is probable that they were sometimes sharpened up with a hone to remove burring and notches. But apart from rectifying actual damage, these blades owing to their thinness would require but little attention in the way of sharpening.

African types.

In general shape these spear-heads resemble those used in parts of Africa at the present day. None have been found in ancient Egypt at all resembling them, and the few specimens of early date from Mesopotamia also bear no resemblance to them.¹ It affords a proof of the isolation of the Indus Valley from the rest of the ancient world, save in trade, that a people there should have used such primitive weapons when countries not so far away, Elam and Sumer, as early as and before 3000 B.c. had the socketted type of weapon in use and a strengthening mid-rib.

Tangs.

It will have been noticed that the tangs of most of the spear-heads are comparatively long; those of Nos. 1, 4, and 7 in Pl. CXXXVI are broken. As a rule, a long tang is not required for implements used for thrusting; but just enough to enable the blade to fit securely in its shaft and to prevent side-play. The end of the tang of the spear-head illustrated in Pl. CXXXVI, 6, was sharpened to an edge to facilitate easy insertion into the shaft. This, coupled with the fact that all the tangs are rectangular and not round in section, strongly suggests that hollow shafts were used, such as bamboo.

Plate CXXXVI.

Descriptions.

No. 1 (C 1978). See also Pl. CXXXV, 2. Length, 9·1 inches; breadth, 4·1 inches; o·15 inch thick near tang. Probably a portion of the tang is missing. Point and edges blunted by corrosion. A slight concavity in one edge of the blade is perhaps due to constant sharpening. Material, copper. Level, 2 feet below surface. Room 14, Block 8, Section C, DK Area.

No. 2 (HR 3832). Length, 7.6 inches (estimated length, 8.3 inches); breadth, 2.6 inches; thickness, 0.12 inch. Material, copper. Level, 4 ft. 2 in. below surface. Room 62, House IX, Block 2, HR Area.

No. 3 (HR 5799). See also Pl. CXXXV, 1. Total length, including tang, 7·15 inches; breadth, 2·62 inches; thickness of blade, 0·12 inch; thickness of tang, 0·2 inch. It is quite evident that this weapon was beaten out from a strip of copper not much thicker than the present thickness of the tang. Point, perfect and rounded. Edges, blunt and a little thinner than the middle of the blade. Material, copper. Level, 3 feet below surface. Second street in front of House XXIII, Block 5, HR Area.

No. 4 (C 1978). Tang, tip, and portion of side missing. Present length, 7.68 inches; breadth, 2.7 inches; thickness of blade and tang 0.12 inch, tapering down to 0.06 inch at the point. Material, copper. Level, 2 feet below surface. Room 14, Block 8, Section C, DK Area.

No. 5 (HR 5415). Lance-head measuring 3·15 inches long by 1·19 inches wide by 0·09 inch thick. Irregular in shape. Flat tang, 0·35 inch wide by 0·08 inch thick. Material, copper. Level, 5 feet below surface. Room 87, House IX, Block 2, Section B, HR Area.

Edged tang.

No. 6 (HR 2742). See also Pl. CXXXV, 9. Point missing. Present length, 4.92 inches; breadth, 1.65 inches; thickness, 0.1 inch. Flat rectangular tang, 0.41 inch

¹ Cf., however, the so-called daggers of Anau. Petri., Tools and Weapons, pls. xxxv, 99, and xxxvi, 130.-[ED.]

wide by O.I. inch thick. Tang runs to an edge for easy insestion in the shaft. Material, copper. Level, 3 ft. 2 in. below surface. Western side of First Street, HR Area.

No. 7 (HR 4458). Length, 4.8 inches; maximum breadth, 1.8 inches; thickness, 0.06 inch. Material, copper. Level, 3 feet below surface. Lane 1, between Houses III

and VII, Block 2, Section B, HR Area.

No. 8 (SD 1062). See also Pl. CXXXV, 8. A very fine specimen. Length, 11.3 inches; maximum breadth, 3.5 inches; thickness near tang, 0.15 inch. Most of the blade is OII inch thick. Very thin, and likely on this account to have been easily bent. Material, copper. This spear-head was unearthed at a level of 10 feet below the surface in the street between the eastern wall of the Great Bath enclosure and Block 1 of the complex of buildings south of the Stupa area (Pl. XXVII).

No. 4 (HR 2872). Length, 3.82 inches; maximum breadth, 1.15 inches; thickness, 0.08 inch. Small tang. Material, copper. Level, 2 feet below surface. First Street,

HR Area.

No. 10 (DK 1240). Length, 7.55 inches; breadth, 2.2 inches; thickness of blade, 0.09 inch. Tang, flat and 0.18 inch thick. Material, copper. Level, 6 ft. 9 in. below surface. Room 8, Block 2, Section C, DK Area.

Specimens of same type not illustrated.

SD 2007. Lance-head. Leaf-shaped. Length, 3.5 inches; breadth, 1.2 inches; thickness, 0.08 inch. Point missing. Material, copper. Found in Block 4 of Southern Buildings Section. Level, 4 feet below surface.

Arrow-heads

No arrow-heads of flint or any other stone have been found as yet at either Mohenjo-daro Absence of flint or Harappa, and there is therefore reason to think that only metal arrow-heads were used, at arrow-heads. all events in the later periods. The specimen illustrated in Pl. CXLIII, 12, is the only type of arrow-head that has been unearthed, and it obviously had a flint prototype; for it is but a slight modification of the concave-based flint arrow-head known to us in Egypt, 1 Northern Persia, and Western Europe in the neolithic and chalcolithic periods. Metal arrow-heads of this shape are known in early Greece and the Caucasus.^{2, 3}

Our specimen (DM 61), which unfortunately has lost the point of one barb, measures 1.33 inches long and 0.5 inch thick. It was evidently cut from a piece of sheet copper.

Level, 5 feet below surface. Stupa Section.

Knives and Daggers (Pls. CXXXV and CXXXVII)

Pl. CXXXVII.

No. 1 (HR 4212a). See also Pl. CXXXV, 5. This copper knife is 9 inches long by 2.2 inches wide by 0.12 inch thick. Both edges blunted owing to corrosion. Level, 6 feet below surface. Room 8, House VIII, Block 2, HR Area.

No. 2 (HR 5562). See also Pl. CXXXV, 3. Copper knife, 6.7 inches long by True knife. 1.23 inches wide. Back of knife thick near tang (0.17 inch) and fines down towards tip of blade. Edge sharp and graduated. Rough tang, rectangular in section with slightly rounded angles. Level, 7 ft. 6 in. below surface. Structure V, Block 2, Section B, HR Area.

1 Brunton and Caton-Thompson, The Badarian Civilization, pl. lxxxiii.

3 Three perfect specimens have since been found at Mohenjo-daro.

² Petrie, Tools and Weapons, p. 35, pl. xli; Glosz, Aegean Civilization, p. 90.

Leather-cutter.

No. 3 (HR 4057). See also Pl. CXXXV, 6. This object may possibly be a leather-cutter, since its tip is curved. It has been restored in Pl. CXXXV, 6, from a perfect example found at Harappā. Present length, 6.2 inches; estimated width, 2.1 inches; thickness, o.1 inch. Flat tang, averaging 0.42 inch wide and 0.12 inch thick. Appears to have been edged only on the convex side. Material, copper. Level, 3 ft. 5 in. below surface. Western side of First Street, HR Area.

No. 4 (HR 4212a). See also Pl. CXXXVIII, 9. A piece of bronze that seems to have been intended for a knife; 2:58 inches long by 0:15 inch thick; tapers gradually towards the right hand. Level, 6 feet below surface. Room 8, House VIII, Block 2, HR Area.

Absence of rivet-holes.

The first three specimens have fairly long tangs and the absence of rivet holes shows that they were just inserted into wooden handles without any other fastening.

No. 2 is a true knife, for it has an edge only on one side. The leather-cutter (No. 3) also seems to have but one edge, but corrosion could easily account for the blunting of the other. This implement was probably used for paring small hides.

The smallness of the number of knives and daggers found at Mohenjo-daro is rather arresting, unless we include as knives some of the narrower implements grouped amongst the spear and lance-heads.

Razors (Pls. CXXXVII and CXXXVIII)

Curved form.

The blade illustrated in Pl. CXXXVIII, 11, appears to be a razor (VS 3054). It is 2.2 inches long and has a fine curved edge, 1.05 inches wide. There are two holes at the back, 0.08 inch in diameter, by which it was riveted to a handle. Possibly the handle was set at right angles to the blade, as was the case with many of the ancient Egyptian razors. The blade has swollen slightly through corrosion, but it is estimated that originally it was 0.12 inch thick. Material, bronze (?). Level, 5 feet below surface. South-western corner of House XVII, VS Area.

What is seemingly a razor of another kind (L 238) is illustrated in Pl. CXXXVII, 5, and in Pl. CXXXVIII, 12.2 It is badly broken and now measures 2.38 inches across. Sharp curved edge. The average thickness of the blade is 0.9 inch. The tang, which averages 0.32 inch wide and 0.12 inch thick, is rectangular in section with slightly rounded edges. Material, bronze. Level, 6 feet below surface. Room 104, Block 85 L Area.

Saws (Pl. CXXXVII, 6 and 7; Pl. CXXXVIII, 4 and 8)

Shell cutting.

The fine bronze saw (C 100-1) illustrated in Pl. CXXXVII, 7, and in Pl. CXXXVIII, 8, is of much the same shape as the iron saws used at the present day to cut up shell (see Chapter XXVIII). Its length is 18.3 inches and maximum breadth 6.3 inches. In thickness it now varies from 0.05 inch to 0.1 inch; but corrosion makes it difficult to estimate the original thickness. Its poor condition also makes it uncertain whether the tang was longer than it now appears. There are two holes in the tang for riveting. The upper one is 0.15 inch in diameter and situated 2.1 inches from the end of the tang and 0.58 inch from the upper edge of the saw. The second hole is smaller and separated from the first by a distance of 1.4 inches, which shows that the handle was of considerable width. It is uncertain whether the top of this saw was ever backed, as are the modern examples. There are no rivet holes along this part of the blade, but a backing of metal may have been squeezed on, or even wood may have

1 Petrie, Tools and Weapons, pl. lxi, figs. 78 and 79.

² That the conjectural restoration is correct, is proved by numerous perfect examples since found at Mohenjo-daro.

been used to stiffen the blade. The teeth are well preserved at the tip of the saw and are dentate and somewhat irregular. Level, 5 feet below surface. Room 9, Block 12, Section C, DK Area.

What may have been a portion of a bronze saw is pictured in Pl. CXXXVII, 6, and Fragment of again in Pl. CXXXVIII, 4. The upper edge is straight like that of a saw; the lower edge saw. is unfortunately broken. As, however, two parts of it are in the same straight line, we may suppose that they are parts of the original edge and that the saw was not very wide, i.e., some 2248 inches. One rivet hole, 0.12 inch in diameter, is seen in the illustration and a trace of another can be made out in the curved portion of the saw to the right of it. A portion of the tang, which is 1.23 inches wide and 0.14 inch thick, is missing; it was broken off at a third rivet hole. No teeth are now visible. Level and number unknown.

Sickle-shaped Blade (Pl. CXXXVIII, 10)

From the curvature of this copper object (VS 1802), which is 4.7 inches long and Convex edge. 1.05 inches wide, we may perhaps conclude that it is a portion of a sickle-blade. The pointed end is the original shape, but probably a large portion is missing from the square end. Curiously enough, the inner edge of this fragment is of thicker metal (0.15 inch) than the convex side, towards which the metal fines down to a sharp edge. The outer edge must, therefore, have been the cutting edge. This object may perhaps be compared with the sickle-shaped pieces of metal that have been found at Kish and that still remain unexplained.1 Level, 4 feet below surface. South-western corner of House XXI, VS Area.

Fish-Hooks (Pl. CXLIII, 24 and 25)

Fish-hooks are common at Mohenjo-daro, but the examples found are generally very badly corroded.2

No. 24 (DK 4140) is in very bad condition. It is 1.65 inches long and the maximum thickness of the shank is 0.15 inch. It appears to be bronze. Level, 7 feet below surface. Room 61, Block 7, DK (g) Area.

No. 25 (HR 3312) is 1.95 inches long and the maximum diameter of the shank Loop-eye. is 0.12 inch. The end of the shank has been fined down and bent over to form an eye. Bronze. Level, 3 feet below surface. House IX, Block 2, Section B, HR Area.

Chisels (Pls. CXXXV and CXXXVII)

The chisels are of three types:—

Types.

- 1. Rectangular or square in section with dimensions very much the same along their entire length, as Nos. 11 and 14 in Pl. CXXXV.
- 2. Rectangular or square in section with flattened tangs, as Nos. 12, 13, 15, etc., in Pl. CXXXV.
 - 3. Round in section, as No. 15 in Pl. CXLII.

The first two types are frequently found, but the third is very rare. Chisels of Type : Manufacture. were made from square or rectangular rods of metal, which were probably cast in this shape, as it would have entailed considerable labour to hammer them out. In the majority of cases the sides and faces are parallel, but sometimes there is a slight thinning toward butt or edge, of which the latter is almost invariably slightly splayed. This intentional thinning was

Mackay, A Sumerian Palace, pt. i, pl. xxix, fig. 6; pl. lxi.

² Possibly due to their being generally made of bronze.

502

probably produced by hammering, for both butt and edge would have required the additional hardness that in a copper tool can only be produced by the hammer. It is not possible to connect chisels of this type with those of any other country in particular, for the shape is common to most early civilizations.

Indus Vælley type. Type 2, however, seems to be confined to the Indus Valley civilization. The long, flattened shanks certainly appear to have been made expressly to be fixed in handles, for only one example has been found whose butt was badly burred by hammer blows (Pl. CXXXVII, 8). As it would have been difficult to bore a rectangular hole in a piece of hard wood to serve as a handle, we must conclude that a short piece of hollow bamboo was used; the comparatively sharp angles of the shank would prevent the chisel turning in a handle of this nature. This type of chisel would also be useful without a handle, as its flat end would prevent its twisting in the hand. That it was occasionally used without a handle is proved by the burred butt of the specimen mentioned above.

It might be thought that these chisels with flattened shanks were made with the idea of providing a broad edge to the tool as well as a narrow one. We find, however, that their butts are always cut off squarely. Only one chisel, and that not of this type, has been found with

an edge at each end (SD 2052).

Pointed chisels.

Chisels of Type 3 were probably used only for working stone. The specimen illustrated in Pl. CXLII, 15, has a plain point which is not edged in any way; it is best described as a pick-chisel.

Doubleslope edges. As in the prehistoric chisels of Egypt, the edges of all those found at Mohenjo-daro have a double slope, which for the sake of strength is always abrupt. Not a single example of a single-sloped or true chisel has been found at Mohenjo-daro, though this form was used in Egypt as early as the First Dynasty.¹ At Susa the earliest chisels are also double-sloped, and so are all the Sumerian chisels of early date that I have seen.

Both Types 1 and 2 were manufactured from square or rectangular rods. There is, however, one exception, an unillustrated specimen (VS 2601), which was made from a round rod.

Mortise cutting.

None of these chisels are suitable for deep mortise cutting, for their splayed edges would prevent easy withdrawal from the hole. Certainly none of them show evidence of having been used on hard materials. They were probably employed for simple woodwork, and it may be for soft stones, such as steatite, which was very commonly used at Mohenjo-daro.² The smaller tools were perhaps employed for graving; No. VS 2601 has such a narrow edge that there can be no doubt that it was used for work of this kind.

Bronze rare.

Chisels of bronze are rarer than those of copper. Only three definitely bronze specimens have been identified (Pl. CXXXV, 15, and Pl. CXXXVII, 3a, 11). These are comparatively small tools, which suggests that tin was a rare commodity, though one would expect that, if so, it would have been more commonly used for such useful and hardworked implements as chisels rather than for axes, whose weight alone would conduce to their longevity.

Type I (Pl. CXXXV, II and I4; Pl. CXXXVII, 3a and II; Pl. CXLII, I3)

Descriptions.

Pl. CXLII, 13 (SD 1899). See also Pl. CXXXV, 11. Length, 9 inches. Splayed edge, 0.64 inch.wide, abruptly sloped on both sides. Made from a rectangular rod measuring 0.5 inch wide by 0.38 inch thick. Butt slightly burred by hammering. Tapers slightly towards butt and edge. Material, copper. Level, 11 feet below surface. Block 4, Southern Buildings Section.

1 Petrie, Tools and Weapons, p. 19.

2 Not, be it said, for large objects.

Pl. CXXXVII, 3a (VS 3599). 2.6 inches long, 0.45 inch wide, and 0.2 inch thick. Eage, 0.6 inch wide, splayed and abruptly sloped both sides. Butt very much burred.

Material, bronze. Level, 2 feet below surface. Room 43, House I, VS Area.

Pl. CXXXVII, 11 (HR 3797). See also Pl. CXXXV, 14. Length, 3.85 inches. Breadth at unsplayed cutting edge, 0.25 inch. Made from a rectangular rod measuring 0.23 inch by 0.17 inch. Edge unequally sloped on the two sides. Butt shows no sign of hammering. Material, bronze. Level, 6 feet below surface. Chamber west of Room 46, House V, Block 2, HR Area.

SD 2052 (not illustrated). Length, 4.8 inches. Edge at each end. Made from rectangular rod, 0.24 inch by 0.12 inch. Material, copper. Level, 3 feet below surface.

Type 2 (Pl. CXXXV, 12, 13, and 15; Pl. CXXXVII, 8, 9, 10, and 12)

Pl. CXXXVII, 8 (HR 4212a). Length, 6 inches. Edge, 0.4 inch wide, abruptly sloped on both sides. Shank flat and burred over at butt; measures 0.45 inch by 0.22 inch in section. Material, copper. Level, 6 feet below surface. Room 8, House VIII, Block 2, HR Area.

Pl. CXXXVII, 9 (HR 4212a). See also Pl. CXXXV, 13. Length, 5.95 inches. Edge sloped gradually on both sides and slightly splayed, 0.43 inch wide. Shank flattened, measures 0.7 inch by 0.23 inch; fines down slightly towards the butt. Material, copper.

Level, 6 feet below surface. Room 8, House VIII, Block 2, HR Area.

Made from a square rod, measuring 0.4 by 0.4 inch. Shank measures 0.7 inch by 0.16 inch and is cut square at the butt. Material, copper. Level, 6 feet below surface. Room 8, House VIII, Block 2, HR Area.

Pl. CXXXVII, 12 (HR 42120). Length, 5.05 inches. Edge missing. Made from a square rod 0.22 by 0.22 inch in section. Rod tapers towards missing edge which must have been quite narrow. Shank flat, measuring at the butt 0.4 inch by 0.15 inch. Material, copper. Level, 6 feet below surface. Room 8, House VIII, Block 2, HR Area.

Pl. CXXXV, 15 (D 603). Length, 3.6 inches. Made from rectangular rod measuring 0.12 by 0.8 inch. Flat shank, measuring 0.2 inch by 0.06 inch and fining down gradually to a blunt-edged butt. Material, bronze. Level, 4 feet below surface. Trench D, DK Area.

DK 896 (not illustrated). Similar in pattern to Pl. CXXXVII, 10. Length, 5.25 inches. Edge missing. Made from rectangular rod measuring 0.19 inch by 0.15 inch. Shank flattened, measures 0.35 inch by 0.11 inch. Material, copper. Level, 3 feet below

surface. Space north of Block 1, Section C, DK Area.

VS 2601 (not illustrated). Similar in pattern to Pl. CXXXVII, 10, except that it is rounded in section towards its edge. Length, 4.55 inches. Shank flat and rectangular with square cut butt, measures 0.25 inch by 0.1 inch. Made from a round rod 0.12 inch in diameter. Its very narrow unsplayed edge, only 0.1 inch wide, was clearly intended for fine work. Material, copper. Level, 5 feet below surface. House XIII, VS Area.

VS 2701 (not illustrated). Similar to Pl. CXXXVII, 9. Length, 6.9 inches. Splayed edge, 0.32 inch wide, slopes-on both sides. Made from rectangular rod measuring 0.28 inch by 0.24 inch. Flat shank measures 0.5 by 0.18 inch. Material, copper. Level,

7 feet below surface. House IX, VS Area.

HR 2089 (not illustrated). Length, 4.65 inches, Made from rectangular bar measuring 0.19 by 0.13 inch. Flat shank, measuring 0.35 inch wide by 0.12 inch thick, and fining down slightly towards butt. Material, copper. Level, 8 feet below surface. From ground between Houses III and VI, Section A, HR Area.

Type 3 (Pl. CXLII, 15)

Pl. CXLII, 15 (L'1166). See also Pl. CXXXV, 16. Length, 4.55 inches. Butt partly missing, round in section; now measures 0.39 inch in diameter. Fines down to a blunt point. Material, copper. Level, 2 feet below surface. Room 58, Block 2, L Area.

Awls and Reamers (Pls. CXXXV, CXLII, and CXLIII)

Plate CXLII.

Square point.

No. 14 (HR 4993). See also Pl. CXXXV, 7. An unusual object, 7.7 inches long, made from a metal red ô.28 inch square in section. Towards the end it fines down to a point. The shank has been hammered flat and at the butt measures 0.37 inch by 0.1 inch. Point bent. From the sharpness of its angles it seems likely that this tool was used as a reamer. Material, copper. Level, 4 feet below surface. First Street, HR Area.

Plate CXLIII.

No. 31 (VS 540). 4·12 inches long. Round in section, 0·12 inch in diameter. Blunt point at one end and a more graduated point at the other, part of which is missing. Material, copper-antimony alloy. Level, 3 ft. 6 in. below surface. House XXI, VS Area.

No. 33 (HR 5805). 3.62 inches long and 0.13 inch in diameter. One end blunt, a gradual, but broken, point at other end. Material, copper-antimony alloy. Level, 2 feet

below surface. House XLII, Block 5, Section B, HR Area.

No. 37 (SD 2511). See also Pl. CXXXII, 6. 3.52 inches long, with maximum thickness of 0.1 inch. Somewhat abrupt point at one end, long tapering point at the other. Material, copper. Level, 3 feet below the surface. Court 4, in the constructions south of the Great Bath.

These awls being of metal were probably used for heavier work than the bone awls illustrated in Pl. CXXXII and described in Chapter XXIV.

Needles (Pls. CXXXII and CXLIII)

Metal needles.

Pl. CXLIII, 20 (DM 187). See also Pl. CXXXII, 2. Copper (?). Is described in Chapter XXIV. Stūpa section, SD Area.

Pl. CXLIII, 21 (HR 300). See also Pl. CXXXII, 1. Copper (?). Is described in

Chapter XXIV.

Pl. CXLIII, 36 (DK 430). See also Pl. CXXXII, 5. Copper (?). Is described in Chapter XXIV. Room 5, Block 9, Section C, DK Area.

Metal Rods (Pl. CXLIII)

No. 30 (DM 121). Round copper rod, 5 inches long by 0.18 inch in diameter. Both ends bluntly rounded. Level, 7 feet below surface. Stūpa Seccion, SD Area.

No. 32 (SD 1781). Round copper rod, 2.5 inches long by 0.1 inch in diameter. One end a blunt point, other missing. Level, 4 feet below the surface. Passage 12 of the Great Bath Building.

No. 34 (HR 5292). Round copper rod, 3.78 inches by 0.17 inch in diameter. Tapers very gradually towards the ends, which are both cut-off square. Level, 6 feet below surface.

No. 35 (HR 4964). Round bronze rod, 3.35 inches long by 0.19 inch in diameter. One end cut off square, the other rounded and polished. Level, 6 feet below surface. Found with a second rod (2.62 inches long) in Room 105, House XII, HR Area.

The use of these copper and bronze rods is uncertain. It seems probable that they Kohl-sticks. were used for applying cosmetics like the kohl-stick of both ancient and modern Egypt. Their blunt ends preclude their being awls, and the fact that the ends are usually carefully rounded and polished proves that they are not pieces of unused metal.

Finger-Rings (Pl. CXLIII)

No. 1 (HR 4058). Internal diameter, 0.72 inch. Made of wire, 0.13 inch in diameter. Ends closely touching. Material, copper. Level, 2 feet below surface. House V, Block 2, HR Area.

No, 2 (HR 2619). Internal diameter, 0.7 inch. , Average diameter of wire, 0.13 inch. Ends taper slightly and touch. Material, copper. Level, 6 feet below surface. Court 49, House V, Section A, HR Area.

No. 3 (DK 3343). Internal diameter, 0.55 inch. Rounded ends just meet. Wire irregular, averages 0.15, inch in diameter. Material, bronze (?). Level, 2 ft. 8 in. below surface. Room 6, Block 8, DK (g) Area.

No. 4 (DK 3411). Made of four continuous coils of fine copper wire. Internal Coiled wire. diameter, 0.6 inch. Wire slightly flattened, measures 0.08 inch wide by 0.07 inch thick. The ends of the wire do not meet, nor do they come opposite each other.1 Level, 6 ft. 4 in. below surface. Room 77, Block 7, DK (g) Area.

No. 5 (HR 6036). Internal diameter 0.65 inch. Slightly oval. Made of bronze wire of unequal calibre; average diameter 0.06 inch. Level, 9 feet below surface. Room 85, · House IX, Block 2, HR Area.

The remaining rings, Nos. 5-8, are simple strips of copper, with their ends just meeting Flat wire. in some, and in others overlapping slightly.

Earrings (Pl. CXLIII, 11)

An earring of very unusual shape is seen in Pl. CXLIII, 11 (HR 3254). The portion Unusual type. that was passed through the lobe of the ear is of bronze wire, 0.09 inch in diameter. This was formerly a loop, but has been bent out of shape, so that the earring now measures 1.5 inches long. The loop of wire was first passed through a ring of coiled wire and then through a glazed steatite bead of cylindrical shape, 0.24 inch in diameter and 0.13 inch high. Below this bead, seven beads of washer-shape with bevelled edges form a kind of fluted drop. The base of the earring is much corroded and a portion is missing. After being threaded through all the beads, the wife was probably secured by coiling its end so as to keep everything in position. Level, 4 feet below surface. First Street, HR Area.

Bracelets (Pls. CXLIII and CXLIV)

Pl. CXLIV:

No. 7 (HR 3987). Outside diameter, 2.55 inches. Round in section, measuring 0.3 inch in diameter. Points slightly tapered and do not meet. Material, copper. Level, 12 feet below surface. Room 11, House XIV, Block 3, Section B, HR Area.

No. 9 (HR 4999). A child's bracelet of copper. Outside width, 2 inches. Slightly Oval section. oval in section, 0.29 by 0.22 inch in measurement. Tapered ends overlap slightly. Level, 6 feet below surface. Found in wall, Room 7, House II, Block 1, HR Area.

No. 11 (L 652). Outside diameter, 2.41 inches. Made from a round rod of copper of unequal thickness and slightly flattened inside. Thickest portion 0.21 inch wide by 0.16 inch. Late Period. Room 16, L Area.

¹ The same type of ring, in silver and in copper, is found at all periods in both Mesopotamia and Persia.

Pl. CXLIII.

No. 26 (L 713). A child's copper bracelet. Outside diameter, 2.21 inches. Made from a rounded rod, 0.25 inch wide by 0.22 inch thick, with a slightly flattened inner surface.

Ends taper only slightly. Level, 3 feet below surface. Room 15, Block 5, L Area.

No. 29 (HR 3988). Internal diameter, 1.42 inches. Round in section, except for a slight flattening on the inside; measures 0.28 inch by 0.25 inch. The ends, which are tapered, overlap a distance of 1.4 inches; they are not visible in the illustration. Material, copper. Level, 12 feet below surface. Room 11, House XIV, Block 3, Section B, HR Area.

Miscellaneous Objects (Pls. CXXXIX, CXLIII, and CXLIV)

Pl. CXXXIX.

Jar-handle.

No. 11 (C 1978) is a bent-up piece of copper now measuring 7.5 inches long. It shows little attempt at working and appears to be a rough casting that for some reason was not used and was thrown aside to be melted up again. It was possibly intended for the handle of a jar, as a portion near the middle is flat and has two holes bored through it, each 0.08 inch in diameter. These holes seem to have been cast and both are bevelled. In section the longer end of this casting is lozenge-shaped, measuring 0.65 inch by 0.5 inch. The shorter end is rectangular in section, 0.62 inch wide by 0.3 inch thick. Level, 2 feet below surface. Room 14, Block 8, Section C, DK Area.

Pl. CXLIV.

Piping.

No. 1 (C 100-1). A piece of piping, 22.5 inches long by 0.78 inch in diameter on the outside. Thickness of metal, 0.11 inch. One end is complete and the other missing. The complete end, which is slightly fractured, seems to have been open; the edge has been turned down outside the tube for a distance of 0.32 inch to stiffen it. There is no sign of a join or overlap to the tube, and it is possible that it was cast. Material, bronze (?). Level, 5 feet below surface. Room 9, Block 12, Section C, DK Area.

Copper bull.

No. 2. Roughly modelled copper bull with lowered head and marked hump. A very curious feature is that one ear is tied to a horn by a strip of woven material; the folds and twists of this are clearly shown in the casting, though they are not seen in the illustration. The other ear-was similarly treated, but corrosion has effaced all detail. The animal is a solid casting and there is a piece, of waste metal near the tail which was not removed. It stands on a pedestal with a ring beneath. The object of this ring is difficult to understand; it could hardly have been used for suspension, as the bull would have hung upside down. Length, 1.85 inches.

Shield boss (?).

No. 3 (SD 2468). Irregular circular piece of copper, 3.3 inches in diameter at its widest part. Around its edge, which is sharply bevelled, are nine rivets and a hole that once contained a tenth. This object is probably a patch of some kind, or it may once have formed part of something else, e.g., it was possibly the boss of a shield.² The plate including the rivets averages 0.22 inch thick. Level, 4 feet below surface. Found between two walls on the northern side of Block 5, south of the Great Bath.

Copper animal.

No. 4 (HR 4363). A copper model animal, whose species it is difficult to determine. The long snout, a portion of which seems to have been broken off, suggests an elephant.

1 Another identical figure has since been found.

² It would perhaps be too small for this purpose, and there is no evidence of shields having been used by the Indus people.

This object was roughly cast—if the roughness be not due to corrosion. Its comparative lightness suggests that it is not solid right throughout. Length of animal, 1.25 inches. Level, 4 feet below surface. Room 40, House LV, Block 7, HR Area.

Nos. 5 and 6 show different aspects of a bronze figure of a dancing girl before cleaning; the same figure after cleaning is also shown in Pl. XCIV, 6-8. This little figure is fully described in the chapter on the figurines (Chapter XVIII). Level, 6 ft. 4 in. below surface. Room 40, House LV, Section B, HR. Area.

No. 8. Roughly made hollow copper casting of a bird, now 1:1 inches high. Is broken Bird. and has a portion missing. From the shortness of its beak it seems likely that a dove is represented. The eye-holes appear to have been drilled, doubtless to take inlay.

No. 10 (HR 4964). Possibly a tubular covering of a handle; upper portion missing, Copper tube. but lower edge perfect.' Sides overlap slightly, but this may have been caused by earth pressure. Present length, 2.85 inches. Thickness of metal, 0.02 inch. A hole has been bored through at 0.35 inch from the lower edge, apparently in order to fasten this object by means of a nail to a wooden base. Level, 6 feet below surface. Room 105, House XII, Block 2, HR Area.

Pl. CXLIII.

Nos. 9 and 10 (DK 2278 and 2279). See Pl. CLVIII, 3 and 7. Objects cast in copper or bronze, with cells to take pieces of inlay. They are described in Chapter XXVIII. No. DK 2278 was found in Room 14, Block 2, Section B, DK Area, and No. DK 2279 in Room 4, Block 16, Section C, DK Area.

No. 13 (VS 2327) is a necklace terminal of a shape well known at Mohenjo-daro. Terminals. Length, 0.78 inch. The thinnest portion is a copper tube, 0.21 inch in diameter and 0.02 inch thick. The tube shows no sign of a lengthwise join. One end of the terminal appears to be a cast bead, 0.38 inch in diameter, a portion of whose interior has been drilled out to take the tube. The bead appears to be of bronze, and the tube of copper. Similar terminals are seen at the ends of the girdle illustrated in Pl. CLI, b. Level, 6 feet below surface. Room 105, House XVI, VS Area.

Nos. 14 and 18 (E 2044 and L 572) are bronze girdle terminals of a shape which is frequently found at Mohenjo-daro. The first is described in Chapter XXVI, and illustrated in position in Pl. CLI, b. Room 1, House I, Trench E, DK Area. The second comes from L Area; it is made from a single piece of metal without the use of solder. Its maximum width is 2.08 inches and it is 0.24 inches thick. The inside is hollow and there is a hole, 0.19 inch in diameter, at the apex of the curved portion. Level, 2 feet below surface. Room 23, Block 4, L Area.

No. 15 (C 95) is a six-holed bronze spacer, 2.35 inches long by 0.25 inch wide Spacer. The holes are slightly oval and average o I inch in length. by 0.05 inch thick. It is uncertain whether they were purposely made oval, or whether they were worn so by the threads passed through them. Level, 4 feet below surface. Room 9, Block 12, Section C, DK Area.

No. 16 (C 95). Group of cast bronze beads, slightly cylindrical in shape and with Beads, rounded edges. They vary somewhat in size, averaging 0.27 inch long by 0.3 inch in diameter. They are all pierced, but it is uncertain whether the holes were made in casting or were drilled afterwards. Probably both methods were employed. Level, 4 feet below surface. Room 9, Block 12, Section C, DK Area.

508

Spacer.

No. 17 (HR 5660) is a five-holed bronze necklace spacer, 2·39 inches long by 0·42 inch wide by 0·09 inch thick. The holes have been filled up by corrosion. Level, 4 feet below surface. Room 112, House XLVI, Block 5, Section B. HR Area.

No. 19 (HR 6186) is a group of bronze buttons, which are described in detail in Chapter XXVI. Level, 6 feet below surface. Chamber 107, House XII, Block 2, HR Area.

Copper casting.

No. 22 (HR 5650). This object is a copper casting, 0.9 inch high and varying from 0.6 inch to 0.65 inch in diameter. At the tapered end it is hollowed out to a depth of 0.75 inch, the resulting walls being 0.1 inch thick. It was evidently intended to cap something, perhaps a handle. It has been left in the rough state in which it was taken from the mould. Level, 5 feet below surface. West Court (19), House XVIII, Block 4, HR Area.

No. 23 (DK 1695). A cross-shaped ornament somewhat irregularly cut from a flat piece of copper. Measures 1.05 inches across and is 0.03 inch thick. Level, 2 feet below

surface. Street between Blocks 8 and 9, Section C, DK Area.

No. 27 (HR 4410). This type of chain is still extensively used at the present day. Each link was cut from a strip of copper or bronze, 0.05 inch wide by 0.05 inch thick. Owing to corrosion, no sign of soldering is visible; it is probable that the links were cut out whole from a flat sheet of metal and then bent into shape. The fact that the metal of which they are made is rectangular in section suggests this latter process. Each link is 0.55 inch long with a maximum width of 0.22 inch. Level, 6 feet below surface. House LIX, Block 8, HR Area.

No. 28 (HR 3433). Each link of this piece of chain is made of round bronze or copper wire, 0.08 inch in diameter. The links were once presumably oval, but have been pulled out of shape. There are no signs of soldering, but as the ends of the wire forming each link neither overlap nor are twisted together, some metal must have been used to join them. Level, 5 feet below surface. Southern portion of Room 46, House V, Block 2, HR Area.

¹ It was used in Egypt at the time of the sixth dynasty. Petrie, Arts and Crafts of Ancient Egypt, p. 87, fig. 94. A gold chain of the same pattern was found in an E.M. II tomb at Mochlos. Evans, Palace of Minos, vol. i, p. 98, fig. 69.

Chains.

CHAPTER XXVI

PERSONAL ORNAMENTS

S in most ancient countries, the women of the Indus Valley decked themselves out with jewellery, and it is probable that the men did likewise. The commonest ornaments were long strings of beads, some of considerable size. None of the male figurines, except one, are ever represented as wearing ornaments, but that men did in fact do so is definitely indicated by holes cut in the necks of some of the stone statues, in which to tie the ends of a string or strings of beads.

One male statue at least wears an armlet (Pl. XCVIII, 1). But armlets are never represented on the clay female figurines and they were possibly worn only by certain classes. The bronze figure seen in Pl. XCIV, 6-8, represents a dancing girl—always an inferior class in India—and the left arm is almost concealed beneath a multiplicity of such ornaments. This little statue does not give us any indication of the material of these bracelets, but if they were made entirely of metal the weight must have been excessive.²

Some of the gold jewellery that has been found beneath the pavements of houses is of quite an elaborate nature. Gold and silver were evidently by no means rare metals at Mohenjo-daro. We find pure gold as well as a kind of electrum, which may be either natural or artificial. Bronze and copper were also used in the manufacture of spacers and terminals for strings of beads.

There is a link between Sumer and ancient Sind in the use in both countries of a fillet around the head, a thin ribbon of either gold or silver, whose ends were tied at the back of the head by means of a thread. At Mohenjo-daro fillets were worn by both sexes. Apart from the use of these fillets, there is little resemblance between the style of hairdressing in the two countries.

Stone beads of practically every shape and form were in use. Some are of large size and are even made of such comparatively soft stones as limestone and alabaster. Beads of this kind could hardly have been worn solely for purposes of ornamentation (unless they were painted); probably they served also as amulets. The favourite material for beads was chalcedony in all its forms, carnelian being especially common and artificially treated to enhance its colour. No precious stones, as we understand them, were used, perhaps on account of their extreme hardness and the difficulty of working them. That they were known seems probable, as India is a country especially rich in them.

Only four examples have been found at Mohenjo-daro of carnelian decorated with white lines, but that this technique was well-known is shown by beads and other objects being made of other substances to simulate decorated carnelian (Pl. CLVII, 8-12).

1 The figure illustrated in Pl. XCIV, 509, 11.

² See infra, p. 531, note 2.

There is every probability, that in India bead-making was one of the most ancient arts, since in most places the requisite materials were ready to hand. This was not the case in

Mesopotamia, where even the commonest stone was difficult to procure.

A city site is rarely sufficiently productive of the jewellery and ornaments worn by a people for a really comprehensive survey of them. Beyond those rare finds that occur beneath the pavements of houses and hoards that have been buried by thieves, but little jewellery is unearthed in the ruins of a city. For a proper study of this subject we have to rely in most cases on cemeteries; and, unfortunately, we have had no success as yet at Mohenjo-daro in our search for the graves of the dead. Were a cemetery to be found, we should doubtless obtain from it a much more extended knowledge of the personal ornaments of the people than is at present possible.

Beads (Pls. CXLV, CXLVI, and CXLVII)

The beads that are illustrated in Pls. CXLV, CXLVI, and CXLVII are for convenience divided into types, as described below:—

Cylindrical Beads (Pl. CXLV, 1-10)

Beads of this shape are quite common at Mohenjo-daro. They vary greatly in length, from long thin specimens to beads so short that they might almost be described as disc-shaped.

The materials used in the manufacture of these beads are very varied; those illustrated are made of the following materials:—(1) Soft black stone; Room 20, Block 4, L Area.

(2) Faience. (3) Steatite; Room 20, Block 4, L Area. (4) Steatite; Room 15, Block 4, L Area. (5) Calcite. (6) Faience; Trial Trench D, DK Area. (7) Pottery; Room 71, Block 3, L Area. (8) Shell; Room 45, Block 1, L Area. (9) Steatite with gold caps;

Room 2, Block 16, Section C, DK Area. (10) Calcite.

Bead No. 6, which is best described as tubular, is now a brown colour which suggests that it was originally green, the change being due to an oxide of iron. It is one of eighteen, of which seventeen were originally green and one blue, which has now faded to white. Judging from the size of the hole, this bead must have been threaded on a thick cord, as was apparently the case with the majority of the beads of this type. No. 9 was made of glazed steatite and capped at each end with gold.

Cylinder beads of faience are found in considerable numbers at all ancient sites and they were evidently very popular at Mohenjo-daro. The string illustrated in Pl. CLII, 15, f, exactly resembles beads from ancient Egypt and Mesopotamia in both colour and shape.

Cog-Wheel Type (Pl. CXLV, 13-20)

Beads of this type are very common at Mohenjo-daro in both the Late and Intermediate levels, but are unknown at the ancient sites, of Elam and Mesopotamia, nor do I know of their occurrence further west. These cog-wheel beads are always made of paste and are usually glazed. Their original colour was either green or blue, but in most cases the colour has entirely disappeared. One would have thought that faience was much too soft a material for beads of such a shape, and, as a fact, many of the projecting cogs are broken off. A number of them, however, on a string would mutually strengthen one another. All these beads were made in a mould, and in section are of various shapes, ranging from a simple disc (No. 13) to a short barrel-shape (No. 20).

Materials used.

Capped bead.

Foreign comparisons.

Materials.

Some of the beads of this type are marked with shallow concentric grooves on one side only, e.g., No. 15. Others are plano-convex, as No. 17. It seems hardly likely that these two varieties, with which must be coupled Nos. 16 and 1,8, were strung; possibly they were sewn to the clothing. The great majority, however, were certainly worn as beads.

No. 15 is made of shell and was found in Room 72, Block 3, L Area. No. 16, of faience, Shell. comes from space 74 in the same block. No. 17, faience, was unearthed from Block 2, Section B, DK Area, and No. 20, also of the same material, from Room 15, Block 4, L Area. They belong to the Late Period, but seem to occur also at the latter end of the Intermediate Period.

Fluted Tapered Bealls (Pl. CXLV, 21-3)

Beads of this type were either used as pendants or were strung in couples with their Pendants. wider ends together. From the levels at which they were found they appear to belong to both the Late and Intermediate Periods, but in neither were they very common. They were all made in moulds and are of a fine white paste coated with a glaze which appears to have been originally coloured blue.

Long Barrel-Cylinder Beads (Pl. CXLV, 24-32; Pl. CLI (b))

This type of bead is of unusual interest, as similar beads found at Kish have been dated Plasma. to the pre-Sargonic Period.² As, however, beads of this type were uncommon in early Mesopotamia and fairly plentiful at Mohenjo-daro, in both the Late and Intermediate Periods, there is reason to think that they were made in India and exported to Mesopotamia. They have apparently not been found in Elam. Beads of this shape were always made of a beautiful translucent red carnelian (Nos. 24-8), or of pottery (Nos. 29-32); the one exception, which, unfortunately, is broken, is of a dark green coloured chalcedony (SD 2508), known to geologists as "plasma".

The pottery beads are probably an imitation of the carnelian beads. They are Imitation very roughly made and closely resemble pottery beads of the same shape found at Jemdet carnelian. Nasr in Mesopotamia, which site is closely dated by its painted pottery to the period of Musyan in Elam. But only pottery beads of this shape were found at Jemdet Nasr; there were none of carnelian. Sometimes these pottery beads are coated with a smooth red slip (Pl. CLII, 19, a-c).

Some difficulty seems to have been experienced in drilling the holes (slightly conical) Boring. through these stone beads, which is not to be wondered at considering their length. The boring was done from both ends, and in some cases the two holes did not meet exactly in the middle. All the beads of this type were probably cut and polished before the boring was commenced, for the translucency of the polished stone would naturally help the lapidary to see whether his drill-holes were running straight.

The boring of these exceptionally long beads was probably done with a piece of thin copper rod and emery powder. The abrasive used must have been exceedingly fine, since the holes throughout their length are polished 3; the process, too, must have been laborious and doubtless there were failures, though it must be confessed that we have not yet found Once the drill was set in a perfectly straight line with the bead and had entered

I imagine that they were attached to the clothing in the manner of sequins, as they have only one hole.

² Mackay, A Sumerian Palace, etc., pt. ii, pl. xliii, figs. 8 and 9. These carnelian beads I regard as important from the point of view of dating our site. They seem not to have been worn in Babylonia later than c. 2700 B.C., and are also unknown in India, as far as I can ascertain, except in the Indus Valley civilization. At Kish the same form of bead was made in lapis-lazuli. Ibid., pl. lx, Nos. 18 and 19.

³ The same polish was found inside the early earnelian beads from Kish.

512

the bead a short distance, the process would become, in a measure, automatic; provided, of course, that not too much pressure was employed. Presumably some form of lathe was employed and the drilling done with the bead placed in a horizontal position.¹

Finish.

Though these beads, whether of pottery or carnelian, are not always quite regular in shape, they are sufficiently so to look well to the casual eye. The carnelian beads are exceptionally well polished and their ends are slightly rounded. The beads made of pottery have no slip, and their holes were probably made by moulding the bead upon a piece of fibre, which was burnt away when the bead was baked. Indeed, their irregularity suggests their having been moulded with the fingers.

An interesting bead of this type (L 993), found in Chamber 22, L Area, is shown in Pl. CLII, 18, and again in Pl. CXLV, 26. This is made of red carnelian, but is streaked and mottled with white markings—whether natural or artificial it is difficult to decide.

Short-barrel Beads (Pl. CXLV, 33-9)

Crystal.

This shape of bead was extremely popular at Mohenjo-daro and was made in every conceivable material, including copper, bronze, gold, and silver. Crystal beads are rarely found, but when they occur it is usually in this form. No. 33 is uncommon in shape. It is made of shell and like most beads made in this material was threaded on a thick cord. The hole of No. 38 is unusual in the way it widens towards the outside at each end; this is not due to wear, as would be expected.

Jade.

No. 34, a green jade bead,² was found with others in Room 2, Block 16, Section C, DK Area, and No. 35, of silver, was unearthed from Room 1, House I, Trench E, DK Area. No. 36, which is made of steatite, was found in Room 104, Block 8, L Area, and No. 37, also of the same material, came from Chamber 52, Block 1, of the same Arca. No. 39, of white limestone, was unearthed in Chamber 10, Block 5, L Area. All five belong to the Late Period.

Long-barrel Beads (Pl. CXLV, 40-53)

This type of bead is also found in large numbers. Only those beads whose length is markedly greater than the diameter are included in this type. The smaller specimens are made of various materials, but the larger ones are either of faience or of varieties of soft stone, limestone being especially common. No. 46 is made of a comparatively soft black stone mottled with dark grey, and No. 50 is white limestone. This last comes from 7 feet below the surface in Block 3 of the Southern Buildings Section. No. 51 is a soft brown stone with green specks, and the large finely made bead No. 52, of limestone striped in white, red, and brown, comes from Passage 12 of the Great Bath building. No. 53 is made of agate and is the largest hard stone bead that has yet been found at Mohenjo-daro. No. 40 is from Room 30, Block 4, L Area; Nos. 43, 45, and 49 from Space 91, Block 9; No. 46 from Chamber 20, Block 4; No. 47 from Room 4, Block 5; and No. 53 from Chamber 37, Block 1, L Area. With the exception of the last, all these beads belong to the beginning of the Late Period.

Barrel-shaped Beads, Oval in Section (Pl. CXLVI, 1-15)

Early type.

This type of bead also is found in considerable numbers in all the levels at Mohenjo-daro and is made in a large variety of materials, including silver and gold. Some of the beads of this type are very flat in section and others considerably fuller, Nos. 11 and 14 being very

¹ The bow-drill was probably used.

² See Pl. CXLVIII, a, Fig. 6, and p. 519 infra.

nearly round in section. No. 15, which is of shell, is flat on one side and half round on the other, a shape that is not uncommon in this type of bead. The same shape is well-known at Jemdet Nasr, where it is associated with early painted pottery. It is also found at Nal in Southern Baluchistan, another early painted pottery site.1

Bead No. 2 was made of a white stone veined with black and was found in Poom 83, Block 4, L Area. No. 3, of faience, comes from Room 112, Block 7, and No. 5, of white paste, from Room 21, Block 4. No. 8, made of faience, was found in Chamber 8, Block 5; and No. 10, of white paste, comes from Room 104, Block 8. No. 15, also of the same material as the last, was found in Court 69, Block 3, L Area. Beads 3, 8, 10, and 15 are of the Late Period and beads 2 and 5 of the Intermediate Period.

Reclangular Beads, Oval or Half-round in Section (Pl. CXLVI, 16-19)

These beads are numerous in both the Late and Intermediate levels, and were made of all kinds of materials. Those which are oval in section were by far the most popular, but beads that are half-round in section are far from being rare. No. 16, of glazed steatite, is of Intermediate date and was found in Chamber 14, Block 4, L Area. No. 17 is of agate, No. 18 of steatite, and No. 19 of green felspar.2

Disc-shaped Beads (Pl. CXLVI, 20)

Disc-shaped beads were rare on the whole, though found in both the Late and Materials. Intermediate Periods. The specimen illustrated (No. 20) is of unusual size and made of faience. A very fine series of disc-shaped beads of gold separates the large green jade beads in the fine necklace in Pl. CXLVIII, a, fig. 6. Beads of this shape were also made in pottery (Pl. CLII, 20), but none in carnelian have as yet been unearthed at Mohenjo-daro, though they were exceedingly common in early Mesopotamia and in Egypt. The material most frequently used for this kind of bead was shell; in this material, however, the edge of the bead is flattened and the central ridge missing. No. 20 of Pl. CXLVI was found in the clay packing to the north of the Great Bath, at a level of 4 feet below the surface of the ground.

The absence from the site of the rougher make of carnelian disc-shaped bead, which is so common in early sites in other parts of the East, proves that bead-making was well advanced. It is, of course, possible that we may yet find this variety of bead in the lower levels, though, if they do occur there, we should have expected that examples would be picked up and re-used by the people who inhabited the upper levels. This rough form of disc-bead has been found by Sir Aurel Stein in Chalcolithic sites of Northern Balūchistān, and I gather that the same explorer has found similar beads in the south of that province.

Globular Beads (Pl. CXLVI, 21-7; Pl. CLII, 15 a, b, and c)

Globular beads in the majority of cases are small in size. They are made in all sorts Metal forms of materials, except shell. There were minute gold beads of this shape in two hoards of common. jewellery found in the DK and HR Areas at Mohenjo-daro, all of them cast. Larger beads of this shape were also made in gold, silver, copper, and bronze, sometimes cast and sometimes beaten out of thin material and soldered together. The beads shown in group 15, a, b, and c, in Pl. CLII, are of blue faience, a type of bead that was very common in ancient Egypt, especially during the Twelfth Dynasty. This form of bead is found at all levels at Mohenjo-daro.

¹ Mém. Arch. Surv. Ind., No. 35.

² From string No. 7, Pl. CXLIX. Cf. p. 523.

51

Analysis.

An analysis by Dr. Hamid of the glaze of one of these globular beads resulted as follows :-

0		Per ce	ent.	
Silica		. 87.1	I	
Ferric oxide and a	lumina.	. 4.8	9	
Lime		. 0 2.4	2	
Magnesia .		. 0.3	o Bead No.	HR 3352
Alkalies (by differe	ence) .	. 3.7	I	3-1-20-5
Oxide of copper			2	
Loss on ignition		. 1.0	5	
			-	
Total		. 100.00		

Dr. Hamid states that he assumes that no foreign adhesive was used to bind the body of this bead together. The glaze alone was sufficient for this purpose. Only the surface glaze of this bead was examined; the body is made of a softer material. The colour is now a faint blue.

No.-21, of steatite, comes from Chamber 15, Block 4, L Area, together with No. 27, which is made of limestone. No. 22, a carnelian bead, is from the same area and was found lying close to the surface in Chamber 104. Both Nos. 23 and 25, of gold, were unearthed in Room 1, House I, Trench E, DK Area. Nos. 24 and 26 are of glazed steatite. All seven beads belong to the Late Period.

Segmented Beads (Pl. CXLVI, 28-30)

Faience.

Foreign examples.

This type of bead is somewhat rare. The material is always faience; Nos. 28 and 29 are blue in colour and No. 30, now yellow, was once green. The shape may have originated in the accidental sticking together of oval or globular beads in the process of being glazed, but on the other hand this type of bead, carved in ivory, has been found at Badari in Upper Egypt. No glaze has yet been found in the graves of the Badarian civilization, though glazing was practised by the early predynastic peoples of Egypt.

The same type of bead, also in faience, is known in the pre-Sargonic period in Mesopotamia, and also in later times in Egypt, where it was especially popular, coated with various coloured glazes, during the Eighteenth and Nineteenth Dynasties. Stone beads of this shape have been found amongst Ægean material and dated to Early Minoan II.² Later on, the same type of bead, but in glaze, appears in Middle Minoan III.³ Beads of this form appear to belong only to the Late Period at Mohenjo-daro.

Unclassified Types (Pl. CXLVI, 31-9)

The following beads, being of unusual forms, are described separately :-

No. 31 (L 689). Faience and unique in shape. The missing portion has been restored in the drawing. Level, 4 feet below surface. Found in Chamber 20, Block 4, L Area, and dated to the Late Period.

Lapis-lazuli.

No. 32 (DK). Faience. This shape is unusual at Mohenjo-daro, but fairly common in the pre-Sargonic graves at Kish, where it was made in lapis-lazuli. DK Area.

¹ Brunton and Caton-Thompson, The Badárian Civilization, pl. xlix, fig. 76 (A. 3).

² For a description and history of these beads, see Evans, Palace of Minos, vol. i, pp. 491-3. Also Childe, Dawn of European Civilization, p. 39.

3 Univ. of Penns. Pubs. Anthrop., iii, 3, p. 184

A Sumerian Palace, etc., pl. lx, 7; p. 183.

No. 33 (DK 2999). Glazed paste,1 apple-green in colour. It is hollow and has four small holes in pairs near the base, set opposite to each other. It seems probable that this object is not in reality a bead, but was made to be sewn to a dress. The same shaped object has been found without the holes. A number of the perforated type, including No. 33, were found together in an upper level which can be dated to the Late Period. Level, 1 ft. 6 in. below surface. Room 3, House I, Block 1, Section B, DK Area.

No. 34 (HR 4212a). This type of bead is made of two circular pieces of thin gold Soldered bead. with a groove across the centre of each. The plates are soldered together with the grooves coinciding. (See also the lowest string of beads in Pl. CXLIX, B.) A very similar bead was found in the "A" cemetery at Kish, where, however, it was lozenge-shaped and made of silver; the method of manufacture was identical.2 Room 8, House VIII, Section B, HR Area. Judging from the level at which they were found, 6 feet below the surface, No. 34 and the other beads found with it appear to belong to the Intermediate Period.

No. 35 (L 402). Steatite. Semi-circular in section. This is possibly the lug of an Lug of seal. ordinary stamp seal carefully rubbed down smooth to make it serve as a bead. The irregular placing of the hole somewhat confirms this. Found in Room 104, Block 8, L Area. Late Period.

No. 36 (VS 3474). Glazed paste. Disc-shaped with a deep groove round the edge. Late Period. Room 10, House V, VS Area.

No. 37 (HR 2467). Shell. Ornamented with lines and circles as well as having a serrated edge. Found at a high level; therefore, presumably belongs to the Late Period. House LXVI, HR Area.

No. 38 (HR 2211). Faience of a beautiful blue. Obviously an imitation of a metal Metal origin. bead in shape. •It was found 7 feet below the surface and belongs to the Intermediate Period. House III, Block 2, Section A, HR Area.

No. 39 (L 468). Steatite. Only the rounded side is fluted, the flat side being left plain. Probably two of these beads were fastened back to back. Late Period. From Chamber 28, Block 4, L Area. Level, 4 ft. 6 in. below surface.

Decorated Beads (Pl. CXLVI, 41-53; Pl. CLVII, 8, 9, 10, and 12 (?))

No. 40 in Pl. CXLVI simply shows the decoration of No. 41 (HR 3723), a steatite Trefoil pattern. bead whose surface is somewhat irregularly covered with a trefoil pattern. Level, 5 feet below surface. Area south of Room 43, House V, Block 2, HR Area.

No. 42 (VS 3187). Steatite. A thick disc-shaped bead decorated on the edge with a wavy line. Level, 6 feet below surface. Lane between Houses XXXVIII and XXXII, VS Area.

Nos. 43, 44, and 45 are three carnelian beads decorated with fine white lines which Decorated have been burnt into the surface of the bead. Only four beads of this kind have, as carnelian. yet, been found at Mohenjo-daro, but the process is still carried on in India.3

No. 43 (VS 2546) was found in House XVII, VS Area, at a depth of 1 foot below the surface.

No. 44 (L 225) comes from Chamber 114, Block 6, Section A, L Area, from just beneath the surface.

No. 45 (SD 1198) was found in the passage west of Chamber 8 of the Great Bath building at a level of 5 ft. 5 in. below the surface.

1 Possibly moulded steatite. 2. Mackay, A Sumerian Palace, etc., pt. i, pl. vii, fig. 11.

3 I have seen an ornamented bead of this kind made by an old man in Sind.

The largest of these heads, No. 43, is also illustrated in Pl. CLVI, 9. From the level at which all of them were found they must belong to the Late Period.

Foreign examples.

A number of very similar beads have been found at Kish in a cemetery of the pre-Sargonic period.¹ Several of these decorated carneliar beads were found at Ur in a necklace of a date between the eighth and fifth centuries B.C.,² and similar beads have been picked up in considerable quantities at Brahmānābād in southern Sind.³ Mr. Cousens, however, is of the opinion that the specimens that he found belong to the historic period.⁴ If this be so, the beads of the Ur necklace may be of late manufacture, but consideration must be given to the possibility that as carnelian beads are practically indestructible, the specimens from Ur are of much earlier date and had been re-used.⁵

Mr. Horace Beck is of the opinion that these beads were first etched before the white was applied to the ground. Where they are broken, the white lines can be seen to have penetrated for some distance, but the structure of the stone is continuous across the part where the colour has changed.⁶

Bobbin-shape.

No. 46 in Pl. CXLVI (C 109) is a long, hand-made, bobbin-shaped bead of pottery, somewhat irregularly grooved. Though included amongst the decorated beads, there is a possibility that it was used for some other purpose. Level, 4 feet below surface. Room east of Chamber 6, Block 11, Section C, DK Area.

No. 47 (HR 3046). Pottery. Irregular in shape and ornamented with spiral grooves. Intermediate Period. Room 49, House V, Block 2, HR Area.

No. 48 (HR 4370). Faience. There is a decorated beading round the hole on each side of the bead. Late Period. Level, 18 inches below surface. House XVI, Block 3, Section B, HR Area.

Trefoil design.

No. 49 (L 668). Steatite. Cylindrical in shape with its entire surface covered with a trefoil pattern. Level, 5 feet below the surface. This bead comes from Room 8, L Area, and is dated to the Late Period.

Glazed pottery.

No. 50 (HR 5026). Brown bead with white bands. An analysis of the glazes that cover this object will be found in Chapter XXVIII on "Ivory, Shell, Faience, etc." This bead has a pottery base overlaid with two coloured glazes. The latter were in a very ropy condition when applied and were subsequently re-heated in a kiln, though not enough to ensure a proper adherence of the inlaid brown bands to the glaze of the bead. On the outside this bead bears a remarkable resemblance to one wholly made of glass. It was only on taking a sample from it that we discovered its pottery interior. There can be no doubt, I think, that this bead is an attempt to copy the decorated type of carnelian bead. Level, 6 feet below surface. Room 18, House XV, Block 3, Section B, HR Area.

No. 51 (SD 123). Steatite artificially treated to represent decorated carnelian. The stone is brownish-red outside and grey inside. Level, 2 ft. 6 in. below surface. Late Period.

No. 52 (VS 130). Faience, still retaining some of its original blue colour. Cylindrical. Heavily grooved along the sides. Level, 2 feet below surface.

1 Mackay, "A" Cemetery at Kish, pt. i, p. 56, pl. iv, fig. 30; A Sumerian Palace, etc., pl. xiii, fig. 9; pl. lx, figs. 54-8; JRAS., Oct. 1925, pl x.

² Mackenzie, Ancient Civilizations, p. 166.

3 Ann. Rep. Surv. Ind., 1903-4, pl. xlix. Cf. Cousens, Antiquities of Sind (Arch. Surv. Ind.), pp. 54 and 55, pl. xiii.

4 Beads of this class have been found on many other historic sites in India.—[Ed.]

5 Many of the Arabs of to-day in Mesopotamia and Egypt wear beads that they have picked up from ancient sites.

⁶ From a personal communication.

7 Compare chape with fig. 380, p. 113, t. vii of Mem. Del. en Perse.

No. 53 (L 445). (See also Pl. CLII, 17.) Steatite. An exceptionally fine bead. Inlaid bead. The interiors of the trefoils were probably filled in with either paste or colour. The former is the more probable, for in the base of each foil there is a small pitting that may have been used for keying a coloured paste. The depth of the cutting is 0.05 inch. Level, 3 feet below surface. Late Period. Found in Chamber 27, Block 4, L Area.

The most interesting of these beads are those with the trefoil pattern, which also occurs on the robe worn by the statue pictured in Pl. XCVIII. The trefoils on both the beads and Statue are irregular in shape and in this respect differ from the pattern as we ordinarily

know it.10

No. 8 (SD 1998) in Pl. CLVII is a long, rectangular bead measuring 1.5 inches long by Decorated 0.35 inch wide and thick. It is made of a coarse white paste that resembles powdered carnelian copy. steatite. Its surface is covered with a smooth red slip that is ornamented, somewhat roughly, with three white bands, possibly in imitation of decorated carnelian. This unusual bead was found in Chamber 26 of the Bath Building, 8 feet below the surface.

It is a little uncertain whether the objects seen in Pl. CLVII, 10 and 12, which were Kushan beads. evidently coloured to represent decorated carnelian, were worn as beads or not. Their holes are very large, and if used as beads, they must have been threaded on a very thick cord. Objects very similar to these in shape, of Scytho-Parthian or Kushan date, which come from Chārsadda in N.W. India are quite definitely beads; a proof that this shape survived to a fairly late period.2

Pottery Beads (Pl. CXLVII, 37-40)

A number of pottery objects found in the DK Area appear to be beads, for similar objects Chamfered are seen strung together in Pl. CLII, 16. As the illustration shows, they are roughly apertures. made with strongly chamfered holes, which are unduly wide; indeed, the cord must have been very thick to prevent the beads wobbling upon it.

None of these beads are decorated in any way; some are quite plain and others are coated with a cream slip. They have been found at various levels of the Late and Intermediate

Periods.

Spacers (Pl. CXLIII, 15 and 17; Pl. CXLVII, 1-20)

The number of spacers that have been found at Mohenjo-daro is quite remarkable, showing that many of the necklaces worn by the inhabitants must have been composed of several strings of beads.

The holes in the spacers range from two to six in number, and the materials of which Materials. they are made include faience, pottery, paste, copper, bronze, and gold. A great many of the spacers are single flat strips pierced with the number of holes required, but in some cases gold beads were soldered together to form spacers, as in the central string of Pl. CXLVIII, a, fig. 7. The majority of the spacers are flat rectangular beads (Nos. 2-9), which are nearly always plain, but occasionally decorated, as in No. 10, which is made of faience

1 For another example of this ornamentation, see the bull illustrated in Jastrow, Civilization of Babylonia and Assyria, pl. liii, and the Sumerian bull from Warka shown in Evans, Palace of Minos, vol. ii, pt. i, p. 261, fig. 156. Sir Arthur Evans has justly compared the trefoil markings on this latter bull with the quatrefoil markings of Minoan "rytons", and also with the star-crosses on Hathor's cow. Ibid., vol. i, p. 513. Again, the same trefoil motif is perhaps represented on a painted sherd from Tchechme-Ali in the environs of Teheran. Mém. Dél. en Perse, t. xx, p. 118, fig. 6.

² Ann. Rep. Surv. Ind., 1902-3, pl. xaviii.

and is ornamented with concentric circles on one side only. Many of these spacers are very roughly made, e.g., the pottery example, No. 17. Even the metal spacers are not always free from irregularity, as may be seen from No. 18.

No type of spacer can be dated to either the Late or Intermediate Period exclusively.

We shall probably find them in the early levels also, when these are excavated.

The following are the materials of which the various spacers that are illustrated are made:—

(1) Steatite; Room 19, L Area. (2) White paste; Room 30, L Area. (3) White paste; Room 104, E Area. (4) Calcite; Room 4, L Area. (5) Faience. (6) Glazed steatite; Room 86, L Area. (7) Calcite. (8) White paste; Room 15, L Area. (9) Faience; Room 15, L Area. (10) Faience; Room 56, L Area. (11) Pottery. (12) Faience. (13) Faience; House LI, HR Area. (14) Shell; Room 104, L Area. (15) Faience. (16) Faience; House LI, HR Area. (17) Pottery. (18) Copper. (19) Copper; Room 1, House I, Trench E, DK Area. (20) Gold; Room 8, House VIII, Block 2, Section B, HR Area.

Terminals (Pl. CXLIII, 14 and 18; Pl. CXLVII, 21-7)

Multi-stringed necklaces.

For necklaces composed of a number of strings of beads terminals were necessary and were usually made of metal, either gold, copper, or bronze. The exceptions are mostly faience. No. 21 (E 2044), of bronze, is also shown in position in Pl. CLI, B, and will be dealt with fully in the description of this piece of jewellery.

No. 22 (HR 4604) is of faience. That it is a terminal seems likely from its shape; the two strings of the necklace were probably passed through the terminal and knotted on the outside. Space between structures XLVIII and XLIX, HR Area. Level, 5 feet below surface.

No. 23 (HR 4212a), though like a terminal, is not one in the strict sense of the word. It is one of the gold caps of a bead in the seventh string in Pl. CXLIX, b, which came from Room 8, House VIII, Block 2, HR Area.

No. 24 (HR 4212a) is a gold terminal—one of those seen on the sixth string from the bottom in the same plate.

No. 25 (HR 2862), which is made of faience, from its shape can hardly be anything other than a terminal. Vicinity of First Street of HR Area. Level, 3 feet below surface.

No. 26 is a terminal made in gold. Found with other pieces of jewellery in Room 8, House VIII, Block 2, HR Area, at a depth of 6 feet.

No. 27 (VS 2101) is a triangular terminal of faience with holes to take four strings. A fifth hole through the apex of the triangle was provided to take a short cord to fasten the necklace at the back of the neck. This object is so far unique. From the position in which it was found it evidently belongs to the Late Period. House XXV, Block 4, VS Area.

The metal terminals are very simply made from thin sheet metal, in some cases entirely without soldering; in others the metal was cut to shape and then bent over and soldered down one side. A hole was always pierced through the curved top of the terminal. The bases are always found open, but they appear to have once been closed by a thin sheet of metal pierced with holes, very similar in appearance to the usual type of spacer.¹

Make.

¹ It seems to me that we have the same kind of terminal with beads attached portrayed on painted pottery sherds from Tépé Deuceva in the environs of Susa. Mém. Dél. en Perse, t. xx, p. 113, fig. 19. Very similar terminals are

JEWELLERY AND NECKLACES

Hoard No. 1 (Pl. LXII; Pl. CXL, 1; Pl. CXLVIII, a and b)

The jewellery illustrated in Pl. CXLVIII, a, was found in the silver vessel (DK 1341), Silver vessel. illustrated on the right of the plate,1 which was unearthed by Mr. Dikshit in a long trench that he dug to connect up Sections B and C in the DK Area. The site of this find is shown in Pl. LXII, Block 16, the find spot in Room 2, at the eastern end of the Block, being marked by a cross. As the walling in this Block is of the Late Period and the depth of the find was only 3 feer below the surface, this hoard of jewellery can be definitely dated to that Period.

The large necklace is made up of barrel-shaped beads of a translucent, light-green jade, Jade beads. measuring 0.9 inch long by 0.45 inch in diameter in the middle and 0.25 inch at the ends. These beads are not all accurately graded, but in this respect nevertheless they compare well with other specimens of ancient jewellery. Each jade bead is separated from its neighbours on either side by five disc-shaped gold beads, 0.4 inch in diameter and 0.2 inch wide, made by soldering two cap-like pieces together. The joint is very fine and can only just be detected in some of the beads.

In the front of the necklace seven pendants of agate-jasper are suspended by means of a thick gold wire passed through each, which was thinned out and coiled two or three times at its proximal end to form an eyelet for the cord. The pendants are separated one from another by a small cylindrical bead of steatite capped at each end with gold.² The smaller necklace (No. 7) inside the large one is made up of small globular gold beads, all of which are cast. The spacers were made by soldering two of these beads together, and it is probable that the beads were originally strung into a bracelet of two rows.

Together with these strings of beads several rough pieces of silver were found, one Chisel of which bears chisel-marks remarkably like cuneiform characters. A cast of this piece of markings. silver was submitted to Mr. Sidney Smith, of the British Museum, who, however, could not identify any definite sign upon it. This fragment, which measures 0.95 by 0.9 by 0.25 inch, is part of a bar, from which it was snapped after both ends had been struck with a broad chisel. Judging from this piece, the original bar was quite rough and had been run in a clay mould.3

A couple of silver earrings found in this hoard were made of wire, 0.2 inch in diameter, Silver wire. roughly bent round with the ends overlapping. The two bangles (Nos. 1 and 4 in Pl. CXLVIII, b) were each made of thin sheet gold wrapped over a core which has now disappeared 4; the metal overlaps slightly on the inside of the bangles and no solder was used. The original diameter of these bracelets seems to have been about 3 inches, and a small hole bored at either end was probably intended for fastening the ends together. They had been bent up for remelting.

One of the most interesting objects found in the silver jar was the conical gold cap Conical gold measuring 1.35 inches high, which is shown at the top of the plate (No. 2). It was made without cap. soldering by being beaten out from a plate of gold, and was then stiffened by bending out the edge at right angles all round. Inside the cap a gold loop was soldered at the pointed tip, apparently in order to sew or fasten it to something. Metal ornaments of this shape are used in India at the present day, a strand of hair being passed through the loop inside to keep them in position on each side of the head.

1 See also Pl. CXL, No. 1. ² We are not, of course, sure of the original order of threading.

³ This silver fragment now weighs 23:389 grammes, but it should be noted that some of its original weight has been lost in the process of cleaning.

⁴ No traces were found of a core of either shellac or bitumen in these or other bracelets.

Silver ring.

Yet another object of interest is the silver ring shown at the bottom of the plate (No. 13), whose bezel, I inch square and 0.2 inch thick, bears a design of crosses and semi-crosses, similar to those in shell, illustrated in Pl. CLV, 34 and 35.1 A border around the edge of the bezel is formed by two lines set close together with oblique dashes between them. The ring itself, which is a simple strip of silver 0.25 inch wide by 0.1 inch thick, is roughly soldered to the bezel. The back of the bezel shows traces of having been fused and the ring may have been discarded on this account. The band itself is broken and most of it is missing.

The two silver bracelets shown in Pl. CLXIV, a and b, were also found with this

hoard. They are described later on amongst the bracelets.

Broken metal.

From the fact that there was so much broken and scrap metal in this find, it appears that it belonged to a jeweller or a dealer in precious metals. Indeed, the gold bangles had been twisted up into as small a compass as possible, probably with a view to re-melting. The ring also was quite useless as an ornament.

Hoard No. 2 (Pl. LXV; Pl. CXL, 4, 5, 9, and 18; Pl. CXLI, 5 and 12; Pl. CXLIII, 13 and 14; Pl. CLI, B)

Find in copper bowl.

The very fine necklace (E 2044) illustrated in Pl. CLI was found in a large copper bowl which was covered by a shallow copper dish.² Both bowl and dish are illustrated in line in Pl. CXL, 9 and 18, and in photograph in Pl. CXLI, 12. An empty copper vessel lying beside them appears in Pl. CXL, 12. Together with the jewellery, the two covered dishes shown in Pl. CXL, 4 and 5, were found inside the bowl, and also the fragment of a copper censer illustrated in Pl. CXLI, 5.

Provenance of hoard.

This hoard was found in the north-western corner of Room 1, House I, one of two buildings (M) excavated by Mr. Dikshit halfway along Trench E in the DK Area, the plan of which will be seen in Pl. LXV. The exact place of the find, which was at a depth of 4 feet below the surface, is marked by a cross on the plan. The date of the hoard can be safely placed to the Late Period.

Details.

The long carnelian beads of the necklace or girdle (Pl. CLI, B) are 4.85 inches in length by 0.4 inch in diameter in the middle and 0.3 inch at the ends. The shorter beads are about the same in diameter, but 3.25 inches in length. These beads are beautifully made and of a bright translucent red colour. They were bored from both ends, the holes averaging 0.17 inch in diameter at the outer end and tapering slightly to a little less in the middle. These holes meet more or less accurately in the middle of the beads, but in a few cases the alignment of the two holes is so inaccurate that the thread can only be passed through the middle of the bead with difficulty. Any deviation from the straight in the alignment of the holes in beads of such length is most difficult to correct after the boring has begun; it could only be rectified by employing a drill of larger diameter than that first used, and then only with a certain amount of difficulty. In some of the beads it is quite evident that a larger drill was employed at one end of the bead than at the other, probably for this very reason.

Terminals.

At each end of the necklace or girdle there is a semi-circular terminal of hollow bronze like a flattened cup, measuring 2.2 inches each way, the metal of which is about one-fifteenth of an inch thick. There are no signs of a join or soldering in these terminal pieces, and it seems that they were beaten out of a piece of bronze without a join being necessary. These terminals can hardly have been cast; the metal is too thin.3

1 Large square hezels are very rare in ancient rings.

3 Pl. CXLIII, 14, and Pl. CXLVII, 21.

² The dish was adhering so fast to the bowl that a portion of the latter had to be cut away in order that its contents might be extracted.

PERSONAL ORNAMENTS

679 5

The globular beads at each end of the stone ones are of bronze; the spacers also appear to be of the same metal. The latter are 2.45 inches long by 0.27 inch wide by 0.1 inch thick. Each has six holes, all of which are slightly oval in section owing to wear.1

A bronze tube (Pl. CXLIII, 13) was once fastened to the curved outer end of each Make. terminal, with a knob-like head to prevent its passing through the latter. Both tabe and head were made from strips of bronze bent round a mandril with the edges simply pressed together and not joined by solder."

Together with this necklace were found two gold studs, each 1.2 inches in diameter, Gold studs apparently intended for the ears. They are shown in the same photograph (Rl. CLI, 7, 8, and 11), in the middle and at the left-hand corner. The edge of each stud is decorated with a beading that was soldered on. This beading is so regular in make that one suspects that it was hammered or cast in a mould rather than filed into shape. In the centre of each stud at the back there is a hollow tube, 0.5 inch long and 0.27 inch in diameter, which tapers very slightly towards the outer end, on to which it is probable that another tube of slightly larger diameter fitted with a smaller head for the back of the ear. That these two objects could not have been used as nose-studs is shown by the length of the tube fastened to each.

Three very curious objects found with the studs and the necklace appear to be netting Netting needles of gold. They are shown just above the ear-stude and also in the lower right-hand needles (?). corner of Pl. CLI, B, 3-5 and 12-14.

The largest of these needles (E 2044a) is 2.5 inches long. The handle is hollow and sylindrical and tapers slightly, being 0.2 inch in diameter at the needle end. The needle point is 0.5 inch long and has a roughly shaped oval eye at its base.

The medium sized needle (E 2044b) is 2.5 inches long and of the same pattern; but the cap that closed the end of the handle is now missing. The point which has an oval eye at its base is 0.3 inch long.

The third needle (E 2044c) is only 1.7 inches long, with the point 0.3 inch in length. Its handle, which is otherwise similar to those of the other two needles, is badly dented.

The exact use of these three objects is open to question, for they could have been used for either sewing or netting. The handles seem to have been drawn, as there is no sign of a soldered line, but the caps at either end were soldered on with an alloy that is very little lighter in colour than the gold itself. The two smaller needles have evidently been held between the teeth on more than one occasion.

A number of bead-caps, shown in the centre of the plate, were also found in the copper Bead-caps. bowl, but not the beads to which they once belonged. The gold of which the caps are made varies greatly in colour, ranging from almost coppery-red to pale yellow. These caps were first drawn out of sheet gold to form a tube, and one end was then covered with a gold plate soldered in position. The other end of the tube was adjusted to fit the end of the bead. The longest of these caps is 0.75 inch long by 0.48 inch wide; all are oval in section.

Another curious ornament (No. 9) found with this hoard is shown just below the smaller Unusual objects in the Pl. CLI. It is an irregularly shaped bead of turquoise matrix with a mirute ornament. hole through the centre and capped at each end with gold. A long gold bar with its ends bent at right angles acts as a kind of clip to keep the gold caps against the stone.2 A silver tube was soldered inside each cap to allow of a thread being passed through them more easily. It would appear that the two gold caps were not originally made for this particular stone, as they do not fit it properly. Though the caps are of the same size, the hole at the outer

¹ Pl. CXLVII, 19.

² This bar arrangement is obviously so makeshift that one suspects that it was fitted at home.

522

Electrum.

end of one of them is 0.1 inch in diameter, and of the other 0.3 inch in diameter. The holes on the bent-over ends of the clip are also of different sizes. It is, of course, possible that this object is really a pendant rather than a bead, and that a bigger hole was required at one end than the other. The caps and clip seem to be electrum rather than pure gold, for they are very pale in colour and appear to have a large admixture of silver. The alloy might of course be either natural or artificial.

Hoard No. 3 (Pl. XXXIX; Plan; Pl. CXL, 2 and 3; Pl. CXLVII, 20 and 24; Pl. CXLIX; Pl. CL; Plan; Pl. CLII, 13)

Remarkable find.

A remarkable find of jewellery was made in the HR Area at a depth of 6 feet below the surface in Room 8 of House VIII, Block 2, Section B. The chamber belongs to the Late Period and the jewellery, therefore, must be of that date. This find is numbered HR 4212a, and the several necklaces made up of loose beads are distinguished by different letters according to their find numbers. The majority of the beads were loose in the soil, but there were indications that they were once wrapped up in cloth. A small silver jar (Pl. CXL, 2) was found with the beads with a fragment of cloth still adhering to it. The small silver jar, No. 2 in the same plate, also formed part of the find, together with a copper vessel filled with implements of copper. The latter vessel was, however, in too fragmentary a condition to be restored and drawn.

Waste metal.

Judging from the quantity of waste pieces of metal, some of which are illustrated in Pl. CLII, 13, and the rolled-up condition of some of the gold ornaments, it appears probable that this hoard was the property of a goldsmith, who kept it by him until he had enough material to warrant re-melting.

Gold bracelet.

The chief object in this find is the gold bracelet (HR 4212a (e)), shown at the top of Pl. CXLIX, No. 3, which has been reconstructed from a number of loose beads. The gold spacers found with these beads show that they were originally threaded in six rows. The ends of this piece of jewellery are finished off with hollow, flattened, semi-circular terminals of gold, through a small hole in the outer edge of which the threads of the bracelet passed. These small beads were cast, and the spacers cut out of sheet metal. The terminals must have been beaten out of thin sheet gold, as there is no trace of soldered edges, and then pressed flat. One of the terminals and a spacer of this bracelet are illustrated in Pl. CXLVII, 20 and 24.

Pendants.

The necklace, No. 4, immediately below this bracelet in Pl. CXLIX is composed of minute gold beads, globular and cylindrical in shape, interspaced with tiny globular beads of steatite. The latter are now white, but a few of them show slight traces of the original blue glaze. The small cylindrical pendants on the necklace are made of gold and glaze; the latter has retained its sky-blue colour. They are attached to the cord of the necklace by loops of thin gold ribbon wire; this was doubled and the two ends were passed first through a gold washer, then through a gold cap on the end of the bead, then through the bead itself and finally through another gold cap. The two ends of the wire strip were soldered to the base of the lower cap (HR 4212a (f)).

String No. 5 (HR 4212a (k)) is made up of beads of various coloured stones, such as riband-jasper, carnelian, etc., alternating with small gold beads. The latter and also the two large gold beads on either side of the central ornament were cast, and some of the beads are capped with gold. The gold terminals are of the same pattern as those in bracelet No. 3.

Cf p. 585 intra.

String No. 6 (HR 4212a (1)) is made up of gold and glazed steatite beads in five Minute gold rows held by eight five-holed spacers. The gold beads are minute and either globular or beads. cylindrical in form. The steatite beads, which are cylindrical only, average in size o.1 inch long by 0.08 inch in diameter, which is about the same size as the cylindrical gold beads.

The necklace, No. 7, at the bottom of the Plate (HR 4212a (d)) is composed of flat gold beads, beads of onyx, green felspar and turquoise matrix, and small globular gold beads. The flat gold beads, one of which is illustrated in Pl. CXLVI, 34, were made by soldering Method of together two circular pieces of gold, each grooved across the centre, in such a way that the manufacture. grooves coincided to make the hole for threading. There is no sign of soldering at the edges; the solder was concealed between the two plates. The central bead of this string, which is agate, is capped at each end with gold. The dome-shaped caps of the pendants have small gold loops inside—a curious arrangement which is also seen in the hollow hemispherical bronze buttons with a loop inside that were worn both by the Hallstatt and Koban folk in Hungary and found in deposits assigned to the Early Bronze Age. Very similar ornaments have also been found at Anau in Turkestan,2 as well as among the jewellery described earlier in this chapter.

The stones in this necklace were carefully selected for their colour as well as for the Carefully regularity of their markings, the latter being in some cases so even that they might almost matched stones. have been artificially produced.3

The central string (HR 4212a (i)) in Pl. CL is a necklace of very fine beads of jade, jasper, carnelian, chalcedony, agate, etc. The first bead on the string is gold.

The second string from the inside (HR 4212a (j)) comprises beads of jasper, carnelian, On x. agate, lapis-lazuli, etc., and six of silver. Outside this is a fine string (HR 4212a (g)) of stones of diverse materials, colours, and shapes, including two cleverly cut onyx eye-beads.

The outermost string (HR 4212a (h)) is also made up of beads whose variety in shape, markings, and colour is extraordinary. A long flat bead, oval in section, was a favourite shape. This necklace also includes several skilfully cut "cat's eye" onyx beads.

A full description of most of the stone beads by Mr. A. L. Coulson, of the Geological

Survey of India, will be found at the end of this Chapter.

The find-spots of these three groups of jewellery leave no doubt that they belong to the Capped beads. "Indus" civilization. But it is noteworthy that in some respects they resemble jewellery of Achæmenian workmanship. Small globular beads of gold, separated by spacers and stones capped with gold, are well known in the jewellery of the First Persian Dynasty.4 On the other hand, I have found at Kish a carnelian bead, capped at both ends with gold, of undoubted pre-Sargonic date. It is within the bounds of possibility that this bead came from India.

As far as we can ascertain at present, silver was used more freely than gold at Mohenjo-daro; Silver plentiful. it was not the rare metal that it was in ancient Egypt or Sumer. Pending further analysis of the silver objects made by the Indus Valley peoples, we are uncertain from what sources the metal was obtained and what ores were used.⁵ Dr. Lucas has pointed out 6 that silver is found in nature in three conditions-metallic, non-metallic in ores, and thirdly, combined with gold. Metallic silver is not likely to have been the source of the silver used at Mohenjo-daro; it is still rare and was necessarily still rarer in ancient times. Silver is more

¹ Childe, The Aryans, p. 124. ² Pumpelly, Explorations in Turkestan (1904), vol. i, p. 153, fig. 259.

³ I am inclined to think that in some cases they were.

⁴ Mém. Dél. en Perse, t. viii, p. 56, figs. 91 and 92. See also Woolley, Antiquaries Journal, vol. iii, pl. xxx.

⁵ The possible sources of silver and lead are discussed by Sir Edwin Pascoe at pp. 675-8 infra. See also pp. 29-30 supra.

commonly found in the form of sulphide or chloride, mixed with other metals, e.g., lead, zinc, or copper, but a certain amount of knowledge and skill is necessary to reduce it to its metallic state. Silver frequently occurs in small quantities in conjunction with lead as argentiferous galena. Lead is by no means rare at Mohenjo-daro, and it may be that silver was extracted from this ore, for Dr. Hamid found a small trace of lead in a sample of silver submitted to him, the analysis of which I give below:—

Sa	mple	DK 57	74, I	nterm	ediate	P	er	ioc	l.	Per cent.
,	0	Silver								94.52
		Lead								0.42
		Copper								3.681
		Insolubles (silver chloride, etc.)								0.85
										99.47

Lead.

A sample of lead (DK 6314) that Dr. Hamid also examined for me contains no trace of silver.2

Dr. Lucas in his valuable paper cited above concludes "that the earliest Egyptian silver and, by inference, also that of Mesopotamia, was a natural alloy of silver and gold containing sufficient silver to have a white colour, and was not obtained from an ore".

Electrum.

We have not yet chemically examined any of the gold found at Mohenjo-daro to ascertain if there is any proportion of silver mixed with it, but I have already pointed out that some of the gold is of a very light hue and that it closely resembles electrum. This might, of course, be due to the admixture of some other metal with the gold to harden as well as to cheapen it. On the other hand, the extensive use of natural electrum in ancient Egypt suggests that this alloy may also have been employed in ancient Sind, and that it likewise occurred in a natural state in India. The above analysis, however, shows a very high proportion of silver and no trace of gold; which again suggests that, unlike the earliest Egyptian silver, that of Mohenjo-daro was extracted from an ore. If this was so, the people of Mohenjo-daro, with whom must be coupled those of Harappā, had evidently considerable knowledge of metallurgy. Whether, however, this art originated in India or elsewhere, it is as yet impossible to say.

Indian lead.

In Chapter XXXII Sir Edwin Pascoe points out that in ancient times, as now, lead was extensively mined in various parts of India, chiefly on account of the silver associated with it. Taking into consideration, therefore, the presence of lead in the sample of silver analysed by Dr. Hamid, it seems more likely that it was from argentiferous galena that the silver found at Mohenjo-daro was extracted.⁵

- I Dr. Hamid suggests that the "cupellation" process may have been used for the extraction of silver from its ores, and that the presence of copper is due to adulteration. Mr. Sana Ullah considers that the parent ore was contaminated with copper. He instances the cerussite found in Balūchistān, which is frequently associated with cuprite.
- ² Minute traces of silver have been found in lead samples from Mohenjo-daro submitted to the Sumer Committee of the British Association. See p. 487 .upra.
- 3 Electrum in Egypt contains from 60 to 80 per cent of gold and 20 to 30 per cent of silver, with sometimes a trace of copper. See also p. 543 infra.
 - 4 I conclude that they prepared the metal, as well as afterwards working it up.
- *5 The process of extraction of silver from lead is fairly simple. But unless the galena is exceptionally rich in silver, large quantities would have to be treated to obtain sufficient of the metal.

Stones 1

A remarkable point about the beads is the comparative scarcity of lapis-lazuli; sindeed, Lapis-lazuli this material was rarely used for beads or anything else at Mohenjo-daro. In Mesopotamia, rare. on the other hand, this stone was very commonly used, especially in the pre-Sargonic period at Kish, for cylinder seals as well as for beads, the source of supply probably being Persia, where the stone is abundant. In view of the numerous connections with both Sumer and Elam shown by the objects found at Mohenjo-daro, one would naturally expect lapis-lazuli to be nearly as common at Mohenjo-daro as in Mesopotamia, especially as India can obtain it from a nearer source than Persia, viz., from the Badakshan District of Afghanistan, a few miles above Firgamu in the valley of the Kotcha.

On the other hand, Mr. Hargreaves found at Nal, in southern Baluchistan,2 several strings Common at of beads composed entirely of lapis-lazuli, both disc-shaped and cylindrical. It is possible Nal. that the lapis-lazuli found at Nal came from Persia, and that, for some unknown reason, this source of supply was not readily available to the inhabitants of Mohenjo-daro. this mineral could be obtained in Afghanistan may at that date have been unknown.

Green felspar (Amazon stone) was, on the other hand, much favoured as a material for Green felspar. beads. It is not yet known for certain whence it was obtained.3 Beads of this stone were especially popular in the twelfth dynasty in Egypt and are known as far back as the pre-dynastic period of that country.4 It is said to be found at Gebel Migif in the eastern desert of Egypt 5 and also in the Sudan.

The occurrence of beads made of green felspar in many Chalcolithic sites in the Near Foreign and Middle East, India included, is interesting, as few localities are known from which the examples. stone could be procured. Possibly in ancient times a considerable trade was done in this semi-precious stone, which may have been valued for other properties than its beauty. Some considerable difficulty was always experienced in working felspar into beads, for in whatever country they are found they are always very irregular in shape. 6 The stone seems particularly associated with painted pottery, though no specimens have been recorded as coming from Anau. It was not found in the "A" cemetery at Kish, though a few miles away it was fairly common at Jemdet Nasr, a definitely "painted pottery" site. It was also found at Nal.

Turquoise and turquoise-matrix were also occasionally employed for beads at Turquoise. Mohenjo-daro, but not in Sumer. It was well known, too, in the earliest times in Egypt, which country obtained its supplies from Sinai. Very fine tarquoise is still obtained from mines near Nishāpur in the Persian Province of Khorāssān.

The inhabitants of Mohenjo-daro also made extensive use of various varieties of agate, such Agate. as carnelian, chalcedony, onyx, etc., for making beads. Some of these stones seem to have been tinted artificially, chiefly the beautiful red carnelian with designs upon it in white (Pl. CXLVI, 43-5). The tinting of agate is still an industry of India,7 and it is possible that

¹ The provenance of the stones found at Mohenjo-darg is discussed by Sir Edwin Pascoe in Ch. XXXII, pp. 677-84.—[ED.]

² Mem. Arch. Surv. Ind., No. 35, pp. 33-4.

³ See infra, p. 678.

⁴ Lucas, Ancient Egyptian Materials.

Ball, Geog. and Geol. of South-eastern Egypt, Cairo, 1912.

⁶ Its lamellar crystalline structure makes it brittle and difficult to work.

Principally in the Rajpipla State of the Bombay Presidency.

526

in ancient times tinted stones and decorated carnelian beads were exported from India to Mesopotamia.1

Amethyst.

Amethyst has been found at Mohenjo-daro, both in the form of beads and also in rough nodules. As it is a fairly common form of quartz its use has no special significance. It was a favourite material for beads in Egypt from very early times, but in Babylonia it seems to have been rare before the neo-Babylonian period, when it was extensively used for both smooth and facetted beads.

Steatite.

It is of interest to note the very extensive use of steatite at Mohenjo-daro, both in bead-making and for other objects, and to note that it was coated with a blue glaze. Steatite beads are more common than those of any other material, and there is no doubt that the people of Mohenjo-daro as well as Harappā had access to plentiful supplies. This soft stone was very extensively used in ancient Egypt from the earliest times, and there also it was usually glazed. In ancient Babylonia, also, it was coated with a blue glaze, but not so frequently in that country. Lapis-lazuli, which was very popular, probably took its place.

Common stones.

Even stones of such dull aspect as limestone and alabaster were made into beads at Mohenjo-daro, and we have numerous instances of even pottery being utilized for the same purpose. Doubtless, beads made of these materials were worn only by the very poor.

Unfinished Beads

Unfinished beads Several unfinished beads found at Mohenjo-daro—all of agate—show that they were shaped and smoothed before being bored (DK 1421, DK 2936, SD 254). The steatite bead (HR 2399), however, had been bored, though its form was left unfinished. But it must be remembered that, owing to the tendency of steatite to split along the cleavage planes, it was perhaps necessary to do the boring first in order to avoid waste of time, if breakage should occur.

In connection with agate beads which were shaped before being bored, it is interesting to recall that in the early periods of Egypt, beads were shaped by first boring and stringing them and then rolling them to and fro in a groove cut in an abrasive material such as emery.

Flaking.

In making beads of the harder stones they were first of all chipped roughly into shape; an unfinished onyx bead (SD 2325) is a long, barrel-shaped stone that had been roughly shaped first by very careful flaking, the marks of which were nearly, but not quite, removed in an attempt to trim it up.

Stone Pendants (?) (Pl. CXLVII, 28-36)

A number of very curious objects which are fairly common are illustrated in Pl. CXLVII, 28-36. They seem to have been associated with jewellery in some way, for they occur in several of the hoards.

Hornblende.

Those of the type illustrated in Nos. 28, 29, and 31-3 were always made of a polished hard black stone. They are slightly conical in shape, with a flat base and a top sometimes flat, and sometimes slightly rounded. A characteristic feature of these objects is a deep groove running round the head just below the top.

Nos. 30 and 34-6 are different in form, though made of the same hard black stone.2

Decorated carnelian beads have been found at Kish, and dated there to the pre-Sargonic period. JRAS. 1925, pp. 697 sqq.

² Composed chiefly of hornblende and is best termed an amphibolite. Sir Edwin Pascoe suggests that the present dark-colour of these pendants may be due to some process of artificial darkening, such as heating in oil.

In these the base is wide and flat and the upper surface more or less rounded, and in some cases almost conical. In this type, the groove occurs close above the base; possibly the objects

of this group should have been placed the other way up.

I am inclined to think that in both groups the groove was intended to take a wire, and Pendants (?). that Nos. 28, 29, and 31-3 were perhaps used as pendants and Nos. 30 and 34-6 as ornaments of another kind. Objects of both groups have been found in both the Late and Intermediate Periods. No. 29 was found in Room 45, Block 2, L Area, and is dated to the Late Period, and No. 31 in Room 9, Block 16, Section C, DK Area. No. 32 was found in Room 13, Block 10, Section C, DK Area.

Fillets (Pl. CLI, A, 4-8)

A set of three very curious gold fillets was found with the jewellery from the HR site Nose that has already been described. No. 6, the largest (HR 4212a (q)) is a band of very ornament (?). thin gold averaging 0.4 inch in width, with a small hole at each rounded end and another at the bottom of the V-shaped piece in the middle. If these fillets were worn as they are photographed, it is possible that a cord was threaded through the hole in the middle of the fillet to support a heavy nose or forehead ornament. In modern Sind, especially heavy nose ornaments are often supported by a thread tied to the hair. These three fillets are somewhat out of shape, for each had been rolled into a ball, presumably for re-melting. Yet despite their age and ill treatment, the gold still retains a certain amount of spring. head in Pl. XCIV, 1, shows, I imagine, how these fillets were worn.

At the top of Pl. CLI (A, 1) a broken gold band (HR 4212a (x)) is shown, which had also been rolled up. This band measures 6.2 inches long by 0.75 inch wide and has two holes at each end and also a row of small holes along the upper edge. The row of small holes perhaps served to secure the fillet to a head-dress, or, if worn the other way round, beads

or sequins may have been fastened along it.

This ornament was stiffened by a very ingenious device, the metal being twice box-pleated Mode of '

lengthways, not far from either edge.1

On either side of the gold bangles, Nos. 2 and 3, are coiled up fillets (HR 4212a (t and u)) of another form, respectively measuring 16 inches long by 0.52 inch wide and 15.1 inches long by 0.35 inch wide. Both these fillets taper slightly towards the rounded ends, each of which is perforated with a hole.

A very interesting fillet of the same kind from the VS Area (VS 3091) was found Embossed in a niche in the south-eastern corner of House XIV, Block 2, VS Area, at a depth of 3 ft. 6 in. design. below the surface. It measures 16.5 inches long by 0.55 inch wide in the middle, and tapers to 0.4 inch wide at the carefully rounded ends. These ends bear a very rough design made by embossing the metal with a blunt point,² and in each there is a small hole which has been pulled slightly out of shape by tension. The metal is 0.05 inch thick, and is bright-yellow gold which still retains a good deal of its original spring. The design on the two ends of Cult object. this fillet is illustrated in Pl. CXVIII, 14, and resembles the cult object that is always represented in front of the unicorn animals present on most of the seals.3

stiffening.

¹ It is possible, however, that by this means three narrow strips of gold were joined together to form a wider band.

The same method of ornamentation is to be seen on some of the jewellery from Mochlos, dated to the Early Minoan II Period. Evans, Palace of Minos, vol. i, p. 96, fig. 67.

³ Pointed out to me by Mr. Hargreaves.

528

Comparisons.

This last fillet is very similar in shape to a silver fillet found in a grave at Kish and dated to the pre-Sargonic period, which was also ornamented as well as stiffened by embossing with a point.1

Finger-rings (Pl. CXLIII, 1-8; Pl. CXLVIII, 13)

Finger-rings have occasionally been found at Mohenjo-daro, the best example being the silver ring in the hoard of jewellery discovered in the DK Area (DK 1341), which has already been described.

Materials.

Small rings of shell, copper, and bronze, all of very simple design, found at varying depths at Mohenjo-daro, were probably worn as finger-rings, there being no reason to think that the inhabitants of Mohenjo-daro differed in this respect from their neighbours of Elam and Sumer. A number of these objects were found with the hoard in the HR Area and are illustrated in Pl. CLII, 13. Other finger-rings are described in Chapter XXV.

Earrings (Pl. CXLIII, 11; Pl. CXLVIII, 11 and 15)

Rarity.

Earrings are, on the whole, rare at Mohenjo-daro, a fact which can possibly be explained by their not being removed from the body on its burial or cremation, whichever rite was practised. Even at the present day in India, earrings are not removed by the Hindus when preparing a body for cremation; they become the property of the priest when the ashes are collected. Nor do the Muhammadans remove ornaments of this kind when burying their dead. Moreover, the very secure method of attaching earrings to the ear in the East precludes their being easily lost or mislaid, which would explain their being so rarely found loose.

Those earrings that have been found are not particularly interesting. As a rule they consist of a simple coil of wire with the ends slightly overlapping. Sometimes the wire is coiled round two or three times, making a circular band of about 0.15 inch wide and 0.75 inch in diameter. To avoid enlarging the hole in the ear the ends of the wire are not always brought together, but a narrower space is left for the lobe. The wire of which they are always made is a thin strip of metal that is hammered round. It would seem that the people of Mohenjo-daro did not use a draw-plate in making their wire, though this craft was known to the Sumerians, as proved by the wire of a gold chain found at Kish.²

Ear and Nose Studs (Pl. CLI, b, 7, 8, and 11; Pl. CLII, 7, 8, and 14)

The two gold studs in Pl. CLI, 7, 8, and 11, have already been described and reasons given for thinking that they were intended for the ears rather than the nose.

Nose studs.

The three studs in Pl. CLII, 7, 8, and 14, are, however, somewhat different in shape, and it seems probable that they are nose studs. No. 7 (SD 898) is of faience, and is 0.6 inch in diameter and 0.35 inch thick with a head at the back 0.25 inch in diameter. There is no design on this stud.

No. 8 (VS 1537a) on the same plate is also of faience. It is 0.8 inch in diameter and has a projection at the back similar to that of No. 7. The edge of this ornament is serrared and there is a four-pointed star in the middle enclosed in a circle. House XXIII, VS Area.

Mackay, kepert on the Excavation of the "A" Cemetery at Kish, p. 52, pl. iv, No. 24. For an example from Ur, but decorated by a different process, see Antiquaries Journ., vol. viii, pl. ix, 3.

² A Sumerian Palace, etc., p. 182; pl. xliii, fig. 3.

The design of No. 14 (VS 63) is like that of No. 8, but the stud is considerably larger, Rope pattern. measuring as it does 1.0 inch in diameter. The border of this stud more nearly resembles a cable pattern than does that of No. 8. Found in Room 6, House XXIX, Block 5, of

These studs were found at levels ranging from 1 ft. 6 in. below the surface in the case of No. 14 to 5 feet below (No. 7), and must therefore all belong to the Late Period.1

Bracelets (Pl. CXXXIV, 1-2 and 5-7; Pl. CXLIII, 26 and 29; Pl. CXLIV, 7, 9, and 11; Pl. CLII, 1-6 and 9-12; Pl. CLXIV, a and b)

The bracelets found at Mohenjo-daro were made of a variety of materials-gold, silver, . copper, bronze, shell, vitrified paste, faience, earthenware, and pottery. No stone bracelets have yet been found.

The gold bracelets shown in Pls. CXLVIII, 1 and 4, and CLI, 2, 3, 9, and 10, are all Fibre core. of sheet gold, which was originally wrapped round a fibre core that has now entirely disappeared. The join of the gold wrapping was always on the inside of the bracelet; sometimes the edges overlapped and sometimes they were just allowed to meet. The ends of the bracelets were trimmed sharply off, apparently with a saw.

Two silver bangles found with the jewellery shown in Pl. CXLVIII (DK 1341) and pictured on Pl. CLXIV, a and b, are slightly oval in shape and were made on a core in exactly the same way as the gold bracelets. Their ends also have the sharp edges caused by the cutting of a saw. There is a gap of 0 15 inch between the edges of the metal on the inside of each bracelet,2 and the average diameter of each in its thickest part is 0.55 inch. The diameter at the ends of each bracelet is 0.4 inch. The thickness of the sheet silver employed in their manufacture is one-thirtieth of an inch.

Copper and bronze bracelets are found in considerable numbers. They are always Wire bracelets. quite simply made of thick wire with the ends generally just meeting, or nearly so (Pl. CLII, 4, 5, and 6); the ends seldom overlap as in the earrings. The thick wire of which they are made was always hammered into the round. Nos. 4, 5, and 6 in Pl. CLII were found with thirteen others of similar make, in Room 1, House XIV, Block 3, of the HR Area, at a depth of 6 feet below the surface.

The bracelets made of faience were far more elaborate, as will be seen in Pls. CXXXIV, Faience. 1, 2, 5-7, and CLVII, 22 and 48. All the specimens illustrated are badly broken and it was felt, therefore, that drawings were preferable to photographs.

Plate CXXXIV.

No. 1 (VS 3603) is of a light green vitreous paste incised with a herring-bone pattern. Details. Found in Chamber 50, House VI, VS Area, at a level of 5 feet below the surface.

No. 2 (HR 4467), made of a vitreous paste, now of a greenish colour, has a deep groove around its edge. Level, 2 feet below surface. House XIX, Block 4, Section B, HR Area.

No. 5 (HR 5196) resembles No. 2, except that it has two grooves instead of one. It is made of faience and still retains a considerable amount of its original blue. Level, 6 ft. 6 in. below surface. Street between Houses LII-LIH and LVI, Blocks 7 and 8, Section B, HR Area.

No. 6 (HR 5196) is still more elaborate; it is ornamented with three grooves or flutings instead of two. Like No. 5, with which it was found, it is made of blue faience.

¹ They are also met with in the Intermediate Period.

² Probably caused by the swelling of the core before it decayed.

Plate CLII.

No. 3 (SD 427), also shown in Pl. CLVII, 48, is of a light green, vitreous paste with an incised herring-bone pattern on its outer face. This bangle was originally 3 inches in diameter by 0.3 inch thick and 0.45 inch wide. Found in Block 2 of the Southern Buildings Section at a depth of 4 feet below the surface.

No. 9 (L 1184) is a fragment of a bracelet with a deeply serrated edge. It is made of faience and is now an apple-green colour. From Room 58, Block 2, L Area, just below the surface. Late Period.

Plate CLVII.

No. 22 (DM 132). A fragment of a bangle in glaze with a fluted decoration. Colour, a greenish-blue, which extends right through the material. Paste shows blow-holes and is of a vitreous nature. Level, 4 feet below surface. Stupa Section, SD Area.

No. 48 (SD 427) is also illustrated in Pl. CLII, 3, and is described above.

Bracelets of this material were particularly liable to breakage, though no more so than the glass bracelets that are so commonly worn in the East at the present day. The material of which bracelets Nos. 22 and 48 were made differs radically from that of the others. Instead of the paste being softer inside than on the surface, it is just as hard. It would appear that in these cases a glaze was mixed with the paste instead of only being applied to the surface, with the result that a much stronger material was produced.

Pottery bracelets, which were presumably worn by the poorer classes, are very common. The majority are roughly made, and in some cases the join is barely concealed, e.g., Pl. CLII, 11. An exceptionally well-finished specimen made of a very fine clay coated with a smooth pink slip is illustrated in Pl. CXXXIV, 7, and again in Pl. CLII, 12.² This bracelet

was found in Room 116, Block 6, L Area. Late Period.

Another type of pottery bracelet was made of a heavily fired clay, dark brown or black on the outside and light grey inside, of a fine uniform texture, and free from blow-holes. Indeed, these bracelets are so heavily burnt that they ring like metal when struck and in some cases break with a glass-like fracture. Owing to their brittleness, they are practically always found in pieces, but a perfect specimen (HR 1325) is shown in Pl. CLII, 1, which was found in Court 18, House I, Block 1, HR Area, at a depth of 9 feet. In most cases, like the faience bracelets, these ornaments were made in a mould; the majority are very well finished.

Mr. Sana Ullah has made the following analysis of the material of which these particular bracelets are made. He would prefer to style this make of bracelet as stoneware rather than terra-cotta, for the former implies a better grade. The dark colour is due to ferrous oxide. The sample examined was numbered VS 502.

				Per cent
Silica .				54.28
Alumina .				19.63
Ferric oxide				nil
Ferrous oxide				8.70
Manganese oxid	le	-		0.13
Lime .				9.63
Magnesia .				4.39
Alkalies .				3.43
Water		492 3		nil
Carbonic acid				nil
Phosphoric acid				nil
Total	1		199	
1 otal			1	100.19

¹ Cf. the ornamentation of the fluted bone bracelets from Knossos (16th cent. B.C.). Evans, Palace of Minos, III, p. 409, fig. 271.

² It is still uncertain whether the more roughly made specimens are not jar-stands.

Liable to breakage.

Pottery bracelets.

Heavy firing.

Analysis.

Rarely, these bracelets are inscribed with one or two pictographs, which may be either Pictographs. the name of the maker or of the owner. The characters are always so minute that it is difficult to see them at all.

Shell bracelets like that illustrated in Pl. CLII, 2 (L 404), which measures 2.25 inches Shell bracelets. in diameter by 1 inch wide and 0.12 inch thick, are often found. They were roughly cut from large sank shells, the columella being first removed and the shell then sawn into sections. Beyond smoothing the edges of the cuts and removing the saw-marks, no further attempt was made in the majority of these bracelets either to round or to ornament them. None the less, despite this lack of finish, they are quite presentable objects, which probably accounts for their great popularity at all periods.1 Similar bracelets are favoured ornaments in Bengal at the present day, but they are better finished and sometimes engraved. The illustrated specimen was found in Room 89, Block 9, L Area. It dates from the Late Period.

That a great number of these or similar bracelets were worn on one arm is proved from the little bronze statuette shown in Pl. XCIV, 6, 7, and 8. The armlets worn by this dancing girl were probably made of shell or similar light material, since metal would have proved much too heavy.2

Hair-Pins and Hair-Pin Heads (Pl. CLVIII, 1-6, 8-11, and 13)

Not a single pin that can be definitely called a hair-pin has yet been found at Rarity of pins. Mohenjo-daro. We have, however, sure evidence that they were sometimes worn in the fact that a hair-pin with a short shaft and a plain round head is carved on the back of the sculptured head pictured in Pl. XCIX, 6, and that various pieces of carved stone, ivory, and shell would seem, in some cases certainly, to be pin-heads. The head of the statue that is shown wearing a pin is that of a man, which proves beyond doubt that, as in ancient Sumer, men as well as women were accustomed to use these articles.

The absence of hair-pins is somewhat difficult to explain, for objects of this nature are Possibly made very frequently lost owing to their liability to slip from the head. A possible explanation of wood. is that they were mainly made of wood, which could not have survived the damp and salty soil of Mohenjo-daro.

No. 1 in Pl. CLVIII (VS 2041) must be the top of a hair-pin. This now measures Hair-pin heads. 1.3 inches high and is made of ivory. The animal apparently represents an ibex, but the horns are broken off. Level, 3 feet below surface. Room 23, House IX, Block 2, VS Area.

No. 2 (HR 1279) is 0.6 inch high by 0.85 inch in diameter. It is made of steatile. A deep hole in its base is 0.25 inch in diameter. There is a design carved on the sides of the head similar to that on handle No. 17 in Pl. CXXXII, but the wavy pattern is not so On the top of the head is another design similar to the pattern shown in Pl. CLV, 48 and 49. Level, 9 feet below surface. North-east corner of House III, Block 2, Section A, HR Area.

No. 4 (HR 6097) measures 0.8 inch in diameter by 0.55 inch high. It is made of a vitreous paste, bluish-green in colour. There is a small hole in its base to affix it to a copper pin. Level, 10 feet below surface. House XLI, Block 5, Section B, HR Area.

No. 6 (HR 6216) is 0.8 inch in diameter and 0.45 inch high. Faience or vitreous paste of a light blue colour. Small hole in base. Level, 6 feet below surface. House XLI, Block 5, Section B, HR Area.

1 For similar types, see Petrie, Predynastic Egypt, pl: xxxi, figs. 21 and 27.

² I have seen, however, Indian dancing-girls with a score or more of silver and gold bracelets on their arms. Such bracelets are commonly made of thin metal, with or without a core of lac, and need not be unduly heavy.—[ED.]

Both Nos. 4 and 6 are imitations of the capsules of some variety of lotus or

water-lily.

No. 5 (HR 1053) is a pin-head carved into the form of three monkeys clasping one another around the shoulders. It is 0.65 inch high and 0.6 inch in diameter, and is made of steatite. The hole in its centre which runs right through the head is 0.15 inch in diameter. This motif was a favourite one in Egypt in the twelfth dynasty, where two or more monkeys are shown around the sides of kohl-jars. Level, 8 feet below surface. Found in Chamber 22, House III, Block 2, HR Area.

No. 8 (HR 2861) is a round head, 1.2 inches in diameter. The material is limestone. The face of this globular head has been irregularly drilled with depressions of varying size, each of which has a smaller depression at its base. Some of the larger depressions engage one another, forming an irregular trefoil pattern. It was evidently intended to fill in these depressions with a coloured paste. Level, 3 ft. 6 in. below surface. First Street, HR Area.

No. 9 (DK 2546) is flat on one side and rounded on the other. The edge is notched. This pin-head measures 1.12 inches in diameter and 0.23 inch thick. Material, pottery.

Level, 6 ft. 6 in. East of Room 7, Block 2, Section B, DK Area.

No. 10 on Pl. CLVII (HR 5467) is made of steatite. It is 1.2 inches in diameter by 0.65 inch high. Its base is flat. The upper part of the object bears a carved design similar to Nos. 48 and 49 in Pl. CLV. There is a hole through its centre, 0.2 inch in diameter. Owing to the large size of this object there is some doubt whether it was a pin-head. It may possibly be a spindle-whorl. Level, 4 feet below surface. Room 85, House IX, Block 2, HR Area.

No. 11 (SD 233) measures 0.97 inch high and 0.91 inch in diameter. A hole running right through its centre is 0.1 inch in diameter. The material is baked clay. Four

vertical grooves adorn the sides. Level, 5 feet below surface. SD Area.

No. 13 (E 1348) is a plain head cut from a piece of shell; it measures 0.7 inch high. In its base is a deep hole measuring 0.15 inch in diameter. Trial trench E, DK Area.

Combs (Pl. CXXXII, 13 and 21; Pl. CXXXIV, 4)

Specimens rare.

Combs have been included under Personal Ornaments for the reason that they were probably worn in the hair. Only two examples have been found at Mohenjo-daro, possibly

for the reason that the majority of combs were made of wood.

No. 13 in Pl. CXXXII (HR 5870) is also illustrated in Pl. CXXXIV, 4. It is fairly well preserved and measures 1.3 inches long by 0.8 inch wide and 0.15 inch thick. It is decorated on both sides with concentric circles filled in with a black pigment. As it was found 2 feet below the surface of the ground, it clearly belongs to the Late Period. Room 32, House VI, Block 2, Section B, HR Area.

No. 21 in Pl. CXXXII (C 2165), which was found in the DK Area, is made of ivory and measures 1 65 inches high and 0 14 inch thick. It has been badly burnt and blackened. Both ends are missing. Level, 8 feet below surface. Room 5, Block 8, Section C,

DK Area.

Use by both sexes.

Doubtless combs were used by both the men and women of Mohenjo-daro, as at the present day in India; for we know from more than one of the statues (Pl. XCIX) that the Indus Valley folk wore their hair long. Of the combs found none are complete, but the top of No. 21 has a well-polished, bevelled edge, and is sufficiently well preserved to show that it had only a single row of teeth.

Buttons? (Pl. CXLIII, 19; Pl. CLV, 5-7)

A number of dome-shaped copper objects (HR 6186), measuring 0.7 inch in diameter, appear to be buttons (Pl. CXLIII, 19). Each was evidently beaten into a dome 0.2 inch high, and then a small portion of the top of the dome was pressed in to form a projection on the inside. This projection was then pierced, so that the object could be sewn on to the clothing. Besides being used as buttons, these objects could also have been used to ornament a dress, and, if applied thickly enough, would have served the purpose of scale armour. Indeed, from the number that were found in the same place and the regularity of their size, one is inclined to surmise that they were perhaps mainly used either for ornamentation or for the making of armour. Level, 8 feet below surface. From Chamber 107, House XII, Block 2, HR Area. Intermediate Period.

Together with these supposed buttons smaller dome-shaped pieces of copper have been found with a plain rounded top. Each measures 0.5 inch in diameter and 0.25 inch high, and has a minute hole pierced close to the edge on either side.

Buttons made of faience are illustrated in Pl. CLV, 5-7.

No. 5 (HR 955) measures 1.45 inches in diameter and, including the knob, is 0.42 inch thick. Its glaze still bears traces of its original blue or green colour. An eye for attaching the button to the clothing was made in the centre of its flat base by roughly scooping out a depression and bridging it over with a strip of paste. This was a very clumsy method of making an eye, and I am inclined to think that perhaps this particular object was used solely as a dress ornament. The bridge across the aperture in the base of this object could stand but little pulling or hard wear. From south-west corner of House I, Block 1, Section A, HR Area. Level, 4 feet below surface.

No. 6 (HR 665) is made more simply. It has a flat base and slightly rounded top, and measures 1 inch in diameter by 0.2 inch thick. A loop for the thread was made by boring two small holes that meet one another obliquely in the middle of the base.1,2 Level, 3 ft. 6 in. below surface. Chamber 3 or 4, House I, Block 1, Section A, HR Area.

No. 7 (DK 1506) is 1 inch in diameter, with a flat base and a rounded top with a little knob in its centre. The eye, formed by two converging holes, is in the middle of the base. Level, 5 feet below surface. Room 9, Block 2, Section C, DK Area.

Bullæ (Pl. CXXXIII, 1-3)

Three very curious pendants have been found at Mohenjo-daro, all of which are made of pottery.

No. 1 in Pl. CXXXIII (C 2750) is triangular in shape and measures 2.35 inches long Pierced pottery by 0.25 inch thick. The lower portion of the ornament is pierced with a double row of small roundels. holes, but whether the holes in this particular object are for the purpose of decoration or for attaching the object to a garment, it is difficult to say. Level, 3 feet below surface. Room 1, Block 2, Section C, DK Area.

No. 2 (VS 1054) is a circular object measuring 1.65 inches in diameter and 0.18 inch thick. It is ornamented by a double row of fine pittings that, however, do not penetrate right through the object as in the case of the first. Its obverse surface is very slightly

Faience buttons.

¹ Pumpelly, Explorations in Turkestan (1904), vol. i, p. 162; fig. 338.

² Buttons with V-shaped perforations are known in the Danubian civilization and the Chalcolithic civilizations of Portugal and Spain.

rounded, and the back is flat. Level, 3 ft. 6 in. below surface. Vicinity of the S.W. corner

of House XXVI, Block 4, VS Area.

No. 3 (VS 1447) is 1.5 inches in diameter and 0.2 inch thick. Its surface is flat and its back slightly rounded. The face is decorated in rather an irregular manner with pittings. Of particular interest is the strip of clay that has been placed across the face of the object at the top, evidently with the idea of preventing the suspension holes from tearing owing to the thinness of the ornament. Level, 2 feet below surface of ground. House XXX, VS Area.

All three objects are hand-made and are of somewhat rough workmanship, none being coated with a slip or possessing any trace of colour. They could hardly have been worn

solely as ornaments, and must have had a special purpose.

Copies of leather cases.

These objects have all the appearance of being copies of stitched leather cases, and it is possible that originally similar cases, made of leather, were used to enclose amulets. Later on, perhaps, the cases themselves came to be regarded as more important than their contents, and subsequently were copied in pottery.¹

APPENDIX

DETERMINATION OF BEADS FROM MOHENJO-DARO

I. Introduction

Density.

The chief physical property employed in the determination of the beads described below was that of density. As it was considered of value and interest from a scientific as well as from an archæological standpoint, the determination of the densities was made with extreme accuracy. The beads were weighed in air suspended by a fine platinum wire composed of two pieces which hooked into each other. The weight of this wire in air and suspended in distilled water to a certain mark was previously noted. It is worthy of remark that the weight of the suspending wire in water (0.1667 grammes) was more than its weight in air (0.1654 grammes) on account of the surface tension of the water acting on the wire.

Each bead was suspended in water to the same mark on the platinum wire by means of a glass rod placed across the beaker. Distilled water was used in all cases and the level of the water in the beaker was kept constant. To ensure that no air bubbles adhered to the surface of beads, the beaker, containing the bead suspended as above, was placed in a large glass jar and the air removed by means of a Fleuss Vacuum pump to a pressure varying between 1.5 and 1.8 cm. of mercury. This usually involved the exhaustion being prolonged for fifteen minutes, as it was found that all air bubbles were not removed under this period.

Air was again admitted to the large glass jar and the beaker removed and placed on a convenient stand over one pan of a chemical balance. The platinum wire suspending the bead was gripped by forceps and the glass rod removed; then the suspending wire was hooked to the other wire which had remained suspended from the balance.

The weight of the bead suspended in water to a fixed mark on the platinum wire was

then determined, and the temperature of the water taken.

¹ Compare with these some gold and silver ornaments from Susa, dated to the time of Dungi (about 2278-2170 B.C.), the embossing on some of which also suggests stitched leather. Mém. Dél. en Perse, t. vii, pl. xii, p. 69.

The densities were then obtained by means of the following expression:-

weight of solid in air weight of solid in air - weight of solid in water

These values required correction for the buoyancy of air and for the deviation, from standard (unit) value, of the water density at the temperature of the weighing.

Let d = the approximate value of the density of the solid as obtained in this way.

D = the true density of the solid.

 $_{
m W}^a=$ the density of distilled water at the temperature of the weighing.

 δ = the density of the air at the time of the weighing in air.

Then D =
$$d (d - \delta) + \delta^1$$
W

i.e. the correction to be applied to the approximate value, d, in order to obtain the true value, D, of the density of the solid is

$$D - d = d (d - \delta - 1) + \delta$$
W

In actual practice, determinations of the density were made at temperatures between 18.5° and 26.5° C. Corrections for temperatures up to 25° C. were obtained from Glazebrook, and for temperatures higher than 25° C. by extrapolation beyond the tables given by Glazebrook. Thus the densities given in the following section are all true densities and are thus strictly comparable. The limit of error may be taken as + .002. The largest correction made to the approximate densities was -05 for the gold bead j 19. A correction of - 014 was made for the densities of beads g 15 (26.5° C.) and j 15 (24° C.). correction was -.005 for beads i 43 and i 41 (18.5° C.).

Colour, hardness, and action upon light were also employed as means of identification. Other physical On account of the great value of the beads, it was not possible to break off fragments and properties then employ the usual optical methods adopted in the identification of unknown minerals. employed. In a few cases, however, a few fractions of a milligramme of a bead were detached by means of a small bit very carefully turned by hand in the core of the bead. The refractive indices of the extremely minute fragments were then determined by comparison with liquids of known refractivity (determined by means of the Abbé refractometer) by use of the Becké line test.

Dr. W. A. K. Christie has been kind enough to perform certain microchemical tests upon, and optical determinations of, some of the beads in string j, and to him, also, is due the determination of the refractive index of the jade beads in string i.

The nomenclature adopted by Bauer and Spencer (Precious Stones, 1904) has been Nomenclature. followed as far as was possible. In the description which follows, the numbers of the beads are those beginning from the numbered end of each string. The weight of each bead in air is given, as this is considered to be of interest.

The references given after specific colours refer to plates in Ridgway's useful book on colours (Color Standards and Nomenclature, by R. Ridgway, Washington, 1912).

1 R. Glazebrook, Didionary of Applied Physics, iii, 1923, p. 132.

II. DETERMINATION OF THE BEADS

Table of weights and densities.
String g.

HR 4212 A. (Pl. CL, String g, Nos. 1-29)

		Weight	True "	4
	Number.	in air in grammes.	Density.	Determination
	ī	1.5056	2.561	
1	2	1.7828		Riband-jasper. Riband-jasper.
		1.8268	2·549 2·616	
	3	1.4620	2.608	Agate.
	4			Agate.
	5	2.5182	2.658	Red jasper.
		2.2035	2.623	Agate-jasper.
	7	3.1348	2.551	Riband-jasper.
	. 8	1.9578	2.597	Agate.
	9	3.1469	2.657	Red jasper.
	10	2.1496	2.574	Agate.
	11	2.4880	2.534	Onyx.
	12	2.4570	2.192	Blue jasper.
	13	4.5597	2.598	Chalcedony.
	14	3.6725	2.639	Red jasper.
	15	7.6433	3.343	Jade.
	16	5.6586	2.761	Jasper.
	17	4.2693	2.579	Moss-agate.
	18	2.7017	2.594	Agate.
	19	2.9555 1	2.697 1	Amazon stone.
	20	2.1148	2.661	Riband-jasper.
	21	3.8876	2.657	Red jasper.
	22	1.9796	2.607	Agate.
	23	2.6583	2.596	Moss-agate.
	24	1.8786	2.616	Riband-jasper.
	25	2.4036	2.663	Red jasper.
	2 26	1.9006	2.573	Agate.
	27	2.4860	2.528	Riband-jasper.
	28.	1.9116	2.548	Riband-jasper.
	29	0.8405	2.569	Agate-jasper.

Notes.

This string (g) is mostly composed of agate and jasper beads. They have been arranged by the excavators more or less symmetrically on either side of bead 15, which is a lettuce green (V, 29, k) jade bead; thus, bead 9 corresponds to 21 and 5 to 25, all being red (claret-brown: I, 5, m) jaspers; 8 corresponds to 22, both being agates; and 2 corresponds with 28, both being riband-jaspers (mouse-grey: LI, 15"", —, and cinnamon: XXIX, 15", —).

In addition to the jade mentioned above, there is but one representative in this string of the following stones: onyx, chalcedony, and amazon stone. The chalcedony is pale orange citrine (IV, 19, k), whilst the amazon stone is light sulphate green (XIX, 39', b) and white in colour. The latter stone was unfortunately in a cracked condition.

¹ This bead has a metallic-looking core and hence its high density.

Beads 5, 9, 14, 21, and 25 appear to have been cut from the same jasper stone, their densities being 2.658, 2.657, 2.639, 2.657, and 2.663, respectively. The skill of the lapidary is well exhibited in the way in which these stones have been cut so as to show white bands of quartz on the claret-brown (I, 5, m) background; also beads 2 and 28 show central mouse-grey (LI, 15"", —) bands with terminal cinnamon (XXIX, 15", —) bands. The two agates 3 and 4 are probably made from the same stone (densities 2.616 and 2.608 respectively), and have been beautifully cut so that the white bands pass in a parallel manner across one side of each bead, the general colour of the stones being slightly darker than buckthorn brown (XV, 17', i); they are similar to the "Pagoda stones" or agates from Burma. On the reverse side of bead 3 there are visible a few bands which just come to the surface.

Bead 8 is also an agate which shows a series of white bands encircling a vandyke brown (XXVIII, 11", m) bead. Bead 22 is a fine specimen of agate which has been cut so that the white bands which, in the natural stone, would be in the form of a spheroidal mass, now encircle the bead, being apart on one side and meeting on the reverse side. The stone has thus been

cut across the base of the banded spheroid.

The moss-agates, 17 and 23, have both been cut to show an oval aggregation of green (nearest colour: meadow green, VI, 35, k) enclosures in a white oval band on paler chalcedonic masses.

The agate bead, 18, which is of the riband-agate type, shows a fine "mitre" pattern on one surface and the onyx bead, 11, shows concentric white bands on a black stone.

With reference to the riband-jaspers 1 and 27, the lapidary has so cut the beads that they exhibit two cross-bandings which form a cross-hatching, more conspicuously displayed on the latter bead.

In addition to the stones specifically mentioned above, one could enthuse over most of the remainder; but enough has been written to indicate that the lapidary had brought his art to a high state of perfection in the days when the city of Mohenjo-daro was flourishing. All the beads possess a high polish and are in an excellent state of preservation.

HR 4212 A. (Pl. CL, String h, Nos. 1-38)

	Weight		
	in air	True	•
Number.	in grammes.	Density.	Determination.
I	0.8712	2.626	Heliotrope.
2	0.5327	2.624	Heliotrope.
3	0.6573	2.612	Plasma.
4	0.5180	2.611	Agate-jasper.
5	0.9651	2.587	Riband-jasper.
6	0.8334	2.604	Riband-jasper.
7	0.8576	2.534	Yellow jasper.
8	1.4504	2.612	Agate-jasper.
9	1.3331	2.557	Riband-jasper.
10	1.7065.	2.587	Agate-jasper.
II	2.5751	3.027	Lapis-lazuli.
12	2.1811	2.796	Riband-jasper.
13	1.7948	2.616	Riband-jasper.
14	2.4703	2.931	Riband-jasper.
15	1.8828	2.681	Jasper.
16	2.2028	2.546	Riband-jasper.

Table of weights and densities. String h.

		Weight		
		in air	True	•
0	Number.	in grammes.	Density.	Determination.
	17	0 2.5271	2.627	Riband-jasper.
	18	3.0418	2.582	Agate.
	19	2.6951	2.643	Riband-jasper.
	20	3.6536	2.627	Heliotrope.
	21	2.7487	2.586	Riband-jasper.
	22	2.3331	2.523	Riband-jasper.
	23	, 1.8094	2.559	Riband-jasper.
	24	2.5264	12.516	Riband-jasper.
	25	1.9121	2.666	Jasper.
	26	2.5460	2.573	Riband-jasper.
	27	2.4197 0	3.058	Tachylite.
	28	2.0951	2.605	Agate-jasper.
	29	2.6245	3.016	Lapis-lazuli.
	30	1.8971	2.682	Riband-jasper.
	31	2.0483	2.546	Riband-jasper.
	32	1.4790	2.843	Riband-jasper.
	33	0.6848	2.582	Riband-jasper.
	34	1.3245	2.728	Jasper.
	35	0.7448	2.486	Agate-jasper.
	36	0.8023	2.824	Riband-jasper.
	37	0.5075	2.622	Riband-jasper.
	38	0.4168	2.669	Red jasper.

Notes.

String h, also, has been arranged more or less symmetrically around a heliotrope bead (20). Sometimes this symmetry is due to the beads being of the same shape though of different stones, as, e.g. 19 and 21, 13 and 27, 10 and 30; but in other cases the stones correspond, as e.g. 11 and 29, which are both lapis-lazuli, 15 and 25, and 14 and 26, which are pairs of similar jaspers.

This string is chiefly composed of jasper beads which vary greatly in colour. Most of them are banded varieties and the full beauty of the bands is invariably displayed. Particularly noticeable are the beads 1 c and 25, most likely cut from the same stone, and bead 16, in which there is a fine range of colours. A double set of markings similar to those on g 1 and g 27 is again exhibited on h 9.

There is but one representative of true agate, 18, and of plasma, 3; also the peculiar bead 27, which is most probably an ultrabasic rock, has none other like it.

The beads forming this string are generally well preserved, but some are rather badly chipped.

Table of woights and densities.
String i.

HR 4212 A. (Pl. CL, String i, Nos. 1-43)

Number.	Weight in air in grammes.	True Density.	Determination.
ı,	0.5636	2.597	Moss-agate.
2	0.5920	3.225	Jade.
3	0.5611	2.601	Carnelian.
4	0.8323	3.319	Jade.
5	0.4299	2.604	Agate.

9	Weight		
	in air	True	9
Number.	in grammes.	Density.	Determination.
6	1.4367	3.355	Jade.
7	0.7546	2.655	Red jasper.
8	1.0203	3.346	Jade.
9	0.9184	2.600	Agate.
10	0.9015	3.353	Jade.
II.	1.1260	2.594	Chalcedony.
12	0.8132	3*354	Jade.
13	1.6820	2.606	Chalcedony.
14	1.0611	3.382	Jade.
, 15	1.2639	2.575	Agate.
16	0.9758	3.311	Jade.
17	1.7354	2.61	Agate.
18	2.7962	3.395	Jade.
19	2.2970	2.544	Carnelian.
20	4.7317	3.314	Jade.
21	4.0480	2.614	Chalcedony.
22	4.8003	3.365	Jade.
23	2.6274	2.611	Chalcedony.
24	3.8166	3.314	Jade.
25	1.6720	2.613	Agate.
26	2.2731	3.322	Jade.
27	2.3116	2.598	Agate.
28	0.9902	3.312	Jade.
29	1.9049	2.612	Agate.
30	1.4406	3.358	Jade.
31	1.6571	2.586	Agate.
32	0.7704	3.342	Jade.
33	1.3146	2.618	Chalcedony.
34	1.1896	3.342	Jade.
35	0.7998	2.626	Agate.
36	0.9438	3.351	Jade.
	Density not tal		Red jasper.
	is encrusted w	vith calcite.	
38	0.8531	3.323	Jade.
39	0.5824	2.593	Agate.
40	0.9976	3.347	Jade.
41	0.4894	2.608	Chalcedony.
42	0.7088	3.364	Jade.
43	0.3286	2.593	Agate.

String i is the most beautiful of the four strings of beads. It consists of alternate beads Notes. of a peculiar jade with, most commonly, agate or chalcedony beads separating them. The soft green colour of the jade shades through many tints from cerro green (V, 27, m) to lettuce green (V, 29, k) and almost to a lumiere green (XVII, 29', b) or a chrysolite green (XXXI, 27'', b) with even lighter coloured patches. The commonest shade is a light lettuce green, and this blends harmoniously with the prevailing buckthorn brown (XV, 17', i) and yellow ochre (XV, 17', —) tints of the chalcedony beads.

The beads have also been arranged symmetrically on either side of the jade bead 22; thus, pairing the stones, we have 21 and 23, 11 and 33, all of which are chalcedony; 17 and 27, 15 and 29, 9 and 35, and 5 and 39, all of which are agates; and 7 and 37, both of which are jasper beads. The beads are well matched in size and shape and they diminish in size more or less uniformly towards either end.

The most outstanding beads are two carnelians, 3 and 19, the latter being a fine large specimen. Their colour is between Brazil red (I, 5, i) and English red (II, 7, i).

There is a single moss-agate bead, 1, which commences the string.

All the beads possess a remarkably fine polish, and again great skill has been displayed in their cutting.

Table of weights and densities. String J.

HR 4212 A. (Pl. CL, String j, Nos. 1-39)

	Weight	True	
Number.	in air in grammes.	Density.	Determination.
I	0.7425	2.098	Nepheline-sodalite-rock.
2	0.4256	2.635	Red jasper.
3	0.4887	2.730	Riband-jasper.
4	0.5231	2.566	Agate-jasper.
5	0.7569	2.586	Agate.
6	0.6372	2.593	Agate-jasper.
7	0.9532	2.602	Heliotrope.
8	1.5776	2.645	Jasper.
9	1.3899	2.671	Plasma.
10	2.8371	2.587	Riband-jasper.
II	2.1104	2.675	Variegated green jasper.
12	2.2356	2.435	Jasper.
13	1.8376	2.575	Moss-agate.
, 14	3.2065	2.594	Riband-jasper.
15	0.239	3.9	Silver.
16	3.3307	2.782	Lapis-lazuli.
17	Density not	determined.	Silver.
18	1.7360	, 2.624	Jasper.
19	Density not	determined.	Silver.
	0.1663	14.23	Gold.1
20	6.0476	2.993	Lapis-lazuli.
21	Density not	determined.	Silver.
22	1.8978	2.574	Agate.
23	Density not	determined.	Silver.
24	2.8954	2.993	Lapis-lazuli.
25	Density not	determined.	Silver.
26	1.6840	2.552	Riband-jasper.
27	3.5212	2.943	Lapis-lazuli.
28	1:6497	2.626	Jasper.
29	1.6094	2.564	Green jasper.
30	2.9658	2.626	Heliotrope.

¹ This is a bead that was found it side the silver bead.

Number.	Weight in air in grammes.	True Density.	Determination.
31	1.5323	2.613	Heliotrope.
32	0.8860	2.620	Agate-jasper.
33	0.9604	2.647	Jasper.
34	0.9036	2.655	Plasma.
35	0.5124	2.596	Agate.
36	0.6559	2.604	Riband-jasper.
37	0.5882	2.608	Agate.
38	0.4198	2.560	Riband-jasper.
-39	0.2711	2.440	Nepheline-sodalite-rock.

String j is in many ways the most interesting of the four strings of beads, and was Notes.

undoubtedly much handsomer at the time when it was worn than it is to-day.

The silver beads have become ugly and brittle, through the formation of silver chloride; the lapis-lazuli beads have lost much of the brilliant azurite blue (IX, 53, m) they must originally have possessed, if they resembled the fresh Badakshān lapis-lazuli; and also the first and last beads, as will be seen later, have lost much of their original beauty.

A small gold bead was found inside the silver bead 19.

BEAD (DK 1341). From Necklace (No. 6) illustrated in Pl. CXLVIII, a.

Weight in air in grammes . 4.5296

True density 3.356

Determination . . . Jade

III. DESCRIPTIVE NOTES

I. Fade

The following beads have been identified as jade: Pl. CL: g 15; i 2, 4, 6, 8, 10, 12, 14, 16, 18, 20, 22, 24, 26, 28, 30, 32, 34, 36, 38, 40, 42; and a bead from necklace No. 6 in Pl. CXLVIII, a. The average density of these twenty-three beads is 3.340, the range of their density being from 3.225 (i 2) to 3.395 (i 18). There is, however, but one bead with a density less than 3.311, and there are only two with densities greater than 3.365.

The variation in colour of the beads has already been noticed (p. 539). No pleochroism was observable in the beads when held in a Feuss dichroscope, and, on account of the absence of plane faces, efforts to obtain the refractive indices of the beads by means of a Herbert Smith refractometer proved unavailing. Accordingly extremely minute fragments of one of the beads were detached by the method previously described (p. 535).

The mean refractive index of bead i42 was determined as 1.651 + .002, and its

birefringence is less than .005.

The hardness of beads i 42 and DK 1341 was determined as 7.5.

The name "jade" is loosely applied to two different minerals, one nephrite, which is an amphibole, and the other jadeite, which is a pyroxene. Dana gives the hardness and density of nephrite as h = 6-6.5, g = 2.96-3.1, and of jadeite as h = 6.5-7, g = 3.33-3.5 respectively.

Larsen,1 no doubt following Michel Levy and Lacroix, gives the mean refractive index

of jadeite as $\beta = 1.654$, and its birefringence as B = .029.

¹ United States Geological Survey, Bull. 679, p. 220.

The hardnesses, densities, and refractive indices of such specimens of jade as were available in the collections of the Geological Survey of India were determined as under:—

	Hardness.	Density.	Refractive Index.
I	7.5	3.336	β 1.651 + .002
II	7.5	3.326	β 1.651 + .002
III	7.5	3.324	β 1.65 ± .004
IV	6.5	2.98	Between 1:575 and 1:590
V	5:5	2.582	-
`VI	6.5	3.088	

- I. Chinese jade (M 1645), presented by the British Museum.
- II. Burmese jade, collected by Dr. J. Coggin Brown and presented to Dr. W. A. K. Christie.
- III. Jade, from Uru river, Upper Burma (1716).
- IV. Jade, from near Belakchi, Kārākāsh valley, South Turkestān (M 1384), collected by F. Stoliczka.
- V. Jade (? bowenite), from Kābul, Afghānistān (G 321).
- VI. Jade, from Mirzapur District, United Provinces, India (G 319).

(Numbers in parentheses refer to the registers of the Geological Survey of India.)

It is interesting to note that the average density of the five specimens of jade from Burma which were analysed by Bleeck 1 is 3.335.

Considering the results given above, one notes that, though the mean refractive index (1.651) and birefringence (less than .005) of the bead i 42 differ from those usually given for jadeite (1.654 and .029), yet the figures obtained are in agreement with those of samples of Burmese and Chinese jade.

The yellowish-green colour of the beads might suggest them to be peridots; and they are more translucent than most varieties of jade. However, the refractive indices of olivine (1.661-1.697) and birefringence (036) differ widely from those of the beads, and it appears certain that the beads are made of a peculiar form of jade, which, in all probability, was obtained from China or Burma.²

2. Lapis-lazuli

The six beads (h 11, 29; j 16, 20, 24, 27) determined as lapis-lazuli have an average density of 2.959. They are generally navy-blue (XXI, 53', m) in colour, though originally

they were probably azurite blue (IX, 53, m).

Lapis-lazuli is the name loosely given to the mineral lazurite, the silicate and sulphide of sodium and aluminium, the density of which is given by Dana as 2·38-2·45. It must be remembered, however, that lapis-lazuli is a rock, inasmuch as it may contain in addition to lazurite or hauynite (sometimes changed to a zeolite) the following minerals: a diopside free from iron, amphibole (koksharovite), mica (muscovite), calcite, pyrite; also in some varieties a relatively small amount of scapolite, plagioclase, orthoclase, apatite, titanite, zircon, and an undetermined mineral.

The high density inclines one to the view that the beads under examination were probably lazulite, the hydrous ferro-magnesian and aluminous phosphate, the density of which is given by Dana as 3.057-3.122. As the variation in density of the beads under examination was large, minute fragments were detached from the cores of beads j 16 and j 24.

¹ Rec. Geol. Surv. Ind., xxxvi, 1907, p. 274.

It was at once seen that several minerals made up the beads. Lazurite was present; it was isotropic and azure-blue in the thinnest section, and possessed a refractive index of 1.494 ± 0.003 . There were, in addition, at least three other minerals; one with $n\beta$ less than 1.596 but greater than 1.573; another with $n\beta$ greater than 1.596; and a third with refractive indices lying between 1.543 and 1.520. For fear of damaging the beads, the precise determination of these minerals could not be proceeded with; but it is quite possible that the mineral with the high refractive index is the one possessing a high density which is at least more than 3. It is suggested that this mineral might be diopside, the refractive indices of which are given by Larsen as 1.673-1.680, and whose density is 3.2-3.38.

Microscopic examination of the beads shows abundant patches of a creamy-white mineral which varies in amount in individual beads. In view of the remarks above, it is more than likely that there are several such white minerals present. In addition, pyrite can be seen though most of this mineral appears to have been worn off the surfaces of the beads.

Ball ¹ describes the occurrence of lapis-lazuli in Badakshān. A specimen in the collections of the Geological Survey of India (M 730) was examined and the lazurite in it found to have the refractive index of 1.494 + .003. This mineral was associated with diopside, calcite, and pyrite.

Thus it appears extremely likely that the source of the lapis-lazuli found at Mohenjo-daro was Badakshān.

(As an additional check upon the determination of lazurite, the refractive indices and density of lazulite from Gulābgarh, Padar district, Kashmīr, which is in the collections of the Geological Survey of India (I 35) were determined to be between 1.610 and 1.646 and as 3.179 respectively.)

3. Gold

Inside one of the silver beads (j 19), and loose, was a bead of gold spherical in shape, both outside and in (3.9 mm.) in diameter and 3.0 mm. long, with circular openings of 1.4 mm. diameter). The diameter of the gold bead very nearly coincided with that of the aperture of the silver bead. This gold bead was found to have a density of 14.3, which is below the limits given by Dana (15.6 - 19.3). Hintze, however, records the following occurrences of native gold with a density about 14:—

				•	Silver.
				Density.	Per cent.
I.	Verespatak.			13.82	28.0
II.	Malpaso .			14.706	11.76
III.	Rio Sucio .			14.690	12.06
IV.	Santa Rosa de	Osos		14.149	35.07
' V.	California .			14.60	8.80
VI.	West Africa			14.63	10.07
VII.	Marmato .			12.67	26.48

It is presumed that there is a large percentage of silver with the gold, as this will partly account for the low density.

¹ Geology of India, iii ! Economic Geology, pp. 528-30.

² Handbuch der Mineralogie, 1, i, pp. 313-19 (1904).

4. Agate, Agate-Jasper and Moss-Agate

Agate is the most important variety of chalcedony; it is built up of layers which differ

conspicuously from each other in colour and transparency.

Bauer 1 defines agate-jasper as stones which are intermediate in character between jasper and chalcedony, and which usually show opaque, dark-coloured portions intermixed in various ways with translucent, lighter-coloured portions. In actual practice it is very hard to define the border-line types.

Moss-agentes are characterized by the presence of green enclosures, which usually take the form of long hairs and fibres much intertwined, and have the general appearance of a piece

of moss.

The following beads were determined as agate: g 3, 4, 8, 10, 18, 22, 26; h 18; i 5, 9, 15, 17, 25, 27, 29, 31, 35, 39, 43; j 5, 22, 35, 37. They range in density from $2 \cdot 573 - 2 \cdot 626$, the average density of the twenty-three beads being $2 \cdot 597$.

Ten beads were determined as agate-jasper, viz.: g 6, 29; h 4, 8, 10, 28, 35; j 4, 6, 32.

These ranged in density from 2.486-2.623, their average density being 2.587.

The four following beads were identified as moss-agate, viz.: g 17, 23; i 1, j 13.

They ranged in density from 2.579 to 2.597, the average density being 2.591.

The thirty-seven beads mentioned above present a wonderful variety of colours, and in all instances they still possess a high polish.

5. Chalcedony

The following beads have been determined as common chalcedony or chalcedony in the more restricted sense of being white or some very pale shade of grey, yellow, brown, blue, or green, and uniformly coloured: g 13; i 11, 13, 21, 23, 33, 41.

Their density ranges from 2.594 (i 11)-2.618 (i 33) and their average density is 2.607.

The greatest departure from the average density is 0.5 per cent.

The beads are various shades of yellow in colour, e.g. buckthorn-brown (XV, 17', i), yellow ochre (XV, 17', —), and pale orange citrine (IV, 19, k).

6. Carnelian

Only two beads are carnelian or red chalcedony, viz.: i 3 and i 19. As noted before, the colour of these beads is between Brazil red (I, 5, i) and English red (II, 7, i). Their respective densities are 2.601 and 2.544.

The large bead shows fracture lines which have probably been induced in the past by

some hard blow or blows upon the bead.

7. Heliotrope

Heliotrope, or blood-stone, differs from plasma only in that its green colour is spotted,

patched, or streaked with a fine blood-red.

The six beads which have been recognized as heliotrope (h 1, 2, 20; j 7, 30, 31) have densities between 2.602 and 2.626, their average density being 2.619. The finest specimens are 1 and j 30, which show fine morocco red (I, 5, k) patches on a dull, blackish-green (XLI, 35", m) stone. It is interesting to note that the greatest variation in density from the average density given above is less than 1 per cent.

1 Op. cit., p. 501

8. Plasma

Plasma'is the name applied to green chalcedony, the colour of which ranges from dark

leek-green, the commonest shade, through pale apple-green, to almost white.

Three beads, h 3, j 9, and j 34, have been identified as plasma. They vary in colour from a dull greenish-black (XLVII, 33"", m) to an elm-green (XVII, 27', m). It is of interest to note that their densities range from 2.612-2.671, the average density being 2.639.

9. Jasper

It will have been noticed that by far the greatest number of beads have been referred to the impure variety of massive quartz known as jasper. This is distinguished from hornstone by its large even conchoidal fracture, the dull lustre of its fractured surface and by its perfect opacity and deep colour. There is, however, no sharp line of demarcation between jasper and hornstone, or between jasper and chalcedony.

The following varieties of jasper have been distinguished:-

Common jasper: Eight beads, g 16; h 15, 25, 34; j 8, 18, 28, 33. The average density of these beads is 2.674. There is another jasper bead, j 12, which is somewhat similar in appearance to j 18 and j 28; this bead, however, has the very low density of 2.435, and it is thus a hydrated jasper.

Blue jasper: Another hydrated jasper noticed was the blue jasper g 12, which has a

density of 2.192.

Red jasper: There are nine red jasper beads $(g \, 5, \, 9, \, 14, \, 21, \, 25; \, h \, 38; \, i \, 7, \, 37; \, j \, 2)$, their average density being 2.654. Their colour, as has been noted before, is really claret-brown $(I, \, 5, \, m)$, and they all show veins of white quartz.

Green jasper: Bead j 29, which has a density of 2.564, is sage-green (XLVII, 29"", —) in colour. The variegated green jasper j 11 has patches of invisible green (XIX, 41', m),

upon a light seal brown (XXXIX, 9", m) background. Its density is 2.675.

Yellow jasper: The yellow jasper bead, h 7, which has a density of 2.534, has a

predominant citrine (IV, 21, k) colour.

Riband-jasper: Riband-jasper has differently coloured riband-like bands, which alternate regularly with each other. The greatest number of the jasper beads in the strings under examination fall into this class, there being thirty-three so classified: g 1, 2, 7, 20, 24, 27, 28; h 5, 6, 9, 12, 13, 14, 16, 17, 19, 21, 22, 23, 24, 26, 30, 31, 32, 33, 36, 37; j 3, 10, 14, 26, 36, 38. Their average density is 2.618, but they range in density from 2.516 to 2.931. Space does not permit of a description of the colours of the individual riband-jasper beads; suffice it to say that the range of colours and the beauty and shape of the beads reflect great credit upon the lapidaries responsible for their manufacture.

10. Amazon Stone

Only one bead, g 19, was identified as Amazon stone or the peculiar so-called verdigris-green microcline. The bead in question was light sulphate green (XIX, 39', b)

in colour, and it possessed a density of 2.697.

Dana gives the density of microcline as 2.54-2.57. The high density of g 19 is due to a central metallic-looking core, which has been inserted inside the bead. Under the microscope a thin chip of the bead, which was unfortunately broken when received by this department, showed the usual cross-hatching of microcline when examined between crossed nicols.

Amazon stone has been recorded from Dodabetta, in the Nilgiris, and it is also said to occur at Chishoti, in the Padar district of Kashmīr.

11. Tachylite

Bead h 27 has been determined as being tachylite or a basaltic or ultrabasic glass. Its

density is 3.058, which falls within the limits of density of the peridotite family.

Microscopic examination of small fragments shows the bead to be chiefly composed of a brownish glass with a considerable number of minute anisotropic minerals. The refractive index of the glass was found to be $1.587 \pm .004$. Its specific refractivity, when calculated

from the expression $K = \frac{n-1}{d}$ where n is the refractive index and d the density, is 0.192,

assuming the density of the glass to be equal to that of the bead. This value of the specific refractivity is lower than the specific refractivity of basaltic glasses as given by Tilley 3; but, as he states,4 the specific refractivities of tachylites tend to be somewhat vitiated by the presence of crystallites in the glass.

12. Silver

The six beads, j 15, 17, 19, 21, 23, and 25, are made of silver. Most of the silver has been converted to silver chloride (cerargyrite or horn silver) by weathering, and not only are the beads covered inside and out with a thick, pimply coating of this mineral, but the metallic portion itself is impregnated with chloride to such an extent that it has become very brittle.⁵

In the minute quantity used for examination no other metal was found by microchemical tests after precipitation of the silver as chloride.

The fresh metal has a high lustre and a slightly yellowish tinge.

The nodular coating of silver chloride is predominantly brownish, with a greasy lustre. Its hardness is about 1. On dissolving it in ammonia, the presence of myriads of minute silver spangles is disclosed. Several green specks are also present; these were shown chemically to consist of a salt of copper. Although no copper was detected by the sensitive triple nitrite test in the metallic portion, this must originally have contained the copper found in the incrustation.

On the edge of the fractured bead, j 15, three distinct layers are visible, suggesting that the ornaments have been formed by beating thin sheets together. The beads are barrelshaped, both outside and inside, and were probably hammered on a specially shaped boss.

13. Nepheline-Sodalite-Rock

The two beads, j_0 I and j_0 39, which have the low densities of 2.098 and 2.440 respectively, have been determined after exhaustive tests as nepheline-sodalite-rock.

The general appearance of both beads is rather greyish, but one end of j 1 is distinctly pale blue in colour.

- 1 H. Congreve, Madras Jour. Lit. and Sci., xxii, p. 249.
- ² Verbal communication from Mr. C. S. Middlemiss.
- 3 Min. Mag., xcvi, March, 1922, p. 279.
- 4 Op. cit., p. 287.
- ⁵ Cf. Alexander Scott, The Cleaning and Restoration of Museum Exhibits, 1926, p. 22.

Microscopical examination of the material detached from the centre of the beads showed this to be largely a decomposition product; it was soluble to a certain extent in dilute hydrochloric acid.

A small quantity was scraped out of the inside of bead j 1 and dried at 107° C. It weighed (on a Kuhlmann balance) 0.000271 grammes. This was treated with cold, double normal hydrochloric acid for five minutes and filtered through an Emich tube filter 1: the residue was washed three times with distilled water, and dried at 107° C. It weighed 0.000211 grammes, showing some 22 per cent is soluble in dilute hydrochloric acid. The solution gave no precipitate with ammonia; calcium was present in abundance; and no magnesium was detected. As the solution in hydrochloric acid is accompanied by effervescence, it may be presumed that 20–25 per cent of the material is calcium carbonate. Fresh material does not effervesce with dilute hydrochloric acid.

The beads are both rocks, not minerals. They are very fine-grained, the average diameter of the grains of bead j 1 being less than 1-100th of a millimeter.

When examined under the microscope fresh material is seen to be made up of a pale yellow mineral or minerals, a pale blue mineral, and at least three colourless minerals.

One colourless mineral is isotropic and has a refractive index of 1.483 + .001; it is thus sodalite. Some, at least, of the yellow material is sodalite, it being isotropic and possessing a similar refractive index. It is thought that the pale-blue mineral is also sodalite.

Another colourless mineral had very low double refraction and a refractive index much

greater than 1.539. This is probably a felspar (? andesine).

Some of the colourless material is nepheline. Its double refraction is very low, probably about .005. The lowest refractive index found was 1.539 ± .001, and no fragment in any orientation had an index of more than 1.543. Nepheline is uniaxial and negative in optical character. The mineral in question is doubtfully uniaxial; no piece was found sufficiently large to give a definite uniaxial figure. One cleavage fragment was observed with positive "elongation". As, however, the basal cleavage of nepheline is sometimes well developed, it can easily happen that a cleavage fragment of nepheline may show positive "elongation"; this was proved experimentally for another specimen of nepheline.

Thus one can safely infer that the beads under examination are made of nepheline-

sodalite-rock.

As an additional check upon this determination, a specimen of elaeolite-sodalite-syenite from Kishangarh, Rājputāna (No. 4675 in the duplicate collection of the Geological Survey of India), was examined. This is a beautiful rock in the hand specimen, the sodalite being azurite blue (IX, 53, m), and shading with admixtures of the accompanying white minerals to pallid violet-blue (IX, 53, f) and other lighter shades.

Small fragments of this specimen were very similar to those from the beads and the

same suite of minerals was found to be present.

There are the remnants of a yellow incrustation upon bead j r. In this connection it is interesting to note what Dr. Heron has said regarding the weathering of elaeolite in the sodalite-bearing rocks of Kishangarh²: "Both in the syenite and the associated pegmatites it (nepheline or elaeolite) weathers with a thin soft yellowish-grey crust resembling the chalky crust on flint, but this decomposition is superficial, and immediately underneath the mineral is found to be quite fresh."

¹ Mikrochemisches Praktikum, Munich, 1924, p. 63.

² Rec. Geol. Surv. Ind., lvi, ii, 1926, p. 189.

At first sight it seems hard to understand why the lapidaries of Mohenjo-daro, whose appreciation of colours has already been stressed, should utilize two ugly grey beads such as j 1 and j 39; but when one lealizes that the beads are made of nepheline-sodalite-rock and when one sees the beauty of such rock when fresh, one can be sure that the beads were once things of beauty with a brilliant display of azurite blue colours. Their present appearance is evidence of the ravages of time, and cannot be considered as a reflection upon the art of Mohenjo-daro.

CHAPTER XXVII

GAMES AND TOYS

HE children and adults of Mohenjo-daro were just as fond of toys and games as they are in Sind at the present day, and numbers of toys and gamesmen have been found, some of them quite ingenious in design.

The majority of the toys were made of baked clay, a substance which can be easily Pottery. modelled and baked even by the smallest child. There is no doubt, I think, that wood also was used for toy-making, but this material readily decays in soil as salt as that of Mohenjo-daro. It is probably for this reason that no traces have been found of wooden playthings.

It is a moot point whether many of the animals and human figures in baked clay were Cult objects. not cult objects rather than toys. The figurines vary very considerably in quality. Some are exceedingly well modelled, whereas others are of the roughest workmanship. For this reason and because it is often difficult to distinguish between actual toys and cult objects, the majority of the pottery figures, both human and animal, have been described in a separate chapter.

Human Figures as Toys (Pl. CLIII, 25 and 38)

It is not certain whether the figure No. 38 (VS 38) should be classed as a toy, but the Movable once movable arms certainly suggest it. On the other hand, the figure is obviously figure. represented as pregnant and the extreme exaggeration of the buttocks suggests steatopygy. It is hardly likely, therefore, that the figure was the work of a child. The height of the figure is 3.8 inches, and a hole in the soles of the feet suggests that it was carried on a thin stick. This model is of well-burnt clay of a light-red colour and uncoated with a slip. Level, 4 feet below surface.

No. 25 (HR 6213), the figure of a woman lying in bed nursing a small child, is obviously Nursing a toy. The woman wears a kilt which is rather longer than those worn by the cult figures, mother and also a very curious cap whose top hangs down the side of the head. The bed has uprights at the head and foot, and is obviously too short for its occupant. This toy, which, including the bed, is 4.1 inches long, is somewhat roughly made but does not appear to be the work of a child, though it may have been made for one. First Street, HR Area, at a depth of 4 feet below the surface.

A similar exaggeration of the buttocks is to be seen in many figures of other countries, as, for instance, in clay figures from the Black Earth Lands (Peake and Fleure, Priests and Kings, p. 164, fig. 101), and from the Alt valley (ibid., p. 160, fig. 99). See also the limestone figure, represented as pregnant and with very pronounced buttocks, from Islatum Bunar on the borders of Lycia and Pamphylia (Evans, Palace of Minos, vol. i, p. 48, fig. 6), and certain figures of the First Thessalian Period (Cambridge Ancient History, vol. i (plates), p. 113, (c)).

550

Votive object.

The possibility must not be overlooked, however, that this figure of a mother nursing a child may have been a fungrary object, or it may even have been intended as a votive offering to a temple or shrine in order to ensure fertility to the giver.

Foreign comparisons. Funerary objects of this kind made in pottery are well known in Egypt in the seventeenth and eighteenth dynasties. In each case a woman lying on a bed was intended to serve as wife to the deceased in the next world. I do not know, however, of a case from Egypt where the woman is nursing a child. The model beds of pottery that are so often found in Mesopotamian sites, chiefly in the neo-Babylonian period, may also have served as votive offerings.

Toy Animals (Pl. CLIII, 24 and 39)

Movable head.

The toy animal from the DK Area seen in Pl. CLIII, 39, is of exceptional interest. It represents a humped bull or cow and has a movable head, including which the figure is 4.5 inches long. In the illustration it will be seen that a string has been passed through the hump of the animal and its hind quarters. This, of course, is modern, and is not altogether satisfactory, because by its means the head can only be pulled back, not pushed forward. Originally a firmer material, such as a bristle or stiff hair, was probably used. The head of the animal in the illustration was not found with the body and can hardly be assumed to have actually belonged to it: but for all that the reconstruction is obviously a likely one. The body of this animal (DK 1719) was found east of Room 6, Block 10, Section C, DK Area, at a level of 4 feet below surface. The head (DK 2183) comes from outside Room 3, Block 16, Section C, DK Area, 3 feet below surface. That this kind of toy was very popular is proved by the number of loose heads that have been unearthed, all of bulls or cows.

Bird-chariot.

The pottery animal HR 2186 (Pl. CLIII, 24) is of a composite nature. It has the head and horns of a ram, and the body and tail of a bird. It measures 4.5 inches in length, is hollow, and made of a light-red ware liberally coated with a deep red wash. There are two opposite holes in the animal's sides, through which a stick was probably once passed, either to swing the animal upon, or, as seems more likely, to accommodate a pair of wheels.² A smaller hole through the neck was probably intended to take a cord by which this bird-chariot could be pulled along. The figure, which is entirely hand-made, is too good to have been the work of a child, though in all probability it was made for one. Level, 9 ft. 6 in. below surface. Court 124, House X, Section B, HR Area.

Monkey.

Of a figure that is not illustrated (E 351) the head and legs are missing, but a tail shows that it was intended to represent a monkey. A hole through the shoulders evidently accommodated a peg to hold the arms very much as in No. 38 in Pl. CLIII. A small hole at the back of the figure suggests that it was fixed upon a stick. This figure is of light-red pottery and somewhat roughly made, though certainly not the work of a child. Its present height is 3.35 inches. Level, 6 ft. 6 in. below the surface.

Clay Baking Pans (Pl. CLIII, 1 and 2)

Saddle-querns.

The two clay dishes Nos. 1 and 2 in Pl. CLIII were evidently made by children. The first (HR 4326) is 2.7 inches long and appears to represent a pan with a saddle-quern in its middle, on which rests a muller. Something has evidently been broken off the end of the pan—possibly the figure of a woman engaged in grinding corn.³ House XVIII, Block 4, Section B, HR Area. Level, 3 feet below the surface.

- 1 For an excellent illustration of such a figure, see Ancient Egypt, 1917, pt. ii, p. 77.
- ² See two articles on very similar bird-chariots by C. B. Seligman in JRAI. 1920, pp. 153-8, and 1928, pp. 247-54.
- 3 Since writing the above a complete figure has been found at Harappa. See ASR. (1926-7), pl. xxiii, fig. c.

No. 2 is somewhat similar, with a quern in the middle upon which rests a muller. In this also something is missing at one end. It is 2.8 inches long and was formerly coated with

Despite the very rough workmanship of these pottery objects, it is possible that they Possible use. were intended to be placed in graves, just as similar figures of women kneading bread were placed in some of the earlier tombs of Egypt. As, however, they were found in a house and not in a grave, they have been included amongst the toys.

Whistles (Pl. CLIII, 17 and 18)

Toys of this kind are common at Mohenjo-daro and are invariably in the form of Bird forms. a bird, hollow within and with a small hole in the back near the tail, which when blown into produces a shrill whistle. It is not easy to recognize the species of bird, but it is likely that a dove is intended. The pedestal-like bases with which the birds are provided permit of their standing easily on a flat surface, and make them convenient to hold. It is possible that various modulations could be produced from such whistles and especially the call of a dove.

No. 17 (VS 2162) is made of straw-coloured pottery and stands 2.25 inches high.

Level, 4 feet below surface. VS Area.

No. 18 (HR 737) is of light-red clay and is 3 inches high. It resembles No. 17 in everything but colour. Level, 4 feet below surface. Room 2, House II, Section A, HR Area.

Rattles (Pl. CLIII, 11)

Round pottery rattles with small pellets of clay inside are well known at Mohenjo-daro. The one illustrated (C 2567) is among the best of those found. It is 2.55 inches in diameter and is of light-red ware decorated with parallel circles in red paint. Level, 12 feet below surface. Room 9, Block 8, Section C, DK Area.

The rattles found vary in size from 1.5 inches to 2.6 inches in diameter, and are all made Decoration. of light-red ware. Some are plain and others decorated with thick linec, always of red and

arranged either laterally or vertically.

These rattles were probably made by wrapping the clay round a combustible core, in Mode of the centre of which the roughly made baked clay pellets were placed to produce the sound.1 manufacture? In every case they are hand-made, not moulded, and they are invariably well finished, but without a slip. They are found at all levels. In hone of the rattles was there a vent-hole to allow the gases resulting from the combustion of the core to escape. Possibly the porous nature of the pottery would of itself permit a gas to pass through easily, and that ma, be the reason why these toys were not coated with a slip.

Dice (Pi. CLIII, 7-10)

That dicing was a common game at Mohenjo-daro is proved by the number of pieces that have been found. In all cases they are made of pottery and are usually cubical, Pottery. ranging in size from 1.2 by 1.2 by 1.2 inches, to 1.5 by 1.5 by 1.5 inches. One die, however, is rectangular, measuring 1.6 by 1.4 by 1.1 inches. I have found by experiment that owing to the inequality of its sides, all of which are numbered, this particular die has a distinct bias towards the higher numbers.

The dice of Mohenjo-daro are not marked in the same way as to-day, i.c., so that the sum Marking.

In one rattle tha we opened were three small clay pellets.

of the points on any two opposite sides amounts to seven. Instead of that, I is opposite 2,

3 opposite 4, and 5 opposite 6.1

All the examples found are exceedingly well made with well-defined edges; the points are shallow holes averaging o 1 inch in diameter. The clay of which they are made is light-red in colour, well baked, and sometimes coated with a red wash.

These dice must have been thrown on a soft surface, such as a piece of cloth, or on dusty

ground, for their edges show little evidence of wear.

It is not yet known whether these objects were used in pairs, but two specimens found in the DK Area, not far from each other, are exactly the same size. Dice have been found at levels ranging from 1 foot to 15 feet below the surface of the ground, and must, therefore, have been used in the Late and Intermediate Periods at least, if not in the Early Period as well.

It is quite possible that dice were used in conjunction with board-games. Mr. Woolley found dice associated with a draught-board at Ur, but I do not yet know if these dice were

vedic dice. similar to those of Mohenjo-daro.

Along with horse-racing, dicing was also one of the amusements of Vedic India,² and it is interesting, therefore, to find it practised in pre-Āryan times in India. The dice used in Vedic times seem, however, to have been entirely different in shape from those discovered at Mohe jo-daro.

No. 8 in Pl. CLIII (DK 1200) is 1.2 by 1.2 by 1.2 inches in size. The points are 0.1 inch in diameter. The material is baked clay of a light-red colour. Level, 5 feet below

surface. Room 4, Block 16, Section C, DK Area.

No. 10 (DK 2362) measures 1.25 by 1.25 by 1.25 inches. The points are 0.1 inch in diameter. Light-red clay that has been well-baked. Level, 1 foot below surface. Room 4, Block 16, S Rion C, DK Area.

Balls and Marbles (Pl. CLIII, 3-6 and 12-15)

Ornamented ball.

Board-games.

No. 6 (VS 804) is a most curious object. It is globular in shape, though not quite round, and reasures 1.75 inches in diameter. It is hand-made and its surface is irregularly covered with small round pellets of clay, each having a small hole pricked in its centre. Some of the pellets have fallen off, disclosing the fact that they were once keyed into place by depressions in the ball itself. Possibly the pricking of each pellet was intended to give them a still firmer hold. As far as can be ascertained without breaking it, this ball is solid throughout, and such an object could only have been used as a plaything. Level, 3 feet below surface. Room 24, House XIX, Block 3, VS Area.

Shell balls.

The three other decorated balls (Pl. CLIII, 3-5) are unusually interesting. That they were used as toys seems likely from the fact that none of them is bored for use as a bead or attachment to a pin. All three are made of shell and each is ornamented with the same design of concentric rings, so cut as to appear in relief. They are all carefully made and finished, and all polished by much wear.³

² Macdonnell and Keith, Vedic Index, p. 2.

¹ Cubical dice were found at Brāhmanābād in 1854 by Mr. Bellasis, who remarked that they were numbered exactly like the dice of the present day. Arch. Surv. Ind. Ann. Aep., 1908-09, p. 85. Mr. Cousens, however, doubts whether the antiquities unearthed by Mr. Bellasis, and now in the British Museum, were found at a low level.

The mode of decoration of these shell balls recalls the ornamentation on a round schist casket of the Buddhist period from Ghaz Dheri. Chārsada; on the latter, however, there is a flower in the middle of each ornament. Ann. Rep. Surv. Ind., 1902-03, p. 175, fig. 21.

No. 3 (HR 4087) is 1.1 inches in diameter. Level, 3 feet below surface. Room 1, Details. House XIV, Block 3, HR Area.

No. 4 (HR 4478) is 1 inch in diameter. Level, 1 ft. 6 in. below, surface. House XXIII, Section B, HR Area.

No. 5 (DK 3201), is 1.2 inches in diameter. Level, 4 feet below surface. , Street between Blocks 1 and 2, Section B, DK Area.

Three exactly similar balls were found in the HR and VS Areas, one (HR 648) being 1.15 inches in diameter, the second (HR 2701) 1.21 inches in diameter, and the third (VS 695) I inch in diameter. The first was found west of House II, Block 2, Section A, HR Area, at a depth of 4 feet below the surface.

Another ball (VS 2172) measuring 0.85 inch in diameter was found at a level of 2 ft. 6 in. below the surface of the ground in the vicinity of House XI, Block 2, VS Area (Pl. CLIII, 12). It is beautifully made of variegated agate and is highly polished. The accuracy of its shape is remarkable. Another stone ball (Pl. CLIII, 13) of veined agate (DK 3056) is 0.95 inch in diameter and also of excellent workmanship and highly polished. This was found south-east of Block 1, Section B, DK Area, at a level of 18 inches below

No. 14 in Pl. CLIII (HR 6007) is a ball made of a hard black stone, r carefully polished. It was found at a level of 5 ft. 6 in. below the surface in Room 87, House IX, Block 2, Section B, HR Area. No. 15 (VS 2962) is 1.1 inches in diameter and beautifully made of variegated agate. Level, 1 ft. 6 in. below surface. Room 113, House XVII, Block 2, VS Area.

A number of small balls (HR 337), averaging 0 48 inch in diameter, were made of Store marbles. agate, slate, veined onyx, and some kind of red and white breccia. The ball made of this last material is not perfectly round, and is also only semi-polished. These marbles, as we may perhaps best call them, were all found together at a level of 2 feet below the surface. From Courtyard 13, House II, Block 2, Section A, HR Area.

There is only one way of making stone marbles of this kind, and that is by continually rolling them in a pan in water mixed with an abrasive. Before doing this, however, each has to be roughly dressed into shape, and we have been fortunate enough to find one that was left in the rough (DK 961). As only the more homogeneous stones can be successfully rolled into shape, we can understand the breccia marble mentioned above being out of shape.

Together with the stone marbles were two measuring 0.4 inch in diameter made of white paste and faience respectively. On the latter an equator was painted in manganese. Both these last-mentioned balls were made in a mould.

Marbles are known from many ancient sites, but they were uncommon in early Sumer, Connections. possibly for the reason that knuckle-bones took their place. They have been found in large numbers at Anau, especially in the South Kurgan, made of pottery as well as of stone.2 In Egypt they were in use from prehistoric times down to the third dynasty; and they resemble the marbles of Mohenjo-daro in being made of various hard stones.3

Knuckle-bones

Curiously enough, we have not found a single example of the knuckle-bone, a game that was extremely common in ancient Babylonia and is equally popular in Iraq at the present day.

¹ Possibly hornblende. ² Pumpelly, Explorations in Turkestan (1904), vol. i, p. 172.

3 Petrie, Prehistoric Egypt, p. 32, pl. xlvi, 26-31

Wheels (Pl. CLIII, 34-7)

A considerable number of pottery wheels have been found in various parts of Mohenjo-daro. At first sight they might be mistaken for spindle-whorls, but that they are the wheels of carts and other toys seems beyond a doubt.

Of the four wheels illustrated in Pl. CLIII, 34-7, No. 34 (DK 319) is 2.5 inches in diameter and 0.7 inch thick, including the boss. The reverse, which has no boss, is slightly concave. Chamber north of No. 6, Block 8, Section C, DK Area, 3 feet below surface.

Sumerian comparisons.

Some pottery chariot wheels found at Kish are very like those found at Mohenjo-daro, the only difference being that the Sumerian wheels have a raised hub on both sides of the wheel instead of a hub on one side only, as was the rule in ancient Sind.¹ We know for certain that the wheels of the Sumerian vehicles were built up from more than one piece of wood, and very much the same form of construction must be imagined for the wheels of the vehicles used by the Indus Valley civilization, especially as the wheels of the modern Sindi cart closely resemble those of Sumer, and like them were fixed to an axle that revolved with them.²

Toy Vehicles (Pl. CXXXI, 38; Pl. CLIV, 7, 10, and 11)

Cart-frames.

An object commonly found at Mohenjo-daro and Harappā is a pottery frame of the shape illustrated in Pl. CXXXI, 38 (VS 1018), a portion of which is missing. A restored example is seen in Pl. CLIV, 7. These frames were at first very puzzling, chiefly because they were always found broken with either one end or the other missing. In addition to the holes that are seen in the illustrations of these objects, there are always two others, which pierce two of the three middle bars horizontally. These holes are quite large and served to take a pole. In the illustration (Pl. CLIV, 7) a piece of string is threaded through them. The restoration of one of these frames shows it to be a part of a vehicle that was very similar to those used in Sind at the present day (see Pl. CLIV, 11). Judging from the number of these frames that have been found, we must conclude that toy carts were very popular with the children of Mohenjo-daro.

The restored frame that is illustrated in Pl. CLIV, 7, now measures 7.5 inches long by 3.4 inches wide by 0.62 inch thick. The old portion was entirely made by hand (not in a mould), and could easily have been the work of a child. The ware is light-yellow in colour and moderately baked. There is no doubt about this restoration, as a perfect example was found in the season 1928-9. All the broken frames that have been found would, if similarly restored be about the same size as the one illustrated

similarly restored, be about the same size as the one illustrated.

The open frame of this ancient cart was probably covered with either a hide or a rope-net. The latter is frequently used for this purpose in modern Indian carts, though the present Sindi vehicles are all provided with a solid wooden frame.

The few models or pictured representations that are known to us of wheeled vehicles of very early date are as follows:—

Ur chariot

- 1. The chariot pictured on the limestone slab from Ur, which is dated by Mr. Woolley to about 3200 B.C.³
- 1 Exactly the same kind of wheel is known at Anau. Pumpelly, Explorations in Turkestan (1904), vol. i, pl. 47, fig. 0.
 - 2 See the writer's remarks on the Sindi cart and a chariot from Ur in the Antiquaries Journal, Jan., 1929.
 - 3 Ibid.

2. The pottery model of a four-wheeled wagon found by Pumpelly in the South Kurgan at Anau,1 which I feel inclined to assign to about the same age.

3. Exactly similar wagons, as well as chariots of the same form as on the Ur slab, in a pre-

Sargonic level at Kish.²

4. The so-called model tented-wagon found at Ulski, north of the Caucasus, in a kurgan burial of Chalcolithic date. I am inclined, however, to think that this is not a wagon at all; moreover, its date is still uncertain.3

At a later date, wheeled vehicles appear in Cappadocia and Egypt. Evidence of their Syrian and first appearance in the former country is afforded by a seal in the British Museum, published Egyptian by Mr. Sidney Smith and approximately dated by him to between 2100 and 1900 B.C. On chariots this cylinder seal a four-wheeled chariot, or wagon, drawn by four horses, is represented.4 In Egypt the chariot appears in Hyksos times (C 1800 (?)-1580 B.C.), but it does not seem to have been in popular use, even in later days, and was only employed in warfare.

The earliest European example of the wheeled wagon is a painted toy vehicle of pottery, provided with four wheels, that was found at Palaikastro in Greece and dated by

Sir Arthur Evans as "somewhat anterior to the close of the third millennium B.c." 5

As far, therefore, as the archæological evidence takes us at present, the wheeled vehicle Central Asian originated in Central Asia, and seems to have passed thence to the west about a millennium origin. later.6 Which people were responsible for the invention, we do not know, but they may well have been the inhabitants of Mesopotamia. We may surmise that it did not come from India, because the ancient vehicles found there are of a more primitive pattern than those found at either Kish or at Ur. But it is too early as yet to dogmatize on this subject, for the lower levels of Mohenjo-daro may prove the contrary.

We know from one of the signs on the stone pictographic tablet from Kish 7 that the Sleage. sledge was in use in Sumer at a very early period, as, indeed, it was in Egypt. Such a vehicle must sometimes have been employed in moving very heavy objects. As time went on, plain wooden rollers would sometimes have been found necessary to reduce friction, and a combination of sledge and rollers must then inevitably have led to the invention of the wheel. Indeed, such a combination of sledge and rollers is actually depicted in a scene in the tomb of Sebeknekht of the thirteenth dynasty at El Kab in Egypt.8 The wheel of the cart used in Sind to-day, as I have already pointed out, resembles that of the ancient Sumerian vehicle; it is, in fact, a superior type of roller, for the axle is so fixed that it revolves with the wheels.

Two models of carts found at Harappa show no warlike features. One is made of pottery Carts from and the other of bronze.9 The latter is provided with a canopy for protection from the sun. Harappa.

- 1 Explorations in Turkestan (1904), vol. i, pl. xlvii, fig. 11, and p. 172. See also the four-wheeled wagons pictured on a mosaic standard from Ur and dated by Woolley to about 3500 B.C. See-Woolley, The Sumerians, p. 51.
 - ² Mackay, A Sumerian Palace, etc., pt. ii, pl. xlvi.
 - 3 Childe, Dawn of Civilization, p. 142, fig. 64.
 - 4 Smith, Early History of Assyria, pl. vii, fig. b.
- ⁵ Cf. BSA., Suppl. Paper, i (1923), fig. 12. For another illustration see Evans, Palace of Minos, vol. ii, pt. i, p. 156, fig. 78. A third illustration is given by H. R. Hall, The Civilization of Greece in the Bronze Age, p. 85, fig. 94, where a brief history of the chariot is given.'
 - 6 I think it may be regarded as certain that the invention was made in an alluvial or non-hilly country.
 - Mackay, A Sumerian Palace, etc., pl. xxxvi, figs. 7 and 8; Antiquaries Journal, vol. viii, pl. lxvii.
- 8 See article by Davies in Jour. Eg. Arch., April, 1926, p. 111. Mr. Davies suggests, however, that the objects under the sledge are wheels and not rollers. If this be so, the wheel must have been in use in Egypt before the arrival of the Hyksos.
 - 9 Ann. Rep. Surv. Ind., 1926-7, pl. xxiii, d.

Casting Bones (?) (Pl. CXXXII, 19, 20, 22-45)

Possible use.

The exact purpose for which these pieces of bone and ivory were used is at present uncertain. At first they were thought to be rectangular forms of dice, like the Roman tali, but the fact that the markings are very commonly the same on all three or four sides hardly bears this out. Nor for the same reason could they be pieces of inlay. The only apparent solution is that some of these objects at least were used in a game of chance, such as throwing a number on the ground together and noting which way they lay. As will be seen in Pl. CXXXII, there is a considerable diversity in the shapes of these objects. Some are rectangular or square in section, in some cases tapering slightly towards one end (Nos. 23, 24, 25, 29, 31, 38, and 45), and some are round (No. 44); these last are very rare. Bones of triangular section are very common (Nos. 22, measuring 3.07 inches long; 26, 27, 30, 35, 37—2.06 inches long; and 43). Nos. 28, 33, 36, 39, and 42 are of peculiar shape, especially No. 28 (VS 2545) which is shaped like a leg and measures 2.65 inches long by 0.21 inch thick. Several examples have been found of this last type. That No. 28 is not a piece of inlay is proved by the same pattern being incised on both sides. The thin edges of this piece are marked with V-shaped lines. From House IX, VS Area.

No. 34 (C 2004) is cubical like a die, and measures 0.55 by 0.5 inch. It has the same markings on all six sides. This object may possibly have been a piece used on

a board-game, for the similarity of its markings prevents it being used as a die.

Evidence of wear.

These ivory or bone objects vary considerably in size. Those found up to the present range in size from 1.65 to 3.25 inches in length. Most of them show evidence of much wear; their edges are rounded and sides highly polished with use. Constant handling has darkened most of them to a deep brown tint. The circular markings upon most of them were made with a tubular drill, and from the clean way in which they are cut, the straight lines seem to have been made with a saw. Care was evidently taken to make the designs as regular as possible, and there is little difference between the designs on the various sides of any one piece, except in their proportions. Where a piece is very thin, the edges as a rule are undecorated. Sometimes, if there was sufficient space, the square cut ends of these objects were decorated with one or two circles; as a rule, however, the ends are plain.

Ornamentation.

No. 23 (VS 2529) has three circles on each of three sides, one at each end and one in the middle. The fourth side is decorated as shown in the illustration. No. 27 (HR 2514) is rectangular in section and has three of its sides marked as in the illustration; the fourth side bears only five simple circles. No. 29 (E 610) is square in section and has two different designs arranged in pairs on adjacent sides. This feature is rare, for as a rule the opposite sides bear the same design. Lastly, No. 45 (C 2004), which is rectangular in section, has the same pattern on three sides, while the fourth is plain except for three longitudinal lines.

Used as dice.

It is, of course, conceivable that these last four objects were used as dice, either in a game by themselves or in conjunction with a board-game of some kind. Even so, there are only two different patterns on each bone; but further combinations could, of course, be made by throwing two or more bones together.

Occasionally, these bones are found in pairs, though not always of the same shape and size, nor marked in the same way.² For instance, No. 27 was found with No. 31 in First

1 Sticks that were found associated with a gaming-board in the tomb of Tutankhamen are said to have had different values according to the way they fell when thrown. For illustrations of these objects, see Illust. Lond. News, 5th Oct., 1929, p. 576.

2 That these bones were sometimes used in threes is proved by the finding of a set of this number in the DK Area.

All are much the same size and bear the same marks.

Street between Sections A and B of the HR Area, at a depth of 9 feet below the surface; and No. 34 was found with No. 45, which is entirely dissimilar in shape. Again, No. 23 and No. 24 were together, though of different size and differently marked.

No. 41 (DK o) has lost one end. It now measures 1.4 inches long-and is square in section. One end is pointed and there is reason to think that it was employed as an awl. A similar example of one of these sticks being converted into an awl may be seen in No. 12 on the same plate.

Nothing quite like these objects is known in either Mesopotamia or Elam, but somewhat Comparisons.

similar sticks have been found in Egypt, where they belong to the First Dynasty.1

The curious pieces of ivory shaped like a fish (Pl. CXXXII, 19, 20, 32, and 40) I regard Fish-forms. as being of very much the same nature as the sticks just described. They could hardly have been intended for use as amulets since they are not perforated in any way.2 Their very high polish, showing that they had been much handled, precludes their having been once enclosed in a wrapping. Some very similar fish, also carved in ivory, have been found in a royal burial at Nagadeh in Egypt,3 and may have been placed there as a food offering. is no evidence, however, that these model fish were used for that purpose in ancient Sind.

No. 19 (C 2164) measures 2.58 inches long and 0.25 inch thick. One side is rounded and the other flat. The eye and scale markings are filled in with a red paint. Level, 8 feet

below surface. Room 5, Block 8, Section C, DK Area.

No. 20 (E 628) is 2.58 inches long and 0.24 inch thick. It is rectangular in section with slightly rounded angles. Scale markings are filled in with red paint. Level, 6 feet Trench E, DK Area. below surface.

No. 32 (DK 2736) measures 3.24 inches long. Rectangular in section with slightly rounded edges. The eye was marked with red paint and the scales in black. Level, 6 feet below surface. Room 10, House IV, Block 2, Section B, DK Area.

No. 40 (DK 7) is 1.78 inches long by 0.12 inch thick. White deposits in the incisions

on this fish suggest that the eyes and scales were filled in with white paint.

It should be observed that the markings on these fish are the same on both sides. No. 19 Markings: could possibly have been used to mark the moves in a board-game, as its sides are differently The remaining three fish, being cut from flat pieces of ivory, have identical sides.

All these objects (with the exception of the fish) are common at all levels except the end

of the Late Period.

Gamesmen or Amuless (Pl. CLIII, 16, 19, 20, 21-3, 26-33; Pl. CLV, 11-25)

That some form of game or games played with pieces was common at Mohenjo-daro Board-games. is proved by the great number of gamesmen that have been found.4 The materials of which these pieces are made are comparatively few. In order of popularity they are-faience, pottery, shell, marble, agate, slate, and steatite.

No. 11 in Pl. CLV is made of black marble and comes from Room 88, Block 9, L Area. Details. No. 12 is beautifully made of agate, and was unearthed in the chamber south of No. 1, Block 8,

¹ Petrie, Objects of Daily Use, p. 52.

² Amulets, however, are by no means always perforated; they are commonly carried on the person wrapped, it may be, in a piece of cloth or even loose in the pocket.—[ED.]

³ de Morgan, La Préhistoire Orientale, t. ii, p. 203, fig. 255.

⁴ See, however, Chap. V, pp. 60-2. It is by no means certain that these objects were gamesmen. The larger ones could certainly not have been such, as they are much too heavy, -[ED.]

Section C, DK Area. No. 13 is of faience and was found in House XXIII, Block 4, VS Area. No. 14 is faience, and comes from the chamber west of No. 2, House XIII, Block 4, Section B, DK Area. No. 15, of white limestone, was unearthed from Room 114, Block 6, L Area. No. 16 is made of green slate and comes from House X, Block 2, VS Area. No. 17, of shell, was recovered from House XIV, Block 2, VS Area. No. 18 is well made in faience and was taken from Block 2 of the Southern Buildings Section. Nos. 19 and 20 are of faience; the former was found in Chamber 18, House IV, Block 2, Section B, DK Area. No. 21 is pottery and came from Room 59, House LIX, Block 8, HR Area. No. 22 is cut from a piece of agate, and Nos. 23, 24, and 25 are made of pottery. Of the last three, No. 23 was found in House XVI, Block 2, VS Area, and No. 24 came from Chamber 6, Block 2, Section C, DK Area.

Nos. 23, 24, and 26 are especially interesting in that they are decorated. The first two are coloured white and red, evidently with the idea of imitating decorated carnelian. The third is more elaborate still; it is painted in red and black on a cream ground, the hatched lines in the illustration denoting red. Its base is slightly concave. No. 21, also of pottery, is painted dark brown to imitate some kind of stone.

The majority of these pieces are exceedingly well made and finished. In many cases those made of faience still retain their original colour to a certain extent, in some cases green and in others blue. All the pottery and faience pieces were made in a mould.

No. 16 in Pl. CLIII is well made of light-red pottery coated with a red wash, and its smooth flat base shows signs of wear. It is 1.9 inches high and 1.6 inches in diameter at the base.

No. 19 (SD 893) is also well made. Its base has been rubbed flat on a hard substance. It is 2 inches high and 1.05 inches in diameter at the base. Found in Block 2 of the Southern Buildings Section at a level of 5 feet below the surface.

The cone-like shell objects illustrated in Pl. CLIII, 21-3 (HR 5539), may possibly also be gamesmen. The three were found together, and average 1.9 inches in height and 1 inch in diameter. Level, 3 feet below surface. Court 36, House LXII, Block 8, HR Area.

No. 26 (VS 1192) is also illustrated in Pl. CLV, 16. It is carefully made of green slate.

Level, 3 ft. 9 in. below surface. House X, Block 2, VS Area.

No. 27 (VS 2622) is made of steatite and stands 1.05 inches high. It has a hole in its base, 0.65 inch deep and 0.1 inch in diameter. The decorative grooving is so regular that one suspects this piece to have been turned on a wheel. Level, 7 ft. 8 in. below surface. House XXII, Block 4, VS Area.

No. 28 (HR 4480) is made of faience, now light green in colour. It is 1.2 inches high, with a flat base 0.7 inch in diameter. It is well made, but the grooves are slightly irregular and were once filled in with a plastic inlay. Level, 2 ft. 6 in. below surface. Room 30, House LXI, Block 8, HR Area.

No. 29 (VS 3) is also illustrated in Pl. CLV, 22. It is of agate and somewhat roughly made. Level, 2 ft. 6 in. below surface.

No. 30 (DK 1554) is of shell. There is a hole in the centre of the flat base, 0.65 inch deep and 0.2 inch in diameter. This piece is 1 inch high. Level, 8 feet below surface.

Chamber 9, Block 2, Section C, DK Area.

No. 31 (HR 4395) is of paste and shows traces of yellow on its surface. It is 1.1 inches high and 0.65 inch in diameter at the base, in which there is a round hole, 0.7 inch deep and 0.25 inch in diameter. This piece, which is moulded, is covered with an irregular trefoil design. In one place, as shown in the illustration, a cross with a linear filling is incised upon it. Level, 4 feet below surface. Passage 20, House XVIII, Block 4, HR Area.

Finish.

Shell-cones

Inlay.

Trefoil design.

Nos. 32 and 33 are also illustrated in Pl. CLV, 23 and 25, and have already been described.

The two regular tetrahedra illustrated in Pl. CLIII, Nos. 40 and 41, are very similar Tetrahedral to objects from both Kish and Ur, except that the Mesopotamian specimens that I have seen, forms. though of the same form, have rounded corners, frequently decorated with a small spot of inlay. At Kish and Ur 1 these curiously-shaped gaming men are of extremely early date and belong to the pre-Sargonic period. Though the examples from Mohenjo-daro are not decorated in any way, they can, from their shape, be fairly compared with the specimens from Sumer. If they were not used as gamesmen, it would be difficult to find another satisfactory purpose for them.2

No. 40 in Pl. CLIII (SD 2880) measures 0.94 inch along each side. It is coated with Descriptions. a now green-coloured glaze. The blackening of the latter in some places is due to overfiring. Level, 3 feet below surface.

No. 48 (C 46) is made of white limestone. It measures 0.75 inch each way and its corners are slightly rounded. Level, 1 ft. 6 in. below surface. Chamber 6, Block 11, Section C, DK Area.

Both these objects show evidence of considerable wear, especially at their edges, Evidence of suggesting that they were used on a hard surface. No particular polish is observable; the wear. first example, being glazed, has a naturally smooth surface.

The poorer people used gamesmen made of pieces of potsherd roughly rubbed into Pottery a suitable shape. The board on which these pieces were used was probably roughly marked gamesmen. on the ground, either in the form of squares or small holes scooped out in the dust. With such a board and pieces a game could be played almost anywhere, as the materials for it were always to hand.

We have not yet been fortunate enough to learn for what game these pieces were made. As, however, not more than three gamesmen of identical form and material have as yet been found together, there is reason to think that comparatively few were used, unless, like chessmen, the pieces differed slightly to show their rank. Of this, however, we have no evidence. The boards upon which the pieces were moved were probably of wood and have, therefore, perished.3 The playing boards that have been found in Egypt and Mesopotamia all have a small number of squares, on which only a few pieces could have been used. The two very early boards, one of dumb-bell shape and the other square, that have lately been found by Mr. Woolley at Ur, have twenty and twelve squares respectively.4

Gamesmen of this kind are found at all levels, except those of tetrahedral shape which Dating. are of very early date. The evidence at present is insufficient for us to say that certain shapes were confined to certain periods.

Absence of Model Boats

Up to the time of writing we have not found any models of boats at Mohenjo-daro or Harappā. Pottery boat-models are fairly common in Mesopotamia from the earliest times, and also in Egypt. In all probability, the Indus anciently, as now, allowed of a certain amount of navigation, though, as on all rivers of its type, navigation must always have been very difficult, owing to shifting sand-banks and the changing of the river's course. Albeit,

4 Antiquaries Journal, vol. viii, pl. vii; Museum, Journal, University of Pennsylvania, vol. xix, No. 1, pp. 20 and 21.

¹ Antiquaries Journal, vol. viii, p. 20.

² They may, perhaps, also be compared with the four-sided pyramidal gamesmen found at Jemdet Nasr.

³ Bricks have since been found marked with squares and holes, which were almost certainly used for a game.

however, that we have found no model boats nor any indication that boats were used, there is every reason to think that the people of Mohenjo-daro must have been well acquainted with shipping and that they made use of the river for purposes of trade.

Model Chairs (Pl. CLIV, 1 and 4)

Despite the fact that wooden articles have almost invariably perished, we know the shape of the wooden chairs in use during the Indus Valley period from the fortunate discovery of the two model chairs in pottery illustrated in Pl. CLIV, I and 4.

No. 1 (VS 1731). The seat of this model measures 2.25 inches long by 1.5 inches wide, and the whole chair stands 2.75 inches high. The back of the seat is supported by a strut. The one leg of the seat is notched—possibly a rough attempt to represent carving or moulding. This model, of which part of the base is missing, is rather roughly made of light-red ware and has no slip. Level, 4 feet below surface. Court of House XXVII,

Block 6, VS Area.

No. 4 (HR 6029) has a slightly curved seat measuring 2.5 inches long by 1.3 inches wide. It stands 1.85 inches high. As in No. 1, the back of the seat has a strut. This model is also perfect except for one end of its base, and it is made of a light-red ware coated with a grey slip. It was found in Room 87, House IX, Block 2, HR Area, and is assignable to the Intermediate Period.

There is no doubt that these two objects are toys; from the roughness of their make, they appear to have been the handiwork of children. These chairs perhaps explain the seated position of some of the pottery figures (Pl. XCV, 19); and we may reasonably conclude that the children of Mohenjo-daro were as fond of doll's parties as is the child of to-day.

The heavy clumsy appearance of these chairs strongly suggests that they were cut from one piece of wood, like many of the African stools of the present time. They may have been used mainly for ceremonial purposes.

NOTE ON BIRD-CHARIOTS IN INDIA, EUROPE, AND CHINA

(by N. G. Majumdar, M.A.)

In the Journal of the Royal Anthropological Institute, 1920, pp. 153-8, Professor C. G. Seligmann drew attention to the "bird-chariots" that occur in Chinese art during the Han period (206 B.C.-A.D. 220), and stated that they "are not Chinese in origin, but were derived from the bird-chariots of the later Bronze Age of Europe". Precisely the same connection was suggested also by B. Laufer in an article published in the Boas Anniversary Volume (New York, 1906). Professor Seligmann has since published another article on the subject in the aforesaid Journal for 1928, pp. 247-54, in which he points out that the bird-chariot occurs in China also in the third-fourth century A.D., and in modern times in Japan and Siberia. By Chinese artists the bird-chariot is treated as a decorative element, as in the case of a vase in the Victoria and Albert Museum representing a mythological bird supported at the side by two wheels. Often there is an additional bird, but of a smaller size, that takes its place on the back of the bird to which the wheels are attached. In the European examples the bird is mounted on the wheels, and as in some of the Chinese examples, a smaller bird is seen perched upon it. But the bird-chariots of Europe are dated between 1300 and 900 B.C., whereas the Chinese ones are not older than 200 B.C. Therefore, it does not seem plausible that the latter should have originated from the former, and we are thus-compelled to look for another source.

Details.

Work of

In India terra-cotta bird-chariots have been discovered at the prehistoric sites of Mohenjo-daro and Harappā which belong to a date much earlier than 1300 B.c., and they seem to be the earliest of their kind yet known. In these specimens the bird is pierced at the sides by a hole to take a pair of wheels and there is another hole below the neck evidently to pass a string by means of which the bird, could be drawn. It will be seen that the idea of the chariot in the case of the Indian as well as Chinese specimens is the same. But the gulf of time between them is too great to enable us to imagine that the prototype of the Chinese bird-chariots are those dug out in the Indus Valley. The type of the bird-chariot as found in the Indus Valley examples appears, however, to have survived down to the historic period in India. Thus, terra-cotta birds pierced with holes for wheels have been discovered at sites which are posterior to the Christian era, as, for instance, at Basarh in the Muzaffarpur District of Bihar (Archæological Survey Report, 1903-04, p. 98, and Pl. XXXIX, The object illustrated in the aforesaid Report is similar to those from Mohenjo-daro and Harappa and belongs probably to the Gupta times. In view of the close communication between India and China that was, established during the Han Period, the most likely theory seems to be that the bird-chariot as a toy was introduced into China from India rather than from Europe of the Bronze Age. As to whether Bronze Age Europe was dependent on the East, especially India, for the conception of its bird-chariots, is a question that cannot be decided in the present state of our knowledge.

¹ Cf., for example, Pl. CLIII, 24.

² Dr. Th. Bloch was of opinion that the holes at the sides were intended to fix the wings. Since then a number of terra-cotta rams pierced with similar holes were found at the same site and Dr. D. B. Spooner suggested that the holes were meant for fixing wheels.—Archwological Survey Report, 1913-14, p. 170, No. 432.

CHAPTER XXVIII

IVORY, SHELL, FAIENCE, AND OTHER OBJECTS OF TECHNICAL

* INTEREST

Ivory

Ivory comparatively rare.

ONSIDERING that the elephant is so commonly portrayed on the seals, strangely few ivory objects have been found at Mohenjo-daro.¹ That the salty nature of the soil is not responsible for this scarcity of ivory is proved by the fact that, if it is not allowed to become alternately wet and dry and is well packed with earth, this material will survive when seemingly harder materials perish.

Plaque.

The ivory plaque shown in Pl. CXXXII, 10 (L 375) is, however, much decayed owing to its position just below the surface of the ground. It is 1.8 inches long by 1.05 inches wide and 0.4 inch thick, but there must be about one-half missing; the circular device was probably in the middle with another figure on the other side.

On the obverse there is a male figure facing to the left with hands on hips. He is represented, in fact, in exactly the same attitude as are the human figures amongst the pictographs on the seals.² The same curious position of the arms is also seen in many of the figures on archaic seals from Susa.³ This figure wears a close-fitting cap with plumes at the back and a short loin-cloth, and carries what may be either a boy or a quiver of arrows on its back. The nose is prominent and the eye elongated, like the eyes of some of the stone statues (Pls. XCVIII and XCIX).

Bow.

In front of this figure is a circular device which may once have contained an inscription, but its surface is very worn and the inscription, if any, has disappeared.

Carving.

In several places, especially at the Back, this piece of ivory shows evidence of having been sawn into shape. The carving of the figure and of the circular device before it is exceedingly rough; no attempt was made properly to round the limbs. It is probable that the tool used was a narrow chisel. The back of the plaque is flat and undecorated, except for some roughly scored lines at unequal distances, which, if this be a piece of inlay, would have served to key it in its place.

Provenance.

This plaque was found in Chamber 104 of the L Area together with three seals (Nos. 304, 341, and 382) and the copper blade-axe illustrated in Pl. CXXXIX, 5. In its vicinity several gold-capped beads were found, exactly similar to the pendants in the string of beads No. 4 immediately below the six-stringed bracelet in Pl. CXLIX, and also a small

The few that are found are mostly casting sticks, handles, etc., such as are illustrated in Pl. CXXXII, 15, 17, 22-45.

² See Nos. 18, 38, 101, 111, etc., in this work.

³ Mem. Del. en Perse, t. viii, p. 11; t. xvi, pl. xxiii.

pottery jar of the same shape as Nos. 6 and 7 in Pl. LXXXI. Only the northern and eastern walls of Chamber 104 remain, and they belong to the Late Period; this plaque and the

objects associated with it must, therefore, be dated to that period.

Other ivory objects are illustrated in Pl. CXXXII, 7-8, 11-13, 15, 17, and 19-45, Ivory sticks. some of which are described in Chapter XXVII on Toys and Games. Their exact purpose is unknown. As most of them are ornamented on every side, they cannot be pieces of inlay; and the fact that the greater number of the longer pieces bear the same device on each side proves that they could not have been used as dice. They may, however, have been used in some other form of game or as a means of divination.

Among these ivory objects found at Mohenjo-daro should be noticed the two combs Combs. illustrated in Pl. CXXXII, 13 and 21, and the two ivory handles in Nos. 15 and 17 of the

same plate, of which the latter is exceptionally well carved and finished.

The five ivory cylinders shown in Pl. CXIV, 529-33, are the only ones that have been Cylinders. found. As they are all inscribed, there is a possibility that they were used as seals. No other use can at present be ascribed to them. They cannot be broken hair-pins inscribed with their owner's names, as they never had any points. Experiment has proved that they would serve well enough as seals.

Hair-pins, awls, etc., of ivory are also very rare. The few that have been found are illustrated in Pl. CXXXII, 3, 7-9, 11, and 12, and they are fully described in Chapter

XXIV on Household Objects, Tools, and Implements.

SHELL

The people of Mohenjo-daro were fortunate in having in shell a material which is in Superiority of some ways superior to ivory, although its brittleness makes it more difficult to work. The shell. supply of shell was inexhaustible, whereas ivory was not so easily procured. It is, indeed, possible that the only source of ivory was the discarded tusks of elephants. If this animal was sacred, as seems probable by its frequent occurrence on the seals, sometimes with and sometimes without the cult object before it, it might not have been considered lawful to hunt it for either its meat or ivory. If this, indeed, was the case, it would sufficiently explain the comparative scarcity of ivory objects.

In the manufacture of articles of shell the people of the Indus Valley civilization were Proficiency. extremely proficient. In this respect they resemble the inhabitants of early Babylonia.2 The extensive use of shell for ornaments and, in particular, its use in the manufacture of cylinder seals has been adduced as a proof of the entry of the Sumerians into Babylonia from the south, but there is every likelihood that the Sumerians, even if they did not already know the art

of shell-working, found the craft well established in the country of their adoption.

Shell-working is still extensively practised in India and a full report of the methods

employed may be found in one of the Memoirs of the Asiatic Society of Bengal.3

At the present day, the shell used in the manufacture of bangles is the sacred Indian Species of shell. sank, or conch (Turbinella pyrum Linn.), most of which comes from the Gulf of Manhar

¹ We have lately found two undoubted cylinder seals, both made of steatite and of the shape that is usual in Mesopotamia and elsewhere.

² In the manufacture of shell inlay, however, the people of Mohenjo-daro were not so adept as the Sumerians. In India, we do not find the wonderful figures carved in this material that we find in Sumer. Possibly the people of Mohenjo-daro used wood as their chief medium of expression; and this material would have had no chance whatever of survival in the damp soil of this site.

² By James Hornell, vol. iii, 1910-14.

between India and Ceylon. It is said that frequently 4,000,000 to 5,000,000 of these shells

are imported into Madras and Calcutta in a year.

Most of the shells that have been found at Mohenjo-daro are, however, of another genus (Fasciolaria trapezium Linn.), though one specimen of Turbinella pyrum has been recorded by Colonel Sewell. A single specimen is also recorded of Turbinella pyrum, var. fusus Sowerby, as Colonel Sewell explains in Chapter XXXI on the Animal Remains. It is probable, therefore, that the people of the Indus Valley civilization obtained their shells from a number of places along the coast of India and the Persian Gulf.

Mother-of-

It is noteworthy that the shell of the pearl-oyster was not used for any purpose at Mohenjo-daro, despite the beauty of this material and the fact that it is common in many parts of the Persian Gulf. The Sumerians made frequent use of mother-of-pearl for their inlay; it seems, indeed, to have been as common with them as the sank shell, especially in the pre-Sargonic period.

Modern shell-working.

The method of preparing the sank shell in modern India is interesting. According to Mr. Hornell, the columella is extracted by sawing off a slice of the lip and then breaking down with a hammer the septa connecting it with the walls of the shell. The apex of the shell is then smashed and the columella freed. This leaves a hollow tubular piece of shell which can readily be sawn into bracelets.

Use of saw.

The iron saw used in India at the present day is worked by hand and is of deep crescentic form with a horn at each end of the upper edge. The thickness of the blade is 2 mm., except for a distance of 1 inch from the cutting edge, where it is thinned down to a thickness of 0.6 mm. The teeth of the saw are extremely minute, and dentate in form instead of serrate. The upper edge of the saw is reinforced by a piece of iron piping, whose weight doubtless assists in the cutting. The saw requires frequent resharpening owing to the hardness of the shell, but this process does not take very long. Mr. Hornell remarks that shell-slicing calls for the possession of a highly trained eye, perfect steadiness of hand and arm, and an iron-like capacity to sit for long periods in a position of great discomfort. On an average it takes 4½ minutes to saw once through a shell.

After a section has been sawn off the inwardly projecting beak, which is the remnant of the septum between adjacent whorls left after removing the columella, has to be chipped off with the greatest care; this part of the ring is its weakest point. A sharp-edged hammer is used for the remnant.

is used for the purpose.

The rubbing down of the inside of the segments is don't with a wooden spindle coated with fine river sand embedded in lac, several segments being smoothed down at the same time by a to and fro movement. All that then remains to be done is to polish the outer surface and to engrave it, if required, the tools used for this purpose being drills, files, and small saws.

The manufacture of shell articles was evidently carried on in certain parts of the L Area at Mohenjo-daro. We found no less than thirty-five shells in Chamber 44; eleven shells in Chamber 53; fifteen shells in Court 69; twenty-four shells in Space 70; and twenty-three shells in Chamber 27, as well as smaller numbers in other parts of the area. Most of these shells were whole, but from some the columella had been removed, and from the condition of the latter it is clear that the columella was detached from the walls of the shell by means of a hammer, just as is done at the present day.

At Mohenjo-daro practically the whole of the shell was utilized. The walls were used for bangles, both wide and narrow, and the columella for making beads. For the simpler forms, such as disc-shaped or cylindrical beads, the columella was simply sliced up with a saw;

Finish.

Manufactories.

Waste.

for the more elaborate beads a considerable amount of shaping by other means was required after they had been sawn off. The columella was also used for making pieces of inlay work, which required considerable skill, especially in the fretting of the designs, which is a most difficult task with such a very brittle material.

In Pl. CLVI, 20 and 21, two of these sank shells are seen with their columellæ lying beside them (Nos. 22 and 23); and a smoothed columella with several partially finished

beads may be seen in Nos. 15 and 24 on the same plate.1

The shell dippers illustrated in Pl. CLVI, 26-9, must have taken up a large part of the Dippers. shell for their manufacture, the smaller ones being made from small shells, and the bigger ones from those of larger size.2

In Pl. CLVI, II (L 781), a shell object of unknown use is illustrated, which measures 1.7 inches high. This object seems to have had another piece of shell fitted to it, for it has a slanting and somewhat roughly finished back, with a vertical channel scooped in it measuring 0.25 inch wide. There is a lightly incised herring-bone pattern around the base of the object, and each of the exposed sides bears an incised pattern, as shown in the illustration. object may possibly be part of the head-dress of a small statue. It was found in Chamber 4 in the L Area just below the surface of the ground.

Shell Inlay (Pl. CLV, 26-42 and 44-67; Pl. CLVI, 1, 4, and 12)

The shell inlay illustrated in Pls. CLV and CLVI, No. 12, gives the reader a very good Curvature. idea of the capabilities of the shell-cutter at Mohenjo-daro. Most of the circular designs must have been cut from the columella of the shell and were limited in size by its diameter. Others of the designs were cut from the wall of the shell, but these pieces, if large, suffer from the disadvantage that its natural curvature rendered them barely flat enough for inlay work. In the smaller pieces, where thinness does not matter, this difficulty could be overcome by rubbing down one or both surfaces; but in the larger pieces this process involved the risk of fracture.

It is not yet known how these pieces of inlay were fretted out, for we have not found Fretting. an unfinished specimen. There are three possible ways: -by means of a small chisel or burin, by means of a fine saw, or by means of a drill. The third method would certainly have been the simplest. Yet the edges of most of the pieces of inlay show marks that might have been made by either a file or saw. Possibly, when the shape of the piece had been outlined with the drill, a fine saw was used to complete the cutting and then a file to smooth the edge.3

In most of the simple designs the outer edges of the pieces of inlay, whether of faience Bevelled edges. or shell, were slightly bevelled for keying. In the more complicated pieces, this bevelling was unnecessary; there was enough surface without it to hold the inlay in place.

The thickness of these pieces of inlay varies considerably. Some of the smaller pieces Thickness of are as thick as, or even thicker than, the larger pieces, chiefly because it was unnecessary inlay. to rub them down to reduce the curvature as in the case of the larger ones. In addition, the cement in which they were set amply allowed for variation in the depth of the pieces of inlay which average from o I inch to o I5 inch in thickness.

Owing to the fact that wood perishes in a salty or damp soil, no pieces of furniture have Bitumen been found with the inlay still in position. In early Babylonia the method usually adopted cement. in inlay work was to press the pieces into a cement of bitumen, whose dark colour contrasted

¹ The smoothed down columella illustrated in No. 15 has been notched for slicing.

² Murex (chicoreus) ramosus, Linn.

³ Even a fine wire coated with an abrasive could have been used for this purpose.

Mohenjo-daro; we have evidence that bitumen was known there since this substance was used to line the inner wall of the Great Bath. As in early Babylonia, the use of shell inlay was perhaps not confined to the adornment of wooden articles, but was extended to stone and for the inlay of the eyes of statues, as in the one illustrated in Pl. KCVIII.

Plaster cement.

In the angles of the piece of inlay figured in Pl. CLV, 48, traces of a white substance were found that suggest that this particular piece, at all events, was laid in plaster. The surface of the latter would probably have been coloured to make a contrast with the cream tint of the inlay itself.²

Petals.

Nos. 26-8 in Pl. CLV, which average o 15 inch in thickness, are very common shapes and evidently formed part of a floral design; they probably represent the petals of a flower. The incurved end of No. 27 suggests that it was once laid against a circular piece of inlay, which may have formed the centre of the flower.³ It is hardly likely that the centres of these petals were left hollow; like the inlay in Pl. CLVI, 12, they were probably filled in with other pieces of shell of exactly the same shape, but smaller in size. No. 30 is most unusual; indeed, it is the only piece of this shape that has yet been found. It, too, probably formed part of a floral design. No. 27 was found in Room 34, House XXVIII, Block 5, Section B, HR Area, and No. 28 in the street between Blocks 1 and 2, Section B, DK Area. No. 30 comes from Room 87, House IX, Block 2, Section B, of the same Area.

Stepped designs.

Nos. 31-3 in Pl. CLV, which are all of shell and an average thickness of 0.2 inch, illustrate a design which is very common, especially in the L Area. As they are generally of large size, these pieces were usually cut from the walls of the shell instead of from the columella. Curiously enough, this design does not appear on any of the painted pottery of Mohenjo-daro, though it is frequently found on the modern painted ware of Sind. The motif No. 33 is exceedingly common on the painted pottery found by Mr. Hargreaves at Nāl in central Balūchistān. The shape illustrated in No. 32 has also been found on a piece of pottery from Nāl. It is also incised on a stone vase found at Bismya, but it is an open question whether the design does not in this case represent a ziggurat or temple-tower.

Very much the same design is found on some of the painted pottery from Anau in Turkestan,7 and what appears to be a variation of the same motif occurs on painted ware of the First Period of Susa.8 It is unknown, however, on the painted pottery of Jemdet Nasr, nor do I know of its occurrence on any other pottery from Mesopotamia. Both Nos. 32 and 33 came from Chamber 15 of the Great Bath Building, and No. 31 from Chamber 53, Block 2, L Area.

Cross designs.

Nos. 34 and 35 in Pl. CLV, which are also of shell and are 0.08 inch thick, are allied to the three pieces of inlay just described. Each is made up of two pieces, one inside the other. They were found amongst a number of other pieces of inlay in House 9 of Section B of the HR Area at a depth of 4 feet below the surface. As the walls of this house belong to the Intermediate Period, this inlay must also be of that date. The form of cross shown in No. 34

¹ Chap. III, p. 25.

We have now positive evidence that plaster was frequently used to hold inlay and that its surface was coloured red. This plaster is generally gypsum.

³ Compare in shape the pieces of crystal inlay from a Minoan medallion of M.M I. period. Evans, Palace of Minos, vol. i, p. 470, fig. 337.

^{4.} Mem. Arch. Surv. Ind., No. 35, pl. xvii, fig. 48. 5 Ibid., pl. xviii, fig. 9.

⁶ Banks, Bismya, p. 242. Compare also fig. 137, t. xii, and pl. vi, t. xvii, in Mém. Dél. en Perse.

⁷ Pumpelly, Explorations in Turkestan (1904), vol. i, pl. 35.

⁸ Mem. Del. en Perse, t. xiii, pl. v, fig. 9; pl. vi, fig. 5; and pl. viii, fig. 6.

and again in Pl. CLVI, 12, also occurs on the bezel of the silver ring seen in Pl. CXLVIII, a, 13. With arms of equal length, the motif is known on the pottery from Susa 1 and also on seals from that place.2 In some cases, both on the pottery and seals, the resemblance is rendered closer by there being one cross inside another, as in No. 34.3,4

This cross design also occurs on a painted potsherd from Harappa. It has not yet been Foreign found on the painted pottery of Mesopotamia, but on Kassite seals it is very common indeed, examples of

both with and without the central cross.⁵ It does not appear on the pottery of Anau.

Equal armed crosses are, of course, known in many parts of the ancient world, but, as far as I an discover, it is only in early Crete, Babylonia in Kassite times, Elain, and India that representations occur of this double cross, In Crete this cross, as well as a plain one, appears in M.M. III, the former as a piece of faience inlay and the latter in marble.7

On the pottery of Susa, another form of cross, the pattée, seems in some cases to be allied with the one under discussion; the plainer cross tends to approach to the pattée form, as if the jar painter were not quite certain in his mind what particular form of cross he intended Indeed, one form was probably derived from the other, and the pattée form is

probably the older, as it is so common in the earliest period of Susa.

The design of Nos. 36 and 37 (Pl. CLV), which are both of shell, is fairly common at Rosettes. Mohenjo-daro and is found on some of the seals of the adjacent countries. Here we may have an early form of the rosette that was used as a decoration in the early as well as the late periods of Persia, Mesopotamia, including Assyria, and Egypt.8 Such a simple design may well, however, have been invented independently; no doubt it was derived from one of the Compositæ. No. 37 was found in the Great Bath at a level of 3 feet below the surface of the ground, and No. 36 in Chamber 13 of the same building.

Nos. 38-47, which range in thickness from 0.15 to 0.2 inch, are all variations of the Heart-shaped same motif. With the exception of No. 43, which is of faience and was found in the Great Bath designs. building, they are all made of shell. No. 38, from Enclosure 50, Block 1, L Area, is of especial interest, as its centre has not been fretted out, though otherwise it appears to be finished. I do not know of its occurrence outside India, in either its simple or more complex form, unless it be the same motif that occurs at Knossos and is said to represent the seed-vessel of the silphium, an umbelliferous plant which is supposed to be extinct, but "whose nearest available comparison is said by Evans to be supplied by the narthex of north Kashmir".9

Very much the same device is seen on the side of an antelope on a copper tablet Animal (Pl. CXVIII, 3), and also on a rhinoceros (Pl. CXVII, 7). Represented as it is on animals markings. of two separate species it cannot be intended for a natural marking. Perhaps this symbol was painted on the living animal as a decoration, as are the various painted devices that adorn

1 Mém. Dél. en Perse, t. xiii, pl. ii, fig. 1; pl. vii, fig. 1; pl. xv, fig. 4; pl. xxi.

² Mém. Dél. en Perse, t. xvi, pl. vi, fig. 101, and pl. xxi, fig. 314; t. viii, p. 5, fig. 9; p. 10, fig. 20.

3 Mem. Del. en Perse, t. xii, p. 94, fig. 65, and p. 91, fig. 42.

According to Herzfeld this cross motif is found on painted pottery in Iran as late as 2000 B.C. Illustrated London News, 1st June, 1929, fig. 11.

Ward, Cylinder Seals of Western Asia, pp. 184-92.

- 6 But see Mem. Arch. Surv. Ind., No. 37, pl. xvi, DN. d. 28, for an example of this motif from northern Balüchistan.
- ⁷ Evans, Palace of Minos, vol. i, p. 515, fig. 375. It is possible that the motif was introduced into the West from Elam by the Kassites.
 - 8 It is found in the First Dynasty of Egypt and in inlay work from the royal tombs of Ur.
- Evans, Palace of Minos, vol. i, pp. 284-5. Sir Arthur Evans points out that the motif, as well as occurring in the Knossian signary, is also found on coins of Cyrene, for which also see reference above. The resemblance is especially close to the markings on the two objects pictured as Nos. 10 and 12 in Pl. CLVII of this work.

state elephants in India at the present day. With it may be compared the trappings (?) on the withers of the so-called unicorn on the seals.

No. 44 was unearthed from Reom 14, Block 16, Section C, DK Area, and No. 47 from

Room 7, Block 2, Section B, DK Area.

Frendl roundels.

Nos. 48-51 are all circular motifs with their interiors fretted out in various ways. The same design that is present in Nos. 48 and 49 is also seen on some of the Nāl pottery,¹ but it does not occur on the painted pottery found by Sir Aurel Stein in Northern Balūchistān and, as far as I can ascertain, it is unknown in both Susa and Mesopotamia.² In Crete the pattern occurs on a gaming board dated to the M.M. III period.³ The same motif is son on the faience nose-ornaments illustrated in Pl. CLII, 7, 8, and 14.⁴ There seems a possibility, however, that this design may have been derived from the cross enclosed in a circle that is seen on some of the pottery of the First Period of Susa.⁵ If the cross itself be removed from the Susian designs a motif very much like Nos. 48 and 49 is left. No. 50 is especially elaborate and is the only example of this design that has been found. Like the rest of the inlay it is made of shell. No. 51, of shell, was found in Chamber 41, Block 1, of L Area. No. 48 came from Chamber 14, House I, HR Area.

Eye designs.

Leaf design.

Nos. 52, 54, 55, and 56 are pieces of shell inlay that probably once formed part of a complicated design. No. 53 is perhaps unfinished, though it could have been used in its present state. No. 54 originally fitted inside No. 55, in which position it is shown in Pl. CLVI, 12. No. 58 is a simply cut piece of shell, very similar in form to some pieces of ivory (?) that were found beneath the foundations of a temple at Susa. The same simple motif occurs repeatedly in a painted plaster frieze in a palace at Nimrud. The design, however, is so simple, being either a square or in some cases a rectangle with incurved sides, that its use in several different countries need have no significance. The lozenge-shaped piece of inlay (No. 57) was unearthed from Chamber 51, Block 1, L Area, and No. 55, which was associated with No. 44, came from Room 14, Block 16, Section C, DK Area.

That No. 61 was cut from the walls of a shell is evident from its curvature. It is clearly a leaf that once belonged to a floral design. I found exactly the same shape, but smaller, in a very early level at Kish. This same pattern is also extensively used in Syrian mother-of-pearl inlay at the present day. From the northern end of First Street, HR Area. Level, 10 feet below surface.

Nos. 59 and 62 are simple pieces of shell inlay, but No. 60 is of uncommon shape and very closely resembles some small pottery amulets found at Harappa, which seem to be peculiar to that place as none have been found at Mohenjo-daro. This last piece was recovered from the lane between Blocks 4 and 5 of the Southern Buildings Section, at a level of 3 feet below the surface.

Petal.

No. 63, again of shell, found in Block 5, Section C, DK Area, is evidently a part of a floral design, and so is No. 64, which is also illustrated in Pl. CLVI, 1. This last comes from Chamber 45, Block 1, L Area. This segment is 0.2 inch thick and its reverse is plain.

¹ Mem. Arch. Surv. Ind., No. 35, pl. xx, d.

² Compare the design on a bronze stamp from Anau. Pumpelly, Explorations in Turkestan, vol. i, pl. 51, fig. 8.

³ Evans, Palace of Minos, vol. i, pl. v.

And on the pottery figured in Pl. LXXXVII, 2 and 4, and Pl. XC, 22. I suggest that this motif is derived from interlocking circles.—[ED.]

Mêm. Dêl. en Perse, t. xiii, pl. vii, fig. 1; pl. xvii, fig. 6.; pl. xviii, figs. 3 and 4; pl. xxi, fig. 4.

⁶ Mém. Dél. en Perse, t. vii, p. 120, fig. 422.

⁷ Babelon, Manual of Oriental Antiquities, p. 115, fig. 87.

Nos. 65, 66, and 67 are all of shell and may be unfinished specimens, though No. 67 is an especially common shape at Mohenjo-daro. The latter has been included amongst the shell inlay as it seems to belong nowhere else. It could hardly have been used as a finger-ring owing to its thinness, in addition to which there is insufficient room for the finger. comes from Room 2, Block 6, Section C, DK Area.

A variety of inlay work is illustrated in Pl. CLVI, 2-5. These pieces of shell seem to Shell segments. have once decorated handles in a similar manner to the pieces of shell which were strung on stout copper wire alternately with similar shaped pieces of some other material to form

certain wand-like objects found in early Sumer and Elam.1

No. 2 (VS 2187) is unfinished and unperforated. It is 1.05 inches in diameter and 0.61 inch thick. It is heavily grooved both on the top and base, so that a wavy appearance of the edge is produced. Level, 5 feet below surface. House XXII, VS Area.

No. 3 (VS 2182) is a similar piece, but perforated. It is 0.51 inch thick and the diameter

of its hole is 0.39 inch. Level, 4 ft. 6 in. below surface. Structure XVII, VS Area.

No. 4 (HR 210) is only a fragment of a once finished piece. It is 1 inch high and its estimated diameter is 0.6 inch. The thickness of its wall is 0.2 inch. Level, 8 feet below surface.

No. 5 (B 441) is well preserved and measures 0.37 inch high. The diameter of its hole is 0.33 inch. Level, 4 feet below surface. It was found in Room 5, Block 3, Section B, DK Area.

All these objects were cut from the columella of the shell, and the grooves on the top and base were made with a saw before the piece was perforated. Those pieces which were finished were always very carefully made and polished, except on the top and base, where they would have been covered. Articles of very similar shape, made of white paste and coated with a red slip to simulate carnelian, are illustrated in Pl. CLVII, 10 and 12.2

Animal figures in shell or any other kind of inlay were apparently not made at Animal figures. Mohenjo-daro, though they are frequently found in Babylonia, where it might almost be said that animal and human devices were as common as floral or other designs. To cut a figure in shell is a difficult piece of work; it was for this reason, perhaps, that animal designs were not

used in inlay work by the people of the Indus Valley Civilization.

A few shells with their excrescences smoothed off and the columella removed seem to Shell have been used as receptacles for water. Occasionally, the smooth surface of the shell was receptacles. ornamented with small concentric circles made with a drill, and in one case two of these placed near the apex of the shell were apparently intended, to represent eyes (HR 3157, Pl. CLVI, 25).3 This last object measures 4 inches long and was found in First Street of the HR Area, at a depth of 5 feet below the surface of the ground. In Sumer similarly smoothed shells were used as drinking cups or for libations or ablutions,4 and sometimes with accretions as lamps.5

A partially finished piece of cut shell illustrated in Pl. CLVP, 14 is 1.95 inches long. Unfinished This interesting fragment (HR 1828) was perhaps intended for the eye of a statue, for an object. eye has been distinctly incised upon it and the piece has been carefully rounded on one side to follow its outline. This fragment of shell is 0.2 inch thick, and it has been partially sawn

¹ Mém. Dél. en Perse, t. i, p. 121, fig. 253; t. vii, p. 102, figs. 330 and 331.

² For these undulating rings see supra, pg. 61-3.—[ED.]

³ These eyes do not appear in the illustration.

E.g., at Kish. For a good example, also decorated with eyes, see Mackay, A Sumerian Palace, etc., pt. ii,

⁵ Woolley, Antiquaries' Journal, vol. viii, pl. vii, fig. 2.

57.0

through along its edge, forming a groove 6.04 inch wide. Level, 8 feet below surface. House III, Block 2, Section A, HR Area.

Jar-stopper.

There is one example of a jar-stopper (DK 1602) made from a piece of shell. This is illustrated in Pl. CLVI, 6. Though somewhat roughly finished, this object with its long shank must have admirably served its purpose. It is, 1.72 inches long and was found 4 feet below the surface, in Chamber 7, House XII, Block 4, Section B, DK Area.

FAIENCE AND PASTE (Pl. CLV, 43, 68, and 69; Pl. CLVII, 13-53)

That the art of glazing flourished at Mohenjo-daro is proved by the number of pieces that have been found. Unfortunately, some of them are so broken that it is difficult to determine what they once were, but some of the better preserved pieces are illustrated in Pl. CLVII, 13-53.

Faience inlay rare.

Only a very few pieces of faience inlay, however, have been discovered. In most cases they are quite unlike the pieces of inlay made of shell, though occasionally the shell patterns were copied, e.g., Pl. CLV, 43, and Pl. CLVII, 34. This piece of inlay measures on inch thick and has bevelled edges which were intended to key it well into the substance in which it was set. It is made of a soft paste coated with a glaze, which is now light green in colour.

No. 68 in Pl. CLV is a long piece of faience which is flat below and slightly rounded

above. The upper curvature of the piece sufficed to key it firmly in its setting.

No. 69 in Pl. CLV (see also Pl. CLVII, 31) is 0.25 inch thick. Its upper surface, which is flat, is decorated with incised parallel lines set obliquely. It is made of paste and still shows traces of the original glaze, which is now light green in colour. It was first of all thought that, as this piece is decorated on both sides, it could not be a piece of inlay. As, however, it is unperforated, it could hardly have been used for any other purpose. Being made in a mould, like all the faience objects, it is possible that both sides were decorated so that after glazing the better side could be placed uppermost. The grooving of the underside would then have served to key it in position. Room 12, Block 3, Section B, DK Area.

In Pl. CLVII, No. 13 (DK 3002), which is 2.15 inches wide, appears to be the cover of a box. Only the decorated top is shown, the underside being similar to that shown in No. 14. The thickness of the cover is 0.15 inch, or, including a slight edging that formerly ran round all four sides, 0.4 inch. The design upon it was a favourite motif. It is found on pieces of shell inlay and on the faience nose-studs seen in Pl. CLII, 7 and 8. Level, 1 ft. 6 in. below surface.

Room 9, House IV, Block 2, Section B, DK Area.

No. 14 (DK 1818) is a fragment of a similar cover, which is decorated with a simple design of incised parallel lines set close together and apparently once filled in with a white paste. Level, 3 feet below surface. Room 15, House XII, Block 4, Section B, DK Area.

Both these covers seem to have been backed inside with a canvas-like material, whose impression is shown in No. 14. This backing must have been used to hold together the paste of which they were made preparatory to glazing them. It was burnt away in the kiln. The surface glaze has almost disappeared from both covers, though traces of the original blue or green still remain here and there. In each case the glaze penetrated well into the paste forming a hard, but somewhat brittle material. No. 13 has a minute hole on either side of the unbroken corner, perhaps for a string hinge.

No. 15 (DK 2256), which is 1.8 inches long, is a fragment of a cover of a box. Its interior surface shows that the light green, vitreous paste of which it is made was laid on

Petal.

Box-cover.

Canvas.

Incised decoration.

1 Compare in shape with fig. 423, p. 120, t. vii, of Mém. Dél. en Perse.

a foundation of some woven material; as is the case with Nos. 13 and 14. The edge of the cover is rather deeper than usual, i.e., 0.25 inch. The outside of the edge is decorated with scored parallel lines placed obliquely. Level, 1 ft. 6 in. below surface. Room 17, Block 3, Section B, DK Area.

No. 16 (DK 2691) is a fragment of a small piece of inlay, flat and plain on one side and scored with lines on the other. It is made of a vitreous paste and is light blue in colour.

Level, 3 feet below surface. From between Blocks 1 and 2, Section B, DK Area.

Nos. 17 and 18 (DK 2992) illustrate a hollow, cone-shaped object with a small rounded head, measuring 1.27 inches high and 1.2 inches in diameter at the base. Inside there is a flat projection with a small hole in it to enable it, perhaps, to be sewn to a garment. This object, which is now of a light-green tint, closely resembles the conical gold object No. 2 seen in Pl. CXLVIII at the top of Photograph A. Level, 1 ft. 6 in. below surface. Block I, Section B, DK Area.

No. 19 (HR 1546) is 1.15 inches high and 0.1 inch in diameter at its base. A hole Paste inlay. runs through it, of equal diameter-0.45 inch-throughout. On the upper part of the object there are three horizontal grooves, each of which is o 1 inch in diameter and about the same in depth. These grooves were doubtless intended to contain a paste inlay. The use of this object, which is too short to have served as a handle, is uncertain. Its glaze is now apple-green in colour, and was evidently overfired. Level, 7 ft. 6 in. below surface. space between Houses III and VI, Section A, HR Area.

No. 20 (L 809) is a glazed spacer of unusual shape, which still shows traces of the original glaze, now green in colour. This bead, which is 0.8 inch in diameter and 0.2 inch thick, was found just above the second pavement of Chamber 59, L Area. It is also illustrated

in Pl. CXLVII, 10.

No. 21 (DK 2172) is a fragment of what may have been a cover, 2.66 inches in diameter and 0.2 inch thick. It is made of a vitreous paste, now light green in colour. Room 14, Block 2, Section B, DK Area.

No. 22 (DM 132) is a fragment of a glazed bangle which is fluted on the outside. It is Bracelet. of a greenish-blue colour right through its thickness. The paste of which it is made is vitreous in nature and pitted with air-holes. Level, 4 feet below surface. Stupa Section, SD Area.

The surface of No. 23 (HR 3465), which is a piece of white paste, has an indefinite design Convoluted carved upon it that is somewhat reminiscent of the trefoil pattern on certain of the beads pattern. and on the cloak of the steatite figure seen in Pl. XCVIII. A number of these pieces were found, averaging 0.25 inch in thickness, but no joins could be made. Judging from their flatness, they may have once formed part of a box. They were found at a depth of 8 feet in First Street of the HR Area, and are probably of Intermediate date.

No. 24 (DM 393). Fragment of a piece of inlay. Base plain and upper surface scored Lozenge with diagonal lines forming a lozenge pattern. Light green, vitreous paste. Level, I foot pattern.

below surface. Stupa Section, SD Area.

No. 25 (HR 5718). 0.75 inch high. This is a solid piece of paste ornamented with horizontal grooved rings that probably once held a paste inlay. The object has a red coating suggestive of a glaze; it may have been a gamesman. Level, 6 ft. 3 in. below surface. Room 37, House XXI, Block 4, Section B, HR Area.

No. 26 (SD 717) is a portion of a small faience vase made of a green, vitreous paste. This piece was found in one of the cells on the southern side of the Great Bath. Level,

5 feet below surface.

1 Or perhaps a baetylic amulet. See supra, p. 61.—[ED.]

Trellis.

No. 27 (HR 769) is a fragment of glaze, now apple-green in colour, that may have been a piece of inlay or the side of a box. It measures 1.9 inches in length by 0.15 inch in thickness. Its very fine moulding gives an idea of the capabilities of the workers in faience at Mohenjo-daro. Level, 5 feet below surface. House I, Block I, A Section, HR Area.

No. 28 (DK 1818) is a portion of a plaque-like object of a green, vitreous paste, full of blow-holes, measuring 2.05 inches long and 0.17 inch thick. The reverse is flat and unornamented, whereas the upper surface is deeply scored with parallel lines. Level, 3 feet

below surface. Room 15, Block 4, Section B, DK Area.

No. 29 (HR 2665) is again a portion of a plaque of a very vitreous, light blue paste full of blow-holes. It measures 1.9 inches wide and 0.3 inch thick. Its reverse is flat and plain, and one corner is missing. The upper surface is ornamented with oblique incised lines which form a series of lozenges. Level, 7 feet below surface. House I'X, Block 3, Section A, HR Area.

No. 30 (HR 2929) is a fragment of vitreous paste, light green in colour and 0.3 inch thick. It is decorated on both sides with oblique incised lines. Level, 3 feet below surface. House X, Section B, HR Area.

No. 31 (DK 2730), which is of white paste with traces on its surface of a light green glaze, measures 2.25 inches long by 0.25 inch thick. As in the case of No. 30, both surfaces are adorned with oblique lines. (See also Pl. CLV, 69.) Level, 4 feet below surface. Room 12, Block 3, Section B, DK Area.

Bevelled edge.

Both these objects are presumably pieces of inlay, especially No. 30, whose edge is bevelled. The advantage of scoring both sides is that, after glazing, the better side could be placed uppermost and the less successful hidden in the cement of the setting.

Nos. 32 and 33 (C 3063 and DK 1933) are two small faience vessels which are also illustrated in Pl. CI, 10 and 8, respectively. They are described in Chapter XX on Stone and Faience Vessels.

No. 34 (SD 1535) is also illustrated in line in Pl. CLV, 43, and has already been described.

No. 35 (VS 990) is part of a cover-like object, which was formerly about 3 inches in diameter and 0.2 inch thick. Its base is flat and the upper surface roughly decorated with incised lines. It is made of a soft spongy paste bearing traces of a glaze which is now applegreen in colour. Level, 3 feet below surface.

Spindle-whorl.

No. 36 (SD 2040) is a spindle-whorl made of a vitreous paste which is light blue in colour and glazed in blue and white, the latter of which may possibly have once been green. It is described in Chapter XXIV on Household Objects, Tools, and Implements. Level, 4 feet below surface. From outside western wall of Block 7, Southern Buildings Section.

No. 37 (DK 2562) is again a fragment of a plaque-like object of a green, vitreous paste, measuring 2.05 inches wide by 0.15 inch thick. Its lower surface is flat and the upper part deeply scored with parallel lines. Level, 3 feet below surface. Street between Blocks 1 and 2, Section B, DK Area.

No. 38 (DK 2256) is a piece of a plaque, or a fragment of inlay, of some kind of vitreous paste, light blue in colour. It measures 1.7 inches in length and 0.25 inch, in thickness. Level, 1 ft. 6 in. below surface. Room 17, Block 3, Section B, DK Area.

Grooved plaque.

No. 39 (DM 226) is a very curious object, 1.7 inches wide by 0.23 inch thick. The two ends are missing. It consists of five tube-like pieces of faience joined together, the

¹ The blue on another piece of faience (HR 5842) was found to contain no trace of copper. Mr. Sana Ullah suggests that cobalt was used for the darker blue.

internal diameter of each tube being of 15 inch. An exactly similar object, but still more badly broken, is seen in No. 46. Both objects were made of a sandy-looking white paste with traces here and there on the surface of a light blue or green glaze. The holes in these objects are much too small to hold an eye-paint, as did somewhat similar objects in ancient Egypt, nor do they contain any trace of colour. They are perhaps beads or spacers of unusual size. Level, 12 feet below surface. Stupa Section, SD Area.

No. 40 (DK 2948), which is a well-made spindle-whorl of a light blue, vitreous paste, Whorls. is again described in Chapter XXIV on Household Objects, Tools, and Implements. As in the case of No. 36, glazes of two different colours were used on this whorl, one blue and the other probably green, which has now faded to white. Level, 3 feet below surface. Street

between Blocks 1 and 2, Section B, DK Area.

No. 41 (SD 1894) and No. 47 (SD 1231) are similar spindle-whorls, which were both made of a soft white paste coated with a glaze which has faded to a light blue colour. They also are discussed in the chapter on Household Objects, etc. No. 41 was found in the clay packing between the two piers on the northern side of the Great Bath at a level of 6 feet below the surface. No. 47 comes from one of the cells on the eastern side of the same Bath. Level, 6 feet below surface.

No. 42 (HR 5536) measures 1.65 inches across and is 0.1 inch thick. The reverse is flat and undecorated. The glaze would seem to have once been green in colour. This object, which is a fragment of a larger piece of inlay, was found 6 feet below the surface of the ground. Room 8, House XVIII, Block 4, HR Area.

No. 43 (HR 4967) measures 0.7 inch wide. Both ends are missing. The reverse is flat and plain, the obverse rounded and fluted. It is made of a vitreous paste which is now white in colour. Level, 6 feet below surface. Room 95, House XIII, Block 2, Section B,

HR Area.

No. 44 (HR 3607) is a fragment of a spindle-whorl that formerly measured 1.7 inches in diameter. Its reverse is flat and its obverse slightly rounded. The hole in its centre to accommodate the spindle is 0.15 inch in diameter. It was made of a soft white paste covered with a light blue glaze. Level, 3 feet below surface. Room 97, House XIII, Block 2, Section B, HR Area.

No. 45 (HR 5837) measures 0.85 inch wide. One end is perfect and the other missing. This object is a piece of inlay very similar to No. 43. Its flat base and rounded lower portion are provided with small holes to take a fine wire which helped to secure the inlay in the cement in which it was once set.1 It is made of a vitreous paste that is now an apple-green colcur. Level, 7 feet below surface. Room 44, House XXIX, Block 5, Section B, HR Area.

No. 46 (SD 1397), which measures 1.8 inches wide and 0.4 inch thick, is similar to No. 39. Both sides are missing. The small hole running through each pipe-like section is 0.15 inch in diameter. From one of the cells on the eastern side of the Great Bath. Level, 6 feet below surface.

No. 48 (SD 427) is a fragment of a bangle made of a vitreous, greenish-blue paste. The Bracelet. bangle was originally 3 inches in diameter by 0.3 inch thick, and is ornamented on the outside

with a herring-bone pattern. Level, 4 feet below surface.

No. 49 (HR 4628). Fragment of a small faience vase made of a white paste. It still shows traces of its original green or blue glaze. Level, 4 feet below surface. From the open space, south of House XLVIII, Block 6, Section B, HR Area.

No. 50 (HR 5804). This is a portion of a bead of cylindrical form, measuring o c inch

The same procedure was adopted in 'early Sumer. Hall and Woolley, Al 'Ubaid, pl. xxxiii.

in diameter. Its sides are fluted. Made of a sandy-looking, white paste with traces of a glaze of greenish colour. Level, 2 feet below surface.

No. 51 (HR 5565). A fragment of a bangle made of a light green vitreous paste.

High Street, N.E. of House I, Section A, HR Area. Level, 2 feet below surface.

No. 52 (HR 5894). Cylindrical bead with fluted sides, measuring 1.2 inches long by 0.5 inch in diameter. Made of a soft grey pasts that was formerly covered with a glaze. Level, 9 feet below surface. Rooms 1 and 13, House XXIII, Block 2, Section B, HR Area.

Base of vessel.

No. 53 (HR 2724). Hollow, cone-shaped object, measuring 0.9 inch high. Possibly the base of a model vase or offering-stand. There is a hole 0.1 inch in diameter through the stem that communicates with the concave base. It is made of a vitreous paste of a light green colour. Level, 5 feet below surface. From western side of First Street, HR Area.

VITREOUS PASTE

Vitreous paste.

In the above descriptions of the faience and paste objects illustrated in Pl. CLVII, a vitreous paste has been alluded to as well as ordinary faience. This vitreous paste resembles glass in some respects. It has a smooth fracture and when examined through a magnifying glass frequently shows a number of air or blow-holes. It is opaque and is therefore not a variety of porcelain. It shows no evident impurities or admixture, as would be the case if a paste had been mixed with an ordinary adhesive to strengthen it.

-Analysis.

I give below the analysis of a sample of this vitreous paste by Mr. Sana Ullah, Archæological Chemist in India:—

			Per cent.
Silica'.			88-12
Alumina .			3.2
Ferric oxide			1.82
Calcium Oxide			1.26
Alkali Oxides			5.04
Cupric Oxide			0.46
-			
Tot	al		99.90

The compounds were fired to about 1200° C.

Another analysis made by Dr. Hamid of a fragment of a small jar, light blue in colour and made of this vitreous paste (HR 3572), is as follows:—

					Per cent.
	Silica				85.90
0	Ferric oxide and	alur	nina		6.74
	Lime				1.73
•	Magnesia .				0.38
	Alkalies .				3.70
	Oxide of copper				0.46
	Loss on ignition			:	1.49
	Tota	1			100.40
					_

Virreous slabs.

ys 195 is a fragment of an irregularly shaped slab of this vitreous material, of a cærulean blue colour. The paste had evidently been poured when in a viscous condition on to some flat surface, to which it had never adhered. The upper part of the slab is slightly rounded

and puckered in places owing to cooling. It was 0.25 inch thick, but its original dimensions cannot be obtained.

Another piece of vitreous paste (VS 1636) was also formerly a part of a similar slab. It is illustrated in Pl. CLIV, 2 and 3. It now measures 1.3 inches wide and 0.22 inch thick; the original length of the slab is not known. The fragment has the same general appearance as VS 195, but is of slightly lighter colour. It also has a rounded upper surface; but its base is flat and it was evidently poured out, or lifted when hot, on to a wire (?) screen, whose impression is clearly seen. Contraction would have separated the slab from the metal as it cooled.

The following is an analysis of VS 195 that was made by Dr. Hamid:

		Per cent.
Silica		84.66
Ferric oxide and alumina		6.31
Lime		1.40
Magnesia		trace
Alkalies		5.48
Oxide of copper		0.97
Loss on ignition		1.18
Total .		100.00

These two slabs are very similar in composition to the finished objects of vitreous paste. Mode of use. Possibly they were intended to be ground to a powder, like the modern enamels, and used for glazing purposes after a little soda had been added to serve as a flux. In practice, however, it was found that after grinding up a sample from the slab it was difficult to make the resulting powder adhere properly to a piece of steatite. This difficulty, of making such a powder adhere to the object to be glazed while being dried and before fusing, could have been overcome in several ways, as, for example, by mixing certain oils with the powder which volatilize at a high temperature, leaving no trace behind them.1 Again, these slabs may have been heated in a flame to a semi-fluid condition and applied in that state to cover such articles as pottery beads and the like. A subsequent and prolonged heating of an object so treated would result in the glaze flowing freely over it. It appears to me that bead No. 50 in Pl. CXLVI was made in this way.2

An interesting piece of vitreous paste is illustrated in Pl. CLIX, 3 (HR 5843). This Inlay is a fragment of a vase of light blue paste. The surface was incised with a knife decoration. to a depth of about 0.15 inch, to form a pattern consisting of a broad band placed between borders of three narrower bands on either side. But no attempt was made to ensure any great accuracy in the width of the bands. The incisions were filled in with a paste that is now white, and this filling was then carefully pared down to make it exactly level with the surface of the vase itself. The vase was then fired at a high temperature. Both the paste of the filling and that of the vase itself were made of a fine, gritty-looking substance that seems. to have been plentifully mixed with a glaze.3 The resulting substances are opaque, vitreous materials with pittings here and there that are probably due to escaping gases. This particular piece resembles the many objects of witreous paste that have been found at Mohenjo-daro

¹ I would instance pear-seed oil, frequently used for enamels at the present day.

² See Chap. XXVI, p. 516, for a description of this bead

³ For a description of the preparation of frits in Egypt, see Petrie, Arts and Crafts of Ancient Egypt, pp. 116-17 Also Lucas, Ancient Egyptian Materials, chap. ii.

and Harappā save for the inlay of another colour. It was unearthed from House XXXII, Block 5, Section B, HR Area, at a level of 2 ft. 4 in. below the surface.

Resemblance to glass.

The outward resemblance of this fragment to an opaque glass is very close; and it was probably still more so when the vessel was first made, for its colours have now faded badly owing to age and the salty nature of the soil in which it was found. nature of its paste proves it definitely not to be a glass.

FAIENCE

Body.

The ordinary articles of faience are composed of a white or greyish paste coated with a glaze, which, presumably owing to the action of salt or damp, has generally faded to a light blue or green. This paste is granular in appearance and sometimes contains black specks, which may be the carbonized remains of an adhesive that it was sometimes found necessary to introduce to hold the paste together before it was dipped in, or painted with the glaze and fired.

From external examination two faience objects, both from the DK Area, the first-being a broken-seated human figurine and the second the base of a small vessel, appeared to have been moulded from a crystalline, siliceous material like the faience of ancient Egypt. Dr. Hamid reports, however, that the body material of these two objects is steatite, which has all the appearance of having been artificially crushed. The technique of moulding, glazing, and firing in this particular case must have been essentially the same as in other faience objects. The relatively small proportion of water is significant, as it shows the effect

Dr. Hamid's analysis of this most interesting composition is given below:—

		Base. Per cent.	Figure. Per cent.
Silica		57.99	57.23
Oxides of Iron 1 and Aluminium		4.85	3.69
Line		4.31	6.39
Magnesia		27.20	28.99
Alkalies		3.54	1.88
Oxide of Copper		1.09	0.46
			1.36
Totals		100.99	100.00

Egyptian faience.

There has always been some doubt as to the material of the body used in the faience of ancient Egypt. It has been stated to be sand, powdered sand, carved sandstone, powdered quartz rock, ground quartz pebbles, etc.2 But whatever the material used, it always contains over 90 per cent of silica. Mr. Lucas is of the opinion that crushed white quartz sand was the material employed.3 No analyses have yet been made, to my knowledge, of early Babylonian faience.

It is questionable whether any added silicate had sufficient adhesive power to hold together the powdered steatite before it was fired.4 Possibly, the object could have been extracted from its mould while still damp and, after being coated with the glaze, was heated

¹ The whole of the iron is expressed as Ferric Oxide.

² Lucas, Ancient Egyptian Materials, pp. 32 and 33.

⁴ It has since been proved by experiment that it does. 3 Ibid., p. 33.

slowly in an increasing temperature until the fusing of the glaze firmly bound the whole mass together.

I do not think that the use of powdered steatite as a body material has ever been detected Powdered in the faience of Egypt. Objects cut from solid stone and then glazed are extremely steatite. common even in the earliest times in that country, and we find the same process frequently practised at Mohenjo-daro. From a technical point of view, the employment of ground steatite in place of carved steatite marks a great advance in craftsmanship; it enabled objects to be readily duplicated in moulds with little expenditure of time or trouble.1

Though faience objects were commonly moulded of this powdered steatite, it was found Moulding. necessary to do a certain amount of work to them before the glaze was applied. The material is too coarse to be run into the moulds in a fluid state; instead, it had to be pressed in. Fine details, such as the hair in the case of animal figures, were inclined to lose their sharpness in such a process, and it was found necessary to touch them up with some kind of tool.

In those objects whose glaze is well preserved it is found to be smooth and thin in the majority of cases, with no evidence of the over-firing that produces a slightly matt and even pitted surface.

We do not find the beautiful blues and greens that are so well known in Egypt; but this Colours. is probably due to the exceptionally high proportion of salt in the soil of Mohenjo-daro.

An interesting piece of faience is shown in Pl. CLIX, 4. This is part of a small jar Painted glaze. (A 129). The paste of which it was made is a coarse, friable material, which was first bound together by some other material than the glaze. Its surface was then covered with a thin glaze, now light blue in colour, and ornamented by thin bands of a purplish-black. These bands were merely painted on the surface of the glaze, so thickly that they lie well above the surface of the jar. Judging from its texture and colour, this paint seems to consist of a frit coloured with manganese. Its present raised and blobby appearance may be due to fear on the part of the maker of the jar that over-firing would cause the bands to run and mix with one another.

Dr. Hamid, who examined this fragment for me, states: "The dark bands consist Description. of an easily fusible silicate glaze which owes its purple-black colour to the presence of manganese. It also contains iron which was probably present along with manganese in the natural ore employed as pigment. It was possible to prepare a sample for analysis from the interior of the body which seemed particularly free from glaze. No copper could be detected in it. It contains only traces of iron. The material is neither steatite nor pottery. From a preliminary analysis its composition seems similar to that of the material described as vitrous paste, though it is softer in nature and free from glaze."

Level, 3 feet below the surface. Room 13, Block 1, Section A, DK Area.

GLAZED POTTERY

Two very interesting glazes covered the bead found in Room 18, House XV, Block 2, Pottery bead. Section B, HR Area (HR 5026), that is illustrated in Pl. CXLVI, 50. It was at first thought that this bead was entirely made of glass, but a closer examination proved it to be pottery thickly coated with two coloured glazes, brown and white. While the brown is only a thin covering, the white glaze extends to a good depth in the body of the bead.2 The former

¹ Though we have as yet found no moulds at Mohenjo-daro, it is certain that they were extensively employed in the manufacture of faience objects.

² See p. 516 supra.

seems to have been coloured with some form of iron. Dr. Hamid has analysed this bead as follows:

		Pottery base of bead. Per cent.				The white glaze. ² Per cent.
Silica		71.12		Silica		86.28
Alumina		9.27		Alumina and Iron	Oxide	7.78
Iron Oxide .		10.01		Lime		2.35
Lime . ,	^ .	1.77		Magnesia .		0.61
Magnesia		1.55		Soda		1.51
Soda and Potash		3.77		Potash		nil
Loss on ignition		1.69	-	Loss on ignition	20	2.05
2 Total		100.08		Total		100-28

Mosaic glass.

The two sherds illustrated in Pl. CLIX, I and 2, look very like copies of mosaic glass, though no true glass has as yet been found either at Harappā or Mohenjo-daro. Both are made of a light-grey clay of medium thickness, well baked and fairly tough.³ The dark, wavy markings are a purplish-black slip, which has been proved to contain manganese. It seems that these two pieces of pottery were first of all coated with this dark slip and then washed over with a glaze; but, before firing, the latter was partially removed with a comb-like instrument so as to leave a wavy pattern. This is an unusual technique, but it is seen on a painted pottery sherd lately found at Kish by M. Watelin.⁴ On this sherd, also, a dark-coloured slip was painted and was subsequently partially removed in exactly the same way and with very similar results, except that the colour of the ground is different owing to the ware in this case being drab in colour. I am inclined to think that the sherd from Kish is of much the same date as the two pieces from Mohenjo-daro.

As some doubt had been cast on the possibility of these two pieces being glazed, they were sent to Dr. H. J. Plenderleith, of the British Museum, for further examination, and his report

is given in Appendix II (p. 692).

Owing to their resemblance to some modern ware, these two pieces of glazed pottery were at first suspect, but during the season 1928-29 I have obtained certain proof that they are the work of the Indus Valley Civilization by the fortunate find of a third sherd of the same technique and colouring at an early level in the DK Area.⁵

No. 1 in Pl. CLIX (VS 195) was found at a depth of 2 feet below the surface of the ground in the VS Area, and No. 2 (HR 1114) at a depth of 5 feet in the HR Area. The third sherd comes from the north-west corner of House I, Block 1, Section A, HR Area.

These four sherds, which, it should be noted, came from different parts of Mohenjo-daro, appear to be the oldest examples of glazed pottery that have as yet been found in any country.

Earliest examples.

- ¹ The colour may have been green in the first place, subsequently ageing to brown.
- The term "glaze", here as well as in some other places, is used rather loosely for want of a better name for this substance, which though glassy in appearance is not a true glass—ancient glasses being essentially soda-lime silicates. It may be that in certain cases water saturated with carbonic acid is responsible for the removal of most of the alkalis.

3 A certain amount of coarse white sand or quartz is present in the paste as well as a considerable amount of dirt, some of which has the appearance of charcoal.

- 4 Now in the Ashmolean Museum, where it is stated to have been found in Area C, Kish, in 1929. This painted shows no trace of glaze and it was the paint that was removed.
 - 5 This season (1929-30) has produced a fourth fragment, also from a low level.

EARLY HISTORY OF FAIENCE, VITREOUS PASTE, AND GLASS

Though we do not yet know with certainty in what country faience was invented, the Invention of archæological evidence at present available would seem to accord this honour to Egypt, where glaze. the glazing of various kinds of pastes as well as of stone was practised as early as pre-Dynastic times. It is possible, however, that the art was introduced into that country from the East. Faience beads first appear in what is known as the second civilization of the pre-Dynastic period of Egypt, which commenced about Sequence Date 38. Petrie would date this between 10000 and 8000 B.C., but others bring its latter end down to approximately 3400 B.C.2 This question need not be discussed here, though in view of the fact that it must be referred to again later on, I would like to state that in my opinion a date between the two given appears to be more probable.

The glazing of beads and other objects made of faience was certainly practised in very Early early times in Mesopotamia, for a number of faience articles were found at Jemdet Nasr near examples. Kish,3 in association with painted ware that has very close affinities with the painted pottery of Musyan and of Susa II. The date of this site and its painted pottery is still open to question, but there can be no doubt that it is as old as, if not older than, the pre-Dynastic period of Egypt. I would myself date it as early as 4000 B.C., if not some time before that.4

In Elam also, faience is associated with painted pottery and was made in very early times. It was probably first manufactured at about the same time as in Mesopotamia, for that the two countries were once occupied by similar civilizations is strongly suggested by the many similarities in their painted wares.

In the lower levels of Anau in Turkestan, faience is represented by a solitary bead which Anau. was found at the level of Culture III.5 But possibly the salty nature of the soil at that site may be responsible for the wholesale destruction of glaze.6 In the mixed layers, however, and also in association with the pottery of the younger culture of the South Kurgan at Anau, Pumpelly found fragments of faience which consisted of a glaze covering a white sandy body; these he compares with Egyptian faience. From the circumstances of their occurrence he was unable to deduce their actual provenance, though he definitely states that the possibility of their being of modern or mediaeval origin is not to be entertained.7

The presence of the one bead in an early level by no means proves that faience was manufactured by the inhabitants of Anau. This solitary specimen may quite conceivably have been imported. Nevertheless, one suspects that even in early times the people of that site were well acquainted with faience ornaments, as the use of this material was so general in the Near and Middle East.

As the glazed objects illustrated in these volumes prove, faience was extensively Common at all manufactured in the Indus Valley; we find it as frequently in the lower as in the higher levels. levels.

1 Petrie, Prehistoric Egypt, p. 5.

² Peake and Fleure, Priests and Kings, p. 34.

3 My account of these is shortly to be published by the Field Museum, Chicago.

⁴ Langdon places the date of Jemdet Nasr about 3500 B.C. (Oxford Editions of Cuneiform Texts, vol. vii, p. iii), and Gadd the date of A-anni-padda of the First Dynasty of Ur about 3100 B.C. at the earliest (Hall and Woolley, Al 'Ubaid, p. 140). If, however, we compare the very archaic signs on the Jemdet Nasr tablets with the considerably more developed writing on the inscriptions of A-anni-padda, 400 years does not seem to me to be enough to allow for the difference between the two styles of writing.

⁵ Pumpelly, Explorations in Turkestan (1904), vol. i, p. 160, pl. 42, fig. 8.

⁶ In certain soils glaze entirely disappears.

7 Pumpelly, Explorations in Turkestan, vol. 2, p. 173.

And it is just as common at Harappā as it is at Mohenjo-daro. We have provisionally dated some of the lower levels of Mohenjo-daro to 3250 B.C., but there is no reason to doubt that faience will also occur in lower strata still at correspondingly earlier dates.

A few glazed beads were found by Mr. Hargreaves at Nal in central Baluchistan associated with painted pottery. There is, however, some doubt about the date of this pottery; Sir Aurel Stein is inclined to regard it as later rather than prior to the painted pottery of the Indus Valley Civilization, despite the facte that its thinness and certain details of its decoration bring it into line with some of the painted pottery of Susa I.²

That faience as well as a kind of vitreous paste was known in Crete as early as the period E.M. II (approximately 2800–2500 B.C.) is proved by the finding of glazed beads and a faience bowl which was unearthed at Mochios.³ It is generally concluded that the art of glazing was introduced into Crete from Egypt in the first place, and that later its manufacture became established in the island itself. The colour is a pale bluish-green resembling that in use during the early dynasties of Egypt, with which it can be correlated in point of time.

It is only in comparatively late times that faience was manufactured in Europe, whither it seems to have been introduced indirectly from Egypt. Certain segmented glazed beads very similar to those illustrated in Pl. CXLVI, 28–30, have been found both in Egypt and Crete, dated in the former country as early as the eleventh dynasty—they are also common in the eighteenth dynasty—and in Crete to Period M.M. III—L.M. III. The same form of glazed bead has been found in many parts of Europe, including Wiltshire and even Scotland, and it is thought that in the British Isles they became a local manufacture. Sir Arthur Evans has devoted especial attention to this type of bead, of which a number are illustrated in his first book on Knossos.4

Taking into consideration the age of the faience objects found in the different countries, the available evidence points to either Egypt or Mesopotamia, with which I include Elam, as being the original home of faience. And owing to the large number of articles of this material that occur in Egypt, the honour of having invented faience has generally been conceded to that country. But it should be remembered that at present we know a great deal about the archæological history of that country and but little about that of Mesopotamia or Elam. The fact that faience was common at Jemdet Nasr, which up to the present is the earliest site that has been excavated there, and which from the nature of its painted pottery appears to be of a date prior to the pre-Dynastic period of Egypt, suggests, indeed, that the Egyptians borrowed the craft from either Mesopotamia or Elam.

Its manufacture is a somewhat elaborate process and requires great attention to detail, first in the preparation of the glaze, then in its application, and finally in firing it in a muffle or kiln. Taking all this into consideration, it seems much more probable that the craft originated somewhere in the Middle East and thence gradually spread over the ancient world. The fine blues and greens that this material provides must always have been appreciated, especially for articles of adornment, for stones possessing these colours, such as lapis-lazuli and greenfelepar, were expensive and in some countries difficult to procure.

1 Mem. Arch. Surv. Ind., No. 35, p. 34.

3 Evans, Palace of Minos, vol. i, p. 85.

4 Ibid., vol. i, pp. 491-3.

Nāl.

Crete.

Europe.

Mesopotamia or Elam.

Not invented independently.

² Compare, for example, the pattern on a lyre found at Ur, dated to 3500-3300 B.C. (Antiq. Journ., vol. ix, pl. xxxiii, fig. 1), with a design on some of the Nal pottery (Mem. Arch. Surv. Ind., No. 35, pl. xvii, figs. 36 and 39). These are almost identical except that in the Sumerian decoration there is a dot in the middle of the eye-shaped roundel. The decoration on the Nal jars is, to my mind, a variant of the Ur pattern, and not very far removed from it in date.

It is significant that the second civilization of the pre-Dynastic period of Egypt, during Protowhich faience first appears in that country, is supposed to have come from the East, though Babylonian perhaps not from so far_off as Mesopotamia or Elam. Petrie provisionally assigns the earlier culture. home of this civilization to somewhere on the Arabian coast, whence it entered the Nile valley by the Koseir-Wady Hammamat route.2 The people who brought this civilization with elements of a proto-Babylonian culture 3 might quite well have been acquainted with the civilization of Mesopotamia and Elam, either direct or through intermediaries. Petrie has, indeed, suggested that they may originally have emigrated from Susa itself and have made a long hait at some point before reaching Egypt.4

In the above remarks I have assumed that the proto-Elamitic civilization was older than that of pre-Dynastic Egypt, a view that is held by Petrie and many others.5 Indeed, further investigations will probably show that the former civilization had greater influence than has hitherto been supposed. 'That it also influenced the Indus Valley Civilization can hardly,

I think, be questioned.

Glazed Pottery

Though we have seen that faience was extensively manufactured in ancient times, the Glazed pottery glazing of pottery vessels appears to have been introduced in most countries at a much later hitherto late. date, probably for the reason that the glazing of comparatively large objects, such as pottery, is a difficult process. As I have already mentioned, the earliest examples of glazed pottery have been found at Mohenjo-daro. In Egypt it appears to be unknown before Roman Yet in Nubia, Reisner is said to have found a large number of pieces of glazed pottery in a tomb dated to the twelfth dynasty, which appears to be of local manufacture.7 If this ware is actually glazed pottery, it is curious that it had not appeared in Egypt by that time. In Mesopotamia, glazed pottery first appears about 1000 B.C., and was especially common at the time of Nebuchadnezzar.8 In Crete, it has not apparently been found at all.

It seems that glazed pottery disappeared for a time in India, but it came in again in the Kushan period. Kushān period (second century A.D.). From then onwards it seems to have survived down to modern times. Ross states that there is a tradition in India that enamelled pottery, by which I conclude he means glazed pottery, and which he calls a sumptuary art, was introduced from China through Persia.9 Some would ascribe the invention of glazed pottery to China on the flimsy ground that, as that country invented porcelain, it must also have invented glazed We as yet know little about the very early fabrics of that country, but it is said on good authority that even glazed pottery was not known in that country before the Han Dynasty (206 B.C.-A.D. 220), long after it was commonly used in Mesopotamia.10, 11 There is, it should

1 Glaze, except on stone, is unknown in the Badarian period. Brunton and Caton-Thompson, Badarian Civilization, p. 27.

² Ancient Egypt, 1917, pt. i, pp. 26-36. Petrie, Prehistoric Civilization, p. 49.

3 Camb. Anc. Hist., vol. i, p. 254.

4 Ibid., p. 256.

5 Ancient Egypt, 1917, pt. i, p. 32.

6 Lucas, Ancient Egyptian Materials, p. 58.

- Ancient Egypt, 1916, pt. ii, p. 87; also Museum of Fine Arts Bulletin, Boston, Dec., 1915.
- ⁸ According to Harrison this was a lead glaze. Harrison, Pots and Pans, p. 53.

Land of the Five Rivers, p. 44.

- 10 Ency. Brit. (11th ed.), vol. v, p. 744: Ceramics. Dr. Andersson has not reported the presence of glaze in Chalcolithic sites in China.
- 11 The Chinese appear to have obtained their knowledge of lead glaze from the West. Harrison, Pots and Pans, p. 53.

582

be noted, a very considerable difference between the processes involved in making porcelain and glazed pottery. The former is a vitrified clay of a special kind, whereas the latter is made by applying a glass-like material to an earthenware base.

Possibly foreign origin.

It is certainly interesting to find that glazed pottery was used in India before it appears to have been known in Mesopotamia. And is should be noted that the quality of the Indian sherds that I have just described is equal in finish to any glazed ware of ancient Mesopotamia. The four pieces found at Mohenjo-daro are beyond a doubt the handiwork of a potter who was well acquainted with the process and able to carry it to a high degree of perfection. From the fact that only four samples of this glazed ware have been found, we must conclude, at least for the present, that it was not extensively manufactured. Indeed, we cannot be certain that it was actually made in India; it may conceivably have been imported. We must, nevertheless, provisionally accept its Indian origin, for there is no other country known to us where glazed pottery vessels were manufactured at such an early date.

Vitreous Paste

History.

The history of this material, which to the casual eye closely resembles an opaque glass, is at present obscure. At Mohenjo-daro it occurs as commonly as faience, and it was doubtless appreciated for its strength and the compactness of its paste. It can readily be moulded, and objects made of it, though simple in design, have their details well defined. I do not know if this substance has yet been found in Mesopotamia; I have seen no samples at Kish or elsewhere. In Egypt, a very similar material to that found at Mohenjo-daro was commonly used in the twenty-sixth dynasty; it is described by Petrie as "a beautiful hard stoneware, apparently made by mixing some glaze with the body, enough to fuse it into a solid mass throughout and with a fine and smooth surface without any face glaze".2

A variety of vitreous paste known as glass-paste is mentioned by Hall as being used in the manufacture of Cretan beads in M.M. III-L.M. I times. This substance, he states, was peculiar to the Minoans, and was not used in Egypt.³ Possibly this is the same substance that Sir Arthur Evans describes as a vitrified paste, and which seems to be the

same material as that manufactured at Mohenjo-daro.4

Possible Indian intervention.

For the present, therefore, we may surmise that this vitreous paste was an Indian invention and that it very slowly spread from that country. It is a distinct advance on faience, though I doubt whether its colour was always as fine, as it has little or no surface glaze.

Glass

· Earliest glass.

As negative evidence is always useful, it is desirable to mention here that no true glass has yet been found either at Harappā or Mohenjo-daro, though the use of glass is not in reality fair removed from the process of glazing pottery. The earliest examples of true glass that have been found up to the present come from Egypt. They include an impressed Hathor head found

That small pottery objects such as beads were frequently glazed, is well known, both in early Egypt and Sumer. But technical difficulties may perhaps have prohibited its use in a larger way. For an example of a glazed pottery object of early date from Suiner, see Mackay, Report on the Excavation of the "A" Cemetery at Kish, pt. i, p. 43, pl. xviii, fig. 20.

² Arts and Crafts of Ancient Egypt, p. 116.

³ Hall, Civilization of Greece in the Bronze Age, p. 198, note.

⁴ Evans, Palace of Minos, vol. i, pp. 489-90

in a pre-Dynastic grave 1 of Sequence Date 41, or the beginning of the second civilization, and glass beads from other pre-Dynastic burials.2 The earliest specimen of glass as yet found in Mesopotamia was unearthed at Abu Shahrein by Hall, who found it in a deposit older than the third dynasty of Ur (c. 2300 B.C.).3 The glass beads discovered by Herzfeld under the town houses of Samagra 4 may be of approximately the same date; and Koldewey slaims that certain vessels of mosaic glass found in Mesopotamia date back to the period when glass was in common use in Egypt (about 1500 B.C.).5 These vessels may, however, have been imported. In Palestine glass appears in the Third Semitic Period (c. 1400-1000 B.C.), but it is thought to have been imported from Egypt.6 Glass was unknown in Crete up to Middle Minoan times, when it was sparingly used for beads at the time of the twelfth dynasty of Egypt (c. 2200–2000 B.C.).7

DECORATED CARNELIAN

Nos. 43-5 in Pl. CXLVI illustrate three beads of especial technical interest.

No. 43 (VS 2546), also illustrated in Pl. CLVII, 9, is a carnelian bead of a Beautiful translucent red colour with a design upon it in narrow white lines. These lines have been burnt into the stone, and the fine colour of the stone itself proves that it had been subjected to heat. Found in House XVII, VS Area, at a depth of 1 foot below the surface.

No. 44 (L 225) is also of red carnelian with a white line around the edge on both faces. It was found just beneath the surface of the ground in Chamber 114, Block 6, Section A, L Area.

No. 45 (SD 1198) is red carnelian covered with fine white lines. It was found in the passage west of Chamber 8 of the Bath Building, at a depth of 5 ft. 5 in. below the surface.

These decorated carnelian beads, as they can best be described, are for some reason— Rare at which cannot at present be explained-very rare at Mohenjo-daro. In fact, only four Mohenjo-daro. specimens are known from that site.8 The process by which the white lines were made to adhere so closely to the stone has already been explained in a short note that I contributed to the JRAS. Carnelian beads treated in exactly the same way were found in a series of graves of pre-Sargonic date at Kish in Mesopotamia, though comparatively few in number. 10 I am told that the process is still carried on in the south of India, 11 where, however, it is a decaying industry. 12, 13

- Petrie, Prehistoric Egypt, p. 43, (110); pl. ix, No. 47. It is suggested that itemay have been imported.
- ² Maciver and Mace, El Amrah and Abydos, 1902.
- 3 Hall, The Civilization of Greece in the Bronze Age, p. 71?
- Frankfort, Studies in Early Pottery of the Near East, No. 1, p. 61.
- 5 Koldewey, Excavations at Babylon, pp. 255-6.
- 6 Handcock, Archæology of the Holy Land, pp. 271-2.
- 7 Evans, Palace of Minos, vol. i, p. 104.
- 8 The fourth bead, which I have not yet seen, was found in the room west of chamber 46, House V, Block 2, of the HR area, at a depth of 6 feet below the surface of the ground.
 - 9 JRAS. 1925, pp. 689 sqq.
- 10 Mackay, A Sumerian Palace, pt. ii, pl. lx, Nos. 54-8 and 62-3. In particular compare No. 62 of the above with No. 44, Pl. CXLVI of this work.
- 11 Decorated carnelian beads are common on sites of the Scytho-Parthian and Kushan periods in the North-West of India.—[ED.]
- 12 Similarly decorated carnelian beads have been recovered by Sir Aurel Stein from sites between Khotan and Kan-chou. See Stein, Serindia, vol. iv, pp. 100, 117; pl. iv. The author also tells me that he has found several specimens on Chalcolithic sites of Makran and Kalat.
 - 13 The industry was carried on at Sehwan in Sind up to 35 years ago.

Design in white

IMITATION CARNELIAN

A few objects that are obviously imitations of decorated carnelian (Pl. CLVII, 8, 10, 11, and 12) have also been found at Mohenjo-daro.

Powdered steatite.

Decorated

No. 8 (SD 1998) is a rectangular bead measuring 1.5 inches long by 0.35 inch wide and thick. It is made of a fine white paste resembling powdered steatite, and is marked with red bands. The red is a thick hæmatite slip that has been carefully polished. Level, 8 feet below surface.

No. 10 (HR 1797) is the same shape as the curious shell and alabaster objects found at Mohenjo-daro (Pl. CLVII, 56 and 57; Pl. CLVI, 2-5), with a wavy surface above and below, and sometimes perforated, sometimes not. The object in question has an outside diameter of 0.95 inch, is 0.5 inch high, and the diameter of its hole is 0.43 inch. It is made of a white paste that contains a gritty material resembling quartz, and its outer surface is smoothly coated with a dark red hæmatite slip that has been carefully polished. Upon this slip somewhat irregular circles have been painted in white with three dots in the centre of each. It has also been mentioned in Chapter XXVI on Personal Ornaments, for despite the large diameter of its hole it may have been worn as a bead. Level, 6 ft. 6 in. below surface. Room 12, House VIII, Block 3, HR Area.

No. 11 (SD 1823) is a fragment of a small vase made of a white paste. Like No. 10, it also was coated with a smooth red slip upon which irregular lines in white were painted which recall the "scrabbled" markings on some of the painted pottery. From Block 4, Southern Buildings Section. Level, 8 feet below surface.

No. 12 (HR 1960) is very similar to No. 10, except that there are more dots inside its circles. It is but a fragment and its estimated outside diameter is 1.5 inches and inside diameter 0.85 inch. Its height is 0.68 inch. Found in Room 4, House VII, Block 3, HR Area, at a depth of 5 ft. 6 in. below the surface.

BRONZE CELLS FOR INLAY

In Pl. CLVIII, 3 and 7, and again in Pl. CXLIII, 9 and 10, two pieces of bronze are illustrated, whose cells were evidently intended to contain inlay. The larger piece, No. 7 (DK 2278), measures 1.55 inches across and 0.3 inch in thickness; the depth of each cell is 0.15 inch. Level, 4 ft. 6 in. below surface. Room 14, Block 2, Section B, DK Area.

No. 3 (DK 2279) is very similar except in its design, but is a smaller fragment. Level,

7 feet below surface. Room 43 Block 16, Section C, DK Area.

Inlaid materials.

In neither of these pieces is any trace of the inlay left, whether of glaze, stone, or shell. The first seems the most probable, as the inlay could be inserted in the cells in a pasty condition and fired in that position. Shell inlay would have required very careful cutting to make each piece fit closely to the cell, for which it was intended. I have not heard of inlay work of this description being found in Mesopotamia, but inlay with a stone backing was well known there in very early times. There is no reason, however, to think that the Sumerian did not sometimes also use metal for this purpose. In Egypt, moreover, especially in the Twelfth Dynasty, cloisonné work was practised extensively, the cells being formed by separate

^{.1} These last are probably unfinished.

² See ASR. 1902-3, pl. xxviii b, fig. 3, and p. 517 supra.

³ Mr. Mackay's view that these objects may have been merely beads seems hardly tenable in view of their obvious resemblance to the ring stones illustrated in Pl. XIII, 9 and 10, and Pl. XIV, 6 and 8. See pp. 61-3 supra.—[Ed.]

pieces of flat wire instead of being cast. The former process may be a development of the latter, as it was probably found that when cast the walls of the cells could not be made of sufficient thinnes's.

WORKED AGATE

Two pieces of worked agate are of considerable interest. It is not possible, however, to illustrate them adequately, as their details are so fine (Pl. CXXXIII, 19 and 20).

No. 19 (SD 872) is rectangular in shape and measures 2.7 inches long by 0.8 inch wide Mode of by 0.47 inch thick. One face shows the natural surface of the pebble; on a second it has working. been first flaked and then partially rubbed down; and the third and fourth faces were both ... carefully smoothed and polished. Level, 7 feet below surface.

No. 20 (SD 820) is roughly rectangular in shape, measuring 3.05 inches long by 0.9 inch wide by 0.55 inch thick. One side shows the natural surface of the pebble; on another side and at one end it has been flaked exceptionally finely and smoothly. On the two remaining sides the flaking has been removed by careful polishing. Level, 3 feet below surface.

For what purpose these two unfinished pieces of agate were to be used, it is difficult to say. Possibly they were intended for burnishers for metal work. On the other hand, what are undoubted burnishers have been found, and they are triangular in section (Pl. CXXX, 10, 32, and 36).1 The fineness and regularity of the flaking in both pieces, which are of Intermediate date, is extraordinary; it shows a very high level of craftsmanship.

In the working of flint, agate, and other hard siliceous stones the people of Mohenjo-daro Proficiency in were extremely proficient, as is proved by the chert weights, the two partially finished objects working hard just described, the burnishers, and some of the harder stone beads. These materials were stones. not, however, used for weapons, copper and bronze being used exclusively; and it is evident that these latter metals were both plentiful and cheap. Flint was, however, employed for ordinary domestic purposes; numbers of flakes (Pl. CXXXI, 1-16) were found in nearly every house, together with the cores from which they were struck.

TEXTILES

No textiles of any description are ordinarily preserved at Mohenjo-daro owing to the nature of the soil of that place, but adhering to the lid of the small silver vase illustrated in Pl. CXL, 3, a small piece of woven material was found which had been preserved by being impregnated with silver salts.

This fragment of cloth was submitted to Mr. James Turner, Director of the Report on cloth. Technological Research Laboratory, Bombay, for examination, who remarks in his preliminary report that "The fibre was exceedingly tender and broke under very small stresses. However, some preparations were obtained revealing the convoluted structure characteristic of cotton. All the fibres examined were completely penetrated by fungal hyphæ. The appearance of one of the convoluted fibres is shown in the accompanying photograph (Pl. CLIX, 6 and 7). As this examination has been confined to a fragment measuring out inch in one direction by 0.3 inch in the other direction, these results can only be regarded as tentative.

(1) Fibre; Cotton.

(2) Weight of fabric: 2 oz. per square yard.

Counts of warp: 34's. Counts of weft: 34's.

Ends (warp threads): 20 per inch. Pock (weft threads): 60 per inch."

1 These burnishers are of chert.—[ED.]

Cotton.

In conclusion, Mr. Turner states: "I would point out that the largest complete fragment recovered, when the paraffin wax was dissolved off, was so small that it is exceedingly difficult to attain certainty in the conclusions. However, I do not myself entertain any reasonable doubt that they are at any rate approximately complete."

doubt that they are at any rate approximately correct." 1

Egypt, which is now a great country for cotton, apparently did not produce this fibre in very early times. As far as we know at present, only flax and ramie were grown for the purpose of clothing. If cotton also had been woven in that country, it would have been noted before now, as owing to the extremely dry climate textiles, especially those from tombs, are exceptionally well preserved.

CEREALS AND FRUITS

Wheat.

Egypt.

In Chamber 60, Block 2, Section D, L Area, a quantity of wheat (L 855) was found lying on a pavement of Late date. It was probably once contained in a basket which had entirely perished. This wheat, of which there was a considerable quantity, was whole, but badly carbonized.

Species.

A sample was examined by Dr. O. Stapf, late Keeper of the Herbarium, Kew, who reports provisionally as follows:—

"The grains show a remarkably wide range in size and shape, as if they had been derived from several strains. From a preliminary examination of the grains, I should say they represent a club-wheat (Triticum compactum), but the plumpest of the grains also approach T. sphærococcum. Both species are still in cultivation in the Punjab."

Professor Percival, of Reading University, has also examined this wheat. He reports that in his opinion it is the Indian dwarf wheat (Triticum sphærococcum).

A sample of wheat from 'the SD Area was also submitted to the same authority, who states it to be probably T. sphærococcum, but not quite typical. It may belong to a form of T. compactum, Host. The latter wheat is not now found in India; it is, however, an old wheat, common in Afghanistan.

Barley.

Samples of barley from the HR Area have been identified by Professor Percival as Hordeum vulgare.

Earliest cultivation.

It is still uncertain whether barley was the first cereal to be cultivated by man. Both wheat and barley have been found in the earliest graves of Egypt. Samples of the former from early pre-Dynastic burials near Badari have been assigned to the "Emmer Group", a species that possesses fourteen chromosomes and varieties of which have been found growing wild in Syria and Transjordania.²

The wheat found at Mohenjo-daro belongs to another group with twenty-one chromosomes known s "Soft Wheats", which occur in a wild state in some parts of Persia.

Only one sample of very early wheat is known from Mesopotamia. This was found by Professor Langdon at Jemdet Nasr, but, unfortunately, there has been some controversy regarding its species.³ Wheat found in the lowest levels of Anau in Turkestan has been identified by Dr. Schellenberg as belonging to the "Soft Wheat" group.⁴

Wheat from Jemdet Nasr.

¹ Since this was written Mr. Turner has been able to examine other samples of textiles from Mohenjo-daro and has published them in Bulletin No. 17, Technological Series, No. 12, Indian Central Cotton Committee, Bombay, to which the reader is referred. See also pp. 34 and 193 supra.

² Peake, JRAI., vol. lvii (1927), p. 33.

³ The Times, 29th Jan., 3rd Feb., 7th Feb., 1927; Percival, Nature, vol. cxix, p. 280.

⁴ Pumpelly, Explorations in Turkestan (1904), vol. ii, pp. 472 and 473.

A species of barley (Hordeum vulgare) found in pre-Dynastic graves in Egypt is the same as that found at Mohenjo-daro. This barley is said to be a later species than the wild H. spontaneum, a native of Western Asia. Barley grains and glumes found adhering to a sundried brick from the lowest level of the North Kurgan at Anau have been identified as H. distichum, a species that approaches veryoclosely to the wild type of barley.

Mr. Peake, in his presidential address to the Royal Anthropological Institute,1 remarks: Asiatic origin of "It is clear that wheat, and the practice of cultivating this grain, must have reached Egypt wheat. from Asia, where the plant is native." The same is probably true also of barley, but that cereal, owing to its more hardy nature, had possibly a much wider range than wheat; it will grow and ripen under conditions that would kill the more nutritious cereal.

Some badly carbonized date seeds (VS 3627) were found in Chamber 37, House I, VS Area, showing that the date was known and presumably eaten in prehistoric Sind. The date-palm is not now a common tree in Sind; it is only sparsely grown in gardens. But in Date-palm. the Panjāb there are several localities where large groves exist, and also in Bahāwalpur State. There is, therefore, no reason to think that dates were imported from abroad in ancient times. If they had been, a likely source would have been the Bahrein Islands or other places in the Persian Gulf, such as Dilmunand Magan, which are mentioned in the earliest Sumerian inscriptions as being famous for this commodity. As far as we can see, the date was not a principal article of food in early Sind, as so few date kernels have been found at Mohenjodaro; but perhaps the damp soil of that site is responsible for their disappearance.

MEDICINES

Organic and sometimes inorganic substances also are subject to decay in the damp mounds of Mohenjo-daro, and by reason of this change they become practically indistinguishable from the soil in which they lie. Pieces of a coal-black substance, which is hard when dry and breaks with a shining black fracture, have been found in the DK and VS Areas and have long been a puzzle. This substance forms a dark-brown solution in water, which might lead one to think that it was some kind of ink.

Mr. Sana Ullah, the Archæological Chemist in India, has now succeeded in identifying Silajīt. this substance. It is not an ink, but an ancient medicine called Silājīt, which is very largely used at the present day in India as a cure for various ills. It is said to be a specific for dyspepsia, diabetes, diseases of the liver and spleen, to regulate the action of the heart, and as a good respiratory stimulant and expectorant.2

The analysis of this substance made by Dr. Hamid is given in Appendix I (p. 690)? At the present day the name silājīt is given to two substances. One is white in colour and is a more or less pure native aluminium sulphate. The second is called black silajit and is of quite a different nature. It exudes from the rocks, and, though it resembles a bituminous alum ore, there is vegetable matter mixed with it. It is this latter substance

Analysis.

¹ Journ. Roy. Anthrop. Inst., vol., lvii, 1927.

² See Dr. Hem Chandra Sen in Indian Medical Record, '14th and 21st May, 1902.

that has been found at Mohenjo-daro. The localities in which it occurs are the lower, central, and upper ranges of the Himālayas, and it is brought down by various hill tribes for sale in

the plains.

Silājīt may, of course, occur in other parts of the world. Prominence is given to it in this chapter, as it may have been exported anciently; and it may, therefore, be found on other sites of the Near and Middle East. If this be so, it may help us in tracing further trade connections with ancient India. This sample was found in the space south of Chamber 2, Block 1, Section C, DK Area, at a depth of 2 ft. 6 in. below the surface of the ground.

CHAPTER XXIX

SYSTEM OF WEIGHTS AT MOHENJO-DARO 1

MONGST the objects excavated at both Mohenjo-daro and Harappā are a large number of small rectangular blocks, mostly of a tawny or light grey banded chert, but also of other hard rocks such as gneiss. In one or two cases their form is cylindrical, but for the most part it is cubical. The blocks are well finished and polished, and are generally in a good state of preservation. None bears any inscription or mark indicating a value (Pl. CXXX, 25, 26, and 34; Pl. CXXXI, 20-35).

The results obtained from weighing these blocks show conclusively that they are weights

belonging to a definite system, which is given in Table I.

In endeavouring to arrive at the most probable value of the unit, the only assumption I have made is that no one particular weight is more accurate than the rest, and that the probable percentage of error is the same for all. The loss due to chipping or wear of the edges in the specimens selected can rarely exceed 3 parts in 1,000, and in most cases is much less; the error due to this is therefore negligible in comparison with the variation of the different specimens of the same weight, which may evidently amount to as much as 10 per cent, though the mean deviation in a group hardly ever exceeds 2 per cent.

The assumption made by some metrologists that any given heavy weight, which happens to be in a good state of preservation and which, artistically speaking, has been made with care, can be taken as an accurate standard and that other weights can be derived from it as submultiples, is one which presupposes a knowledge of modern scientific method which

is not justified by the evidence, particularly in the earlier periods.

The hypothesis of Ridgeway—a very reasonable one—that originally weighing was restricted to the more precious objects which would be bartered in small quantity, would lead us to expect the smaller weights to be the more accurate, and the evidence adduced in the tables shows much the same percentage consistency throughout the whole scale. The method of arriving at the most probable value of the unit was as follows: a casual inspection of the weights 2 showed that, with a few exceptions which were omitted, the weights fell into a series of groups which were in simple numerical ratios with one another. Giving the smallest the arbitrary value of unity, the others are in simple ratios, 2, 4, 8, etc. The mean weight of each group is divided by this ratio and multiplied by the number of specimens. The products for all the groups are added together and divided by the total number of specimens. This gives a mean value for the group of smallest weight in which every specimen weighed is allowed equal importance. The mean values for all the other groups are then obtained by multiplying

In the Annual Report of the Archæological Department for 1925-6, p. 92, Mr. Mackay stated that a large range of weights had been examined by the Archæological Chemist with the object of ascertaining whether in their ratios they agree with the metrological systems of other parts of the Ancient East. I should like to take this opportunity of explaining that it was Mr. Hemmy and not the Archæological Chemist who was the first to work out the system of these weights at Mohenjo-daro.—[Ed.]

² The lists of weights are given at pp. 596-8. See also pp. 461-4.

this mean value by the ratio already found. In this way we arrive at the calculated values, shown in column (7) in Table I.

TABLE I.- WEIGHTS AT MOHENJO-DARO

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
Designation.	No. of specimens.	Mean weight observed.	Mean devia- tion.	c Limits.	Ratio.	Calculated value.	Difference between Cols. 3 and 7.	Remarks.
N L K J H G F E D C B A	1 2 1 6 6 26 32 22 9 9 5 I	1375 gm. 272.95 174.5 135.97 54.21 27.29 13.79 6.82 3.40 2.28 1.77 .87	 	270·70-275·20	1600 320 200 160 64 32 16 8 4 1 × 8	1370 gm. 273.92 171.2 136.96 54.78 27.39 13.70 6.85 3.42 2.28 1.71 .856	597 3·399 57 10 .09 03 02 .00 .06	One weight in Class L is a corrected value. = 211.4 g.t.1

Out of a total of 120 weights selected for their good condition, only seven do not fall into the above table, and curiously enough these form another series, although the number is too small to base any important deduction upon it, vide Table IV.

The weights found at Harappa were treated in the same way, and the results are shown in Table II.

TABLE II.—WEIGHTS AT HARAPPA

(1)	(2)	(5)	(4)	(5)	(6)	(7)	(8)	(9)
Designa-	No. of specimens.	Mean weight observed.	Mean devia- tion.	Limits.	Ratio.	Calculated value.	Difference between Cols. 3 and 7.	Remarks.
N M L K J H G F E D B	1 1 0 0 1 1 13 9 4 3 1	1375 gm. 546·7 — 135·86 54·32 27·55 13·86 6·84 3·44 1·70		26·79-28·64, 13·62-14·94 6·65- 6·98 3·39- 3·49	1600 640 — 160 64 32 16 8 4	1376 gm. 550.4 — 137.60 55.04 27.52 13.76 6.88 3.44 1.72	- I - 3·7 1·74 - ·72 · 03 · 10 - ·04 · 0002	M and N are corrected values.

¹ To avoid the confusion often found between the abbreviations for grams and grains, gm. is used for grams and g.t. for grains troy.

The above table represents thirty-four out of thirty-nine selected weights. The exceptions will be considered later.

This table shows an exactly similar series of weights to the former, and the mean value for unit weight A is 860, which is practically identical with the value 856 found for the unit weight at Mohenjo-daro. There is, therefore, no local variation between the weights in the two places, although 500 miles apart. We may, therefore, combine the results in the two tables and obtain Table III.

TABLE III.—WEIGHTS FOUND AT BOTH MOHENJO-DARO AND HARAPPA

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
Designa- tion.	No. of specimens.	Mean weight observed.	Mean devia- tion.	Limits.	Ratio.	Calculated value.	Difference between Cols. 3 and 7:	Remarks.
N	2	1375 gm.	_	• 1375	1600	1371 gm.	4	
M	I	546.7		_	640	548.5	- 1.8	
2	2	272.9	2.25	270.7 -275.2	320	274.2	-1.3	
2 K	I	174.5	_	_	200	171.4	3.1	_
	7	135.95	.77	134.59-137.81	160	137-1	- I.I	-
H	7	54:23	.23	53.81-54.50	64	54.84	61	
G	39	27.38		26.79-29.00	32	27.42	- ·04	
F	41	13.81	·33 ·26	13.37- 14.94	16	13.71	.10	= 211.5 g.t.
E	26	6.82	.09	6.31- 7.27	8	6.86	04	= 105.8 g.t.
D	12	3.41	306	3.24- 3.21	4	3.43	02	_
J H G F E D C B	2	2.28	.04	2.24- 2.33	13×8	5.58	.00	= 35·3 g.t.
В	6	1.76	.06	1.69- 1.86	2	1.71	.05	
A	I	.87	_		I	-857	.01	= 13.2 g.t.

In the above table are represented 147 out of 159 specimens which were considered in good enough condition to furnish reliable weights. Only three have been corrected, and these were large weights, the original form of which could readily be calculated from their dimensions.

The sequence of ratios is striking. Omitting group C, it runs as follows:

1, 2, 4, 8, 16, 32, 64, 160, 200, 320, 640, 1,600.

There is not a sign here of the sexagesimal system; all the ratios are binary or decimal (with the exception of the two weights in group C, which weigh one-third of those in

group E).

There are certain exceptional weights found in both places. It appears more than a coincidence that the seven found at Mohenjo-daro should be themselves in the simple ratios 1, 2, 3, 4, 24, 48 (vide Table IV), but the number of specimens is too small to build much upon.

TABLE IV.—EXCEPTIONAL WEIGHTS AT MOHENJO-DARO

(1)	(2)	(3)	(4)	(5)	(6)
Designation?	No. of specimens.	Mean value observed.	Ratio.	Label.	Remarks.
U	ı	47·30 24·50	48	DK 3176 DK 1411	-
S	2	3.92	4	VS 3058 DK 220	= 3.93 gms.
R Q P	I I	3.03 2.07 .98	3 2 I	DK 3183 DK 2106 VS 332	(3.92 gm. = 60.6 g.t.)

At Harappā No. 266, weighing 49.73 gm. was made of gneiss, but though the faces were in a state of high polish, the edges were rounded. It is probably a worn member of Group H: No. 1,184, weighing 3.96, is slightly chipped and, therefore, should weigh slightly above 4. It cannot, therefore, belong to Group D, but appears to be a member of Group S in Table IV. No. 3,556, weighing 3.12 gm., is of gneiss, and has its edges rounded. This is probably due to wear, and this weight probably belongs to Group D. B (g) 23, weighing 1.255, made of chert, is in excellent condition. It cannot be placed with any group.

A comparison was made with the weights found at different times and places in Iraq

and at Susa.

Comparison with the Babylonian system. The best collection of data available was that in the Memoir of M. Soutzo, in vol. xii of the Délégation en Perse. For a just comparison it was desirable to make an analysis of these weights in the same manner as above described. Weights described as being broken or in poor condition were omitted, whilst those of doubtful attribution or definitely aberrant are considered separately.

The weights belonging to the Babylonian light mina system are considered together in Table V; in Table VI are given those definitely marked as belonging to the Assyrian heavy mina system, and in Table VII those found at Susa which belong to the Babylonian system. As some of the smaller weights did not appear to be weighed to the nearest decigram, weights less than half a shekel were not taken into account in calculating the mean value of the unit from all the weights.

Table V.-LIGHT BABYLONIAN SYSTEM

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
Designation.	No. of specimens.	Mean weight observed.	Mean devia- tion.	Limits.	Ratio.	Calculated value.	Difference between Cols. 3 and 7.	Remarks.
Talent .	I	29680	_	. –	28800	30240	— 560	Weights in
30 Minas .	I	14975	_		14400	15120	- 145	grams.
jo minas .	2 0		44	2422-2511	2400	2520	- 54	_
	ī	1492	TT	-	1440	1512	- 20	
		970	13	946-995	960	1008	- 38	
Mina	3 6	486	16	468-510	480	504	- 18	_
	6	276	2	240-248	240	2 252	- 6	_
	5	170	4	164-175	160	168	- 2	_
	5	82.8	1.5	80.2-85.5	80	84.0	— I·2	_
	7	41.8	0.9	40-43.7	40	42.0	2	-
	4	16.91	'44	16.45-17.70	16	16.80	.11	0 0-
Shekel	II	8.31	.26	8-9	8	8.40	09	= 129.6 g.t.
	. 16	4.37	·2 I	4-4.80	4	4.20	.17	-
	5	2.15	.10	2-2-30	2	2.10	05	_
B Shekel .	4	.96	.09	-80-1-10	0 1	1.05	09	_

Mean value of Shekel = 8.40 gms. = 129.6 g.t.

TABLE VI.—HEAVY ASSYRIAN SYSTEM

(1)	*(2)	(3)	(4)	(3)	(6)	(7)	(8)	(9)
Designation.	No. of specimens.	Mean weight observed.	Mean devia- tion.	Limits.	Ratio.	Calculated value.	Difference between Cols. 3 and 7.	Remarks.
Talent.	r	60303	_	_	7200	60106	197	_
15 Minas .	I	14933	-	_	1800	15026	- 93	_
,5 ,	r	5043	-	-	600	5009	• 34	_
3 ,, .	I	2865			360	3005	- 140	_
2 ,, +.	2	1962	30	1931-1992	240	2004	-0 42	_
I Mina .	3	990	31	955-1037	120	1002	— I2	_
3 Minas .	ī	666.	_		80	668	- 2	_
Mina .	© I	237			30	250	- 13	_
1 ,	I	198	_		24	200	- 2	-
1 , .	I	178		_	20	167	II	_
1 ,,	T	128	_	_	15	125 .	.3	_
3 Shekels .	ī	52.4	_		6	50.1	2.3	_
2 -,,	ī	36			4	33.4	2.6	_

Mean half large Shekel = 8.35 gm. = 128.89 g.t.

TABLE VII.-WEIGHTS ON BABYLONIAN SYSTEM FOUND AT SUSA

(1)	(2)	(3)	(4)	(5)	(6)	•(7)	(8)	(9)
Designation.	No. of specimens.	Mean weight observed.	Mean devia- tion.	Limits.	Ratio.	Calculated value.	Difference between Cols. 3 and 7.	Remarks.
Mina . Shekel Double small Mina Half shekel . Small Mina	1 3 2 1 2 6 3 3 6 9 2 1 2 8 2 8 2 9 6	10045 4969 2496 2020 1007 504 420 342 257 1165 122 82.4 41.3 33.5 17.26 8.45 5.50	36 27 14 6 10 4 2 5 2 2.7 .8 .5 .46 .32 .10	4985-5007 2469-2523 — 994 -1021 495-519 405-429 335-345 252-260 158-176 121-124 76-86 39-43 33-34 16·50-18 8-9 5·25-5·75	9600 4800 2400 1920 960 480 400 320 240 160 120 80 40 32 16 8 40 32 40 40 40 40 40 40 40 40 40 40	10044 5022 2511 2009 1004 502 418 335 251 167 126 83.7 41.8 33.5 16.74 8.37 5.58 4.18	7 - 53 - 15 11 3 2 2 7 6 - 2 - 4 - 1·3 - ·5 ·00 ·52 ·08 - ·08 - ·01 - ·02	= 129·2 g.t.
Small Mina.	6 1 3	2.77	•16	• 2·40-3·10 ·85-1	1 × 8 2 I	2·79 2·09 1·05	- ·09 - ·10	

Calculated from the mean of all weights not less than a half shekel, the shekel = 8.37 gms. = 129.2 g.t.

It is clear that there is no special local variation in the shekel at Susa and that it is identical with that found in Iraq. Combining the results of Tables V, VI, and VII, we arrive at the result that the Babylonian shekel 8.38 gm. = 129.3 g.t. Comparing column (5) in Table III with the corresponding columns in these tables, we see that there is no overlapping anywhere except that one value of the 18th shekel at Susa, .85, and one from Iraq; .80, are less than the smallest weight, .87, found at Mohenjo-daro, whilst Class C on the Mohenjo-daro system more or less overlaps the quarter shekel. The same succession of ratios from 1 to 32 of the actual weights used in the systems is worthy of note.

There are also certain approximations between the aberrant Indus Valley weights and

those on the Babylonian system. These are shown in Table VIII.

TABLE VIII.—APPROXIMATIONS OF INDUS VALLEY WEIGHTS TO THE BABYLONIAN SYSTEM

Hillah	Babylonian System.					Corresponding Indus Valley Weight.			
Hillah . — L. .95 \$\frac{1}{8}\$ Shekel P VS 332 .98 — Niffer . .959 C. I · 10 \$\frac{1}{8}\$ Shekel — <th></th> <th></th> <th></th> <th>by Soutzo.</th> <th></th> <th></th> <th></th> <th>Limits.</th>				by Soutzo.				Limits.	
Niffer	Hillah	— L.			P		.98	_	
Susa	Niffer	959 C.			_	-		_	
""		— C.	I	,,	-	_	_	_	
""" 51 2 \$\frac{1}{4}\$ Shekel Q DK 2106 2.07 — Susa 12994 2.90 Small Mina R DK 3183 3.03 — Many weights from 3.80 to 4.10 \$\frac{1}{2}\$ Shekel S DK 220 3.93 — Niffer — C. 2.230 \$\frac{3}{4}\$ Shekel C — 2.28 2.24-2	Susa	55	I	,,	_	-		-	
Susa	,,	12860	I		_		_	_	
Susa	,,		2	1 Shekel	Q	DK 2106	2.07		
Many weights from 3.80 to 4.10 \frac{1}{2} \text{Shekel} \text{ S} \text{DK} \text{220} \frac{3.93}{2.28} \frac{2.24-2}{2.24-2}	-						_	_	
Many weights from 3.80 to 4.10 12 Shekel S DK 220 3.93	Susa			Small Mina	R	DK 3183	3.03		
, C. · 2.20		50		1 01 1 1			_	_	
,, C. · 2.20					S	DK 220			
	Nimer		The second secon	2 Shekel	C		2.58	2.24-5.33	
	,			"	-	_			
" B.M. 2·19 "		— в.м.	2.19	"	-	0 -			

The locality of discovery is given where stated, also the catalogue number in the Museum where the specimen is kept. (L = Louvre, C = Constantinople Museum, B.M. = British Museum.)

The weights of doubtful attribution or definitely aberrant found at Susa as well as in várious places in Iraq have been tabulated by M. Soutzo. Omitting those which are stated to be damaged or in bad condition, we observe in the list fifty-three exceptional weights, of which thirty-two come from Susa. Quite a number of these approximate to weights found in the Indus Valley, and Table IX gives a list of these approximations. No Indian weight corresponding to the last item has actually been found, but, as the double of N would form a reasonable part of the system, it has been included.

Table IX.—Approximations of Aberrant Weights found in Iraq and Susa to Indus
Valley Weights

Iraq and Susa.					Indus Valley.			
Locality.	Cat. No.	Weight.	Attribution by Soutzo.	Group.	Cat. No.	Mean Weight.	Limits.	
Susa	— C. 12859 959 C. 14209 40 14206 32 959 C. 28 1988 C. 37 91437 B.M. 1 10 7895 13820	.80 .85 1.25 1.70 1.60 3.50 3.45 3.45 3.36 6.80 12.40 12.25 12.70 13.20 13 14.70 29 47 138.7 268 272 271 538 2769	\$ Shekel """ Shekel (?) Shekels (?) Shekels (?) Mina (?) Mina (?) Minas (?)	A - B D - E F - G U J L - M 2 N	DK 140 B(g) 23	· ·87 · ·1·255 1·76 — 3·41 — — 6·82 13·81 — — 27·38 47·30 135·9 272·9 — 546·7 (2750)	1·69-1·86 3·24-3·51	

We have here twenty-four, or omitting the two which coincide with aberrant Indian weights, twenty-two reasonably close coincidences of aberrant Babylonian weights (of which fourteen come from Susa) with the weights of the Indus Valley system. It may be noted that the greatest number of coincidences, six, and these nearly all from Susa, are with Group F, which is the group of which the greatest number of specimens have been collected. Nevertheless, I do not attach a great deal of importance to these coincidences. The proportional variation of weights in Susa and Iraq is much greater than at Mohenjo-daro, whilst the shapes are characteristically different. Those found in the west are either duckshaped or ellipsoidal, whilst those from India are all rectangular blocks.

It is a matter of interest to endeavour to discover whether the Indus Valley system of

weights can be connected up with any particular grain.

It has been clearly shown, as in Ridgeway's Origin of Currency and Weight Standards, that the Babylonian system is based on the grain of wheat. The weight (= .95 gm.) found at Hillah, marked 22½ grains, gives a value for the grain = .042, but the fact that it is marked with a fraction shows that it has been derived from a higher multiple and that it is intended to be one-eighth of a shekel. This gives 180 grains to the shekel, a likely enough ratio on the sexagesimal system, and taking the 1-180th part of the mean value of the shekel, we arrive at the value .047 for the grain, which is practically the same as that of the wheat grain, .048 gm., which is three-quarters of the barley corn or grain troy, .064 gm.

Starting from the mean value of Group E (= 6.86 gm.), we may divide by various round numbers which may seem likely or possible. The results are as follows:—

Dividing by 256, dividend = .027

" 200, " = .034

" 180, " = .038

" 150, " = .046

" 128, " = .054

" 100, " = .069

" 80, " = .086

" 60, " = .114

The values given in Ridgeway's book for various grains used in weighing are as follows:

Rice grain = ·036 Wheat = ·048 Barley = ·064 Ratti = ·113

The coincidence between the ratti and the dividend by 60 is tempting, but as there is no evidence in favour of a sexagesimal system, I am more inclined to prefer the relation between the rice grain and the dividend by 200.

A system of weights has been therefore discovered which is identical in Mohenjo-daro and Harappā. These weights are with hardly an exception uniform in shape, a rectangular block, cubical in the smaller sizes, and in the great majority of cases of the same material—a hard chert. They are well finished with polished faces and occasionally with bevelled edges. They are made with much greater accuracy and consistency than those of Susa and Iraq.

The system is binary in the smaller weights and then decimal, the succession of weights being in the ratios 1, 2, $\frac{1}{3} \times 8$, 4, 8, 16, 32, 64, 160, 200, 320, 640, 1,600. There is no evidence of a sexagesimal system, but between 1 and 32 we find a similar succession of ratios at Susa. The most frequently discovered weight, of ratio 16, has a mean value 13.71 gm. = 211.5 g.t., which shows no relation to the Babylonian shekel or its double.

No inscription nor mark of value has been found on any of the weights. It is therefore probable (unless marks were originally painted on) that commercial transactions took place between classes of people who were completely ignorant of reading and writing.

APPENDIX I.-WEIGHTS AT MOHENJO-DARO

	Cat. No.	Weight. I	Designation, etc.	Ca	t. No.	Weight.	Designation, etc.
	HR 4479 HR 2390	1375 gm. 266.06	N.	DK		136.5	J. Limits
		corner knocked off Corrected to 275.20	L.	HF HF DK	19	135.28 134.59 136.25	134·59–137·81 Cylindrical.
	S 2678 K 1910	270·7 267·55		DK DK		137·81 53·81	Н.
		Slightly chipped omitted.			1636	54·50	1 Limits 53.81-54.50
"v	S 35	174.5	K.	HP	4292	54.45	

I Sir Flinders Petrie has pointed out that this value comes within the range of the beqa. Egyptian weights of various designations, however, can be found of almost any value between 7.5 gm. and 14.25 gm., so that equality with one or another is more likely than not to occur; but the fact that the beqa is one of the earliest Egyptian weights may give some significance to the coincidence.

Conclusion.

SYSTEM OF WEIGHTS AT MOHENJO-DARO

Cat. No.	Weight.	Designation, etc.	Cat. No.	Weight.	Designation, etc.
HR 46P2 .	54.05	Н. •	HR 3799	13.65	F
HR 4621	54.45		L 208	13.37	
DK 3176	47:30	U.	VS 1737	14.46	
DK 2767	27021	G.	VS 2083	13.62	
DK 1007	27.22	Limits •	VS 2615	13.78	
VS 2986	27.12	26085-29.00	VS 2074	13.85	
DK 1934	26.93	20 0) 2)	VS 2577	14.90	
DK 183	26.85		VS 2281	13.70	
HR 340	26.88		VS .1799	13.62	
HR 1683	27.50		VS 2879	•6.87	E.
HR 2708	27.10		DK 1439	6-85	Limits
VS 3493	27.30		DK 529	6.83	6.31-7.27
HR 154	27.20		DK 1643	6.82	
HR 4535	27.05		HR 2502	6.79	•
VS 3451	27.25		HR 3873	6.92	
HR 2045	26.92	•	DK 643	6.80	
HR 2207	27.30		DK 535	6.31	
HR 5563	27.75		DK 326	6.73	
HR 4941	27.45		DK 1211	6.84	
L 648	29.00		HR 5800	6.76	
VS 3267	27.40		HR 3049	6.78	
HR 5608	27.10		HR 4499	6.83	
VS 3184	27.10	•	HR 3713	6.91	
HR 5654	27.22		HR 2852	6.89	
VS 1006	27.35		VS 3465	6.84	
VS 1740	27.85		HR 4445	6.87	
VS 1879	27.15		HR 5602	6.66	
VS 1148	27.05		VS 1281	7.27	
VS 2172	27.25		DK 1730	6.77	
DK 1411	24.50	T.	VS 2259	6.76	
Unmarked	13.24	F	VS	6.87	
HR 2356	13.67	Limits	DK 220	3.93	S.
HR 2636	13.58	13.37-14.90	VS 3058	3.90	
HR 2046	13.62		DK 1428	• 3.44	D.
C 3262	13.79		DK 232	3.54	Limits
DK 1269	13.62		• DK 787	3:39	3.24-3.59
DK 1572	13.70		HR 2191	3.44	
DK 739	13.50		HR 4284	-2:43	
DK 197	13.60		HR 3587	3.38	
DK 1207	13.64		HR 3029	• 3.30	
DK 2793	13.61		VS 2270	3.48	
DK 1872	13.91		VS 929	3.21	D
DK 2250	• 13.69		HR 3183	3.03	R. C.
DK 813	14.59		HR 4331	2.33	C.
· DK 2012	13.67		HR 3079	3.54	0
DK 909	13.49		DK 2106	2.07	Q.
HS 975	13.59		HR 3906	1.86	B. Limits
HR 4477	14.35		HR 1872	1.81	
HR 4460	13.95	•	VS 340	1.69	1.69-1.86
HR 5608	13.70		VS 2734	1.70	
HR 4388	13.62		VS 3495	1.79	P.
HR 4579	13.60	•	VS 332	0.98	
HR 5602	14.41		. , DK 140	0.87	. A.
To the second second	Britan Britan			• •	

APPENDIX II .- LIST OF WEIGHTS FROM HARAPTA

Gat. No.	Weight.	Designation, etc.	Cat. No.	Weight.	Designation, etc.
1642 1	1261 gm.	Poor condition.	3561	27.43	G. Gneiss.
	Corrected to	Cherty lime-	525	26.79	Grey slate, fair.
	1375	stone. N.	120	25.31	? Grey slate, fair.
421 1	492	Limestone; worn	1 1074	13.87	F. Chert.
	Corrected to	at edges only.	874	13.67	
	546.7	M.	120	13.62	
771	135.86	J. Chert; corners,	120	13.71	0
	, ,	slightly	1173	13.81	
	0	chipped.	120	13.90	
771	54.32	H. Chert; corners	278	14.94	
		good.	1575	13.64	
266	49.73	? Gneiss; edges	185	13.62	Brown steatite.
		worn.	B (g) 22	6.90	E. Chert.
3663	28.21	G. Chert.	817	6.65	
1356	27.28	"	2585	6.82	
1356	27.68	,,	2928	6.98	
855	27.30	"	1184	3.96	S. Chert, chipped.
2550	27.35	,,	1708	3.49	D. Chert.
B (g) 14	28.62	"	120	3.39	
A(f) 284	27.40	"	A (e) 155	3.43	Steatite.
A (e) 155	27.06	,,	3556	3.12	? Gneiss, edges
A 757	27.01	Gneiss.		0	rounded.
854	27.33	Chert.	3831	1.70	B. Chert.
645	28.64	"	B (g) 23	1.255	? Chert, good.

A number of objects of different shapes were weighed, but furnished no evidence of being weights. One (No. 78), however, may be mentioned as a possible exception. It was of sugar-loaf form, carefully shaped, with two round holes pierced near the top and meeting in the middle, through which a rope could be reeved or the weight lifted by the fingers. The material was grey limestone and the weight was 7,900 gms, which bears no obvious relation to the system worked out above. It was found at Nal, in Balūchistan.

¹ Recalculated from density determination and measurement of dimensions.

CHAPTER XXX

HUMAN REMAINS

Introduction

HE human remains that have up to the present time been excavated at Condition of Mohenjo-daro appear to belong to widely separated periods of time. The full bones and account of the excavations and of the finding of the various remains have been method of given elsewhere, and we have, therefore, in the following account confined our remarks preservation. almost entirely to the consideration of the anatomical features of the various skeletons and skulls that have been brought to light. These remains have very kindly been entrusted to us for the purpose of examination and report by Sir John Marshall, to whom we tender our sincere thanks. Of the various skeletons that have been found, No. 1 is of comparatively recent date, but the majority of the others are of considerable antiquity. In the majority of cases the bones were extremely fragile, and in their general appearance and conditions very closely resembled the human remains that were excavated at Nal in Baluchistan,1 and also certain other bones which were brought back by Sir Aurel Stein from the Makran region and were also entrusted to us for examination. Owing to the nature of the soil in which these remains have been lying, the bones were strongly impregnated with saltpetre, and, as a result, decay and disintegration of the bones set in at once, and proceed with great rapidity the moment the remains are exposed. In most cases the bones were so delicate that it was found impossible to handle them for the purpose of examination or of taking measurements, until they had been treated with a solution of shellac dissolved in pure alcohol; owing to the amount of saltpetre with which the bones were impregnated, it was found necessary to repeat the process on several occasions, so that the shellac might become thoroughly distributed throughout the whole thickness of the bone, and, in addition, form a complete coating over the whole surface. Unless this coating is complete, it is hand that, owing to the seasonal changes in the climate, the saltpetre tends to crystallize out and splits the bone in much the same manner as it causes flaking in the exposed brickwork of the buildings. In the majority of the skulls their condition was so delicate that we felt it to be undesirable to attempt to remove the impacted earth from the cranial cavity, especially in those cases in which parts of the skull were missing; we were thus forced to impregnate the whole mass with the shellac solution and then treat the objects as if they were fossils.

The bones themselves, prior to treatment with shellac, were usually of a pale pink or fawn colour, possibly due to the presence of iron in the soil; in this respect they closely agree

¹ Sewell and Guha, "Report on the Bones excavated at Nal": Mem. Archaeol. Survey of India, No. 35: Excavations in Baluchistan, Appendix V, 1929.

with the remains from Nal. Similarly, the general character of the bones indicates that in the present case also there have been considerable changes in the chemical composition of the bones; 'the organic matrix has long since completely disappeared, and the salts themselves have changed.1

Number of skeletons and circumstances of their finding and examination.

The total number of individuals represented in the collection is twenty-six, and of these twenty-two were the remains of complete bodies, while three are represented by the skulls alone. Seventeen of the skeletons were excavated by Mr. Hargreaves during Sir John Marshall's excavations of 1925-6, and he has very kindly supplied us with a copy of the field notes that he made at the time that the excavation was being carried out. In compiling the

following report we have made free use of these notes.

The skeletons or skulls are numbered in the order in which they were discovered. Of the first seventeen to be unearthed, numbers I to 4 were in all probability true burials; numbers 5 to 16 were found lying together in a small room, and appear to be "more like evidence of a tragedy than a form of burial, for the intermingling of the skeletons points to simultaneous interment" (Hargreaves). In addition to this group, a further group of six skeletons was discovered at another site, this time in one of the streets; and this, too, seems to have been the result of a tragedy.² This second group was discovered in the 1925-6 season, and one of us (B. S. G.) immediately proceeded to Mohenjo-daro, and, as it was decided to leave the skeletons in situ, treated them with shellac solution in the hope that they might be preserved; the following year it was decided to remove them, and in March one of us (R. B. S. S.) proceeded to the site, but it was found that, owing to exposure and in spite of the shellac treatment, the skeletons had deteriorated to such an extent that it was impossible to save more than a few fragments. A few additional measurements were taken, and these are given in the report below. The measurements taken by us on the skulls were taken according to the Frankfort Agreement. In the case of all additional measurements the technique followed has been described in the body of the text or full reference has been given.

Measurements

Included in Mr. Hargreaves' notes there are a number of measurements taken on the taken by Camp first group of skeletons, while still in situ, by the Camp Medical Officer. Mr. Hargreaves Medical Officer. remarks "having no instruments could not take correct measurements of the bones, but the young Indian Camp-Medical Officer did his best with an ordinary tape measure". We have converted these measurements from inches to millimetres, and we give them in the following account, as, although possibly not absolutely correct, they give certain indications regarding the stature and physique of the individuals. In calculating the living height of the various individuals concerned, we have made use of the formulæ given by Manouvrier 3 and Pearson,4 but in certain cases the result is not very satisfactory.

Skeleton No. 1

Description of skeletons.

This is a complete or nearly complete skeleton, and is in an excellent state of preservation. The body lay on its left side; the arms were bent and appear to have been placed so that the left hand was under the head and the right in front of the face. From the general condition of the bones and taking into consideration the rapidity with which bones

1 Sewell and Guha, loc. cit., p. 60.

2 For further particulars regarding these skeletons, see pp. 79-81, 107-8, 184-6, and 222-3.

Manouvrier, La détermination de la taille après les grandes os des membres, Mem. de la Soc. d'Anthropol. de Paris, 1893.

4 Pearson, Karl, "Mathematical Contributions to the Theory of Evolution, V: On the Reconstruction of the Stature of Prehistoric Races": Phil. Trans. Roy. Soc. London, vol. excii, p. 169.

become changed, especially in such a locality as Mohenjo-daro, where the effect of the saltpetre in the soil is remarkably destructive, it seems probable that this skeleton is at the most only a few hundred years old, if, indeed, as old as that.

Apart from the position in which the skeleton appears to have been lying, namely in the "embryonic" position, and on its left side, a position characteristic of the early burials of the "Mediterranean" race, another very interesting discovery, made during the process of cleaning away the adhering earth in which the skull was embedded, was the presence of a flat stone close up against the basis cranii at the back of the posterior nares. We have previously, in our report on the human remains excavated at Nal in Baluchistan, called attention to the presence in the skull from that site of a flat stone, that appeared to be an artifact, in the same position, namely behind the posterior nares, and we there discussed at some length the possibility of such an object having been deliberately placed there, either just before or after death, as a part of the death-ceremonies of these early inhabitants of India. A similar find in the present instance is particularly interesting, and, if part of the death-ceremony, would, in combination with the embryonic position of the body, indicate that certain death ceremonies must have persisted in this area for several thousand years. Associated with this skull were a number of other parts of the skeleton. Unfortunately, neither femur was intact; but there were present both humeri, both radii, and a tibia and fibula. We have, therefore, a fairly satisfactory basis for the estimation of the living height of the individual. In the following table we have given the heights as calculated from Pearson's tables and from Manouvrier's :-

	3			Length in	Calculated living height		
	Bone.			mm.	Pearson.	Manouvrier.	
(6)	Humerus Right .			296	1529.934	1558.4	
(6)	" Left .		100	294	1524.426	1553.4	
(c)	Tibia (with spine).			366	1588-110	-	
, ,	" (without spine)			358	1589.756	1624.0	
(d)	Radius			224	1561.072	1595.0	
(g)	H+R			_	1534 - 27	-	
(h)	H and R			_	1532.656	- 10	
` '	Fibula			348	_	1608.6	

The letters in the first column refer to the particular formula given by Pearson. From the resulting estimates we find that there is a variation in the calculated living height between 1524.426 and 1589.756 according to Pearson's formulæ, and between 1553.4 and 1624.0 according to Manouvrier, differences of 65.33 and 70.6 respectively. The average living heights as given by the two methods are 1551.46 and 1587.88 mm. If we adopt the former figure, we can then calculate the proportional length of the two parts of the upper extremity, the upper and lower arms, with regard to the total height of the body. The figures reached are as follows, and for the purpose of comparison we have also given certain other figures, taken from Martin,² of the proportional lengths in the living persons of those races that seem most nearly to agree:—

				Length proportional to the living height of		
	Race.			Humerus or Upper arm.		
				Per cent.	Per cent.	
Mohenjo-daro	(skeleton	1) 9		19.01	14.43	
Polish Jew ?	•			18.90	14.40	
Badener ? .				19.10	14.40	

¹ Sewell and Guha, loc. cit., p. 61.

² Martin, Rudolf, Lehrbuch der Anthropologie, 2nd ed., vol. ii, pp. 391-3, Jena, 1928.

Skeleton No. 2

This skeleton lay with the head towards the east and the face to the south. As in the case of No. 1, the body lay on its left side and the arms were bent so that the left hand was beneath the head and the right in front of the face. With the exception of the head of the right femur, which was still in the acetabulum, the bones of the lower extremities were missing. The skull is badly broken and a large part of the facial region is absent.

Skeleton No. 3 (13b)

This skeleton is represented by the skull only.

Skeleton No. 4

No portion of this skeleton has been received by us.

As mentioned above, Skeletons Nos. 5-16 all lay together in a group.

Skeleton No. 5

The body lay face downwards with the head towards the west and the legs of Skeleton No. 6 passed across the lumbar region. The skull was badly smashed and is too much broken to enable us to give any details of its characters.

Skeleton No. 6

This lay on its left side, with the head towards the south-west. The left arm was extended by the side and the right arm flexed, with the hand over the abdominal region; both legs were somewhat flexed. The skull is in a good state of preservation. Mr. Hargreaves' notes give the following details regarding the proportions of the limb bones:—

From these measurements we can roughly calculate the total height of the individual from the formulæ given by Pearson and Manouvrier respectively. The results thus obtained are given below in tabular form and we have again used the same letters for Pearson's formulæ that he makes use of in his paper:—

After, Peorson.	After Manouvrier.	Calculated		
	Length.	height.		
(a) 1644·02 mm.				
(b) 1725·10 ,,				
(c) 1646·75 "	Femur . 442 mm.	1658 mm.		
(d) 1601·77 "	Tibia . 362 ,,	1654 "		
(f) 1644.63 "	Fibula '. 367 ,,	1675 "		
(4) 1716.83 "	Humerus . 352 ,,	1754 "		
(i) 1687·29 "	Radius . 227 ,,	1616 "		
(k) 1679·99 "	Ulna 245 ,,	1605 "		

The calculated living height thus ranges from 1601.77 to 1725.10 according to Pearson, and from 1605 to 1754 according to Manouvrier. In each case the result obtained by calculation from the length of the humerus is much greater than in the case of the other bones, and of course the same exaggeration is seen in all those formulæ of Pearson in which the length of this bone appears. Excluding the results thus obtained and taking only the rest that appear to agree fairly well, we reach estimates of the living height of this individual of 1661.35 according to Pearson, and of 1641.6 mm. according to Manouvrier, which corresponds approximately to a height of 5 ft. 4½ in. to 5 ft. 5½ in.

Skeleton No. 7

This skeleton lay on its back with its head pointing towards the south and the face turned to the west. The legs were flexed and the thighs abducted. The right leg lay across the fore-arm of No. 11 and the bend of the left knee across the right elbow of No. 8. The Camp Medical Officer gives the following measurements:—

Occipital condyle to	prom	ontor	y of s	acrun	ı .		369	mm.
Length of femur (upp	er ex	tremit	y of h	ead to	o inter	nal		
condyle) .							345	,,
Length of fibula.							276	,,

From the above measurements it is clear that the height of this individual was much below the average. Taking the length of the sacrum as approximately 19 per cent of the total vertebral column, the whole length in this individual must have been somewhere in the neighbourhood of 435 mm., whereas the average height of the whole column in the adult male is 690 mm. and in the female 675 mm. The length of the femur would correspond to a living height of 1302 mm. and the fibula to a height of 1269 mm. or an average of 1285.5 mm. This corresponds to a height of 4 ft. 2.6 in.

Skeleton No. 8

This was found close to No. 7, with the head towards the north. The body lay face downwards with the legs extended and the arms bent and flung forward, the right wrist being in close proximity to the top of the cranium. The skull is in a fair state of preservation, but owing to the position in which it has been lying, it has become very much distorted, and the whole of the right side of the face has been pushed backwards and flattened.

Skeleton No. 9

The remains of this skeleton were much decayed and the skull is badly broken. The body lay north and south, with the head towards the south; the right leg was extended and the left flexed at the knee; the left arm was flexed with the hand on the lower part of the chest, and the right arm bent at the elbow with the hand resting on the pelvis (right os innominatum) of Skeleton No. 8.

Skeleton No. 10

This body lay in the north corner of the room in a line running from north-east to south-west, with the head towards the south-west. The body lay on its face with the head turned towards the left shoulder; the legs were extended, but both arms were flexed. The left

fore-arm as well as both feet were missing. The Camp Medical Officer gives the following measurement:—

Length of femur (upper extremity of great trochanter to the external condyle) 382 mm.

This would correspond roughly to a total length for the whole bone of 396 mm., and calculated from this figure the living height must have been approximately 1493 mm. or 4 ft. 10.8 in.

Skeleton No. 11

This was found close to No. 10, the body lying in a north and south direction, the head towards the south and the face turned to the west. The body lay in line with No. 8, the heads being about 14 inches apart. The arms were outstretched at right angles to the trunk and the fore-arms were flexed at a right angle; the left leg was extended and the right leg flexed. The right hand lay between the feet of Skeletons Nos. 6 and 13, and the left fore-arm was beneath the right leg of No. 7. The skull is not quite complete, the temporal region of the right side being absent, but otherwise it is in a good state of preservation. The Camp Medical Officer gives the following measurements:—

			Living height.		
			Munouvrier.	Pearson.	
Length of tibia		340 mm.	1568	1547 .4	
Length of fibula		328 "	1544	-	
Transverse diameter of the pelvi	s.	142 ,,	_	. —	

Here, again, there is considerable difference between the living heights calculated from the two bones. The length of the tibia, according to Manouvrier, corresponds to a height of 1568 mm., while, according to Pearson, it would be 1547.4, whereas that calculated from the fibula is only 1544 mm. Taking the mean of these three estimates the living height would be approximately 1553 mm. or 5 ft. 1 in.

Skeleton No. 12

This was found near to Skeleton No. 16 and in line with No. 6. The sole remains that were recovered are the skull, which is very badly broken, portions of the mandible and a few fragments of other bones. The skull was lying face downwards.

Skeleton No. 13

This was found lying east and west with the head towards the west. The body was on its left side, with the legs slightly flexed. The right arm was missing and the left much damaged; it was touching the head of Skeleton No. 14.

Skeleton No. 14

This was lying close to and on the north side of No. 13. Only the skull and part of the vertebral column were preserved, but it appears that the body was lying on its back, with the face upwards. The skull is that of a child.

Skeleton No. 15

This was discovered at the extreme south end of the group lying to the south of Skeleton.

No. 5. The remains are stated to have consisted of a small crushed skull in poor condition, and apparently this was not sent to us.

Skeleton No. 16

This was lying to the west of Skeleton No. 5 and close against a wall. It lay with its head towards the north and the right arm extended between the feet of No. 8 and the head of No. 5. The bones were in a very poor and friable condition and the skull badly crushed.

Skeleton No. 17

This skeleton was discovered at a depth of 4 ft. 2 in. in a narrow lane, subsequently termed "Deadman Lane". The body lay on its back and was lying in a north-west south-east line across the corner of a wall. Only part of a skull and the bones of the thorax were discovered. These were all in a poor condition and were not sent to us for examination.

Skeleton No. 18

Fifteen inches to the west of No. 17 a few fragments of a small skull were obtained, but no other remains of this individual were traceable.

The remains of the above skeletons were sent to us for examination in 1926 and with them there was, in addition, part of another skeleton which we have termed M. These fragments consist of a skull, in which the right parieto-temporo-sphenoidal region is missing; part of the upper jaw; the mandible in two halves and with the left coronoid and condylar processes broken off; and a few other small bones, etc.

Skeleton No. 19

This was discovered during the course of excavations in 1926-7. All that was recovered was the skull with the lower jaw. Judging from the condition of the bones and the character of the teeth, which are not at all worn, this skull belongs to a later period than the remains found in the group Nos. 5-16 and those in the separate burials Nos. 2-4; but it is probably considerably older than No. 1.

In 1925-6 a second group of skeletons was discovered, as has been mentioned above (vide supra, p. 600). This group included the remains of six individuals and were found lying in one of the streets.

Skeleton No. 20

This was lying on its face, with the head pointing towards the south and with both arms extended in front of the head. The skeleton measured 5 ft. 5½ in. as it lay. The skull, of which much of the vault and the supra-occipital region is missing, is otherwise fairly well preserved. The following additional measurements were taken on what remained of the body:—

Length of femur (from condyles to top of great trochanter) 448 mm.

This corresponds approximately to a total length for the femur of 456 mm. Applying Manouvrier's formula this would give as the living height 1682 mm. or 5 ft. 6.2 in.

Skeleton No. 21

This lay between the legs of Skeleton No. 20, the head pointing at an angle of 28 degrees west of south. The body lay on its back. Only the skull, which was much eroded an broken, the upper part of the vertebral column, and the right scapula were left. All the resoft the skeleton had completely disintegrated. The skeleton appeared to be that of a chi

Skeleton No. 22

٥.

re

ed

This individual lay to the east of No. 20, close to a wall. The body lay on its back the head directed towards a line 28 degrees west of south and in line with the pelvis of N. The right arm was flung upwards beyond the head and the left lay at the side. Both leg somewhat abducted. The skull was badly smashed, and the whole skeleton disinted beyond hope of recovery.

Skeleton No. 23

To the south of No. 22 lay the remains of another body, again face downwards with the head pointing in a direction 7½ degrees west of south. The left arm was flung forward and the legs were nearly straight. The right arm was completely missing. Here, again, the bones had disintegrated very badly and the skull was completely smashed. The skeleton was remarkable for its size; it appeared to be that of an adult male and the total height was 6 feet, measured from the top of the cranium to the os calcis.

Length of tibia (from spine to border of articulation with astragalus) 423 mm.

According to Manouvrier's tables this would give an approximate living height of 1841 mm., while according to Pearson it would be 1836 or 6 ft. 0.5 in.

Skeleton No. 24

About 3 ft. 8 in. from Skeleton No. 23 and a little to one side of it lay another, that seems to have been also that of an adult. This skeleton lay on its back, with the legs, of which parts are missing, slightly abducted. The left arm was outstretched at right angles to the trunk, and the right flung upwards above the head and bent at the elbow at a right angle. The maximum length of the humerus was 328 mm., which gives a calculated length for the whole body during life of 1671 mm. or 5 ft. 5 in.

Skeleion No. 25

This was the remains of a child and was lying on its back with, as usual in this group, its head towards the south. The legs were somewhat abducted, and the left arm appeared to have been outstretched at right angles to the body. The whole skeleton was in the last stages of disintegration.

Skeleton No. 26

This skeleton is represented by the skull only, which was badly crushed and consisted of a number of fragments.

Description of selected skulls.

From the above collection of human remains we have been able to select twelve skulls, that were sufficiently well preserved or at any rate not too greatly damaged to render reconstruction impossible, and from these to take measurements of a more or less reliable character and draw

deductions from them. It must, however, be borne in mind that some of these skulls have undergone a certain amount of posthumous deformation owing to the pressure of the superincumbent earth, and this process has probably also been assisted by the deterioration of that part of the skull that lay below. It has been shown that in these early burials and interments that side of the skull that lay underneath in contact with the undisturbed soil is as a rule in a much worse state of preservation than the uppermost portion; and the same in the main holds good for the present collection.

In our account of these skulls we have given, in addition to photographs, a series of outline tracings of the various aspects taken by means of the dioptograph. So far as it was possible to do so, we have attempted to take tracings of the true norma, e.g. lateralis, facialis, and verticalis, but, owing to the warping of some of the skulls, this has not been possible and readers, therefore, must not expect to find in every case an exact agreement between the measurements as given by us and the corresponding measurements as indicated on the tracings.

As we pointed out in our previous report,² many of these early long-headed skulls are characterized by the great enlargement of that part of the occipital region that lies behind the external auditory meatus. So far as we are aware, the first author to comment on this condition was Keith,³ who remarked on it in certain Veddah crania. The same condition is present to a very marked degree in certain of the present skulls, and, in order to provide some standard of comparison, we have applied to the external auditory meatus the method that is utilized for determining the position of the bregma. We thus take the total nasion-inion length and, using this as a base line, we then find the distance from the nasion at which a perpendicular line drawn through the centre of the meatus cuts it; from these two measurements we get what we propose to call the "Auditory Meatus Position Index":—

Nasion to foot of meatal perpendicular × 100
Nasion-Inion Line.

In Tables I-VII detailed lists of all measurements, indices, angles, etc., are given.

Skull No. 1 (Text-Figs. 11, 12, and 13; Pl. CLX, Figs. 1 and 2)

This skull is undoubtedly of recent origin and, to judge from its small size, the general lightness of the bones, the small teeth, the small size of the mastoid processes, and the persistence of certain infantile characters, such as the degree of prominence of the frontal and parietal eminences, must be attributed to the female sex. The cranial sutures are well marked and are moderately complicated; there is no trace of any commencing synostosis anywhere. The age of the individual was in all probability between 20 and 25 years, possibly somewhat nearer the former figure.

Norma facialis (Text-Fig. 11).

The face is moderately long and is rather narrow, the facial index being 87.65 (mesoprosopic). The frontal eminences, as already mentioned, are prominent. The glabella is very slightly raised and the superciliary ridges are weak. A supra-orbital foramen is present on both sides. The orbits are high; the orbital index, which is 91.67, falling in the "hypsiconch" group. The malar bones are of moderate development and are not prominent.

- ¹ All dioptographic tracings given as text-figures have been reduced by one-half.
- ² Sewell and Guha, loc. cit., p. 60.
- 3 Keith, "Report on two human crania of considerable but uncertain antiquity": Journ. Anthropological Soc. Bombay, p. 671, 1917, Bombay.

Skeleton No. 21

This lay between the legs of Skeleton No. 20, the head pointing at an angle of 28 degrees west of south. The body lay on its back. Only the skull, which was much eroded and broken, the upper part of the vertebral column, and the right scapula were left. All the rest of the skeleton had completely disintegrated. The skeleton appeared to be that of a child.

Skeleton No. 22

This individual lay to the east of No. 20, close to a wall. The body lay on its back with the head directed towards a line 28 degrees west of south and in line with the pelvis of No. 20. The right arm was flung upwards beyond the head and the left lay at the side. Both legs were somewhat abducted. The skull was badly smashed, and the whole skeleton disintegrated beyond hope of recovery.

Skeleton No. 23

To the south of No. 22 lay the remains of another body, again face downwards with the head pointing in a direction 7½ degrees west of south. The left arm was flung forward and the legs were nearly straight. The right arm was completely missing. Here, again, the bones had disintegrated very badly and the skull was completely smashed. The skeleton was remarkable for its size; it appeared to be that of an adult male and the total height was 6 feet, measured from the top of the cranium to the os calcis.

Length of tibia (from spine to border of articulation with astragalus) 423 mm.

According to Manouvrier's tables this would give an approximate living height of 1841 mm., while according to Pearson it would be 1836 or 6 ft. 0.5 in.

Skeleton No. 24

About 3 ft. 8 in. from Skeleton No. 23 and a little to one side of it lay another, that seems to have been also that of an adult. This skeleton lay on its back, with the legs, of which parts are missing, slightly abducted. The left arm was outstretched at right angles to the trunk, and the right flung upwards above the head and bent at the elbow at a right angle. The maximum length of the humerus was 328 mm., which gives a calculated length for the whole body during life of 1671 mm. or 5 ft. 5 in.

Skeleion No. 25

This was the remains of a child and was lying on its back with, as usual in this group, its head towards the south. The legs were somewhat abducted, and the left arm appeared to have been outstretched at right angles to the body. The whole skeleton was in the last stages of disintegration.

Skeleton No. 26

This skeleton is represented by the skull only, which was badly crushed and consisted of a number of fragments.

Description of selected skulls.

From the above collection of human remains we have been able to select twelve skulls, that were sufficiently well preserved or at any rate not too greatly damaged to render reconstruction impossible, and from these to take measurements of a more or less reliable character and draw

deductions from them. It must, however, be borne in mind that some of these skulls have undergone a certain amount of posthumous deformation owing to the pressure of the superincumbent earth, and this process has probably also been assisted by the deterioration of that part of the skull that lay below. It has been shown that in these early burials and interments that side of the skull that lay underneath in contact with the undisturbed soil is as a rule in a much worse state of preservation than the uppermost portion; and the same in the main holds good for the present collection.

In our account of these skulls we have given, in addition to photographs, a series of outline tracings of the various aspects taken by means of the dioptograph. So far as it was possible to do so, we have attempted to take tracings of the true norma, e.g. lateralis, facialis, and verticalis, but, owing to the warping of some of the skulls, this has not been possible and readers, therefore, must not expect to find in every case an exact agreement between the measurements as given by us and the corresponding measurements as indicated on the tracings.

As we pointed out in our previous report,² many of these early long-headed skulls are characterized by the great enlargement of that part of the occipital region that lies behind the external auditory meatus. So far as we are aware, the first author to comment on this condition was Keith,³ who remarked on it in certain Veddah crania. The same condition is present to a very marked degree in certain of the present skulls, and, in order to provide some standard of comparison, we have applied to the external auditory meatus the method that is utilized for determining the position of the bregma. We thus take the total nasion-inion length and, using this as a base line, we then find the distance from the nasion at which a perpendicular line drawn through the centre of the meatus cuts it; from these two measurements we get what we propose to call the "Auditory Meatus Position Index":—

Nasion to foot of meatal perpendicular × 100
Nasion-Inion Line,

In Tables I-VII detailed lists of all measurements, indices, angles, etc., are given.

Skull No. 1 (Text-Figs. 11, 12, and 13; Pl. CLX, Figs. 1 and 2)

This skull is undoubtedly of recent origin and, to judge from its small size, the general lightness of the bones, the small teeth, the small size of the mastoid processes, and the persistence of certain infantile characters, such as the degree of prominence of the frontal and parietal eminences, must be attributed to the female sex. The cranial sutures are well marked and are moderately complicated; there is no trace of any commencing synostosis anywhere. The age of the individual was in all probability between 20 and 25 years, possibly somewhat nearer the former figure.

Norma facialis (Text-Fig. 11).

The face is moderately long and is rather narrow, the facial index being 87.65 (mesoprosopic). The frontal eminences, as already mentioned, are prominent. The glabella is very slightly raised and the superciliary ridges are weak. A supra-orbital foramen is present on both sides. The orbits are high; the orbital index, which is 91.67, falling in the "hypsiconch" group. The malar bones are of moderate development and are not prominent.

- ¹ All dioptographic tracings given as text-figures have been reduced by one-half.
- ² Sewell and Guha, loc. cit., p. 60.
- 3 Keith, "Report on two human crania of considerable but uncertain antiquity": Journ. Anthropological Soc. Bombay, p. 671, 1917, Bombay.

The nose is long and narrow (leptorrhine), the nasal index being 43.75. The bridge of the nose is highly arched and is narrow; the inter-orbital diameter is 19 mm. The lower margin of the nasal aperture is clean cut and raised in a slight ridge, and the subnasal spine is prominent; the septum is asymmetrical, being pushed over to the left side.

Norma lateralis (Text-Fig. 12).

The cranium is hypsi-cranial, as is clearly shown by the length-auricular height index, which is 63.82, and the length-height index of 76.64. The glabella, as mentioned, is only slightly marked and there is but very slight depression at the nasion. From the glabella,




Fig. 11.

the forehead rises nearly vertically and then turns and sweeps backwards in a more or less uniform curve to the inion. The occipital protuberance is well marked. The line of attachment of the temporalis muscle to the frontal bone is well marked and passes upwards and backwards from the external angular process in a nearly straight line at an angle of about 45 degrees; the continuation of the linea semicircularis across the parietal bone is, however, not marked, and is in places very difficult to trace. Posteriorly above and behind the external auditory meatus the line of attachment of the muscle is raised in a low ridge that can be traced upwards and backwards as far as the squamo-parietal portion of the lambdoid suture. The mastoid process is small but there is a well-marked supra-meatal triangle. The styloid processes were well developed, but that on the right side is broken off. The zygomatic arch is delicate. In the facial part the bridge of the nose is prominent. There is no trace of any subnasal prognathism.





Fig. 12.

Norma verticalis (Text-Fig. 13).

When viewed from above the shape of the skull is seen to correspond to Sergi's "ovoides" type; the frontal and parietal eminences are well marked, the latter particularly so on the



right side. The skull is dolichocranial, the length-breadth index being as low as 70.08. In the posterior part of the frontal bone in the middle line, commencing 11 mm. in front of the bregma, is an oval, slightly depressed area, measuring 27 mm. in length by 13 mm. in breadth, the long axis running antero-posteriorly; this we take to be the scar of an old healed ulcer or wound that has suppurated. A well-marked parietal foramen is present on the left side, and a very minute one on the right. The bregma is situated somewhat far back, the bregma position index being 34.94.

Norma occipitalis.

There is little to record regarding this aspect of the skull. The muscular attachments are only moderately developed. A very small wormian bone is present in the left part of the lambdoid suture at a distance of 26.5 mm. from the lambda.

Norma basilaris.

The foramen magrum is narrow, its index being 81.25. The post-condylar fossa is much more marked on the left side than on the right. The upper jaw is wide, the maxillo-alveolar index being 117.53 (brachyuranic). The palate, as one would expect in a female, is small but broad, the palatal index being 92.31, thus falling within the brachystaphyline series. Unfortunately, most of the teeth of the upper jaw are missing, but those that are present are of moderate size and are only slightly, if at all, worn; the first molar tooth on the right side shows some slight degree of wear. Both third molars have only recently been erupted.

The Mandible.

The mandible exhibits a moderate degree of development and the chin is moderately prominent. As regards the teeth, the canine and the first molar teeth on the right side are slightly worn, but the third molar is absolutely unworn. It is worth noting that the incisors of the lower jaw appear to have fitted behind the corresponding teeth of the upper jaw, when the mouth was closed, and did not meet edge to edge, as they do in certain of the other skulls and, as Keith has shown, is so often the case in early skulls. Unfortunately, some of the teeth are missing. The lower dental arcade bends slightly outwards at its posterior extremity, so that the distance between the outer surfaces of the third molar teeth is 62 mm.; the diameter of the dental arcade opposite the second molar teeth is 55 mm., and between the canines it must have been in the neighbourhood of 31 mm., but unfortunately the left canine tooth is missing. The posterior molar teeth are not set vertically in the jaw, but are inclined inwards, so that the biting surfaces slope somewhat downwards and inwards.

Skull No. 2 (Text-Fig. 14)

The whole skull is in a very bad state of preservation, particularly the left side. The whole of the vault is missing, and so also is the greater part of the face. From the thickness of the bones and the general characters of the skull we infer that it belonged to a male.

Norma facialis.


The left maxilla is completely missing and the left malar bone has been thrust inwards and upwards, filling the whole orbital cavity. The right side of the face is also considerably

1 Keith, Sir Arthur, The Antiquity of Man, vol. ii, p. 670, London, 1925.

distorted and flattened, and the maxilla is twisted over to the left. As a result of this deformation it has been absolutely impossible to obtain any measurements, even approximately correct, of the facial part of the skull.

Norma lateralis (Text-Fig. 14).

The skull is clearly orthocranial, the length-auricular height-index being approximately 59.69. On the right side of the skull the greater part is intact, although the malar region has been badly displaced. The zygomatic arch has been fractured in two places, and the malar bone has been pushed inwards and upwards towards the middle line. The outer diploe of the greater part of the cranial bones has been eroded away and the bones themselves are badly cracked, so that it is impossible to detect the sutures in the greater part of their



course. The region round the nasion is fractured, but it appears to have been depressed. The glabella is prominent and above this point the forehead is retreating. The anteroinferior region of the right parietal bone is fractured and is slightly depressed, and as a result it is not possible to be certain on the point, but it appears that the parietal and alisphenoid met at the pterion. The mastoid process on this side of the skull is intact, and is large and massive; on the left side it is entirely wanting. In the temporo-parietal region of the left side there is a large and depressed fracture; the lower part of the parietal bone and the upper portion of the squamous plate of the temporal bone are broken, and the fractured parts have been driven inwards under the upper and intact portion of the parietal bone; this fractured area measures 85 mm. in length. The depth to which the bone has been driven inwards is much greater in the posterior part of the area, while towards the anterior end the area terminates

in a shallow groove. We hesitate to suggest that this was the cause of death, but the nature of the injury would be compatible with a severe blow from a heavy weapon with a short cutting edge such as an axe.

Norma verticalis.

When viewed from above, it is seen that the skull was certainly dolichocranial in character and probably agreed with Sergi's "ovoides" type. The greater part of the vault is missing, the defect extending from the frontal bone and including the bregma to almost as far back as the lambda. The anterior part of the cranium has also undergone some deformation, the forehead being pushed over towards the left side. The parieto-occipital region of the left side has been somewhat flattened and displaced inwards, so that the occiput appears to be more pointed than in actual life. The bone of the vault was of considerable thickness, and in the region of the back part of the frontal area measures as much as 9:5 mm. in thickness.

Norma occipitalis.

Apart from the distortion mentioned above, there is nothing of interest to note in this aspect of the skull.

Norma basilaris.

As already mentioned, the region of the occipital bone has been damaged and displaced, and the part posterior to the foramen magnum is broken and depressed; the actual margin of the foramen, however, appears to be intact, and, to judge from the position of the occipital condyles, there has been no deformity in that particular part of the bone. If this view is correct, the foramen magnum is extremely long, the foramen index being in the neighbourhood of 56.4 mm. Both condylar fossæ are well marked, but that on the left side is appreciably bigger than that on the right. The muscular attachments on the basi-occipital bone for the longus capitis and rectus capitis anterior muscles are well marked. The digastric fossæ are also deep. The glenoid fossæ are deep and the tympanic plate is proportionately massive.

The Mandible.

The mandible is strong and well developed. Unfortunately, the bone has been fractured a little to the left of the middle line, the line of fracture extending through the socket of the lateral incisor tooth. The upper part of the right ramus, including both the coronoid and condylar processes, is missing. All the teeth, with the exception of the second and third molars on each side, are missing. The bimolar width of the dental arcade, measured between the second molar teeth, is 57 mm. The teeth are greatly worn, the dentine being freely exposed.

Skull No. 3 (13b) (Text-Figs. 15 and 16; Pl. CLX, Figs. 3, 4, 5, and 7)

This skull belongs to a male, who was undoubtedly adult, but we are unable to assign any definite age to it. All the teeth have been erupted and some of the sutures give the appearance of having commenced to fuse; this has certainly taken place in the lower part of the sagittal suture, and part of the lambdoid suture of the left side also appears to have undergone the same process; but it is impossible to be absolutely certain on this point owing to the fractured condition of the bones. The skull is somewhat distorted and the face is pushed over to the left side. The facial portion is intact, but the posterior region of the skull was

entirely fragmentary and was largely pushed inwards and impacted within the anterior region, while the greater part of the occipital bone is missing, including both the basi- and the ex-occipital regions. Extensive reconstruction of the back part of the skull was thus necessary; and, as a result of this, many of our measurements must be regarded with a considerable degree of caution.

The skull appears to differ essentially from all the other skulls in the present collection. It is large and of a heavy build. From the description that we give below and from the photographs and tracings there can, we think, be little doubt that it is characteristically Mongolian in type; for the purpose of comparison we have given photographs of a typical Naga skull, No. N. 189, in the collection of the Indian Museum (Pl. CLX, Figs. 6 and 8). The cranium appears to have been nearer the brachycephalic than the dolichocephalic type.



Norma facialis (Text-Fig. 15).

The face is moderate in length, the superior facial index being 52.86 (mesene). Owing to the damaged condition of the mandible it is impossible to be certain of the total facial length, but this must have been in the close neighbourhood of 125.8 mm., which would give a total facial index of 89.85 (mesoprosopic). The first thing that strikes one in this view of the skull is the decidedly Mongolian character of the face. The forehead is rounded, the glabella is moderately prominent, and the superciliary ridges are not markedly developed. Keith 1

¹ Sir Arthur Keith, "Human Skulls from Ancient Cemeteries in the Tarim Basin": Journ. Royal Anthropol. Institute of Great Britain and Ireland, vol. lix, p. 149, 1929.

has recently called attention to the characters of the Mongolian forehead and the shape of the external angular process of the frontal bone in this type of skull, and the present example agrees very well, so far as those characters are concerned that Keith regards as characteristic of this racial type. The root of the nose is flat and broad, the interorbital diameter being as high as 23 mm. The orbits are very high; the orbital index is as great as 97.1 mm., so that the orbital aperture is very nearly square and falls in the hypsiconch group. The nose is moderately long, the nasal index being 49.1 mm., thus falling within the limits of the mesorrhine group. There is a well-marked subnasal gutter present on each side.



Fig. 16.

Norma lateralis (Text-Fig. 16).

The external auditory meatus and the zygomatic arch are absent on the right side of the skull. On the left side the alisphenoid and the parietal meet at the pterion; the fronto-parietal suture has already closed. In the same paper Keith 1 has devised a new method of estimating the degree of projection of the various features of the face, such as the glabella, the root of the nose, the cheekbones, chin, etc., and he has shown that in the Mongolian skull the outer margin of the orbit is more advanced and is further from the centre of the external auditory meatus than in the European skull. Such a forward projection of the cheeks is well marked in this skull; the malar bones are very prominent and this gives a characteristic

¹ Sir Arthur Keith, loc. cit., p. 169.

flat appearance to the face as a whole. As well as being prominent, the malar bones are of stout build, the orbitale-zygomaxillare distance being as high as 32 mm. The nasion was not depressed and the nose was certainly not prominent; unfortunately, the lower portions of both nasal bones are missing, so that it is impossible to determine the exact degree of projection, but, as mentioned above, the root of the nose is flat and broad. There is a considerable degree of subnasal prognathism, but the face as a whole is mesognathic.

Norma basilaris.

The most striking feature in this aspect of the skull is the great width of the palate and the dental arcade. The palatal index is as high as 95.92 mm. and this is not due in any way, so far as we can judge, to posthumous deformity or warping, for the facial portion of the skull is very well preserved. So high an index as this merits the creation of a special class, which may be termed "hyperbrachystaphyline". The maxillo-alveolar index is equally high, being 138.49, and is therefore "hyperbrachyuranic". The dental arcade is almost parabolic in its curvature, the width between the molar teeth steadily increasing from before backwards; the bicanine width is 41 mm. and bimolar width, measured between the outer surfaces of the second molar teeth, is as high as 71 mm.

. The Mandible.

The mandible is powerfully built, but has undergone a considerable degree of warping and damage. The greater portion of the right ascending ramus, including both the coronoid and condylar processes, is missing, and the right angle is also absent. Unfortunately, the median portion of the jaw between the incisor teeth was badly damaged and considerable reconstruction was necessary. The bicanine diameter of the reconstructed jaw is 37.5 mm., and the bimolar diameter between the second molar teeth is 67.2, while between the outer surfaces of the third molar teeth the diameter is 70.3 mm. All the teeth are badly worn, the dentine being freely exposed. The depth of the body of the mandible cannot be accurately measured between the incisor teeth, owing to the damage to the front part of the jaw, but it must have been approximately 34.7 mm. The depth of the body in front of the second molar tooth is 36.1 mm.; of this there can be no doubt, as this portion of the jaw is well preserved.

Skull No. 6 (Text-Figs. 17 and 18; Pls. CLX and CLXI, Figs. 9 and 10)

This skull is extremely long and appears to have been that of a male. Judging from the fact that all the teeth have been erupted and that none of the sutures have commenced to show any signs of synostosis, there can be no doubt that the individual was in the prime of life at the time of his death.


Norma facialis (Text-Fig. 17).

The glabella and superciliary ridges are not pronounced, and the forehead is rounded. The orbits appear to have been rather low, but the supra-orbital margin of the left side has been fractured and the upper and outer portion has been displaced downwards, thus making the orbit appear rather lower and the vertical diameter less than it was in life; the whole of the outer and lower margin of the right orbit is missing. The nose is of moderate length

(mesorrhine) and the subnasal margin is clear cut, without any rounding off of the edge, or trace of guttering. The distance from the subnasal spine to the alveolar margin is long, 22 mm.

Norma lateralis (Text-Fig. 18).

When viewed from the side it is seen that the forehead rises almost vertically from the nasion. The glabella is only slightly marked and the superciliary ridges are not prominent. The line of the vault of the cranium passes upwards and backwards along the vertex and then downwards to the inion in an almost smooth and uniform curve, that is strikingly similar



to the curvature of the vault in the same view of the "Nal" skull. The alisphenoids, as is usual, come into contact with the anterior inferior angles of the parietal bones on both sides of the skull. The mastoid process is fairly massive and is not unusually prominent. Both zygomatic arches are missing and, in addition, the right malar bone is also absent. The bridge of the nose is moderately high, and there is some degree of subnasal prognathism.

On the right side of the skull, extending from the lambda, or slightly beyond the lambda on the left side, passing across the sagittal suture and then extending forwards in a straight line across the right parietal bone and into the alisphenoid, is a straight cut that measures 146 mm. in length; above this cut the right parietal bone is intact, but below the cut the lower

¹ Vide Sewell and Guha, loc. cit., pl. xxiv, fig. 2.

part of the parietal bone and approximately the upper third of the squamous plate of the temporal bone is missing. We are of the opinion that a cut such as this, that has bitten through the parietal bone without producing any marked fracturing of the portion of the bone that remains, could only have been done during life with a sharp and heavy weapon, such as a sword, and that this was in all probability the cause of death.

Norma verticalis.

When viewed from above the general outline of the skull clearly resembles that of Sergi's "ovoides" type. The frontal eminences are not marked and the parietal eminences are only moderately developed. There has been a certain degree of distortion. The left parietal region has been somewhat distorted and displaced, the result being that the two parietal bone's in the region of the sagittal suture have been forced slightly outwards (upwards). The occipital region has also been forced out and slightly to the left.




FIG. 18.

Norma basilaris.


The distortion of the occiput appears to be much more marked in this view of the skull. The post-condyloid fossa is more developed on the left side than on the right. The ridges of the muscular attachments to the occiput are well developed, but the digastric fossa is shallow. The tympanic plate is comparatively stout and thick; the styloid processes are missing on both sides. The glenoid fossæ are deep. The teeth are all considerably worn, and the wear of the incisor teeth shows that during life they were in apposition with the teeth of the lower jaw, the bite being "edge to edge". There is a small patch of caries in the third molar tooth on the right side. The palate is high and there is a low torus. The upper dental arcade possesses a bicanine diameter of 38.5 mm. and a bimolar diameter between the second molar teeth of 65.5 mm. The molar length is 43 mm.

The Mandible.

The mandible is powerful and the teeth are large. In the lower dental arcade, the bicanine diameter is 35.5 mm. and the bimolar diameter is 59.5 mm. The median length of the dental arcade is 53 mm. The chin is moderately prominent.

Skull No. 7 (Text-Figs. 19, 20, and 21; Pl. CLXI, Fig. 11)

The skull is a small one and appears to have belonged to a female; the bones are very light, the glabella and superciliary ridges are only slightly developed. The skull has undergone a considerable degree of distortion and damage. The facial part of the skull has been pushed over towards the right side, while the occipital area has also undergone considerable displacement towards the same side; thus the sagittal line of the skull follows a curve. The right parietal region has been forced outwards and upwards, and there is a long and slightly S-shaped fracture dividing the posterior half of the right parietal bone into two almost equal



Fic. 19.

parts. The anterior half of the bone is broken and a considerable portion is missing; the temporosphenoidal region of the same side is depressed, and the squamous plate is broken into two parts by a vertical fracture. On the basal aspect of the skull, the right part of the occipital bone has been pushed inwards towards the middle line, and this has entirely destroyed the integrity of the foremen magnum.

Norma facialis (Text-Fig. 19).

The orbits are moderately high, the orbital index being 82.7 mm.; thus, the orbit falls within the limits of the mesoconch group. The nose is narrow at the root, the interorbital diameter being only 18.5 mm.; it is of moderate length (mesorrhine), the nasal index being 50.8 mm. There are no traces of any subnasal gutter, the inferior margins of the nasal cavities being clean cut and sharp. The distance between the lower margin of the nose and the alveolar margin is small, measuring only 15.0 mm. The malar bones are not markedly prominent.

Norma lateralis (Text-Fig. 20)

The glabella is only slightly marked, and the nasion is not depressed. The forehead rises with only a slight backward inclination and then turns into the general outline of the vault, which is very similar to that of the "Nal" skull, being highly arched. The parietals and alisphenoids meet at the pterion. The frontal eminences are not marked nor, as mentioned above, are the superciliary ridges. None of the sutures appear to have undergone any synostosis, and the third molar teeth are only just cut, and have not yet fully developed, so that the age of the individual must have been about 20 to 25 years. The occipital region is extremely long and well-developed, and, as a result, the position of the external auditory




FIG. 20.

meatus lies very far forward; the meatus position index is thus 40.69. The mastoid process is small and the digastric fossæ are not very deep. The tympanic plate shows a degree of moderate development. Unfortunately, the distal ends of both nasal bones are missing, so that it is impossible to draw any definite conclusions regarding the degree of prominence of the nose during life, but it does not appear to have been high. The malar bones are small and the zygomatic arches are missing on both sides, but the root of the process is small and delicate. The distance between the orbitale and the zygomaxillare on the left side is 28.5 mm., which is greater than one would expect from the general appearance of the skull; this increased distance is due to the prolongation of the malar process of the maxilla outwards, the actual depth of the malar bone itself being only 21.0 mm. There is some degree of sub-nasal prognathism.

Norma perticalis (Text-Fig. 21).

When viewed from above, it is clearly seen that the skull was very long, though the warping and damage prevent one from forming any definite opinion regarding the cephalic index or the character of the general outline. The forehead is rounded and the frontal eminences are only slightly marked. The left parietal eminence is well developed, but that on the right side has been distorted and nearly obliterated by damage to the bones.

Norma occipitalis.

There is but little to record regarding this aspect of the skull. The lateral walls of the cranium appear to have bulged slightly outwards, as they rose from the mastoid processes.




Fig. 21.

Norma basilaris.

The palate is somewhat crushed but appears to have been very narrow with a high vault. The teeth are well developed and are very little worn. The third molar tooth does not appear to have erupted on either side, but owing to damage it is not possible to be certain on this point. As regards the dental arcade, owing to the crushed condition of the palate and the skull in general any measurements must be regarded with a considerable degree of caution. The bicanine diameter is 39.5 mm., and the diameter between the outer surfaces of the first molar teeth is 54 mm.; between the surfaces of the second molar teeth it is, however, only 46.5 mm., but this diameter must have been greater during life. The incisor teeth are shovel-shaped. The muscular attachments to the occipital bone are not very well developed and the digastric fossa is small.

Skull No. 8 (Text-Figs. 22 and 23; Pl. CLXI, Figs. 12, 13)

This skull has undergone considerable warping and damage. The face has been pushed over to the right side, the right zygomatic arch has been broken, and the greater part of it is missing. The left orbit has been greatly distorted. The frontal region near the upper and inner angle of the left orbit has been forced outwards and the glabella has also been driven outwards. The nasal bones are separated from the frontal and maxillary bones and driven inwards. The posterior region of the skull has been badly broken; the posterior part of the right parietal bone and the supra occipital part of the occipital bone have been badly fractured, the left side of the occipital region and the posterior part of the left parietal bone is fragmented, and the greater part of the temporal bone, including the mastoid, is absent. From this it will be clear, that it is not possible to arrive at any very definite conclusion regarding the racial affinities of the individual to whom it belonged.




Fig. 22.

Norma facialis (Text-Fig. 22).

The forehead appears to have been rounded and the minimum frontal diameter is of moderate length. The glabella and superciliary ridges are not prominent. The left orbit is greatly distorted, but the right is more or less intact and appears to have been low. The interorbital diameter is wide. There is a supra-orbital notch on the right side, but on the left, there is a foramen. The malar bones are of moderate size and are not prominent. The nose is very broad; the nasal index is 58 mm., which places the skull in the chamærrhine group. The lower margin of the nose does not show any trace of a nasal gutter, the margin being clean cut. Immediately below the nose the subnasal region of the maxilla is depressed and flattened, and at the outer margin of this flattened area the root of the canine tooth raises a very distinct ridge.

Norma lateralis (Text-Fig. 23).

Owing to the damaged condition of the frontal region it is difficult to determine the characters of the forehead; it appears to have risen almost vertically from the glabella. The vertex is of moderate height and was slightly flattened. The post-auricular region of the skull is very distinctly shorter than in the majority of the skulls. The malar bone is, as mentioned already, of moderate development, the depth of the bone being 21 mm., while the distance from the orbitale to the zygo maxillare is 27 mm. The nose has a moderately high arch. The face is prognathic, due in the main to the subnasal prognathic projection of the maxilla. There is also some degree of alveolar prognathism present.




Fig. 23.

Norma verticalis.

When viewed from this aspect it is clear that the skull had a distinct tendency towards brachycephaly, but it is not possible to arrive at an exact estimate of the maximum diameter during life, owing to the damaged condition of the parietal region.

Norma occipitalis.

The sides of the skull rise nearly vertically from the mastoids.

Norma basilaris.

The left half of the foramen magnum is missing. The mascular attachments to the post-occipital area are not marked. The digastric fossæ are of moderate size. The bimastoid diameter appears to have been high; as only one-half of the skull is intact, it is impossible to measure the diameter exactly, but, calculating from one-half, the total diameter seems to have

been in the neighbourhood of 160 mm. The palate is U-shaped, the diameter being 38 mm. and the palatal height 11 mm. In the upper dental arcade the bicanine diameter is 31 mm. It is impossible to measure the bimolar diameter, as the first and third molar teeth are missing on the right side and all trace of the root sockets has been absorbed in the case of both teeth. On the left side the second premolar and all the molar teeth are absent. The biting surfaces of such teeth as are left are remarkably worh.

The Mandible.

The mandible has undergone considerable warping and the posterior teeth are missing. All the teeth that remain are markedly worn. The chin is moderately well developed. The bone as a whole is of moderate build and, to judge from the condition of those teeth that remain, the bite must have been "edge to edge".

Skull No. 10 (Text-Fig. 24)

This skull is comparatively small and the component bones are thin and delicate; the muscular ridges are not well marked and in all probability the individual was a female. The skull, as is shown by the photographs taken at the time of excavation, lay on its right side, and it is interesting to note that, contrary to the usual rule, it is the left side of the skull, which lay uppermost, that has suffered the greater amount of damage. The left side of the cranium and the greater part of the left side of the face are missing. There has also been a considerable degree of distortion; the frontal and right parietal bones have been forced apart, and the bones in the region of the right parieto-temporal suture have been forced inwards. An extensive fracture runs across the occipital region in a horizontal direction, and the two parts of the bone have been forced apart to the extent of about one-half of an inch. All the teeth have been erupted, and there is no sign of any synostosis of the sutures; the individual, therefore, must have been adult and in the prime of life.

Norma facialis.

The forehead is rounded and the frontal eminences are not well marked. The malar bones do not appear to have been prominent. The orbit is high, the orbital index being 86.06 mm., which puts it in the hypsiconch group. The nasal region is fractured and the greater part of the left maxilla, as well as the whole of the left malar bone, is absent; fortunately, the ascending ramus of the left maxilla is present, and we are thus able to reach some conclusion regarding the character of the nose. The bridge of the nose is moderately prominent and the root is narrow, the interorbital breadth being only 21.5 mm. The nose is moderately narrow, the nasal index being 47.8 mm., so that it just falls outside the limits of the leptorrhine group.

Norma lateralis (Text-Fig. 24).

There is little or no depression at the root of the nose, and the glabella is only very slightly marked. The superciliary ridges are inconspicuous. The forehead is slightly retreating and passes upwards and backwards into the general contour of the vertex in a uniform curve. The outline of the vertex presents a smooth, high curve that is in close agreement with the condition that we found in the "Nal" cranium (vide Sewell and Guha, loc. cit., pl. xxiv). It is not possible to be absolutely certain that this high arch of the vault is not due, at any rate in part, to the distortion and compression that the skull has undergone, but we are of the opinion

that it was probably present in life. On the right side the parietal bone meets the alisphenoid at the pterion, but on the left the less usual arrangement of the frontal bone meeting the squamous plate of the temporal bone seems to have been present. The posterior region of the skull and especially of the occipital region is not so markedly developed as in certain other skulls in the collection and, as a result, the external auditory meatus is nearer the posterior aspect; this is clearly indicated by the auditory meatus position index, that is 58-33. The mastoid process is not markedly prominent, but the digastric fossa is deep. The tympanic plate is thin in comparison with certain other skulls, especially Nos. 2, 11, and M. The right zygomatic arch is broken. The malar bone is small, the distance between the orbitale and the zygomaxillare being only 24 mm. The bridge of the nose is moderately prominent.




FIG. 24.

Norma occipitalis.

There is a vertical cut on the posterior aspect of the skull at a distance of half-an-inch to the right of the sagittal suture and extending from a point 67 mm. in front of the lambda into the supraoccipital region. The bone to the left of the cut, including such parts of the left parietal and supraoccipital bones as are left, is depressed. There is a transverse fracture across the occipital bone extending to the right asterion.

Norma basilaris.

The foramen magnum is long. The right postcondylar fossa is much deeper than the left. As mentioned already, the digastric fossa is deep and the glenoid fossæ are also moderately deep. The palate appears to have been moderately wide; its depth is 13.5 mm. The teeth are mostly absent, but those that are present are much worn.

Skull No. 11 (Text-Figs. 25, 26, and 27; Pl. CLXI, Figs. 14 and 15)

This skull appears to be that of a male in the prime of life. The skull is a large one and the bones are thick and heavy. On the right side most of the parietal bone and the squamous plate of the temporal bone is missing. While possessing a long head that agrees in its general shape and configuration with certain other long-headed skulls in the collection, the general characters of the face, especially the great development of the glabella and the superciliary ridges, the depressed root of the nose and the great width of the interorbital diameter, as well as the not very marked projection of the nose itself, all point to this individual belonging, not to the Mediterranean race, but to the Proto-Australoids.




Fig. 25.

Norma facialis (Text-Fig. 25).

The right malar bone and part of the right maxilla are missing. The forehead is low and somewhat retreating. The superciliary ridges are marked, meeting at the glabella, which is itself markedly developed. The root of the nose is wide and depressed. The orbits are not high; the orbital index is 84.46, which puts it in the mesoconch group. The supra-orbital notches are large. The malar bone is strongly developed and projects markedly laterally, so that the face must have been broad in life. The nose is wide, the hasal index being 51.06 (chamærrhine). There is no trace of any subnasal gutter, the lower margin of the pyriform aperture being sharply marked and crest-like. The mandible is heavily built and is wide, the angles are everted, and the bigonial breadth is 105 mm.

Norma laieralis (Text-Fig. 26).

Commencing at the nasion, this, as we have noted above, is depressed, while on the other hand the glabella is remarkably prominent and the superciliary ridges well marked. The forehead is receding, but the general outline of the vault of the skull passes back in a low but uniform curve to the inion, which is very prominent. On the right side of the skull, the lateral part of the cranium is missing, while on the left side it is depressed and fractured; we are, therefore, unable to give an exact reading of the maximum width. On the left side the antero-inferior angle of the parietal bone meets the alisphenoid; on the right side the arrangement of the sutures cannot be determined owing to the extensive fracturing of the bones. The masteid process is long, though not very massive. The tympanic plate is massive and thick. The zygomatic arch on the left side is strong and




Fig. 26.

not markedly curved, but it must be borne in mind that this may be due to postmortem flattening as the result of pressure. The attachment of the masseter muscle
to the lower surface of the arch and the malar bone is remarkably well developed. The
malar bone is strongly developed, and is very deep, measuring 30 mm. between the orbitale
and the zygomaxillare, whereas in a normal modern skull this measurement falls in the
neighbourhood of 25 mm. The nose is moderately prominent. Unfortunately, both
the ascending ramus of the maxilla and the nasal bones are somewhat damaged, so that it is
impossible to measure exactly the degree of protrusion of the nose, according to Keiths'
method. The subnasal spine is also damaged. There is some degree of subnasal
prognathism.. The incisor teeth clearly met "edge to edge"

1 Sir Arthur Keith, "Human Skulls from ancient Cemeteries in the Tarim Basin": JRAI. vol. lix, p. 149 (1929).

Norma verticalis (Text-Fig. 27).

The skull is extremely long and was probably narrow, but as both sides are damaged, it is impossible to give the exact measurement; the cranial index, as estimated by us, is approximately 68.72 (hyperdolichocranial). The sagittal suture is closed, except at the anterior end, and so also is the lambdoid.

Norma occipitalis.

The inion is very well marked and the superior nuchal lines are raised into definite ridges. There is a distinct tendency to scaphocephaly in the posterior part of the parietal region.




FIG. 27.

Norma basilaris.

The foramen magnum is long, the foramen index being 77.61 mm. The muscular attachments of the occipital bone are all well marked and the digastric fossa is very wide and deep. The postcondylar fossa is larger on the left side than on the right. The tympanic plate is thick and well developed, and the glenoid fossa is deep. The palate appears to have been somewhat on the small side for a skull that is, in other respects, so well developed; but apart from this its proportions are normal; it is comparatively high, the height being is mm. Unfortunately, some of the teeth are missing, so that it is not possible to determine exactly the dimensions of the dental arcade. The bicanine width must have been in the neighbournood of 38 mm. and the bimolar diameter is 62.5 mm. The length of the dental

arcade is 51 mm. All the teeth are much worn, especially the incisors, and it is clear that the bite was "edge to edge". There has been considerable exfoliation of the molar teeth owing to the absence of the corresponding molars in the lower jaw.

The Mandible.

The mandible is large and massive and extremely broad, the bigonial diameter being 105 mm.; the angles are everted. The chin is not prominent. All three molar teeth on the left side and the second and third on the right are absent, and all trace of the teeth sockets has been obliterated. As in the case of the upper jaw, the teeth are all extremely worn.

Skull No. 14 (Text-Figs. 28, 29, and 30; Pl. CLXI, Figs. 16, 17, and 18).

This skull belongs to a child, aged between 9 and 10 years. The canines, first premolars, and the second and third molars of the permanent dentition have not yet been erupted. The



Fig. 28.

skull is naturally small and the bones thin and light. The head was markedly brachycranial. The outer part of the right orbit and the whole of the right zygomatic arch are missing, while the left zygomatic arch is also broken and absent.

Norma facialis (Text-Fig. 28).

Unfortunately, the facial part of the skull has been badly damaged. The forehead is rounded and slightly bulging, as one would expect in a child. There is no glabella, nor are the superciliary ridges developed. The orbit is high, the index being 89.85 mm. (hypsiconch). The nose appears to have been moderately long and narrow, but we are unable to give any measurements.

Norma lateralis (Text-Fig. 29).

The glabella is not marked, and there is no depression at the root of the nose. The forehead rises vertically upwards and then slightly recedes. The highest part of the vertex appears to lie in front of the bregma; from this point the vault of the skull slopes slightly

downwards until a point is reached about the middle of the parietal bones, i.e., the middle of the sagittal suture, where the line of the vault bends somewhat sharply downwards to the occipital protuberance. The part of the skull between these two latter points, i.e., the middle of the sagittal suture and the inion, is remarkably flattened. It is probable that this flattening is posthumous, since the skull was lying on the occipito-parietal region, with the face upwards. The left parietal bone and the neighbouring part of the frontal bone are badly cracked, the bones in the region of the pterion are fractured and somewhat depressed. Near the left asterion the lamboid suture has opened up, the bones having been forced apart. A small wormian, bone, measuring 14 mm. by 14 mm., lies near the left asterion. The mastoid process, as one would expect in a child, is small, but the digastric fossa is well marked on both sides. Unfortunately, both the nasal bones and the front parts of the maxillæ, lying below the pyriform aperture, are absent.




Fig. 29.

Norma verticalis (Text-Fig. 30).


The forehead is rounded. The frontal eminences are not particularly marked, but on the other hand, the parietal eminences are particularly prominent. A parietal foramen is present on both sides.

Norma occipitalis.

Two cracks start from the region of the lambda; on the left side the fissure crosses the left parietal bone till it reaches the pterion; on the right side the fissure passes downwards and then outwards and forwards to a point about an inch in front of the parietal eminence. In the supraoccipital region a large part of the bone is missing, measuring about 50 mm. by 15 mm.

Norma basilaris.

The foramen magnum is round, the foramen index being 82.35. On either side of the foramen, the areas of the occipital condyles are low and ill-defined, and they present a pitted surface that closely resembles that found between a diaphysis and an epiphysis; presumably this effect is due to incomplete ossification of the condylar region. The right post-condylar fossa is smaller in extent than that of the left side, but is much deeper. The mastoids are small, but the bimastoid diameter is large, measuring 104 mm. The palate is wide but shallow.




Skull No. 19 (Text-Figs. 31, 32, and 33; Pl. CLXI, Figs. 19, 20, and 21)

The age of this individual lies between 18 and 23 years, and is probably nearer the former figure. The skull appears to have belonged to a female, for it is small and the bones are light, the muscular ridges are not marked, and the lower jaw is small and delicate. The face is narrow. There is no trace of any synostosis in the sutures.


Norma facialis (Text-Fig. 31).

The face is small and narrow. The forehead is rounded and the glabella and the superciliary ridges are only slightly marked. There is a supraorbital foramen present on the left side and the usual notch on the right. The frontal eminences are not marked. The nose is narrow, the nasal index being 44.68 mm., which puts it in the hyper-leptorrhine group. The bridge of the nose is also narrow and is moderately arched. The orbits are hypsiconch, the orbital index being 86.39. The malar bones are small and are not prominent.



Norma lateralis (Text-Fig. 32).

Viewed from the side, the skull appears to be very long and narrow. The forehead rises almost vertically from the nasion. The vertex is not highly arched, as in the "Nal"



type, but, on the contrary, the top of the vault is rather flat. The frontal and parietal eminences are not marked. The occipital region appears to be extremely long, but this is in large part

due to the crushing that the skull has undergone. The mastoid is small; the malar bones are small and the zygomatic arches are delicate. The parietal and alisphenoid bones meet at the pterion. The nasion is not depressed and the bridge of the nose is moderately arched. A considerable degree of both subnasal and alveolar prognathism is present, so that the upper incisor teeth project forwards to a marked degree; the face, as a whole, is mesognathic.

Norma verticalis. (Text-Fig. 33).

The skull is badly crushed from side to side, especially in the parieto-occipital region.

The right parietal bone is broken at the antero-inferior angle, and the anterior part of the bone has been depressed and pushed inwards below the level of the frontal bone. The thickness




Fig. 33.

of the parietal bone in this area is only 3.5 mm. So far as it is possible to judge, the outline of this aspect of the skull during life was an elongate oval; but, as a result of the compression, the bones are badly fractured; there is a Y-shaped fracture in the region of the lambda and the upper stem of the Y passes upwards and to the left about half-an-inch to the left of the lambda, and this continues on over the vertex parallel to the sagittal suture to about the junction of its anterior and middle thirds, where it crosses the suture and then divides into two, one limb running straight to the bregma, while the other passes to the right across the anterior part of the right parietal bone.

Norma occipitalis.

Owing to the lateral compression of the skull, the region of the inion has been forced outwards. The thickness of the skull wall in this region is 5.0 mm.

Norma basilaris.

The basis cranii is badly compressed, so that the two occipital condyles almost touch one another, the foramen magnum being completely obliterated; the basi-occipital bone has been forced downwards and to the left. The muscular attachments to the occipital bone are not marked, and the digastric fossa is remarkably shallow. The tympanic plate is moderately stout; both styloid processes are broken. The palate is long and narrow, but this may be due, at least in part, to the lateral compression; the palatal index, as calculated by us, is laptostaphyline. The teeth are of moderate size and the dental arcade does not present any unusual features. The teeth are hardly at all worn and the last molar tooth has not been erupted. The bicanine diameter is 39.5 mm. and the bimolar measurement is 55.5 mm.

The Mandible.

The mandible, as already mentioned, is small and delicate. There is only a slight degree of prominence of the chin. In the lower dental arcade the bicanine measurement is 30-5 mm.



Fig. 34.

and the bimolar diameter is 540 mm. The lower incisors are small and are irregular; it is clear that during life they did not meet the teeth of the upper jaw in an "edge to edge" bite, but fitted behind them.

Skull No. 20 (Text-Fig. 34)

The whole of the left side of the skull, excepting the mastoid and the frontal region, is absent. The upper portion of the frontal bone on the left side, the whole of the left parietal, and most of the supra-occipital regions are missing. On the right side the greater portion of the parietal is missing and there is a large V-shaped interval, one limb of which extends between the frontal bone and the remains of the right parietal, while the other limb passes upwards and forwards into the frontal region; and the right half of the frontal bone has lost the outer diplæ. The root of the zygomatic arch is extraordinarily stout and heavily built. The mastoid process is long and massive; the digastric fossæ are comparatively small, but the glenoid fossa is moderately deep. The muscular attachments to the occipital bone are well marked. The forehead is rounded and the superciliary ridges moderately well marked.

The Face.

The bridge of the nose is very narrow and moderately prominent. The root of the nose and the upper part of the left maxilla were attached to each other, but separated from the cranium. Both the molar bones are absent.

The maxillary region was entirely separate and in two parts. The incisor region of the left maxilla is missing. Judging from the condition of the right maxilla there was some

degree of subnasal pragnathism present.

The mandible is massive and the teeth are moderately worn. The height of the symphysis is 36.5 mm. and the height of the body is 34.0 mm. Both the ascending rami are broken and the coronoid and condyloid process missing. The chin is not prominent.

The skull was very badly broken and warped and the measurements can only be regarded as approximately correct. We have, therefore, not included them in the Tables, but give them separately below:—

Maximum Cranial Length		172 mm
Nasion Inion Line		165 "
Bimastoid Breadth		123 ,,
Auricular Height		118 ,,
Basi-Bregmatic Height .	 	141 ,,
Length of Foramen Magnum		. 33 "
Breadth of Foramen Magnum		28 ,,,
Depth of Palate		. 13 "

The skull appears to have been that of an adult male.

Skull No. 26 (Text-Fig. 35)

This skull, which was the only part of the skeleton to be found, is much broken, and extensive reconstruction has been necessary. So far as we can judge, it appears to have been the remains of a young female. The bones are light and thin and the frontal region presents well marked eminences, while there is but little development of the glabella and superciliary ridges. A great part of the skull is missing, including the whole of the basis cranii, the posterior part of the frontal, and much of the parietal bones in the region of the bregma and coronal suture, the whole of the occiput, except a small part of the supra-occipital area, the squamous plate of the left temporal bone, and the whole of the left side of the face. In its general character this skull appears to agree with the other members of the mesocranial Mediterranean group.

Norma facialis.

The forehead is rounded and the frontal eminences are fairly well marked. The glabella and superciliary ridges are only slightly developed. The orbits are high; the orbital index is as high as 94.4 (hypsiconch). The malar bones are not prominent. The root of the nose is slightly depressed, and the nose appears to have been of moderate length; there is a tendency to the formation of a subnasal gutter.

Norma lateralis (Text-Fig. 35).

As mentioned already, the glabella is not marked and there is but slight depression at the root of the nose. The nose itself appears to have had a moderately high pitch to the bridge.

Norma verticalis.

So far as we can judge, the skull was probably mesocranial or high dolichocranial. The parietal eminences are moderately well marked. There is no trace of synostosis of the sutures. On the whole the skull would appear, from such parts of it that are left, to conform to Sergi's "ovoides" type.




Fig. 35.

Skull M (Text-Fig. 36; Pl. CLXI, Fig. 22)

This skull reached us bearing no number. It is in a bad state of preservation and a large part is missing, but, as it is of a particularly interesting type, we give such account of it as is possible. The skull appears to have belonged to a male in the prime of life. All the teeth appear to have been cut, and there is no trace of any synostosis in those parts of the sutures that can still be traced, except possibly in the lateral part of the coronoid suture. The size of the cranium is large, the bones are thick, and the muscular attachments are well developed. The thickness of the frontal bone is 6 mm., and that of the parietal is 7 mm.

Norma facialis.

Nearly the whole of the facial part of the skull is missing; all that we have been able to save consists of fragments of the maxillæ. In addition, almost the whole of the right side of the cranium is absent, as well as a large part of the left parietal bone and a portion of the squamous plate of the temporal. The glabella and superciliary ridges are well developed. There is a wide supra-orbital notch on the right side, and a supra-orbital foramen on the left.

Norma lateralis (Text-Fig 36).


When viewed from this angle it is clear that the skull is remarkably long, its great length being due in the main to the great development of the occipital region and the part lying posterior to the external auditory meatus; the meatal position index is 52.36.

Norma verticalis.

Viewed from above the elongate nature of the skull is very marked. The general outline of the skull, judging from that part of it that still remains, would probably conform to Sergi's "ovoides" type. The parietal eminences were apparently not marked.

Norma occipitalis.

There is a wormian bone at the lambda that measures 17 mm. in length by 14 mm. in breadth. The superior nuchal lines are raised into a well-defined ridge, that extends from the inion as far as the asterion.



Norma basilaris.

Extending across the whole width of the basis cranii is a crack that reaches from mastoid to mastoid, running through the foramen magnum; the two parts of the skull have to some extent become separated, the gap between them being about 7 mm. wide. Apart from this crack the margin of the foramen is intact. Even when allowance has been made for the separation, the shape of the foramen during life must have been oval or pyriform, the major diameter lying about the junction of the middle and posterior thirds. The glenoid cavity is deep. The tympanic plates are thick and massive.

The Mandible.

The greater part of the mandible was preserved, but has undergone a considerable degree of warping. The body is of stout build. The teeth in both the mandible and maxillæ are markedly worn, the dentine being freely exposed; the actual degree of wear becomes

considerably greater as we pass from the third to the first molar teeth. The degree of wear of the incisors clearly demonstrates that the teeth during life met in an "edge to edge" bite. The dental arcade is somewhat narrow anteriorly; the bicanine diameter is only 28 mm., but the bimolar diameter must have been in the neighbourhood of 60 mm. The chin is not prominent.

In a number of these skulls it has not been possible to obtain reliable measurements Cranial of the three dimensions, namely, the length, breadth, and auricular height. It has not, Capacity. therefore, been possible for us to calculate the cranial capacity by means of Lee and Pearson's formulæ, neither have we been able in any instance to take a direct measurement, owing to the fragile or incomplete character of the skulls. In those cases where Lee and Pearson's formulæ could not be applied, we have made use of the formulæ given by Wingate Todd.2 It must be borno in mind, however, that his formulæ were calculated for the crania of the white races inhabiting America, and may not, therefore, give very reliable results when applied to skulls of an entirely different character, especially those of the Proto-Australoid race. In the following table we give the various capacities calculated according to these two methods:

No. of	Lee and Pearson's	Win	gate Todd's for	mulæ.	
	formulæ.	Length.	Breadth.	Height.	Average.
	ccs.	ccs.	ccs.	ccs.	ccs.
ĭ	1265.97	1351.98	1183.98	1327 - 51	1282.36
2	-	1487.08	_	1399.60	1443 . 34
6	1201.71	1371 - 75	1232.60	1341.94	1286.99
7	1268 - 56	_	_	_	1268 - 56
-8	1345 - 44	1375.05	1242.33	1399.66	1340.62
10	_	1375.053	-	1385.233	1380.14
II	1551.52	1480.49	1316.66	1515.10	1515.70
14	1157.4	1276.203	1349 · 36 3	1184.353	1241.83
19	_	1434.36	_	1270.44	1352.40
26		_	1222.873	1414.093	1318.48
M-	1494.19	1506.85	1225.98	1500.67	1500.57

From the above results it can be seen that on the whole the figure for the cranial capacity given by Wingate Todd's formulæ and calculated from the breadth measurement is considerably below the figure obtained by the other methods; almost the only exception to this is to be found in Skull No. 14. Soren Hansen 4 has maintained that in fossil skulls very little reliance can be placed on the cephalic index as deduced from the length and breadth measurements, as, owing to pressure from the superincumbent earth, these skulls are frequently deformed and in consequence the dimensions are altered. As the skull usually lies on its side, the breadth measurement will be too small, and, conversely, the length measurement will become increased. The figures given in the above table certainly appear to bear this, out, for in the main the cranial capacity calculated from the breadth measurement is lower, and in certain cases very considerably lower, than the capacity calculated from either the length or the auricular height.

¹ Lee and Pearson, "A first study of the Correlation of the Human Skull": Phil. Trans. Roy. Soc. London, Sories A, vol. exevi, p. 247, London, 1901.

² Wingate Todd, "Cranial Capacity and Innear Dimension in White and Negro": Amer. Jour. Phys. Anthropol., vol. vi, No. 2, p. 167.

³ These figures are probably somewhat too high, as Wingate Todd's formulæ apply to adult males only.

⁴ Soren Hansen, "On Posthumous Deformation of Fossil Skulls": Man, vol. xix, No. 65, p. 121, London, 1919.

On the other hand, in those cases in which it was possible to obtain all three measurements, the capacity calculated from the length or the auricular height is somewhat greater than that deduced in accordance with the Lee-Pearson formulæ, and, of course, a flattening of the skull transversely will tend to increase both the total length of a skull and its auricular height. The exception to the rule, No. 14, is the skull of a child, which is of a markedly brachycephalic type; a reference to the photograph of the skeletons, while still in situ, shows that in this case, unlike most of the skulls, the skull was not lying on its side but was on its back, lying on the occiput with the face upwards, so that, if there has been any flattening owing to the pressure of the earth, the skull will have been rendered more brachycephalic than it was in life, and this will have produced the increased result in the calculation of the cranial capacity from this measurement.

The Teeth.

	No. of		Molar 1.			Molar 2.	
Race.	skulls.	Length. mm.	Breadth.	Index.	Length.	Breadth.	Index.
Mohenjo-dar, Nos. 2, M-:— Proto-Australoid type	3	10.25	. IO.O	97.56	10.2	9.85	96.57
Melanesians	. ,20 . II	11.42	10.96	96.0	10.69	10.55	98.7
Mohenjo-daro, No. 136 (3) Mongolian type	· 6	11.4	10.62	102.5	12.2	11.8	96.1
Chinese	. 2	11.2	11.4	101.8	10.8	10.8	100.0
Mohenjo-daro, Nos. 6, 7, 10, 19, 26:— Mediterranean type	9, 6	*10.53	10.84	102.94	6.69	10.30	106.71
Nal Skull, Mediterranean	. I	11.25	13.0	115.56	10.62	11.75	110.59
Mohenjo-daro, No. 20:— Alpine type	1	11.18	10.95	97.95	10.77	10.63	98.70

From the above it may be seen that there is on the whole a very fair agreement as regards the length-breadth indices of the two first molar teeth between the Proto-Australoid type of skull found at Mohenjo-daro and those of the aboriginal Australians and Tasmanians. In two of the three groups the index of the first molar tooth is higher than that of the second, the exception being the Melanesians; and, further, the index of the Mohenjo-daro skulls falls between those of the other two groups.

As in most early skulls, the teeth are badly worn, the dentine being freely exposed. The only skulls that are exceptions to this general rule are No. 1, which is comparatively recent, and No. 7. Sergi, Buxton, and Keith have all commented on the degree of wear in the teeth of the skulls from Anau, Kish, and Al-'Ubaid respectively, and we have also noted

its presence in the Nal skull.

Conclusions.

In spite of the fragmentary nature of some of the skulls and the degree of warping that others have undergone, it is, we think, possible and justifiable to draw certain conclusions from the material before us. The skulls are, without doubt, not a homogeneous series, and there seems to be evidence that at least four different types are represented.

Type I. PROTO-AUSTRALOID RACE

To this type belong skulls Nos. 2, 11, and M. All these three skulls are remarkably long and fall in the dolichocranial group; the individual indices of the two skulls, that are sufficiently complete to enable us to determine the index, are 68.72 (No. 11) and 63.32

(No. M), the average of the two being 66.02. The sides of the skull are flattened and appear to rise nearly vertically from the mastoid region. The vertex is highly arched, the average height index being 70.68, while the average auricular height is 122 mm. As pointed out in the case of skull No. 11, there may be a tendency to scaphocephaly. The proportion of the skull that lies behind the level of the external auditory meatus is extraordinarily high, the meatus lying nearly midway between the nasion and the inion. As already mentioned (vide supra, p. 607), Keith 1 has called attention to this feature in the long crania of the Veddahs, and, more recently,2 in his Report on the human remains excavated at Al-'Ubaid and Ur. Up to the present time but few anthropologists have paid any attention to this feature, and we, are, therefore, not in possession of data from other collections that we can make use of for the purpose of comparison. In order as far as possible to remedy this defect, we have calculated the auditory-meatus-position index (vide supra, p. 607) from measurements taken on dioptographic tracings of Australian, Tasmanian, and Veddah skulls, as well as from three skulls of a similar type from Adittanallur. In the table below we have given the auditorymeatus-position index in the skulls before us, as well as those calculated from the data given in the various works referred to :-

		Race					Auditory Meatus Position Index.
Mohenjo-dan	ro, N	os. 2,	II, a	nd M	[3	48.1
Veddah .						5	51.43
Tasmanian						20	51.49
Australian	?.					20	53.01
Ādittanallur						3	54.60

From the above it is clear that there is a very close degree of similarity between the different groups, which form a consecutive series.

The superior nuchal lines in all three skulls are well developed, and the individuals appear to have been of muscular development. The glabella is well marked and the superciliary ridges also tend towards a high degree of development. The nose seems to have been comparatively broad, but was also moderately arched. In one of the skulls (No. 11) there was some degree of subnasal prognathism. In those cases where the anterior teeth are still present it is clear that the upper and lower incisors met in an "edge to edge" bite and did not overlap, as in the case of most modern skulls. Keith has stated that this "edge to edge" bite is common in early skulls and in all primitive races. We cannot, therefore, lay much stress on its occurrence in these skulls from Mohenjo-daro, but it is interesting to note that Turner has called attention to the fact that this type of "bite" is a characteristic of skulls

I Sir Arthur Keith, "Report on two crania of considerable but uncertain Antiquity": Journ. Anthropol. Soc. Bombay, vol. xi, p. 671, Bombay.

² Sir Arthur Keith, "Report on the Human Remains" in H. R. Hall, Ur Excapations, vol. i (Al-'Ubaid), p. 232, 1927, Oxford.

³ R. J. Berry and A. W. D. Robertson, "Dioptographic Tracings in three norms of 90 Australian Aberiginal Crania,": Trans. Roy. Soc. Victoria, vol. vi, 1914.

A. J. Berry and A. W. D. Robertson, "Dioptographic Tracings in four normae of 52 Tasmanian Crania": Trans. Roy. Soc. Vidoria, vol. v, 1909.

⁵ (a) P. and F. Sarasin, Ergebnisse naturwissenschaftlicher Forschungen auf Ceylon, vol. iii; Die Weddas von Ceylon und die sie umgebenden Völkerschaften, Wiesbaden, 1892-3. (b) A. Keith, loc. cit.

6 Sir Arthur Keith, The Antiquity of Man, vol. ii, p. 670, London, 1925.

⁷ Sir W. Turner, "The Relations of the Dentary Arcades in the Crania of Australians": "Journ. Anat. and Physiol., vol. xxv, p. 463, London, 1891.

of the Australoid group. The cranial capacity of the skulls is comparatively large. We have given above on page 637 the calculated cranial capacities of all the skulls under consideration, and it is clear that these three skulls, Nos. 2, 11, and M, have a considerably greater capacity than the others. It is interesting to compare the size of the cranium in other races that belong to the same type; we have, therefore, in the following table given certain data on this point:—

Geological period.	Ra	ce.		Author.	No. of skulls.	Cranial capacity, Average.
Pleistocene	Java, Wadjak .			Dubois	2	1600 ccs.
"	Europe, N. Africa			Boule	4	1450 "
"	Australian (Talgai)			E. Smith	I	1300 ,,
"	Rhodesia			Boule	I	1280 ,,
Recent	Proto-Australoid				0	
,,	Mohenje-daro .			_	3	1490 ,;
0 "	Ādittanallur .			_	4	1532 "
,,	Tasmanian .	.0		Martin		1406 "
				Martin		1347 "
,,	Australians .			Boule		1340 "
				Keith	_	1287 "
"	Veddahs			Sarasin	18	1278 "

There is thus very close agreement between the present skulls from Mohenjo-daro, the recent extinct Tasmanian race, and the prehistoric Homo neanderthalensis from Europe and North Africa, the cranial capacity falling between 1400 and 1500 ccs. The Rhodesian skull falls very near the Veddahs, having a very considerably reduced capacity, namely, 1278-80 ccs., and is only just surpassed by the Talgai skull and the modern Australian Aboriginal. The lower jaw in these skulls is very strongly built, with a wide bigonial diameter, and a short ascending ramus. There can, we think, be little doubt that the skulls of this type must be referred to the Proto-Australoid Race. Among the skulls that have been excavated at Adittanallur there are some of the same type and these have been definitely referred to the Proto-Australoid race by Elliot Smith.1 In addition to the evidence of the skulls, we have a certain amount of information regarding the living height of the individuals of this group. As mentioned above (vide supra, p. 604), the data supplied by the Camp Medical Officer gives the length of two long bones, namely, the tibia and fibula, in skeleton No. 11, and from these measurements the calculated living height of the individual would be in the neighbourhood of 1553 mm. or 5 feet and 1 inch. This is distinctly on the small side, and agrees with what we should expect to find in an individual of the Proto-Australoid race.

A comparison of the skulls excavated at Mohenjo-daro with those discovered at Kish and described by Buxton 2 appears to us to indicate that certain of the Kish skulls agree in certain characteristics very closely with those from Mohenjo-daro that we attribute to Type I. Buxton remarks: "The skulls are relatively long and narrow, of small cubic dimensions and occasionally of massive appearance, with heavy brow ridges and a keel-shaped top to their heads." As regards the cubic dimensions of these massive skulls from Kish, the cranial capacity as given by Buxton for Kish skull No. 3 is 1409 ccs.; for No. 5, 1420; and for

¹ G. Elliot Smith, The Evolution of Man, p. 130.

² L. H. D. Buxton, "On the Human Remains excavated at Kish" in S. Langdon, Excavations at Kish, vol. i, pp. 115-25, Paris, 1925.

No. 7, 1431. All three of these skulls belong to his massive type, and their corresponding cranial indices are respectively 66.84, 69.43, and 67.70, thus giving an average of 67.42. It is a matter of some difficulty to compare our skulls with the account given by Buxton, as we have been unable to discover to which, if indeed to any, standard of measurement he is conforming, and he further makes use of terms that do not appear in any of the recognized conventions; for instance, he gives a "palato-maxillary breadth" and "palato-maxillary length" and from these deduces a "palato-maxillary index"; but, so far as we can ascertain, and judging from the dimensions that he gives, he is referring to the palatal length and breadth of the International Agreement. Keith in his recent account of the skulls excavated at Al-'Ubaid and Ur also appears to have had certain skulls that conform very closely to this type, especially Nos. I, II, III, IV, and VII of the Al-'Ubaid skulls. A comparison of the photographs given by us, Pl. CLXI, Figs. 14, 15, and 22 and Text-Figs. 14 and 36, with those given by Buxton (loc. cit., pl. xlvi, figs. 1, 3, and 6, and pl. xlvii, fig. 1) and the tracings given by Keith (loc. cit., pls. lxiii-lxvii) sufficiently indicates how close is the resemblance.

In the Table below we have given some of the characters of the skulls of the present type from Mohenjo-daro, and for the purpose of comparison we have also given these characters for the "massive type" skulls from Kish (Buxton), certain skulls from Al-'Ubaid (Keith), the Veddahs (Sarasin), and a series of nine skulls from Adittanallur:—

	Kish Nos. 3, 5, 7 (Buxton).	Al-'Ubaid Nos. 1, 2, 3, 4 and 7 (Keith).	Mohenjo-daro Nos. 2, 11, M.	Adittanallur 9 skulls.	Veddah (Sarasin).
	ccs.	ccs.	ccs.	ccs.	ccs.
Cranial capacity . ".	1417	1498.5	1490	1532	1278
Cranial index	67.42	72.6	66.02	69.7	70.5
Length-height index .	69.9	71.26	70.68	70.58	73.7
Auricular height index .	_	62.2	60.03	67.06	-
Upper facial index .	49.6	55.1	53.93	50.45	51.4
Total facial index		92.06	88.98	_	88 - 2
Nasal index	44.4	49.2	51.06	51.62	52.7
Nasal length	54.0 (No. 3	53.3	46.5	52	46.9
Orbital index	72.7	83.4	84.46	85.86	89.8
Palatal index	67.3	_	89.36	9 89.32	77.0
Bizygomatic width .	123	127.6	127.0	130.5	123.5

It seems to us that all the above series show evidence of relationship. As regards the cranial index, the skulls from Al-'Ubaid are not so elongated as those from Mohenjo-daro, but the skulls from the other localities form a series of connecting links. In the facial part of the skull, the individuals from Al-'Ubaid have a considerably longer face than those from Kish; the Adittanallur skulls tend to approximate to the Kish type, while the Mohenjo-daro skulls are nearer to those from Al-'Ubaid. As regards both the nasal and orbital indices, we have a regular graded series commencing in the Kish skulls with a nose that is long and narrow; in the Al-'Ubaid skulls the nose is slightly shorter and distinctly broader, and these changes are even more marked in the Adittanallur and Mohenjo-daro skulls, which have chamærrhine noses, and finally the maximum alteration is found in the Veddahs. Similarly, the orbit is very low in the Kish skulls and reaches its maximum height in the Veddahs. Another alteration in the character in the face is the change from orthognathism to prognathism. In

¹ Sir Arthur Keith, "Report on the Human Remains" in Hall, "Ur Excavations, vol. i, Al-'Ubaid, pp. 214-40, Oxford, 1927.

the Kish skulls there is marked alveolar prognathism. (vide Buxton, pp. 115, 116), in the Al-'Uba'd there is, according to Keith, no trace of prognathism, but in the Mohenjo-daro

and Adittanallur skulls prognathism is again evident.

In the Al-'Ubaid skulls the supra-orbital ridges are well developed; in the whole series Keith gives an average measurement of 103.8. In the three skulls from Mohenjo-daro this measurement is 104.7, and three skulls from Adittanallur gives the same average measurement as that of the Al-'Ubaid skulls. The bizygomatic breadth, again, shows a graded series from the Kish to the Adittanallur skulls.

Keith has called attention to the importance of the facial projection in the antero-posterior plane in determining relationships. Beyond the data given by Keith we have no basis of comparison. In these skulls from Mohenjo-daro the orbital margin is very nearly the same distance in front of the meatal plane as in the Al-'Ubaid skulls, the measurements being 69.7 and 70.6 respectively; but the forward projection of the cheeks as shown by the position of the malo-maxillary point is considerably greater in the Mohenjo-daro skulls, being 73.0 mm. as opposed to 70.2 in those from Al-'Ubaid. The nose is markedly less prominent in the Mohenjo-daro skull, the distance from the front margin of the orbit being only 15 mm., while in the Al-'Ubaid skulls it is 20 mm. Associated with this, there is in the Mohenjo-daro skulls a marked depression of the nasion.

Keith (pp. 215-16) remarks: "If we look at a map of Asia on which the areas occupied by the various racial divisions of mankind are indicated... we see that Mesopotamia lies along a racial watershed or zone of transition. To the south and west lies the whole of the great Arabian peninsula, from the Indian ocean to the Levant, marked as the home of the Semites; to the north and east the homeland of the Iranians stretches from the valley of the Indus-to the Black Sea", and he points out that the inhabitants of Al-'Ubaid partook of the characters of both races and represent a transitional stage between the two types. Mohenjo-daro, lying near the mouth of the Indus, may be said to be between the homeland of the Iranians and peninsular India, the homeland of the Proto-Australoids.

Type II. MEDITERRANEAN RACE

To this type we attribute skulls Nos. 6, 7, 9, 10, 19, and 26. These skulls are of considerably less size than those of Type I, the average cranial capacity being only 1332.5 ccs. The shape of the skull is long and moderately long, the average cranial index being 67.67; this is, however, probably slightly too low, for included in the series is one skull that gives a cranial index of only 57.45, and this is in the main due to posthumous compression and fracture. The sides of the skull in this type are not so flattened as in Type I, but tend to bulge somewhat above the mastoid region. Both frontal and parietal eminences are, as a rule, fairly well marked. The proportion of the cranium that lies behind the external auditory meatus is high, the average meatus position index being 52.81. This is appreciably higher than the index in the Proto-Australoid skulls of Type I, which is only 48.1, but is not higher than the average index in the Proto-Australoid skulls from Adittanallur or in the Australian skulls. The muscular attachments are not so markedly developed in this series. The glabella is, as a rule, only slightly prominent, and the superciliary ridges are not pronbunced. The nasion is not depressed. The nasal index is on the average 48.63, talling in the low range of the mesorrhine group. The actual nasal length varies from 41 mm. to 52.29 mm., the average being 46 mm., so that the nose tends to be short. The interorbital width is narrow, varying between 21 and 26 mm., and the bridge of the nose is narrow and high-pitched; in attempting to estimate the degree of prominence of the nose we have

followed the method proposed by Keith, taking the distance between the anterior inferior margin of the orbit and the most prominent part of the nose as shown on the craniogram. The average projection is 26.1 mm., and ranges between 24.0 mm. and 33.5 mm. The mandible is of slight build, and the average bigonial breadth is only 84 mm.

This type of skull we consider to represent the true Mediterranean race, and the examples in the present collection agree very well with the "Nal" skull from Balūchistan and Skull No. 4 in Buxton's account of the Kish remains. In the following table we have given the various characteristic indices, etc., of the skulls that we attribute to this Mediterranean type, and for the purpose of comparison we have also given the corresponding indices, etc., for the Kish skull No. 4, as recorded by Buxton, skulls No. 1 and 2 from Anau, recorded by Sergi, three male skulls from Ur, recorded by Keith, and the "Sialkot" and "Bayana" crania.

0,	,	,					
Character.	Mohenjo-daro Skulls, 6, 7, 9, 10, 19, and 26. Average.	Nāl cranium.	Ur-Skulls & (Keith).	Kish Skull No. 4.	Anau Skulls Nos. 1, 2.	" Siālkot" Skull.	"Bayāna" Skull.
Cranial capacity.	. 1332.5	1443 - 2 4	1413.5	1328	1378-14	13604	1250.5
Cranial index .	. 66.2	70.0	69.8	69.1	76.2	71.1	71.3
Length-height index	. 75.23	77 . 45	72.65	66.49	_	77 . 78	73.60
Auricular height ind	ex 64.02	63.83	60.0	_	57 · 84	66.11	60.67
Facial index .		60.0	57.97	45.2	_	-	-
Nasal index .	. 48.2	46.9	48.77	44.4	46.8	-	-
Orbital index .	. 88.11	782.5	90.0	86.84	83.3	-	-
Palatal index .	. 79.16	79.25	-	75.0	_	-	

There can, we think, be little doubt that all these skulls belong to the same type. So far as the individual differences shown in the table are concerned, especially the differences in the length-height index of the cranium and the various indices of the face, it is possible that we have here evidence of a tendency to the development of separate local races within the limits of a single group, as has been suggested by Buxton,² but one is not justified in arriving at any definite conclusion in the matter owing to the comparatively few skulls available at the present time from any one of these localities. Among the data that we possess, we have evidence of one sort or another regarding the living height of three individuals belonging to this type, namely, of one man and two women. The male was about 5 ft. 4½ in. The two women are considerably shorter than this, measuring, respectively, 4 ft. 9 in. and 4 ft. 4½ in., or an average height of 4 ft. 6½ in.

Type III. Mongolian Branch of the Alpine Stock

This type is represented by a single skull, No. 13 b (3). The skull is quite characteristic, and for the purpose of comparison we have given both side and face views of a Naga skull, No. N. 189, in the Indian Museum collection (cf. Pl. CLX, Figs. 5 and 6 and 7 and 8). The close correspondence between the two leaves no room for doubt regarding the racial origin of the individual.

- 1 Sir Arthur Keith, "Human Skulls from Ancient Cemeteries in the Tarim Basin": Journ. R. Ant. Inst. of Great Britain and Ireland, vol. lix, p. 167. London, 1929.
- ² L. H. D. Buxton, "On the Human Remains Excavated at Kish" in S. Langdon, Excavations at Kish, vol. i, p. 122, Paris, 1924.
- ³ G. Sergi, "Description of some skulls from the North Kurgan Anau" in Pumpelly, Explorations in Turkestan, vol. ii, p. 446, Washington, 1908.
 - 4 Estimated according to Lee-Pearson formulæ Nos. 10 and 11.

TYPE IV. ALPINE

In the present series there is only one skull that can be definitely shown to be brachycephalic, namely, that of the child, No. 14. There are, however, certain other skulls that seem to us to have, in all probability, belonged to this group, namely skulls No. 8, 13, and 20. Unfortunately, all these skulls are in a poor state of preservation, and it is only on No. 8 that we have been able to take definite measurements, and even in this case the skull was badly damaged. No. 13 is the skull of a female, which lay close to No. 14, the brachycephalic child; this skull was very badly damaged, the cranial portion was in two parts, but the left half of the frontal bone, part of the left parietal, and the left temporal bones were more or less intact. The occipital bone was fractured down the middle line, but clearly showed that the supraoccipital region was composed of two large wormian bones of about equal size; the right parietal and part of the right temporal bones were impacted in the right half of the cranium, and the whole of the face and the basis crani were missing. The bones were extremely thin and fragile, and an attempt to reconstruct the skull proved disastrous. So far as we could judge, the skull must have been at least a high mesocranial, and may even have been brachycranial, though not so markedly so as Skull No. 14. That this individual was a female we have no doubt, and if she was, as we are inclined to believe, the mother of No. 14, it is only to be expected that the child would exhibit a greater degree of brachycephaly. Skull No. 20 was one of those that had been left in situ for a year, and when it was removed for examination was in a very bad state of preservation. The nasal and maxillary portions of the face were completely separated and partially missing; the whole of the vault of the skull and the greater part of the occipital area were wanting, as also were the left temporal region and the mastoid. The mandible was without either ascending ramus. As a result, it is impossible to arrive at any definite conclusion regarding the original shape of the skull, but we are of opinion that it was in all probability brachycranial. There is sufficient of the posterior region to show that the skull was not a long one (vide Text-Fig. 34), nor does it exhibit any tendency to the posterior prolongation of the cranium behind the level of the external auditory meatus, a feature that is so characteristic of the skulls of the Proto-Australoid and Mediterranean types. It seems probable that all four skulls of this group belonged to the Alpine race, but beyond this it is impossible to go, and we are not in a position to determine to which branch of the Alpines they may have belonged. The only indication regarding the probable living height of the individuals of this group is derived from Skeleton No. 20, in which the maximum height, as it lay, was 5 ft. 5½ in.

In conclusion, we would express our thanks to Messrs. Provash Chandra Basu, M.Sc., Bajra K. Chatterjee, M.Sc., and Panchkori Chakravarty, who have given us very considerable

assistance in calculating indices and in compiling the various tables.

Average.	mm. 181.81	16.16	2.5 16.43	21.10	12.67	99.5 99.5 67.87 57.64	95.0	102.5	3.5	90.06	. v. v.	91.4	3.2	3.62	S 83 3 . 5 %
-M. & A		414	1111	1 25		22 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	2 2 2	9 10,11 20	3	132 2 3 11 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	11111	» » »	65 5	4000	35 35
0+ 0+	mm 19	118 124	-		34	5, 24	1 ,1		13			- - - -		-	1 1 1 1 1 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8
97	-			기보	JK	*			, ,				*		
19	188 108 ?	128 82 82	24 74	38 17	32.5	560 500 500 500 500 500 500 500 500 500	33	11111	111	1 0 0 8 4		1111	38	330	1320
infant.	1648 140	118.5 85 7	88 40 19:5	34.5	31	يا وا ا	45 45	115.5 87 87	112	124·5 343 300 479	11111	833	11	ابانا	1 701
12 3	E I	11111	1111	i I I	1 1	ii ii ii ii	1 1	11111	111	HIIII	11111	1111	أرأ	1 2 11	ا ا ا ا ا
11	mm. 195 134 ?	137.5	47.5	27	31.25	104.5 102 113 94.7 74.7 65.25.7	33.5	1115	11 25	B.M.66.5 128 ? 399 — —	11111	1 00 1	105	36.5	8 1 1 1
01	179	116 140 83 }	92 }	41.25	35.5	5	35.5	9	111	18861	1111	127	11-	[11P]	11111
*O	mm.	1121	1121	36	* 1	111111	1 1	11111	11 61	111111	11111	1111	19.6	30.25	133°
*0 ee	mm. 172 131	117 130 93 110	124 94 26	4 4		н ,	9 1	14111	110	370 282 491	11111	883	90	41 34 65	116.5
0+	mm. 173.5 120.5 ?	124 140 } 87	96 }	37.75	31.25	211111	1,1	(1111	11 2	366 2 475	11111	120(L.90) 63 (L. 88)	11,	ıjıı	11111
50 9	mm. 178.5 128	113 132 93 113	1 47 1 1	36	30.5	101 114 66 66 50.5	36.5	28.5 103 94	117	290 558 P 1000 135		85	1 65	44 33.75 31	30 . 30
3 of (13 b.)	mm. 180.5 ? 138.5 ?	120 } 133 } 108	1000	38 38	37.5	110 109 74 53 49	4 1	112 100.5	15.5	318 2	11111	100	19.5	~	126°
10 N	mm. 196	93.5	1111	1.11	1 1	۳ ۱۱۱۱۱	1 68	2	111	, 111111	111111111111111111111111111111111111111	111	861	36.5 7	32 31 32
O+ H	mm. 175·5 123	1112 131 91.5 108 96.5	48.25	19 21 37 L 36·5 R	33.5 L 32.75R 64	81.25 103 57 48.5	36	109.25 96.25 88 89.5	11%	346.5 272 464 98 128	102.5	93	90.5	39.5	110°5 110°5 23
		1										L. port.			
										,		ext. occi		:	.,
										· · · (imum)		tre to			andible
Skull	44	· · · · · ·					,			# %		distance from the centre to distance from the centre to chord (nasion bregma)	THE MANDIBLE		the
	cranial length cranial breadth	r heigl egmati adth breadth	£	(dacryon)	. line	line line breadtl length	· į ·	th readth readth ith.		al bread arc uial arc umference arc	e e		mus	8624	dy of
	num crania num crania heisht—	Auricular height Basilo-bregmatic ontal breadth . frontal breadth id breadth .	c brea	(dac	ight sthios	basion line on basion li gnathion li alveolar br alveolar le length	pital foramen (a) length	bread bital bital bital bread	palate	ccipita anial a cranii circui	ambda line ambda line ambda line inion line.	distance from t distance from t distance from t chord (nasion b	the ra	maximum minimum. eal beight	breadt breadt the be side
	Maximum cranial length Maximum cranial breadth Cranial height—		Bizygomatic breadth Bimalar breadth Nasal length Nasal breadth	Do. (dacry Orbital breadth	Orbital height . Nasion prosthion line	Nesion basion line Profition basion line Nasion gnathion line Maxillo alveolar breadth Maxillo alveolar length Palatal length	Occipital foramen-	(b) breadth Biauricular breadth Outer biorbital breadth Infer biorbital breadth Bimaxillary breadth.	Bimastoid . Height of palate . Palatal depth	Greatest occipital breadth Sagittal cranial arc Transverse cranial arc Ilorizontal circumference Biorbital nasal arc	Occipital arc. Nasion lambda line Basion lambda line Nasion inion line.	The position (a) di (b) di (c) Frontal ch	Bigonial breadth . Heigat of the ramus	(c) maximum (b) minimum. Symphyscal height Mandibular length	Mandibular angle. Bicondylor breadth Height of the body Right side Left side
	Maxim	Bin Gre	Nas Nas	Orb)	-	200		Pal	,	-		Big. Hei	Syn	Mas Bico Hei
Sr.	- 44	, 400	V 00 0	13 11	1, 2,	2 2 8 9 9 9 1	23	, 42 %	,	33 30 3 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	24 20 25	38	34	4 44	244

TABLE I.-MEASUREMENTS (Continued)

	Average.	10.5 10.5
-	ñ. đ	# 1 0 0 1 1 2 5 7 7 5 8 8 9 7 7 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5
	ð 92	## # 5 # # 1 1 1 1 1 1 1 1 1
-	t 61	8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8 8
	14 infant	12.4 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
	12	[111114111111]
	11 04	# 1 0 8 0 1 1 0 9 9 5 7 3 9 9 5 3 3 9 9 5 3 3 9 9 5 8 9 9 9 5 9 9 9 9 9 9 9 9 9 9 9 9
	0+	38.37. 1 1 1 1 1 1 1 1 1 1 1 1 1 2 2 1 2 3 3 3 3
1	6	H 50 9 9 5 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
	*O	37.2
-	0+	11.25 10.25 82.75 11.25 11.25 336.2
-	f0 9	H 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5 5
	3 ? (13 b).	9 9.73 11.25 10.25 10.25 10.25 10.25 10.25 11.28 12.86 13.40
_	40 4	<u> </u>
	O+ H	36.5 36.5 36.5 36.5 36.5 36.5 36.5
		1ff molar rift molar r
17	okull okull	Post cer
,		
		Right Left Left Opisthig
		Teeth Upper Jaw Nasion to Nasion to Nasion to Nasion to Nasion to

TABLE II.-INDICES

1 10	1
	77.88

No.

TABLE III.—AVERAGE MEASUREMENTS OF THE DIFFERENT GROUPS

	,				
Measurements.		Group A. Skulls Nos. 2, 11, M.	Group B. Skulls Nos. 6, 7, 9, 10, 19, 26.	Skull No. 3 or 13 b.	Skull No. 14.
Maximum cranial length		197 130 122 139 95 127 46·5 22 23 37 31·25 83 66 53·62 46·5	179 · 8 121 · 1 115 · 8 130 86 · 3 94 46 · 1 22 · 3 20 · 1 37 · 3 32 · 8 61 · 5 46 · 3 37	180·5? 138·5 120? 133? 95 140? 53 26 23 38 37·5 74 53 49 47	164 140 100 118.5 85? 40 19.5 21.5 34.5 31 34 34
The position of ext. and. meatus: (a) Distance of and. perp. fi (b) Distance of and. perp. fi Bigonial breadth	rom Inion	95.5 98 101.5 113°	87·3 95·5· 78 132·5°	95 100 — 126°	76 83

Table IV.—Average Indices of the Different Groups

Indices.	Group A. Skulls Nos. 2, 11, M. 3	Group B. Skulls Nos. 6, 7, 9, 10, 19 26.	Skull No. 3 or 13 b.	Skull No. 14.
1. Length breadth 2. Length height index 3. Length auricular 4. Breadth height index 5. Index of the occipital foramen 6. Total facial index 7. Superior facial index 8. Orbital index 9. Nasal index 10. Maxillo-alveolar index 11. Palatal index 12. Ramus index 13. External auditory meatus position index 14. Bregma position index 15. Facial profile angle	66·02 70·68 62·03 107·25 68·48 88·98? 53·93? 84·46 51·06? 126·04 89·36 61·62 48·26 29·37 79°	66·20 75·24 64·01 112·61 76·47 105·85 	76·73? 73·68? 66·48? 96·03? — 52·86? 98·68 49·06 138·49 95·92 62·65 56·21 40·82 82°	85·37 72·26 60·98 84·64 82·35 — 89·85 48·60 — 109·68 — 53·16 33·54 87°

TABLE V.—MEASUREMENTS ON CRANIOGRAMS

		Q Skull r	of Skull 2	Skull 3 (13 b)	of Skull 6	Ş Skull 7	Skull 8	Ç Skull 10	Skull 11	Infant Skull 14	Skull 19	ි Skull M
Nasion inion line		166	189	169	176	172	170	180	184	158	183	191
Nasion to foot of meatal perpend	icular .	92	85	95	99	700	72	105	87	84	99	100
Nasion to foot of bregma perpend		58	-	69	99	58	69	52	57	53	54	54
Calvarial height		93	92	96	108	98	88	103	114	98	102	112
Auditory meatus position index .		55.42	44.97	56.21	56.25	40.69	42.35	58.33	47 . 28	53.16	54.1	52.36
Bregma position index		34.94	-	40.82	37.5	33 . 72	40.58		30.98	33.24	29.50	27.77
Facial profile angle		90°	78°	82°	81°	82°	79°	83°	80°	87°	82°	-
Frontal inclination angle		01°	-	55°	55°	57°	58°	60°	60°	61°	58°	62°
Occipital inclination angle		. 100°	87°	76°	-	84°	78°	88°	86°	82°	85° ,	86°
Calvarial base angle		190	II°	8°	120	_	15°	30°	14°	17°0	9°	-
Calvarial height index		56.02	48.67	56.86	61.36	56.97	51.76	57.2	47.28	62.02	55.73	58.63

TABLE VI.-FACIAL MEASUREMENTS IN AN ANTERO-POSTERIOR PLANE

Skull 1 91 98 65 5 88 93 85 86 90 91 95 95 95 95 95 95 95						0	-						0
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	Skull No.	Pre-auricular length.	Basi-nasal length.	Projection of lateral orbital margin in front of mid-auricular plane.	Projection of nasion.			Projection of sub-nasal point.	of	Projection of lower alveolar point.	ion	Projection of malomaxillary point.	Projection of the nose.
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	Skull r	91	98	65.5		93 *	85	89	89	82	83		26
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	Skull 2	85	1 -	73	79	-	-		_	-	_	71	-
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$	Skull 3	93	-	67.5	91	89	84 . 5	_	96	92	93 - 5	65	_
Skull 10 100 107 57 98 99 92 101 103 — — 66 33.5 Skull 11 90 90.5 66.5 820 — 83 88 89.5 89.5 90.5 75 15	(136)										,,,,		
Skull 10 100 107 57 98 99 92 101 103 — — 66 33.5 Skull 11 90 90.5 66.5 820 — 83 88 89.5 89.5 90.5 75 15	Skull 6	97.5	103.5	69.5	95	99.5	91	95	98	92.5	93.5	_	24
Skull 10 100 107 57 98 99 92 101 103 — — 66 33.5 Skull 11 90 90.5 66.5 820 — 83 88 89.5 89.5 90.5 75 15	Skull 7			62	69		_	69.5	73			_	_
Skull 10 100 107 57 98 99 92 101 103 — — 66 33.5 Skull 11 90 90.5 66.5 820 — 83 88 89.5 89.5 90.5 75 15	Skull 8	80	84		75	76.5	60		76	73 0	60.5	52	10.5
Skull 11 90 90.5 66.5 82.0 — 83 88 89.5 89.5 90.5 75 15 Skull 14 81 — 61. 78 — — — — — 61 — Skull 19 99 105 69.5 96 101 97 97 100.5 89 84 71 28.5 Nal J 89 — 64.5 85 86.5 80 — 86.5 — — — —	Skull 10		107	57	08		02	TOT	102	13	1 -	66	23.5
Skull 14 81 — 61 78 — — — — — 61 — Skull 19 99 105 69·5 96 101 97 97 100·5 89 84 71 28·5 Nal J 89 — 64·5 85 86·5 80 — 86·5 — — — —	Skull II			66.0	820	77	82	88	80.5	80.5	00.5		15
Skull 19 99 105 69.5 96 101 97 100.5 89 84 71 28.5 Nal J 89 — 64.5 85 86.5 80 — 86.5 — — — —	Skull 14	81	30,	61	78		03	00	09.3	09.3	90.3	67	- 5
Nal J 89 — 64.5 85 86.5 80 — 86.5 89 84 71 28.5	Skull 10		701		76					00	0,		28.5
1441 99 - 04.5 85 80.5 80 - 86.5 - - -	Nat I	99	105	09.5	90	06	97	97	100.5	09	04	71	20.5
	Ival /	09		04.5	85	80.5	80	-	86.5	-	-	-	_

TABLE VII.—MEASUREMENTS SHOWING THE PROJECTION OF THE CHEEK IN AN ANTERO-POSTERIOR PLANE 1

•	Skull No.	A	В	С	D	E	F	
	Skull 1 Skull 2 Skull 3 (13 b) Skull 6 Skull 7 Skull 8 Skull 10 Skull 11 Skull 14 Skull 19 Nal I	74 · 5 · 80 · 5 78 · 5 · 78 · 5 · 69 · 63 · 65 · 76 · 68 · 79 · 5 · 71	67 75·5 70·5 71·5 63·5 57 59·5 70 63·5 71·5 66·5	74 85 77 · 5 81 · 5 68 67 74 79 68 81 75	67 · 5 75 67 · 5 60 59 68 76 · 5 60 72 64	42·5 55 50 40 38 43 49·5 40 4:	21 29·5 26·5 ————————————————————————————————————	

¹ Sir Arthur Keith, "Ancient Cemeteries of the Tarim Basin": JRAS. vol. lix, p. 167, 1929. Letters used in this table are the same as those used by Keith.

CHAPTER XXXI

ZOOLOGICAL REMAINS

O far as I am aware, this is the first occasion on which a thorough investigation of the animal remains obtained by archæological excavation in India has been carried out, and it is therefore of no small interest to see to what extent such investigation can furnish data regarding the conditions in which the early inhabitants of these sites lived, and whether by means of such a study we can confirm or refute conclusions regarding these early peoples that have been drawn from other lines of evidence.

GENERAL CONDITION OF THE ANIMAL REMAINS

In almost every instance the animal remains that I have examined are extremely fragile, as was only to be expected from the length of time that has elapsed since Mohenjo-daro was a flourishing city. In most of the specimens the organic material of the bone has completely disappeared, and all that is left are the calcium and other salts; owing to the nature of the soil in which the remains have been buried, many of the bones are impregnated with a deposit of gypsum, and small patches of the same material are common on the exposed surfaces. A curious fact that seems to me to be worthy of special mention is that bones that had been burnt or charred with fire are very much better preserved than those that have not undergone this process. In most instances the animal remains are very fragmentary in character. In not a single instance has a long bone, such as the femur, humerus, or tibia, of a large animal been recovered intact; smaller bones, such as the carpal or meta-carpal bones and the phalanges, are complete in quite a number of cases, and, as a rule, the teeth are comparatively well preserved, though it was rare to get even a small portion of the jaw to which they belonged.

The general characters of the bones clearly resemble those of the collections made at Anau. Duerst,1 describing this latter collection, remarks: "The greater part of the bones have a yellow-brown colour," and the same is equally true of the present series. In both series all the long bones have been broken, but the smaller bones of the extremities have escaped this fate. Duerst (loc. cit., p. 343) also points out that "among the sheep and pigs, there is a great quantity of bones of very young animals", and the same holds good of the Mohenjo-daro collection. In the case of the cattle also the epiphyses of the vertebra had, in several instances, not fused with the centrum, and many of the teeth were also unworn, indicating that the animal from which they came was young and had probably been killed

for food.

Duerst, "Animal Remains from the Excavations at Anau" in Explorations in Turkestan, Prehistoric Civilization of Anau, ed. by R. Pumpelly, pt. vi, Washington, 1908.

THE NUMBER OF SPECIES REPRESENTED IN THE COLLECTION

In all, I have been able to identify without any doubt no less than thirty-seven, or if we include the Polyzoan and Sponge, growing on the mollusc Fasciolaria, and the Anatinid mollusc living in the coral, thirty-nine different species of animals in the collection. Several of these are, of course, domestic or semi-domestic animals, such as one would expect to be associated with a people that had reached so high a stage of civilization as that exhibited by the inhabitants of Mohenjo-daro; others, however, are wild animals that probably inhabited that part of the country either at the time when Mohenjo-daro was a flourishing city or at some later period when the city had been destroyed. In arriving at any conclusion as to the time or period when these animals lived, one has to rely in the main on the depth at which these remains have been discovered, but it must be recognized that this is not always a reliable criterion, since it is possible that in times past the inhabitants of the country or of the city itself may have buried their refuse, which would naturally include such things as the bones of animals that had been slaughtered for food or had been killed as vermin. In such cases the remains would naturally be found at a somewhat lower level than that to which they properly correspond.

I have given below a list of the various remains that I have been able to identify, with the depths at which they were found; and I have in the main followed the classification that has

been adopted in the various volumes of the Fauna of British India series.

Class MAMMALIA
Order CARNIVORA
Family VIVERRIDÆ
Sub-family HerpestinÆ

Herpestes auropunctatus, the small Indian Mongoose

HR 2119, depth 5 ft. below surface. One skull, almost complete. The skull had been completely burnt.

This species is widely distributed throughout Northern India, including Sind, and extends westward through Balūchistān, South Afghānistān, and Southern Persia. The western variety, described by Blyth as H. pallipes and by Gray as H. persicus, is paler and more grey in colour than the type form. In Pl. CLXIII, Figs. 5 and 7, I have given photographs of this skull from above and from the side, and for comparison (Figs. 6 and 8) the same views of the skull of an example of H. auropunctatus from the collections of the Zoological Survey of India. There are a few minor points of difference between the two skulls, but a study of the available material indicates that these are probably merely a question of age.

Family CANIDÆ Canis familiaris

DM 273, depth 1 ft. 10 in. Part of a skull, including the hard palate and two teeth.

Posterior part of left mandible.

Part of right maxilla.

Part of right maxilla (of a second individual).

Part of left maxilla.

Horizontal ramus of right mandible.

Horizontal ramus of left mandible.

Horizontal ramus of right mandible (of a second individual).

HR 5706, depth 5 ft. 3 in. Fragment of lower jaw, including coronoid and articular processes.

Both the skull and jaws undoubledly belong to a species of dog, and probably both come from the same species. The fragment of lower jaw, HR 5706, shows clear points of difference from the wild dog, Cyon diskhunensis, in that the coronoid process of the jaw springs at an oblique angle from the horizontal ramus, instead of being almost at right-angles to it, as in the case of the wild dog. We can, therefore, I think, exclude this wild species from further consideration; it seems certain that the remains are those of one of the domestic or semi-domestic dogs that are so common at the present day around every Indian village, and at the present time live around the site of the excavations. Duerst, in his account of the animal remains excavated at Anau in Turkestan, has considered in detail the characteristics and probable phylogenetic origin of the dog from that locality, and it is very interesting to compare the Anau remains with those excavated at Mohenjo-daro. Duerst (loc. cit., p. 349) states that the Anau dog "has a very strongly marked resemblance to the European shepherd-dog, especially in the facial part", but that it possessed a slightly less-pointed snout and a wider palate, points of difference that might, however, be attributable to sex. He further points out that the Anau dog stands craniologically very near to the dingo and to a dog the remains of which were found at Bologoa in Russia and age attributed to the late Palæolithic period. The Russian dog was described by Studer² under the name Canis poutiatini. As regards the origin of the Anau dog, Duerst advances two theories, either of which would fit the known facts: (I) the theory first advanced by Studer, that the shepherddog was derived from the Russian Canis poutiatini, or (2) that the dingo must have lived in Southern Asia, and that from it both the pariah-dog and the shepherd-dog have descended.

In the table on p. 652 I have given a series of measurements taken on the remains of the Mohenjo-daro dog, and for the purpose of comparison I have given the same measurements in the Anau dog (from Duerst, loc. cit.), in Canis poutiatini (from Studer, loc. cit.), in two specimens of the true dingo dog from Australia, now in the collections of the Zoological Survey of India, and in three Indian pariah-dogs from the collection of the Biological Department Medical College, Calcutta, lent to me by Professor Ekendranath Ghosh, to whom my thanks are due. Duerst (loc. cit., 1908, p. 346) appears to regard the, dental formula in the upper jaw as 3.1.3.3. In the following account I have followed the

formula as given by Reynolds 3 for the Canidæ, namely $\frac{3.1.4.2}{3.1.4.3}$.

From the measurements given in the Table it is abundantly clear that the Mohenjo-daro dog comes extremely close to the Anau dog, and that both are very nearly related to, if not actually identical with, the palæolithic Canic poutiatini, on the one hand, and the present day Canis familiaris var. dingo on the other. Such differences as do exist between the various series of measurements are very slight; the Anau dog seems to be, for its size, slightly wider in the muzzle, but the measurement falls within the limits exhibited by the other examples and is no wider than the muzzle of examples of Canis familiaris var. dingo from both Australia and India; and the differences between the whole series of examples may quite well be due either to differences of sex or age. It would, therefore, appear to be probable that the Anau and Mohenjo-daro dogs, on the one hand, and the dingo dog of Australia and the Indian pariah on the other, possessed a common ancestry that can be traced back to the palæolithic Canis poutiatini of Russia.

Duerst, "Animal Remains from the Excavations at Anau": Explorations in Turkestan, Expedition of 1904, vol. ii, ed. by R. Pumpelly, Washington, 1908,

² Studer, "Über einen Hund aus der Palæolithischen Zeit Russlands. Canis Poutiatini": Zool. Anzeiger, vol. xxix, Leipzig, 1908.

³ S. H. Reynolds, The Vertebrate Skeleton, Cambridge.

TABLE I .- DIMENSIONS IN MM. OF THE SKULL, ETC., OF THE MOHENJO-DARO DOG

Mohenjo-daro Dog. Mohe
Width of muzzle before front premolar
molar .
Width of muzzle in front of premolar 2
molar 2
Width of palate
Height of snout at ant. end of nasal bones
Length of nasals 62.0 72.0 66.5 82 71.5 70.5 85.0 66.0
Width of hasals
Length of teeth (premolars and
molars) 61 1 69 65.0 62.0 66.5 64.0 64.0 75.0 62.5
Length of carnassial tooth 17.5 16.0 17.0 17.0 — 17 18.0 19.0 17.52 18.5 19.0 19.5
Breadth of carnassial tooth 10.0 8.75 9.5 9.5 — 9 11.0 10.0 11.02 8.5 10.5 11.5 10.0
Length of molar 1
Breadth of molar I 15.0 — 14.0 — — 15.0 16.5 16.02 15.0 — 16.5 15.0
Lower Jaw.
Height of vertical ramus 53? 57? 54 54.0 65.0 50.0
Height of horizontal ramus opposite
molar I
Length of molar 1 18:5 20:0 21:5
Breadth of molar 1 8.0 — — 8.0 — — — 9.0
Length of molar 2 9.5 10.0 10.5 9.5 9.5 — 9.0 8.5 9.0 ² — — 10.0

Family SORICIDÆ

Crocidura bidiana = Pachyura Stoliczkana

VS 207, depth 2 ft. One skull complete except for the tympanic bullæ, and the anterior part of a second.

Both the skulls appear to belong to the same species. In both, the character of the dentition is identical; there is a small tubercle inside the basal cusp of each anterior upper incisor tooth; the second incisor is considerably larger than the third, which is, in turn, about equal to the canine; and there is a well-developed gap between the canine and the second premolar, in which almost the whole of the first premolar tooth is visible from the outside. The specific determination of the modern shrews is, in the present state of our knowledge, almost impossible without a great deal of further research. All that one can do, with any certainty, is to refer individuals to certain groups, and there seems little doubt that the specimens belong to the bidiana (= Steliczkana) group. These little shrews are nocturnal in habit, and at the present day commonly frequent houses in search of insects. In Pl. CLXIII, Figs. 1 and 3, I have given photographs of the better preserved of these two skulls, and for the purpose of comparison I also give corresponding views (Figs. 2 and 4) of a skull of Crocidura bidiana from the collections of the Zoological Survey of India.

I This measurement is the length between the extremes of the teeth sockets; the teeth themselves are missing, and at least 1 mm. should be added to give the true teeth measurement.

² These teeth are badly worn down, and the measurements are therefore probably too low.

Order RODENTIA SIMPLICIDENTATA Family MURIDÆ

Mus rattus = Rattus rattus, The Black Rat

VS 125, depth 4 ft. 3 in. Portion of the left half of the mandible including the teeth.

Both in size and in the character of the teeth this fragment corresponds with the common rat.

Order UNGULATA **SUBUNGULATA** **FORWARD AND TO A PROPERTY OF THE PROPERTY O

Family ELEPHANTIDÆ

Elephas maximus, The Indian Elephant,

DK 1212, depth 6 ft. The upper articular surface or caput of the femur. Trial Trench, depth 6 ft. Tip of small tusk.

SD 1683, depth 3 ft. Tips of small tusks (two).

Although these are the only fragments so far obtained of any bony remains of this animal, pieces of ivory are common, and in at least one case a large fragment of a tusk has been excavated at Mohenjo-daro. That the inhabitants were perfectly well acquainted with the elephant there can be no doubt, but the actual finding of a part of the skeleton, as opposed to the presence merely of ivory, is sufficient to show that the animal actually lived in this region, either in the wild state or as a domestic animal, probably the latter. At the present day, wild elephants are still found along the base of the Himālayas, but formerly their range was more extensive; even as late as A.D. 1600 the elephant was found in the wild state in Mālwā, and Nimār, and up to the latter half of last century in the Chānda District of the Central Provinces.

· UNGULATA VERA

Sub-order PERISSODACTYLA

Family EQUIDÆ

Equus caballus, The Horse (Pl. CLXII, Fig. 9)

DM 293, depth 1 ft. 10 in. A large fragment of the right half of the mandible, containing the premolar and molar teeth; and a second fragment containing the same teeth of the left side.

In size the fragment of jaw corresponds exactly to that of a skull of a modern horse in the collection of the Zoological Survey of India. Duerst, in his detailed analysis of the remains of the horse of Anau, has given a Table of Measurements of the dimensions of the teeth in the lower jaw, and it is interesting to compare the present specimen with the details given by him. For the purpose of comparison I have also given the dimensions of the teeth in a skull of Equus caballus in the Indian Museum.

1 Loc. cit., p. 389.

	Mohenjo-daro Horse.		An Ho		Equus caballus in the Zoological Survey of India.		
		R.	L.	R.	L.	R.	L.
Premolar 2	Length	34.5	32.5	32.0	- IIIII.	33.5	32.0
r remont 2	Breadth	18.0	20.0	15.0	_	10.0	10.0
Premolar 3	Length	2,8.0	29.0	27.0	26.0.	27.0	26.0
a	Breadth	21.0	21.0	17.5	20.0	22.0	21.0
Premolar 4	Length	27.0	27.0	_	25.0	27.0	26.0
0	Breadth	21.0	21.0	_	14.0	21.5	23.0
Molar 1	Length	25.0	25.0	_	23.0	25.0	24.5
	Breadth	18.5	19.0	-	16.0	19.5	19.5
Molar 2	Length	25.0	25.0	_	24.0	26.0	25.0
	Breadth	17.5	18.0	-	14.0	19.0	19.0
Molar 3	Langth	30.5	30.5	-	-	31.5	31.5
	Breadth	16.0	15.5	-	_	15.5	16.0

It will be seen that there is a considerable degree of similarity between these various examples, and it is probable that the Anau horse, the Mohenjo-daro horse, and the example of Equus caballus of the Zoological Survey of India, are all of the type of the Indian "country-bred", a small breed of horse, the Anau horse being slightly smaller than the others.

PECORA Family BOVIDÆ

Bos indicus, The Humped Cattle

Trial trench, depth 6 ft.	3rd molar tooth of the right lower jaw.
" "	3rd molar tooth of the left lower jaw.
" "	3rd molar tooth of the left upper jaw.
DK 347, depth 4 ft.	3rd molar tooth of the left lower jaw.
DK 1170, depth 17 ft.	3rd premolar tooth of the right upper jaw.
DK 2410, depth 4 ft.	3rd molar tooth of the right lower jaw.
VS 342, depth 9 ft. 6 in.	2nd molar tooth of the left upper jaw.
HR 5075, depth 6 ft.	3rd molar tooth of the right lower jaw.
HR 4211, depth 6 ft.	1st premolar tooth of the right upper jaw.
SD 1811, depth 3 ft. 6	part of 3rd molar of the right lower jaw.
SD 136, depth 4 ft.	2nd premolar tooth of the left upper jaw.
,, ,,	2nd incisor tooth of the right lower jaw.
SD 800, depth 6 ft.	1st molar tooth of the right upper jaw.
SD 922, depth 9 ft.	1st premoiar tooth of the left upper jaw.
SD 1159, depth 12 ft.	1st premolar tooth of the left upper jaw.
VS 3655, depth 6 ft.	3rd molar tooth of the right upper jaw.
VS 469, depth 10 ft.	Metatarsal and tarsal bones.
SD 1586, depth 15-16 ft.	Metatarsals, 1st and 2nd molar teeth of right upper jaw.
DK 820, depth 5 ft. 9 in.	1st premolar tooth of right lower jaw and 1st and 2nd molar teeth of left lower jaw.
DK 535, depth 6 ft. 10 in.	3rd molar tooth of left upper jaw.
VS 2331, depth 4 fc. 2 in.	Condyle of lower jaw and part of ramus.
DK 2640, depth 15 ft.	Left horn of Bos sp.
SD 906, depth 3 ft.	Frontal region of skull.

The great majority of the remains of cattle found at Mohenjo-daro consist of isolated teeth. Duerst (vide Pumpelly, 1908, p. 363) remarks in his report on the animal remains excavated at Anau, that among the Taurina proper and the Prototaurina the teeth offer an easy means of discrimination: he quotes Rutemeyer (Versuch einer Natürlichen Geschichte des Rindes, Abt. 1, p. 91), who states that "Bison and Yak have become so sharply characterized that their teeth can be distinguished from those of Taurus, Bubalus, and of the Bibovina (Protaurus mihi), through the weakest development of the accessory collums".




Fig. 37.—The grinding surface of the 3rd Molar Tooth (upper jaw) in various species of cattle.

Bos bubalus: 1, Recent? 2, Mohenjo-daro.

Bos frontalis: 3, Recent.

Bos indicus: (slight wear) 4, Nicobars; 5-6, Mohenjo-daro; 7, Nicobars; 8, Bengal.

", ", (moderate wear) 9, 11, Mohenjo-daro; 10, Nicobars; 12, Bengal.

A study of the various skulls of cattle in the collection of the Iadian Museum has shown that there is a very considerable degree of variation in the characters of the teeth, even within the limits of a single species; much of this variation is, doubtless, due to differences of age and sex, but I do not think that the whole of it can be attributed to these causes; and, until we know the limits within which teeti. may vary in any one species, it is only with some degree of doubt that one can refer isolated teeth, such as form the greater part of the Mohenjo-daro collection, to any particular species. In the present series, of teeth the general characters indicate that they belong to an animal of the Taurine group, and from a comparison with the teeth in the Indian Museum collection of skulls it seems probable that they are referable to Bos indicus, the humped cattle. Even within the limits of this species there are considerable variations in the characters of the teeth, and especially in the complexity

of the foldings of the enamel bands. In many parts of India herds of these cattle have run wild, and in the Indian Museum collection are three skulls belonging to the wild cattle from Canorta Island in the Central group of the Nicobar Islands. The history of this, now wild, herd is well known; they are the descendants of the domestic cattle that were left behind when the Penal settlement on Canorta was abandoned some sixty years ago. I have myself seen these herds on many occasions, and I can say without any hesitation that they have improved enormously as a result of the abundance of open grassland and a copious food-supply; and associated with this improvement in their general character there has been a change in the character of the teeth.



Fig. 38.—The grinding surface of the 2nd Molar Tooth (upper jaw) in (1) example from Mohenjo-daro, (2) in wild cattle from the Nicobar Islands, and (3) recent domestic cattle of Bengal.




Fig. 39.—Showing the enamel foldings at different stages of wear in the same tooth.

In Text-figures 37 and 38 I have given outline drawings of the grinding surface of teeth belonging to the Mohenjo-daro cattle, the wild cattle of the Nicobars, and present-day domesticated cattle from Bengal. A comparison of the two series of teeth, slightly worn and moderately worn, shows that there is a great resemblance between the teeth of the wild cattle and those from Mohenjo-daro, whereas the teeth from the domesticated cattle of Bengal show a considerable simplification in the foldings of the enamel bands. This simplification in the foldings of the enamel bands in the teeth of the domesticated cattle of Bengal is clearly shown at all levels in the teeth, and in Text-figure 39 I have given for comparison a series of

sections through the same tooth in examples from Mohenjo-daro, the Nicobars, and Bengal. In the first series, from Mohenjo-daro (Nos. 7 to 4) it can be seen that the folding of the enamel bands tends, if anything, to become more complicated as we proceed from the surface to the root of the tooth; in the cattle from the Nicobars (Nos. 5 to 7) there is but little change; whereas in the domesticated cattle from Bengal (Nos. 8, 9) there is an equally distinct tendency for the enamel bands to become more simple as the tooth gets worn down towards the roots. We, thus get a progressive series commencing with the Mohenjo-daro cattle and passing through the wild cattle to the present-day domesticated cattle. This change I attribute to a steady and progressive deterioration in the cattle, and correlated with this deterioration there is a change in the actual size of the teeth themselves; in the following Table I have given measurements of teeth from the three series of cattle.

TABLE II.—Showing the Measurements in mm. of the Length and Breadth of the 2nd and 3rd Molar Teeth in Different Series of Bos indicus

	Cattle from Mohenjo-daro					
	Mola	ar 2.	Mol	ar 3.		
	Length.	Breadth.	Length.	Breadth.		
	mm.	mm.	mm.	mm.		
	27.5	21.5	31.0	24.0		
	28.5	24.0	30.0	22.0		
	28.5	20.0	30.5	23.0		
	_	_	31.0	19.5		
0	_	_	30.5	23.0		
	_	_	31.5	21.5		
	-	_	30.0	20.5		
Average size	28.17	21.83	30.64	21.93		
	И	Vild Cattle f	from Nicobar	3		
•	25.0	20.5	29.0	21.5		
	25.5	20.0	29.0	21.25		
	27.0	21.5	29.0	23.5		
	27.0	22.0	29.5	23.0		
	27.0	21.0	28.5	21.0		
	26.5	20.5	28.0	20.0		
Average size	26.33	20.92	28:83	31.75		
	1	Domestic Cat	tle of Benga	1		
	25.5	21.0	29.0	21.5		
	25.0	23.0	28.5	22.0		
	25.0	23.0	25.5	22.0		
•	26.5	19.5	26.0	21.5		
	26.5	18.0	27.5	20.5		
	27.0	20.5	26.5	21.0		
	21.0	21:5	,	-		
Average size	24.36	21.07	27.17	21.42		

A comparison of the measurements given in the above table shows clearly that there has been a reduction in the actual size of the teeth; those from Mohenjo-daro are the largest, while the teeth of domestic cattle of the present day from Bengal are the smallest, the wild cattle from the Nicobars being intermediate.

In addition to the cattle teeth in the Mohenjo-daro collection, there is a large fragment of the frontal region of a skull and a single right horn-core that show an extremely close resemblance to the corresponding parts of a recent skull of Bos indicus (vide Pl. CLXII, Figs. 1-3). The presence of granular ridges at the base of the latter indicate that the animal from which it came was an adult. Both these fragments agree closely with Bos indicus, but here again there is evidence that the Mohenjo-daro cattle were larger than they are at the present time. In the following table I have given the measurements of these two fragments and the corresponding measurements in skulls of the wild Nicobar cattle and the present-day domestic cattle of Bengal.

TABLE III .- GIVING CERTAIN MEASUREMENTS OF THE SKULL AND HORN-CORE IN Bos indicus

•	Mohenjo- daro.	Nicobar 1	Islands.	Bengal.
	mm.	mm.	mm.	mm.
Width between orbital margins	162.0	158.5"	152.0	143.0
Least width across the forehead	167.5	164.0	161.0	158.0
Distance between the frontal foramina	117.0	97.5	97.0	97.0
Length of horn-core along the curve .	240	220	185	182
Diameter at base of horn-core	66	67.5	67	56
Circumference at base of horn-core .	198	198	196	167
Width of condyle of lower jaw	48.5	43.0	40.0	_

Duerst, in his account of the cattle remains from Anau, remarks: "It seems very probable, therefore, that the higher layers contained a smaller breed of cattle, which was formed there by the physiographical influence on the climate and on the production of food during the period of aridity at the end of culture period I; or which came into Anau at the same time as the camel, the goat, the hornless sheep, and the shepherd-dog."

The original wild cattle of Europe were larger than the modern domesticated races, and Hodgson also remarks, regarding the Indian Buffalo, that the wild animals are fully a third larger than the largest tame breeds in India. This same reduction in size appears to hold good with Bos indicus, whether the early examples that we have examined from Mohenjo-daro were wild or domesticated.

Blyth, in a paper on the Flat-horned Taurine Cattle of South-east Asia, remarks: "The humped cattle are unknown in an aboriginally wild state; and I am strongly of opinion that they will prove to be of African rather than of Asiatic origin, however ancient their introduction into India; for no fossil or semi-fossil remains of this very distinct type have as yet been discovered in any part of Asia, where the only established fossil Taurine is the Bos namadicus of the Nerbudda deposits, which is barely (if at all satisfactorily) distinguishable from the European Bos primogenius (or true Urus of Cæsar)."

The humped cattle were well known to the ancient Egyptians, but at present we have no evidence of the time of their first appearance in this country; Blyth (loc. cit.) quotes a note by Cowell to the effect that the earliest reference to this animal in Indian literature is to be found in the tenth book of the Rig Vedá, which he places at 900–1000 B.C.; but the finding of the remains at Mohenjo-daro antedated this by about 2,000 years. It seems possible that these cattle were introduced into India from the west by some immigrating offshoot of the Mediterranean race that spread eastwards across Babylonia and Sumer.

^{, 1} Ed. Blyth, "On the Flat-horned Taurine Cattle of S.E. Asia": JASB. vol. xxix, p. 282, Calcutta, 1860.

Bos bubalus & Bubalis bubalis, The Buffalo

```
HR 2974, depth 3 ft. 3rd molar tooth of the right upper jaw.
```

HR 3043, depth 4 ft. 6 in. 1st molar tooth.

SD 2581, depth ? Calcaneum.

SD 2250, depth 4 ft. Lower portions of left humerus.

VS 2331, depth 4 ft. 2 in. Portions of lower jaw: (1) with molar 3 of left side; (2) molars 2 and 3 of right side; and (3) premolar 2 and 3 and molar 1 of left side (probably of same animal).

DM 10, depth 4 ft. 5 in. Molar 2 of left lower jaw; molar 3 of right lower jaw.

These remains do not appear to differ appreciably from those of the modern buffalo, though a comparison of the foldings of the enamel in the teeth from Mohenjo-daro and those of recent domestic animals in Bengal indicates the possibility that there has been some degree of simplification in these latter races (vide Text-fig. 37, Figs. 1 and 2).

Ovis sp.

Trial trench, depth 6 ft.

HR 2852, depth 3 ft.

HR 3235, depth 2 ft. 6 in.

SD 108, depth 3 ft. 4 in.

VS 128, depth 1 ft. 2 in.

3rd molar tooth of the right lower jaw.

Part of right mandible (burnt).

3rd molar tooth of the left lower jaw.

1st and 2rd molar teeth, right lower jaw.

Family CERVIDÆ

Sub-family CERVINÆ

Cervus cashmerianus, The Kashmir Stag

HR +27, depth surface. Part of right antler.

VS 2831, depth 8 ft. Part of right antler of young specimen. Shed.

Cervus unicolor. Rusa unicolor, The Sambar or Rusa Deer

HR 27, depth surface. Portion of antler of adult. DM 55, depth 4 ft. 6 in. Part of horn in "velvet".

DK 2133, depth 2 ft. Part of horn in "velvet".

VS 3059, depth 8 ft. 2 in. Part of antler.

SD 1297, depth 3 ft. 6 in. Antler. Shed.
SD 1683, depth 3 ft. Part of antler of a young specimen.

SD 1683, depth 3 ft. Part of antler of a you SD 1443, depth 5 ft. Base of antler. Shed.

DK 578, depth 2 ft. 6 in. Portion of antler.

C 517, depth 7 ft. Portion of antler.

SD 696, depth 4 ft. Portion of antler.

SD 1473, depth 3 ft. Fragment of antler.

DK 990, depth 3 ft. Portion of Sambar horn.

DK 1252, depth 6 ft. 9 in. Portion of Sambar horn.

DK 1252, depth of t. 9 in. Fortion of Sambar horn.

DK 2724, depth 3 ft. Portion of Sambar horn.

DK 4630, 12.3 ft. B.D.

DK 4631, 12.1 ft. B.D. Portions of two Sambar horns.

DK 4632, 13.0 ft. B.D.)

DK 4616, 12·18 ft. B.D. Fragment of Sambar horn.

Specimen SD 1297 possessed a circumference measurement of 5.5 inches, and from the fragments labelled DK 4630, 4631, and 4632 I have been able to reconstruct the basal parts of two other antlers; these give the following measurements:—

(a) Circumference of base 6.25 in.

(b) Circumference of base 5 in.

This measurement is taken round the shaft immediately above the brow-tine and compares very favourably with the size of horns of the present-day examples in the collection of the Indian Museum, among which there are the following:—

1 example of 10 in. circumference.
2 examples of over 7 in. and under 8 in. circumference.
21 ,, ,, 6 in. ,, 7 in. ,,
14 ,, ,, 5 in. and over, but under 6 in. circumference.
13 ,, under 5 in. circumference.

In most cases in which the basal part of the antler is preserved, it is clear that the horns had been shed naturally.

Cervus axis = Axis axis, The Spotted Deer SD 2608, depth 4 ft. Base of antler. Shed.

Cervus porcinus, The Hog-Deer

Trial trench, depth 6 ft. Part of antler.

VS 2898, depth 8 ft. Part of antler.

SD 502, depth 5 ft. Base of antler. Sawn off through pedicle.

SD 1852, depth 10 ft. Tip of antler.

VS 200, depth? Base of antler. Shed.

Base of antler. Cut off through pedicle.

Specimen B 712 gave a measurement of the circumference of the horn above the first tine of 3 inches. Among the series in the Indian Museum are eight examples having a circumference of 3 inches or over, and fourteen examples in which the circumference falls between 2½ and 3 inches.

TYLOPODA Family CAMELIDÆ Camelus dromedarius?

SD 1386, depth 15 ft. Lower portion, including the glenoid fossa, of left scapula.

A comparison of this fragment with the corresponding portion of the skeleton of a recent camel in the collection of the Zoclogical Survey of India leaves no doubt as to its identity. It is interesting to note that up to the present time this is the only example of any remains of this animal, so common at the present time throughout Sind.

SUINA Family SUIDÆ

Sus cristatus, The Indian Boar
Trial trench, depth 6 ft.

Portion of right lower tush.

Ist incisor of right lower jaw.

4th premolar of left lower jaw.

2nd molar of right lower jaw.

2nd molar of right lower jaw.

3rd molar of right lower jaw.

3rd molar of right lower jaw.

3rd molar of right lower jaw.

```
Trial trench, depth 6 ft.
                                   3rd mo'ar of left lower jaw.
                                  Tip of left upper tush.
    3314, depth 1 ft. 6 in.
                                  Part of left lower jaw with 3rd and 4th premolar teeth.
DK 289, depth 2 ft. 6 in.
                                  Part of left upper jaw with premolars 3, 4, and molars 1, 2.
DK 1170, depth 17 ft.
                                   3rd molar of right lower jaw.
DK 1170, depth 17 ft.
                                  3rd molar of left lower jaw.
DK 1530, depth 3 ft.
                                   3rd molar of right upper jaw.
DK 1957, depth 20 ft.
                                  1st molar of left upper jaw.
                                   3rd molar of left upper jaw.
DK 2410, depth 4 ft.
DM 24, trench B, depth 7 ft.
                                  3rd molar of right lower jaw.
HR 3056, depth 3 ft. 9 in.
                                  and molar of left upper jaw.
HR 5573, depth 3 ft. 4 in.
                                  Part of 3rd right molar of upper jaw.
SD, trench F, depth 3 ft.
                                   3rd molar of left upper jaw.
SD
      368, depth 6 ft.
                                   Part of right lower jaw with molars 1, 2, and 3.
                                  Part of right upper jaw with premolars 3 and 4.
SD
      368, depth 6 ft.
SD
                                   3rd molar of right lower jaw.
      502, depth 4 ft.
SD
      621, depth 5 ft.
                                  and molar of left lower jav.
     621, depth 5 ft.
                                   2nd molar of right upper jaw.
SD
                                   3rd molar of left lower jaw.
      800, depth 6 ft.
SD
                                  3rd molar of right lower jaw.
     905, depth 8 ft.
                                  Part of left lower jaw with premolars 2, 3, and 4 and molars 1, 2, and 3.
SD 1190, depth 7 ft.
                                   1st incisor of right upper jaw (two examples).
SD 1589, depth 16 ft.
SD 1659, depth 3 ft.
                                  Part of left upper jaw with molars 2 and 3.
                                  Tip of tush of left upper jaw.
SD 1683, depth 3 ft.
SD 1683, depth 3 ft. "
                                   1st incisor of left lower jaw.
                                   1st and 2nd molars of left upper jaw.
SD 2135, depth 13 ft.
                                   1st molar of left upper jaw.
SD 2294, depth 1 ft.
SD 2586, depth 1 ft.
                                  Tip of tush of right lower jaw.
VS 3256, depth 2 ft.
                                   1st molar of left upper jaw.
                                  Tip of tush of left lower jaw.
VS 3654, depth 6 ft.
                                   Part of left lower jaw with premolars 1-4.
DM
      13, depth 2-4 ft.
                                   Molar 3 of right upper jaw and part of maxilla.
HR 5250, depth 2 ft.
                                  Part of left lower jaw with molars 1 and 2.
VS 2331, depth 4 ft. 2 in.
DK 635, depth 6 ft. 10 in.
                                   Molar 2 of lower jaw.
                                  Part of lower jaw with molars 2 and 3.
      929, depth 8 ft. 10 in.
DM 112, depth 5-7 ft.
                                   Incisor 3.
      595, depth 15 ft. 6 in.
                                   Incisor 2 of left upper jaw.
DK 820, depth 5 ft. 9 in.
                                   Molar 3.
                                  (a) Part of right upper jaw with premolar 4 and molars 1-3 (calcined).
SD 1586, depth 15-16 ft.
                                   (b) Molar 3 (calcined).
```

As the above list of finds shows, the remains of pigs are of comparatively common occurrence and have been obtained down to a depth of 17 feet. Blanford (Fauna of British India, Mammasia, p. 561) remarks: "The wild pigs of Baluchistan and Afghanistan may be Sus scrofa, as are, I think, those of Persia and Mesopotamia." The main difference between these two species, the Indian and European ones, lies in the structure of the last molar tooth in each jaw. I have compared the last molar teeth in this series with the corresponding teeth in the jaws of several wild pigs in the collection of the Zoological Survey of India, and I am unable to detect any difference that would justify one in regarding the specimens excavated as being other than Sus cristatus.

AVES? Gallus, sp.

HR 4097 (b), depth 3 ft. Upper end of humerus.

Left femur.

Posterior part of skull.

Upper end of tarso-metatarsus of left side.

The few fragments obtained agree closely in their general structure with the corresponding parts of the skeleton of the domestic fowl. They are, however, considerably larger, the length of a complete femur from Mohenjo-daro being 103 mm., whereas in the domestic fowl of Bengal it measures only 69 mm. This difference is, however, probably due to the deterioration of the present race of fowls in this part of India.

REPTILIA Family CROCODILIDÆ

Gavialis gangeticus, The Gharial

HR 791, depth 10 ft. Part of a vertebra.

Part of a skull.

HR 1142, depth 6 ft. A body dorsal scute.

HR 3721, depth 3 ft. A tooth.

In a region as near to the River Indus as is Mohenjo-daro, it is not surprising that one should come across the remains of one of these river-haunting crocodiles.

CHELONIA Family TRIONYCHIDÆ Trionyx gangeticus?

DK 2399, depth 9 ft. A left remur; the bone had been burnt.

DK 4904 (a), depth 11.35 ft. B.D. The Hyo-, Hypo-, and Xiphi-plastron of each side.

Boulenger, regarding the known distribution of this species, remarks: "Gangetic river-system; Indus?" Prashad has definitely shown that this species is known from the Indus and the finding of portions of the skeleton at Mohenjo-daro makes its occurrence

there at this early date more than probable.

In Pl. CLXI, Figs. 4 and 5, I have given photographs of the plastron excavated at Mohenjo-daro [DK 4904 (a)] and that of a recent specimen in the collection of the Indian Museum. It will be seen that there are certain differences between the two, especially as regards the combined hyo- and hypo-plastra, which in the Mohenjo-daro specimen is somewhat squarely truncated on its median border, instead of being rounded as in the recent example. There is also a prominent median projection on the hypo-plastron of the Mohenjo-daro specimen, which appears to be only slightly represented in the recent form. In these respects, however, the specimen agrees well with other examples of Trionyx gangeticus in the Indian Museum collection. The niphiplastron is narrower and more elongate than in the recent form. In this respect this specimen agrees closely with the figure of a plastron of T. cartilagineus, Bodd, given by Siebenrock 3 (Fig. 7, p. 826). T. cartilagineus is, however, an eastern form and at the present time is known only from Burma, Malay, Siam, Cambodia,

² B. Prashad in Rec. Ind. Mus., vol. x, p. 267.

¹ G. A. Boulenger, Fauna of British India: Reptilia, p. 12.

³ F. Siebenrock, "Zur Systematik der Schildkrötenfamilie Trionychidæ Bell, nebst der Beschreibung einer neuen Cyclanorbis-Art.": Sitzungsb. der Math.-Naturwiss. Classe der Kais. Akad. der Wiss., Wien, vol. cxi, p. 826, 1902.

and the islands of Sumatra, Java, and Borneo. In spite of these differences from the present-day examples of *T. gangeticus*, I consider it inadvisable to suggest that these remains belong to a different, or to a possibly unknown, form, till more is known regarding the degree of variation that may occur within the limits of any one species.

· Chitra indica

DM 18, depth 4-5.ft. Portions of ribs and part of hypoplastron.

This species is stated by Boulenger's to occur in "The Ganges and Irrawaddy; Indus?" It has, however, been taken by Dr. Prashad in the Indus River-system.

Emyda granosa

Trial trench, depth 6 ft.

A complete epiplastron,
A xiphiplastron.

VS 1074, depth 2 ft. 6 in.

C 1632, depth 1 ft.

DK 4904 (a), depth 11:35 ft. B.D.

A complete epiplastron.
A complete hyoplastron.

Portion of carapace.

The present-day distribution of this species is given by Boulenger (Fauna of British India,

Reptilia, p. 17) as "Indus and Ganges plains, in rivers, canals, etc."

The occurrence of these aquatic reptiles is only to be expected in a region such as Mohenjo-daro, in which the close proximity of the Indus river must have rendered the inhabitants perfectly well acquainted with those animals that inhabit it. In most of the fragments that have been preserved there is evidence of charring, and it seems probable that these aquatic reptiles were a source of food at one time or another in the history of the city.

Family TESTUDINIDÆ

Testudo elegans, The common Land-Tortoise VS 128, depth 1 ft. 2 in. Plastron and part of carapace.

The known range of this species is given by Boulenger (Fauna of British India, Reptilia, p. 22) as "India (except Lower Bengal), extending west to Sind and Ceylon".

Damonia hamiltoni SD 1473, depth 3 ft.

Fragments of both carapace and plastron were present in sufficient numbers to enable the greater portion of the anterior half of the carapace and nearly the whole plastron to be reconstructed; there can thus be no doubt of the specific diagnosis. Boulenger (Fauna of British India, Reptilia, p. 34) reports that this species is known to occur in "Bengal, Panjab, and Upper Sind".

Batagur baska?

SD 188, depth 4 ft. 2 in. Part of a plastron that has been sawn square.

VS 720, depth 9-13 ft. Part of a plastron.

It is with some hesitation that I record this species. The plastron (SD 188) has clearly been sawn, so that the remaining plate is square. I have compared this plate with the corresponding part of the skeleton of a specimen in the collection of the Zoological Survey of

1 G.A. Boulenger, Fauna of British India, Reptilia, p. 16.

² B. Prashad in Rec. Ind. Mus., vol. x, p. 267.

India, and the similarity is so close that I believe them to belong to the same species. On the other hand, however, the distribution of Batagur baska, as given by Boulenger (Fauna of British India, Reptilia, p. 38) is "Bengal, Burma, Malay Peninsula". It is possible, therefore, that the specimen may belong to some other species; but equally it is possible that at the time when Mohenjo-daro was an inhabited city this river turtle was living in the Indus. That the remains were contemporaneous with the Mohenjo-daro civilization is clear from the fact that the bone has been sawn into a square to serve some definite purpose.

PISCES Family SILURIDÆ

Rita rita?

VS 2571, depth 5 ft.

"Oubito-humeral process of the pectoral arch.

"Portion of lower jaw.

HR 3948, depth 13 ft.

"Dectoral spine.

"A pectoral spine.

VS 125, depth 4 ft. 3 in.

Portion of a pectoral spine.

VS 504, depth 2 ft.

Spine of Rita?

Wallago sp.

VS 504, depth 2 ft. A portion of the supra clavicle.
VS 2786, depth 5 ft. 6 in. A portion of the supra clavicle.

Arius sp.

Trial trench, depth 6 ft. Basal portion of the pectoral spine.

" Median portion of a spine (pectoral).

In addition to the above, there were present among the preserved fragments the remains of a typical carp fish.

HR 4623, depth 2 ft. The basi-occipital bone. SD 368, depth 6 ft. The basi-occipital bone.

MOLLUSCA PELECYPODA

Lamellidens marginalis (Lamarck)

DK 230, depth 1 ft. 6 in. Several shells, including a pair.

This species is widely distributed in fresh water throughout India, Burma, and Ceylon. Dr. Prashad, who has kindly examined these shells, informs me that they "are all half-grown specimens of the typical form of Lamellidens marginalis (Lam.), and are similar to those found in the upper reaches of the Panjab river".

Parreysia favidens (Benson)

SD 1473, depth 3 st. . Three valves.
VS 496, depth 2 st. 6 in. A single valve.
DM 63, depth 4 st. 6 in. A single valve.
C 517, depth 7 st. Five valves.

This species is widely distributed throughout Northern India, and according to Preston (Fauna of British India, Mollusca, Gastropoda, and Pelecypoda (Fresh water), 1915) has been taken in the Indus River and throughout the Gangetic system, as well as in E. Cachar, Sylhet, and the Madras Presidency.

Arca granosa Linn. HR 2033, depth 8 ft. A single shell.

This is a common species, and is known to occur throughout the coastal waters of Arabia, India, Malay Archipelago, Japan, China, and Australia. It is probable, therefore, that it was imported from the coast in the neighbourhood of Karāchi.

GASTROPODA

Cypræa arabica Linn.

VS 371, depth 5 ft. 6 in. A single specimen in a good state of preservation; the shell had been bored through, presumably for use as an ornament.

This species is common, and is widely distributed throughout tropical seas; Persian Gulf, coasts of India, Ceylon, Burma, New Caledonia, and Australia. It was probably imported from the neighbouring seacoast.

Cypræa ocellata Linn. C 517, depth 7 ft. A single specimen.

This also is a marine species and must, therefore, have been imported into Mohenjo-daro.

Eburna spirata Lamarck HR 129, surface. A single specimen.

This species possesses a wide distribution throughout the coasts of India and Ceylon and as far east as the Philippine Islands; probably it was imported to Mohenjo-daro from the neighbouring coast.

Fasciolaria trapezium Linn.

L 751, depth 1 ft.

LS 765, "below first pavement."

These two specimens were taken at random as samples from a large number of examples of this species that had been excavated.

This species is widely distributed throughout Indian Seas, its known range of distribution extending from the Red Sea on the west to the Philippines, Java, China, and Auckland Islands on the east. These shells had clearly been imported for the purpose of making ornaments, such as bangles, and other objects, as spoons, etc. The shells had not been subjected to any cleaning process, as is clearly shown by the occurrence on one of them of the remains of a colony of Polyzoa, belonging to the genus Membranipora; the actual species appears to have been M. hippopus Levinsen, which is known to occur throughout the coasts of America, Great Britain, the Mediterranean Sea. and India. The same specimen, L. 765, was also bored by a sponge, probably a species of Cliona.

Turbinella pyrum, The Sank Shell Var. acuta Hornell

HR 61, surface. A single specimen.

This variety of the sank shell has been recorded from the coasts of Ceylon, South India, and from Kāthiāwār.

Var. fusus Sowerby VS 1179, depth 4 ft. 6 in. A single specimen.

This variety of the sank has, hitherto, been recorded from the Andaman Islands; but its occurrence along with the other variety makes it probable that it occurred in the same locality and that both specimens had been imported to Mohenjo-daro from the neighbouring coast. Hornell 1 records that var. fusus may occur, though rarely, on Indian coasts.

Genus Indoplanorbis Annandale and Prashad
Indoplanorbis exustus (Deshayes)
DK (S) 4985, depth 14:15 ft. B.D. A single specimen.

This species is widely distributed throughout India, and its occurrence at Mohenjo-daro is in no way remarkable.

GENUS VIVIPARUS
Viviparus bengalensis (Lamarck)
C 517, depth 7 ft. 5 examples.

This species is also of widespread occurrence throughout India, not only in rivers and streams but also in artificial ponds and tanks, where it is of common occurrence in association with *Indoplanorbis exustus* (Deshayes).

MADREPORARIA
Favia speciosa
HR 607, depth 4 ft. A single rounded colony.

This species of coral is at the present day widely distributed throughout the seas of India and the Far East. It has been recorded from the Red Sea, the Seychelles, Chagos Archipelago, the Maldives, Ceylon, the Aracan Coast of Burma, Mergui Archipelago, Cocos-Keeling Islands, the Philippine Islands, Fiji, and the Great Barrier Reef of Australia. It has obviously been imported to Mohenjo-daro, and is probably from the Karāchi or Kāthiāwār Coast. I have to thank Professor G. Matthai, of the Government College, Lahore, for identifying the specimen for me. The specimen was perforated on its upper surface by several holes that lead down into smooth-walled chambers in the coral mass. Each chamber was occupied by the remains of a Lamellibranch mollusc, belonging apparently to a species of Anatinid; but the fragile shells were too broken to admit of their specific identification.

In all, I have been able to determine the presence of remains of thirty-seven different species of animals. In the following table I have given a list of these animals, and the levels at which they occur.

ı	II	III	IV
Less than 2 feet,	Between 2 and 7 feet.	Between 7 and 12 feet.	Below 12 feet.
-	Herpestes auropuncatus		-
Canis familiaris	Canis familiaris	- , •	
Crocidura bidiana		_	_
	Mus rattus	, -	_
	Elephas maximus	_	_
Equus caballus	_ ^		· —
-	Bos indicus	Bos indigus	Bos indicus

¹ J. Hornell, Marine Zoology of Okhamandal, pt. ii, p. 3 et seq., 1916

I	II o	III	IV ,
Less than 2 feet.		Between 7 and 12 feet.	
Bright Bright File	Bos bubalu?		• _
Ovis sp.	Ovis sp.	_ ,	_ •
		Cerous cashmerianus	
Cerous unicolor	Cervus unicolor	Cervus unicolor	Cerous unicolor
. 0	Cervus axis	_ :	-
_	Cervus porcinus	Cervus porcinus	_
, ->	-	• -	Camelus dromedarius
Sus cristatus	Sus cristatus	Sus cristatus	Sus cristatus
	Gallus sp.		• •
_ `	Gavialis gangeticus	Gavialis gangeticus	_
		Trionyx gangeticus	•
	Chitra indica	-	_
_	Damonia hamiltoni	-	_
	Emyda granosa	-	, – °
Testudo elegans	-	_	• –
	Batagur baska	-	_
-	Rita rita	-	Rita rita
_	Wallago sp.	-	_
	Arius sp.	_	_
-	A carp	-	_
Lamellidens marginali		-	
	Parreysia favidens	_	
-		Arca granosa •	7
_	Cypræa arabica		
_	Cypræa ocellata	_	
Eburna spirata	<u> </u>	-	
Fasciolaria trapezium		_	_
Turbinella pyrum	Turbinella pyrum	_	-
var. acuta	var. fusus	-	
	-	-	Indoplanorbis exustus
	Viviparus bengalensis	-	
-	Favia speciosa	-	

I have made no attempt to correlate the various finds with the different periods of Mohenjo-daro civilization; but have, in a purely arbitrary manner, divided the finds into four groups according to the depth at which they occurred. These depths range from the surface to 17 feet below, and I have taken the first group to include all the remains found in the upper 2 feet, and the remaining three groups are from successive strata, each of 5 feet depth. With regard to the surface stratum, it is impossible to decide to what extent deposition or denudation is occurring, but the presence of a portion of an antler of Cervus unicolor (adult), as well as of the shells of two species of marine molluses, namely Eburna spirata and Turbinella pyrum var. acuta, on the surface, seems to me to indicate that at the present time denudation is progressing, since marine shells cannot have been deposited here nor can this stag have been living recently in this region, and the general character of the horn in no way differs from the fragments found at greater depths.

From the above table it is clear that the number of animal remains steadily increases as we get nearer the surface till we reach the top 2 feet, when it not only drops very considerably but we now get the remains of certain wild or semi-wild animals, such as Canis

familiaris, Crocidura bidiana, and Testudo elegans, as well as the remains of the horse, which appears to be absent from the lower levels. The gradual decrease in the number of animals represented in the collection as we reach the lower strata may be due, at any rate in part, to the nature of the soil, but still more to the fact that only a comparatively small area of the lower strata has been excavated. At Mohenjo-daro and throughout the country round the soil is impregnated with saltpetre that rapidly causes the deterioration and final decay of bony objects, and it is possible that the paucity of animal remains from the deeper levels is due to this; on the other hand, it may be that, with an increase or at least a modification of the state of civilization, more animals were introduced as domesticated herds; this would account for the later presence of Bos bubalus, Ovis sp., and Elephas maximus in the 2-7 ft. level, and their apparent absence from the earlier strata, while similarly the utilization of further natural food-supplies would account for the presence in this level of the remains of Batagur baska and Emyda granosa, and a larger number of fish. The remains can be classified as follows:—

(a) Animals probably maintained in a state of domestication :—

Bos indicus
Bos bubalus
Ovis sp.
Elephas maximus
Camelus dromedarius?
Sus cristatus
Gallus sp.
and at a late date
Equus caballus.

(b) Animals that may be termed semi-domesticated, in that they frequent the vicinity of human habitations:—

Canis familiaris
Herpestes auropunctatus
Crocidura bidiana
Mus rattus.

(c) Animals caught and probably utilized as food:

? Sus cristatus
? Gavialis gangeticus
Lrionyx gangeticus
? Chitra indica
? Emyda granosa
Damonia hamiltoni
? Batagur baska
Rita rita
Wallago sp.
Arius sp.
A carp.

As our excavations have rarely penetrated below the upper strata, it seems to me too soon to draw conclusions on these subjects.—[ED.]

(d) Animal remains, such as shells, imported for ornament or use :-

Batagur baska
Lamellidens marginalis
Arca granosa
Cypræa arabica
Cypræa ocellata
Eburna spirata
Fasciolaria trapezium
Turbinella pyrum var. acuta
,, var. fusus
Favia speciosa

(e) Animal remains imported possibly for medicinal purposes :--

Cervus cashmerianus
Cervus unicolor
Cervus axis
Cervus porcinus

horns only.

(f) Animal remains occurring fortuitously:—

Indoplanorbis exustus

Viviparus bengalensis.

Animals maintained in a state of domestication

The very considerable frequency with which the remains of Bos indicus have been met with during the excavations indicates that the inhabitants of Mohenjo-daro at one stage or other of their history maintained large herds of this animal. In quite a large number of cases the teeth indicate that the animal from which they were derived was young; for instance, in the case of the third molars there has, in many cases, been but little wearing down of the tooth surface, while in a few instances this tooth has only just been erupted. This would appear to indicate that the inhabitants slaughtered these animals for food, and it is possible that this may also provide the explanation of the total absence in the collection of any complete long bone belonging to this species; probably such bones were split in order to obtain the marrow.

It seems clear that the pig was present in large numbers in this area from the very earliest time when Mohenjo-daro was a flourishing city; but it is impossible to determine whether or not this animal was actually domesticated or even whether it was used as a source of food by the inhabitant; in those far-off times. At the present time pigs are of common occurrence throughout these parts, and it is possible that in the old days they existed in large herds that roamed the countryside searching for food. At the present day in and around the city of Bīkaner in the Rājputāna desert the wild pig thrives, and each night large numbers of them wander into the city to feed on the refuse and other matter that has been thrown out by the inhabitants; indeed, in Bīkaner the pig performs the function of a drainage system for the removal of sewage, and it is possible that in Mohenjo-daro in the old days they served the same purpose. If so, it is not surprising that their remains are to be found in large numbers.

That the inhabitants of Mohenjo-daro also kept poultry is highly probable, for unmistakable clay figures of these birds, among others, have been excavated, but although a number of avian bones have been excavated, I am at present unable to say with certainty whether any or all of these belong to domestic poultry or to wild birds. As regards their size,

they are for the most part considerably larger than the present-day race of fowls.

Animals caught for food

With the exception of the carp, all the remains of fish are from examples of the family Siluridæ; of the three genera represented, two, viz. Rita and Wallago, are common inhabitants of the large rivers of India. As regards Rita, Day (Fauna of British India, Fish, p. 165) remarks that their distribution is "Large rivers of Sind, India (except its southern portions), and Burma far above Mandalay"; and Wallago (loc. cit., p. 126) is said to occur in the "Fresh Waters of India, Ceylon, Burma, and Cochin China". In the case of Arius, the distribution is given by the same authority (loc. cit., p. 170) as the "Seas and estuaries of tropical regions, ascending to within tidal influence or even entering fresh waters". All the three species are well known to be excellent food-fish, and it is probable that they were used for food in the past at Mohenjo-daro; examples of the first two genera, Rita and Wallago, were probably caught locally, but it is not likely that a fish such as Arius, which is normally confined to estuarine or tidal regions, would penetrate so far up stream as this, and it seems more likely that these fish were caught further down the river in the neighbourhood of Karachi and were dried and brought up to Mohenjo-daro. At the present day large quantities of this species are caught, dried, and salted on the west coast of India and are exported up country, and possibly a similar trade was in existence in past days also.

The presence of the remains of a number of other aquatic animals, such as the Gharial and turtles, remains of which in many cases have been burnt, indicate that such animals were even in these early times an ingredient of the food of the inhabitants. Annandale 1 remarks: "In the Gangetic delta, and I believe in the other parts of India, Trionyx is regarded as an important article of diet," and Prashad 2 States that "in the Panjab tortoises are not much esteemed as an article of food except by the nomad tribes. The Sahnsies consume them in quite large numbers . . . The flesh is eaten, while the fat is stored and used instead of oil or for making embrocations. The Sickligars also eat these animals, but in much smaller numbers." This raises the question as to how these animals were obtained. That the fish were deliberately sought for and caught can, I think, safely be assumed, and it is highly probable that the methods employed for catching fish were by means of nets, traps, or hook and line. Where fish are caught by means of nets or traps in such a river as the Indus, it is certain that from time to time such other inhabitants of the river as turtles, Trionyx gangeticus, Chitra indica, Batagur baska, and Emyda granosa, will also be caught, and it is not improbable that the Gharial, Gavialis gangeticus, was captured in the same manner. It is possible that these turtles or the crocodile were speared, but such fragments of the shell or skeleton as have been preserved do not show any hole or holes, Such as would be caused by a spear.

Animal Remains imported for Ornament, etc.

The occurrence of the shells of Lamellidens marginalis in the uppermost levels appears to indicate that it was only in the later period that they were imported and used as ornaments by the inhabitants of Mohenjo-daro. As regards the marine molluscs there seems no doubt that a regular trade was carried on between Mohenjo-daro and the seacoast. As Hornell's points out, at the present day, apart from the Gulf-of Mannar and Palk Bay, the coast of Kathiawar is the only considerable source of sank shells; and in very early times sank cutting centres existed in the Southern Deccan and in Kathiawar and Gujarat. While

¹ N. Annandale, "The Indian Mud Turtles" in Rec. Ind. Mus., vol. vii, Calcutta, 1912.

² Bajni Prashad, "Notes on Aquatic Chelonia of the Indus System," Miscellanea: Rec. Ind. Mus., vol. x, p. 267, Calcutta, 1914.

³ Marine Zoology of Okhamandal, vol. ii, The Indian Chank, p. 71.

the actual cutting of the sank shell must have been done by means of metal saws, the fragments in some of these early sites are associated with flint or stone implements, as in the case of the neolithic flint implements at Batapur and Damnagar, Amseli Prānt, in Kāthiāwār, or with sandstone hammers at Kamrey in Gujarāt; and the same is the case at Mohenjo-daro, where flint implements have also been found. At the present time, as probably in times past also, the actual cutting of the sank bangles is an industry that is peculiarly localized, and not infrequently the site of this industry has no direct connection with the region where the sank shells are fished from the sea. At the present day, the main centre of the bangle-making industry is situated at Dacca in Eastern Bengal, while the sank shell is fished either at the extreme south of India, in Palk Bay and the neighbourhood, or on the west coast of India off Kāthiāwār. In addition to the actual bangles or fragments of bangles that have been excavated, the presence of a number of cores, from which the bangles have been sawn, clearly shows that in times past Mohenjo-daro was also a centre of the bangle-making industry.

Animal Remains imported for Medicine

The presence of the remains of four different species of deer among the various animal remains that have been excavated is of considerable interest both from the cultural and the zoological points of view. If these remains are taken to be evidence that these animals were in past times actually inhabiting this part of the country, then there can be little doubt that there has been a very great change in the character of the terrain during the years that have intervened between the final destruction of Mohenjo-daro and the present time. Of the four species represented in the collection only one, namely Cervus porcinus, the Hog-deer, is at the present day an inhabitant of Sind and the area around the site of the excavations. According to Blanford (Fauna of British India, Mammalia, p. 550), the Hog-deer at the present day is found "in the Indo-Gangetic plain everywhere from Sind to the Panjab. It is an inhabitant of alluvial plains". One would, therefore, not be surprised to find the remains of this animal; but as regards the other three, not one of them is now known from anywhere in the neighbourhood. The spotted deer, C. axis, is at the present time found, according to Blanford (Fauna of British India, Mammalia, p. 548), "nearly throughout India and Ceylon. It occurs at the base of the Himalayas, not, however, ascending the mountains beyond the lower spurs, from the neighbourhood of the Sutlej to Nepal. It is not found in the Panjab plains, nor in Sind, and only to the eastward in Rajputana".1 The Sambur, C. unicolor, though having a wide distribution (vide Blanford, Fauna of British India, Mammalia, pp. 544-5) "almost throughout the Oriental region wherever there is undulating or hilly country with forest", is " of course wanting in the treeless plains of the Panjab, Sind, and Western Rajputana." In both these cases the natural habitat is found among the dense vegetation of forests and woods, and it is hardly necessary to point out that such vegetation is at the present time not found anywhere in the vicinity of Mohenjo-daro. The fourth deer that has been identified among the remains, namely the Kashmir Stag, C. cashmerianus, is at the present day found, according to Blanford (Fauna of British India, Mammalia, p. 537), in "the Kashmir valley, throughout the pine forests between 9,000 and 12,000 fest in summer, lower in winter. Not found east or north of Kashmir; a few occur in Wardwan, Kishtwar, Badrawar, etc.; none in Ladak. The range westwards is not known. According to Adams,2 these stags "roam from forest to forest, preferring, grassy glades, alternating with dense forest, where there is a copious supply of water ". It would be a matter of considerable difficulty to find in the whole of India an area of country that is less like the

¹ The italics are mine.—R. B. S. S. 2 Adams in Proceedings of the Zoological Society, 18;8, p. 529.

natural habitat of these three members of the genus Cervus than the desert conditions that at the present day exist throughout the greater part of Sind; and it is remarkably significant that the only remains of these deer that have up to the present time been excavated are the horns. If the animals had been living in this region during the time when Mohenjo-daro was a flourishing city, it is more than probable that at least some of the teeth and other parts of the body would have been preserved. From the evidence I think it is more probable that the horns were imported from some other region. From olden times down to the present day stag's horn has been used in medicine, and in many of the fragments of antlers that have been excavated it is clear that the antler has been sawn through, the foagment terminating below in a cut surface, while in others the antler had equally clearly been shed in the natural way and had subsequently been collected. Apart from the specimens that I have enumerated above, there are in the collection a number of smaller fragments and isolated tines. I have not given these in the list, since it is not possible to decide with certainty from which species of deer they were originally derived. Among these smaller fragments are several that, in addition to the flat end, have cuts and notches in the side of the horn, where small fragments have been removed. The flat end may have been produced either by sawing when the part was removed from the original antler, or may subsequently have been ground down during the process of making a powder, in which form the horn is utilized as medicine. The presence of these fragments is strongly in favour of the view that stag's horn was in past times at Mohenjo-daro a commercial commodity and was imported for medicinal or other purposes.

In conclusion, I must record my indebtedness to my colleagues of the Zoological Survey of India for the assistance that they have given me in the correct identification of many of these fragmentary remains.

EXPLANATION OF PLATE CLXII

- 1. The skull of Bos indicus from the collection of the Zoological Survey of India (from in front).
- 2. The skull of Bos indicus from the collection of the Zoological Survey of India (from the right side).
- 3. Fragments of skull of Bos indicu. from Mohenjo-daro.
- 4. The plastron of Trionyx gangeticus from the collection of the Zoological Survey of India.
- 5. The plastron of Trionyx gangeticus from Mohenjo-daro.

EXPLANATION OF PLATE CLXISI

FIG.								
I.	Crocidura bidia	na. Sk	ill from th	e dorsal	aspect;	× 2.	From Mohenjo-	daro.
2.	" "	Sk	ill from th	e dorsal	aspect;	× 2.	Recent, ex coll.	Z.S.I.
3.	,, ,,	Sk	ill viewed	from the	side;	× 2.	From Mohenjo	-daro.
4.	" "	Sk	ill viewed	from the	side;	× 2.	Recent, ex coll.	. Z.S.I.
5.	Herpestes auropu	inctatus. Sk	all viewed	from the	dorsal	aspect.	From Mohenjo	-daro.
6.	" "	• Sk	ill viewed	from the	dorsal	aspect.	Recent, ex coll.	Z.S.I.
7.	,, ,,	Sk	ill viewed	from the	side.	From N	Iohenjo-daro.	
8.	" " "	Sk	ll viewed	from the	side.	Recent,	ex coll. Z.S.I.	
9.	Equus cabaclus.	Lo	wer jaw, r	ight side	$; \times \frac{1}{3}$			

LIST OF ADDITIONAL SPECIMENS

MAMMALIA

DK 3702 Chamber 189 8.9 ft. below datum Upper portion of shaft of right humerus with bicipital groove. Portions of a pair of ulnas and part of shaft of a fibrila. Almost certainly human.

							,
SD	2828	Chamber	41	3.5 ft.	above	datum .	Fragments of bones. One Phalanx. Fragments of horn
	• •						, (? sawn off at butt-end), probably of Cervus porcinus,
•				-		0	the Hog Deer. Great trochanter of femur of small
				,			mammal (? sheep or deer).
DK	3964	Chamber	238	10.0 ft.	below	datum	Fragments of bone. Undeterminable.
DK	4021	Chamber	2541	30.08 ft.	below	datum	Portion of shaft of bone, probably Sambar, Cerous unicolor.
DK	4051	Chamber	264	10.84 ft.			Fragments of a tooth of Elephas indicus.
DK.	4319 (a)	Chamber	53	6.6 ft.			Fragments of bone, undeterminable.
DK	4385	Chamber		13.6 ft.	below	datum	Part of horn of Sambar, Cerous unicolor. Base of horn
100	0		~				and brow tine of a large deer probably either Sambar,
0							Cervus unichlor, or Barasingha, Cervus duvauceli.
DK .	4632	Chamber	203	11.9 ft.	below	datum	Shaft of bone of a Sambar, Cervus unicolor.
				, , , , ,			
				,		Pis	CES
DK	4624	Chamber	305	9.2 ft.	below		Spine of Rita rita (Ham. Buch.). A fresh-water fish.
			., - ,	,			
					0	MoL	LUSCA
DK	3395	Chamber	56	6.0 ft.	below	datum	Shell of a sank (Turbinella pyrum Linn. var. acuta Hornell).
							Marine.
DK	3484	Chamber	127	3.6 ft.	below	datum	Shell of Conus (Leptoconus) monile Hwass. A marine
				,			
DK							
	3860	Chamber	36	6·25 ft.	below o	datum	species.
	3860	Chamber	36	6·25 ft.	below o	datum	species. Shell of Zootecus insularis (Ehrenberg). This species of
	3860	Chamber	36	6·25 ft.	below (datum	species. Shell of Zootecus insularis (Ehrenberg). This species of land snail has a wide distribution throughout India
	3860	Chamber	36	6·25 ft.	below (datum	species. Shell of Zootecus insularis (Ehrenberg). This species of land snail has a wide distribution throughout India and beyond to Cameran Islands, Red Sea, Cape Verde
	3860	Chamber	36	6·25 ft.	below	datum	species. Shell of Zootecus insularis (Ehrenberg). This species of land snail has a wide distribution throughout India and beyond to Cameran Islands, Red Sea, Cape Verde Islands, and Senegambia, Egypt, Abyssinia, South
	3860	Chamber	36	6·25 ft.	below (datum	species. Shell of Zootecus insularis (Ehrenberg). This species of land snail has a wide distribution throughout India and beyond to Cameran Islands, Red Sea, Cape Verde Islands, and Senegambia, Egypt, Abyssinia, South Arabia, and Balūchistān. The genus occurs chiefly
DK A	0			0			species. Shell of Zootecus insularis (Ehrenberg). This species of land snail has a wide distribution throughout India and beyond to Cameran Islands, Red Sea, Cape Verde Islands, and Senegambia, Egypt, Abyssinia, South Arabia, and Balūchistān. The genus occurs chiefly in arid or barren regions.
DK A	4488	Chamber	71	4·1 ft.	below o	datum	species. Shell of Zootecus insularis (Ehrenberg). This species of land snail has a wide distribution throughout India and beyond to Cameran Islands, Red Sea, Cape Verde Islands, and Senegambia, Egypt, Abyssinia, South Arabia, and Balūchistān. The genus occurs chiefly in arid or barren regions. Shell of Arca (Anadra) granosa Linn. A marine species.
	4488		71	0	below o	datum	species. Shell of Zootecus insularis (Ehrenberg). This species of land snail has a wide distribution throughout India and beyond to Cameran Islands, Red Sea, Cape Verde Islands, and Senegambia, Egypt, Abyssinia, South Arabia, and Balūchistān. The genus occurs chiefly in arid or barren regions.

All the marine forms could be obtained on the Kāthiāwār Coast or in the neighbourhood of Karāchi and the brackish-water forms from the Indus Delta.

CHAPTER XXXII

MINERALS AND METALS

CONNECTION OF STREET S

GOLD

ONE of the economically useful minerals is more widely distributed over India than gold, except perhaps iron. The sands of the majority of its rivers have yielded gold, though usually in very small quantities, when washed. Gold-washing has, in fact, been practised in the past in every province of India. The streams of the Dhārwār district of Bombay have, for instance, yielded gold, and traces of old workings are to be seen in the Sāngli State and near Hosūr. In Hyderābād (Deccan) ancient workings have been noticed at Hutti (16° 12': 76° 43'), Topuldodi (16° 10': 76° 51'), and Wondalli (16° 14': 76° 48'). All these areas have since been mined on a large scale. The workings at Hutti contain the deepest ancient shafts known in India, one of them being 620 feet in depth. In Madras, old workings have been found in the following districts: Anantapur (near Rāmgiri, 14° 18' 30": 77° 33'), Coimbatore (Bensibetta, 11° 42' 30": 77° 21'; Hadabanatta, 11° 56' 30": 77° 21' 30"; Kavudahalli, 12° 4': 77° 30'; and near Porsegaundanpālayam, 11° 53' 30": 77° 21'), and Wynaad. The old workings in S.E. Wynaad were made by a mining community known as karumbars, and were discovered in 1831. Prospecting on modern lines at Wynaad has not led to any successful development. Eastwick has endeavoured to show that the great sources of gold reported as having been seized, by the former invaders of India came from the Wynaad mines; he, in fact, identifies India as the land of Ophir. In Mysore, old workings are widely distributed, and gold has been found in every district except that of Bangalore. From the Kolār District comes over 90 per cent of India's production. Occurrences in Mysore are too numerous to mention in detail. The value of the annual output of gold in India a few years ago was well over £2,000,000, though it is a little less than this at present.

In Afghānistān, gold occurs 3 miles north of Kandahār. It is obtained in small quantities also from the north side of the Hindu Kush. Other reported sources are the streams

draining the Kūh-i-Bāba, streams in Kohistān, and above Laghmān and Kunar.

The following are the known gold localities of Persia, but this country can scarcely be regarded as a rich gold-producer: (1) Dāmaghān south of Asterābād, (2) between Nīshāpūr and Meshed and 2 miles west of Meshed, (3) 4 miles west of Zenjān (N.W. Persia), (4) Tihrān Hills, west of Ispahān, (5) the Elwend hills near Hamadān, (6) near Geligah in Māzandarān, (7) near Shāh Abdul Azīm, S.E. of Teherān—in an old lead mine, (8) N.W. of the ruins of Takht-i-Suleimān, west of Zenjān, and (9) Kūh-i-Tukh Rāja.

Western Tibet is thought to be sich in gold; modern supplies are said to be entirely alluvial.

Siberia is rich in gold. Gold is washed in many places in the Kārākoram and in many of the rivers of Central Asia; the metal is obtained from mines in the western and middle Kuen Lūn mountains.

The output of gold from China is not far short of that from India.

In ancient times Arabia was an important gold-supplying land, and is supposed by

many to have included the old gold localities of Havila and Ophir.

From the above it will be seen that there are many possible sources for the gold of Mohenjo-daro, but the chances seem more in favour of Southern India. The gold of India is said to have been worked for at least twenty-five centuries. In Mysore (Kolār) the occurrences are rich and noticeable, and although Afghānistān, Western Tibet, and parts of Persia are nearer, Southern India would seem to have been the most accessible.

SILVER

In the Bhāgalpur, Mānbhūm, Monghyr, and Singhbhūm districts of Bihār and Orissa, silver has been found associated with lead, but neither metal in considerable quantity. Similar occurrences have been met with in the Rewah State, Central India, and in the Drug, Hoshangābād and Jubbulpore Districts of the Central Provinces. Old argentiferous lead mines occur in the Cuddapah and Karnūl districts of Madras. The Kulu valley of the Panjāb Himālaya is rich in argentiferous galena.

Silver associated with gold is produced in considerable quantity to-day at Kolār in Mysore, and to a much smaller extent at Anantapur in Madras. Excluding Burma and the two last-mentioned localities, India at the present day yields no silver. Professor V. Ball, however, was "inclined to accept literally certain ancient and long-forgotten references to its (India's) having been a silver-producing country" (Journ. Soc. of Arts, 28th April,

1882, p. 582).

An ancient lead-mine, the lead from which yields a small quantity of silver, exists at Fārinjal (35° 0′: 68° 44′) in the Ghorband valley of Afghānistān. Silver may also have been derived from the many other lead localities of Southern Afghānistān (see "Lead"). In the same country well-known silver mines existed near the head of the Panjshīr valley in the Hindu Kush; silver deposits were also formerly worked near Herāt.

Persia is said to be very rich in silver-bearing lead-ore; otherwise, its supplies appear to be limited. In S.E. Persia, silver is known to occur in the Kuh-i-Nugre ("silver mountain"), between Fasā and Zahidān, near Herāt, in the Sahend hills near Tabrīz, and at

Guleki not far from Asterābād.

The rich lead and silver deposits of Northern Burma had been exploited by the Chinese for many centuries back, and are now yielding something like 5 million ounces of silver a year.

The silver mines of Gumush Khaneh in Armenia were exceptionally rich and well known in olden times. Small quantities of silver are known to occur in the old land of Midian (now the Hedjaz), and there is an old silver and copper mine at Shaman on the left bank of the Wadi-el-Yrdh in the interior of Arabia.

If the ancients knew how to separate silver from gold, it is possible Mohenjo-darg supplies may have come with the gold from Southern India. The art of separating silver from lead has been known for many generations, so that the Faranjal mine of Afghānistān, the Gumush Khaneh mines of Armenia, and the many lead mines of Persia, and even the lead mines of North Burma, might be locked upon as possible sources.

1 J. M. Maclaren, Gold, pp. 238-40.

COPPER .

The best known deposits of copper in India proper are those of Singhbhūm in Bihār and Orissa. Remains of old excavations and mounds of copper slag from a worked-out ore have been noted in Indore. Old copper workings are frequent in Madras—Coimbatore, Guntūr, and more especially Nellore; the last mentioned District seems to have been of some importance. Many places in the Panjāb and Kājputāna yield copper, the most important being Khetri (28° o': 75° 51') and Singhāna (28° 6': 75° 54'), both in Jaipur. Large heaps of copper slag have been noted at Rohira (24° 37': 73° 1' 30") in Sirohi State. Copper has been obtained by native methods in many places in Sikkim and Kumaor. An old copper mine is known in Kashmīr (Harpat Nāg). At Robāt (29° 32': 63° 35') in Balūchistān, large heaps of copper slag witness to ancient smelting operations.

In Afghānistān ancient copper workings have been found near the Safed-Kūh between Kābul and Kurram. Rich veins of copper-ore are also said to exist in the Shāh Maqsūd (31° 53′: 65° 20′), and to have been worked by Nādir Shāh and the Sirdars of Kandahār.¹ Rich ores are reported to occur at Nesh, 60 miles north of Kandahār. Other localities are Tezin, east of Kābul, Mūsāī in the Shādkāni Pass, and the Silwātū Pass; some of these

places have been worked.

Copper-ore is abundant in Persia. One of the richest localities is the Kārādāgh hills north of Tabrīz. Other well-known mines are those around Kirmān. Polak says of Persia: "Eine Kupfermine hat fast jeder District." 2

The most important copper mine in Armenia is that of Kadabek. Copper is known to occur in many places in the Caucasus. Eusebius-Hieronymus speaks of the copper mines of Southern Syria; the Shaman mine has already been mentioned (see "Silver").

Considerable quantities of copper are described as coming from the Zangskar valley

of Tibet.

China is a small producer of copper, but there is a rich mine in Yunnan, and copper accompanies the lead and silver ores of North Burma. The copper districts of Russia are all in the Urals, Caucasus, or Siberia.

Old and rich copper mines exist at Tokat in Asia Minor,

The nearest copper localities to Mohenjo-daro are: the Jaipur State of Rājputāna, the Shāh Maqsūd and other areas in Southern Afghānistān, and Robāt in the extreme west of Balūchistān. To these we may perhaps add the Nellore district of Madras as a possible source for the ancient city's supplies.

LEAD

Considerable quantities of lead-ore were formerly extracted from mines near Ajmer in Rājputāna. Lead is known to occur at several places in Bihār and Orissa, the Central Provinces and the Cuddapah and Kurnool districts of Madras. The most important deposits of the present Indian Empire are those of Northern Burma; these mines are amongst the largest in the world. There are several other unimportant occurrences of lead in other parts of India. With the exception of iron, there is perhaps no metal whose ores appear to have been worked to so large an extent in India as have those of lead. The ancient workers devoted their attention to the extraction of silver rather than of lead; in North Burma, for instance, most of the lead was dumped as waste by the old Chinese workers.

1 Cal. Journ. Nat. Hist., vi, p. 597.

2 Rersien, Theil 2, p. 174, Leipzig, 1865.

An ancient lead mine with very extensive workings has already been referred to (under "Silver") as occurring at Fāranjal (35° 0′: 68° 44′) in the Ghorband valley of Afghānistān. Lead-ores are common in many localities in Southern Afghānistān, and are said to occur in quantities in the Hazāra Jāt.

Persia is particularly rich in lead, and the mine near Ganjabad appears to have been worked from time immemorial. The richest mines occur around Ispahan, Kirman, Teheran,

and in the Elburz mountains.

Tunis is also a rich lead-bearing country, producing to-day over 5,000 tons a year. The lead of Laurium in Greece was worked on a large scale in ancient times. The only deposit worked in Egypt at the present time is that of Gebel Rosas, which was known to the ancients.

Asiatic Turkey and China both produce lead in some quantity to-day, and the metal is

known to occur in remunerative amounts in parts of Siberia.

The Mohenjo-daro lead may well have come from Ajmer. The oldmines in this District were of great extent, and in 1830 had the appearance of having been worked for centuries. The metal may otherwise have come from the Faranjal mine in Afghanistan, or other mines in the south of that country, or from Persia.

LAPIS-LAZULI

Extraordinary little is known regarding the precise locality in which lapis-lazuli is mined. The name is derived from the Persian word lajward, meaning "blue colour", through the Greek λαζούριον, so that a Persian-speaking country is rather indicated as that in which the rock—for it is a rock rather than a simple mineral—was first discovered and used. It is recorded from the neighbouring countries of Tartary, Tibet, and China, but the best known and most important locality is the valley of the Kōkchā south of Firgāmu in Badakshān, the most northerly province of Afghānistān. Another locality is the western end of Lake Baikal in Siberia. It has been reported to have been found near Ajmer, in India, but the report has never been confirmed.

The lapis-lazuli reported to occur in China, Persia, Tibet, and Bokhāra is probably imported material from Badakshān; as is also that sold in India, Afghānistān, and Balūchistān. The material used by the ancient Egyptians for making scarabs is thought to have been obtained from Persia, but may well have come through that country from Badakshān. The same may be said regarding the small amount of lapis-lazuli used in Assyria, Babylonia, and elsewhere in ancient times. Some of the stone referred to by the ancients as sapphire was, from its description, more probably lapis-lazuli.

It seems most probable that the lapis-lazuli of Mohenjo-daro came from the Badakshan

Province of Afghanistan.

TURQUOISE

Turquoise derives its name from the country of Turkey, but although the European supplies were obtained from this country, there is reason to believe that they originated from Persia and merely passed through Turkey. Turquoise takes on a greenish tinge on exposure to sunlight, and for this reason most ancient ornaments of this mineral are definitely greenish in tint.

The finest turquoise is found in Persia, where the mines are known to have been worked for at least eight centuries. The principal locality is near Nishāpur in the Khorāsān Province;

¹ M. Bauer and L. J. Spencer, Precious Stones, p. 442.

other localities are near Kirman and Karik, and near Mashiz. Recently the mineral has been found in the neighbourhood of Yezd and in Seistan. Turquoise is also said to occur in Turkestan. Turquoise mines have been stated to exist beyond the Persian frontier between Herat and Western Turkestan (Khojent and the Karatyube mountains).

Arabia proper also probably contains turquoise; at least three mines are said to be

situated in the "Midianite country".

The report that turquoise occurs in the Agmer hills of Rājputāna is in all probability incorrect. The stone used for ornaments for the hill women of India and for the mosaic work of Kashmīr probably comes from Khorāsān.

It seems most probable that the ultimate source of the Mohenjo-daro turquoise was the

Persian province of Khorāsān.

AMAZON STONE

Formerly Amazon Stone or Amazonite, a green variety of microcline felspar, was obtained exclusively from the vicinity of Miyask, a town in the Ilmen mountains, which are a southern continuation of the Urals. Microcline is common in India, but the precious variety has so far been recorded only from Dodabetta in the Nīlgiri Hills, and possibly from the Padar District of Kashmīr. The Mohenjo-daro material may well have come from either of these localities.

CRYSTAL

Rock crystal is a very common form of semi-precious silica or quartz, and is fairly widespread in its occurrence. For this reason it would be difficult to decide whence the Mohenjo-daro material emanated. The lapidaries of Cambay obtain their supplies from Tankāra (22° 40′: 70° 48′ 30″) in the Kāthiāwār peninsula. Large prisms were formerly obtained in the bed of the Godāvarī near Rājahmahendri, and in the stream-beds of Tanjore, both in Madras. Delhi was formerly another source. Interesting little bi-pyramidal crystals have for a long time been obtained from the red marls of Māri in the Miānwāli district of the Panjāb; they are known as "Māri diamonds".

Rock crystal has been worked at many localities in India, and wonderful ornaments

carved out of this stone were found in the old palace of Delhi.

The Alps and India are supposed to have furnished the ancients with their supplies of rock crystal, and it is not unlikely that the Mohenjo-daro inhabitants obtained theirs either from Māri, from the Kāthiāwār peninsula, or from Vellum in the Tanjore District of Madras.

STEATITE

Steatite or soapstone is a massive form of tale, a mineral which is said to have derived its name from the Arabic talq. The Egyptians used it usually coated with blue glaze, and it was not unknown to the Assyrians and the Chinese. Its most conspicuous properties are resistance to heat and great softness, the latter character permitting it to be very easily carved.

The mineral is widely distributed among the crystalline rocks of India. Some 2,000 tons are produced annually. The localities are too numerous to be all mentioned, but the nearest of any importance to Sind are: (1) Rājputāna (Dogetha, 27° 7′ 30″: 76° 20′; Gisgarh, 26° 53′: 76° 42′; and Morra, 26° 48′ 30″; 76° 52′ 30″) · (2) Mysore (several districts); (3) Madras (several districts, especially Salein, Bellary, and Karnūl); (4) Jubbulpore District of the Central Provinces; (5) Bihār and Orissa (several districts, especially Singhbhūm, Mayūrbhani, Mānbhūm, and Cuttack).

The present-day production comes, mostly from Jubbulpore and Salem.

Just below the second bridge above Gogamand in Afghanistan, traversing a dark serpentine, is a thin vein of steatite it is too thin to be of economic value to-day, but the stone is of excellent quality.

The most likely source of the Mohenjo-daro material would seem to be Rajputana.

ALABASTER

True alabaster is a hydrated sulphate of lime, but the name was applied in ancient times generally to the carbonate. True alabaster is sufficiently soft to take a scratch from the finger-nail, and does not effervesce with hydrochloric acid; by these simple tests it? can be distinguished from the carbonate. Oriental alabaster, the carbonate of lime, was used in Ancient Egypt for canopic jars and other objects. The derivation of the name is doubtful, but may have its origin in the alabastra—ointment vases or perfume bottles—which were formerly made out of this stone. It is found as travertine deposited from calcareous springs or as a stalagmite on the floor and walls of limestone caverns. The mineral was extensively worked near Suef and Assiut in Egypt, and many ancient quarries have been found in the hills above the Tel-el-Amarna plain. A very beautiful arragonite travertine occurs in considerable quantity 11 miles west of Topchi on the road to Bāmiān in Afghānistān; a similar rock is found in the hills behind Jabal-us-Sirāj, but in very small quantity.

Hydrous sulphate of lime is a form of gypsum, and is the material to which the term "alabaster" is applied to-day; this mineral, however, was undoubtedly used by the ancients, for instance, by the Assyrians; in the ancient city of Calah (Nimrud) blocks of carved and inscribed gypsum can still be seen.

In Europe the alabaster of Tuscany is the best known. ,

Gypsum is abundant in Persia, Mesopotamia, and over a large part of India. Alabaster is merely a refined and semi-transparent form of gypsum; how much, if any, of the Persian or Mesopotamian material is sufficiently fine-grained or delicately shaded to warrant the term "alabaster" is not known. A beautifully marbled or mottled alabaster is described as coming from near the village of Ahar, north of Teheran, on the north side of the Kuh-i-Shamiran.

Gypsum occurs largely in all the younger Tertiary deposits of Afghanistan. The bed at Dasht-i-safed in Kāmard is of the semi-translucent variety known as alabaster, and would make a very handsome ornamental stone; it is nearly 20 feet thick, and very large quantities are available.

Gypsum is plentiful in the neighbourhood of Mohenjo-daro itself, and some suitable fine-grained bed was probably available at no great-distance from the city. Thick beds'of it of sufficient purity are found in the Kirthar range of Sind, and, according to Dr. Buist,1 "the art of making 'plaster of Paris' from it was known to the natives."

The gypsum of Kachhī in Balūchistān is said to be well adapted for ornamental purposes; considerable quantities are also available from the Ghāzībād pass, the Bugti and Marri hills,

and from near Khattan and Spintangi.

Cutch contains large quantities of the mineral, and a certain amount is obtainable in Kāthiāwār and Rewā Kāntha. Thick beds of it occur in the Sherāni Hills. Gypsum in enormous quantities, including massive beds of considerable purity and variety of colour extend along the base of the Salt Range in the Panjab; a compact variety found near Sardi (32° 41': 72° 47') has been quarried and turned to form plates and other atensils. The gypsum of Rājputāna is mostly impure.

Any of these local sources may have supplied Mohenjo-daro with true alabaster.

M Trans. Bomb. Geol. Soc. (1852), x, p. 229.

HÆMATITE 6

Crystalline hæmatite has been, and is still, used for ornamental purposes. Suitable material is, for instance, obtainable in Spain. The kind of hæmatite used for ornamental purposes is the extremely hard, fine-grained compact material or large crystals. Reports do not always describe the precise nature of the ore, and it is therefore difficult to guess how much, if any, of a deposit is suitable for ornamental purposes. Enormous quantities of hæmatite occur in Bihār and Orissa and its Federated States, and much of this is hard finegrained compact ore with a good metallic lustre. Iron-ore deposits have a habit of concealing themselves, and the Bihar and Orissa deposits have only recently been discovered; specimens, however, may well have been picked up in the stream-beds by the ancients and used for ornamental purposes. Large quantities of hæmatite occur also in the Central Provinces. Most of the Madras and Mysore iron-ore is the magnetic variety, but hæmatite is also known; the manufacture of "Wootz Steel" in the Trichinopoly District is an ancient one. Hæmatite occurs in Rajputana and the Panjab in no very large quantities, and is found in many parts of Persia. The largest occurrence in Persia is just east of Yezd: The iron mines of Lebanon were known to Solomon and included hæmatite. In Southern Arabia the old town of Usal provided the Israelites with iron. The material used by the lapidaries of Oberstein is said to come from India.

The occurrence of hæmatite in the islands of the Persian Gulf and on the opposite coast of Persia is perhaps worth special mention in view of the fact that the mineral is unusually conspicuous and must have attracted attention in very early times. The principal hæmatite-containing island is Hormuz, but the mineral is also found in Qishm, Bū Mūsa, Lārak, Sīrri, Dalmeh, probably Henjām, and several others, as well as on the Persian coast in the neighbourhood of Khamīr. It seems more than likely that the Assyrian and Babylonian supplies came from these, and this coast, and the Mohenjo-daro supplies may well have done the same.

AMETHYST

The term "Oriental Amethyst" is sometimes applied to violet-coloured corundum. True amethyst or violet-coloured quartz is found in a very pure state in the gem-gravels of Ceylon. The amethyst localities in the Urals, where the stone is accompanied by beryl and topaz, are extremely important, especially around Ekaterinburg. Amethyst is not a rare mineral, but is casual in its occurrence; in olden times it was obtained from Arabia Petræa.

The mineral has been found in the Santāl Parganas of Bihār and Orissa, and occurs sometimes in the geodes of the Deccan Trap; the latter rock in Jubbulpore has yielded small amethysts in this way. The occurrence of amethystine quartz in the vicinity of Hyderābād (Deccan) has been noted. Amethyst is found at several localities in the Bashahr portion of the valley of the Sutlej. Both Persia and Siberia are important sources of amethyst. There seems little doubt that the Mohenjo-daro material was derived from the Deccan Trap.

SLATE

Poor slate occurs in the Mānbhūm and Singhbhūm Districts of Bihār and Orissa. Good quality, slate is found and worked in the Monghyr District of the same province. Slate of promising quality is known to occur in Baroda, and there are quarries of this rock in Bijāpur (Bombay Presidency). Slate of fair quality occurs in Gwalior. Madras is poor in slate, thin slabs being obtained in the Cuddapah District. Slate occurs in considerable quantity in the Hazāra District, N.W.F. Province, while some of the best slate in India is quarried in the

Panjāb in the Kāngra and Gurgaon Districts. Dehra Dūn and Tehri Garhwāl are slate districts, and the Almora District of the United Provinces produces large quantities of good slate. The slate of Alwar, Rājpūtāna, is being worked at the present day.

Slate is not plentiful in Persia: Some of the best known localities seem to be in

Māzanderān between Ashraf and Asterābād, and near Kashek in the Caucasus.

In Afghanistan slates of very fair, quality could be obtained in large quantities from between Siah Sang and Gardan Diwal on the north side of the Helmand river. Less valuable slate is available north of Jaokal on the left bank of the Helmand river, and also to the east of the Kotal-i-Unai at the head of the Kabul river.

Rājputāna seems to be the nearest locality to Mohenjo-daro from which slate would

be available.

AGATE, CARNELIAN, ONYX, AND CHALCEDONY

Agate, carnelian, and onyx are, as LaTouche observes, "of common occurrence in the amygdaloidal flows of the Deccan and Rājmahāl traps, and the chief sources of supply are the rivers that drain the areas covered by these rocks." The beds of the Kistna, Godāvari and Bhīma rivers have been specially noticed in this connection. Agate, jasper, and carnelian are collected from the Godāvari bed near Rājamahendri (17° 0′: 81° 50′), while many pebbles of agate, onyx, and other forms of chalcedony are found in the Kistna alluvium of the Palnād. The agate employed by the lapidaries of Jubbulpore is largely derived from the Narbadā valley, especially from Bherāghāt or the Marble Rocks. Nodules of agate are found in plenty among the Rājmahāl Hills.

Fine agates and carnelians occur to the north of the Pangong Lake in the Rudok district

of Kashmir.

The most valuable of the veined agate worked into ornaments by the lapidaries of Cambay comes from Rānpur in Ahmadābād. The Kaira district of Bombay has yielded a much prized variety of agate; landscape agate has also been obtained from this locality. A large vein of moss-agate is to be found at Khijaria in the Morvi State of Kāthiāwār; common agate occurs in the same neighbourhood. Other localities in Kāthiāwār are known from which moss-agate, common agate, and chalcedony are obtainable.

The chief source from which the carnelian and agate workers of Cambay derive their material is in the Rājpīpla State near the village of Ratanpur (21° 43′ 30″: 73° 14′ 30″).

According to some, the industry has flourished for over 2,000 years.,

All the above mentioned localities are close to Mohenjo-daro, and are to be considered as potential sources of agate, moss-agate, and carnelian; the chances are, however, more in favour of Kāthiāwār and Rājpīpla. Two of the agate beads from Mchenjo-daro, brown and white in colour, resemble the "Pagoda stones" or agates from Burma. Onyx is widely distributed over parts of Nawānagar; it is especially abundant at Vijarkhi (22° 25': 70° 14' 30", 2 miles east of Khokhri (22° 23' 30": 70° 28'), near Baolidar (22° 9': 70° 13' 30"), half a mile north-east of Bori (22° 9', 30": 70° 18'), and three-quarters of a mile south of Narmāna (22° 5': 70° 13').

JASPER, AGATE-JASPER, AND BLOODSTONE

The rivers draining the Dhārwār and Bijāwar formations all contain pebbles of jasper of a great variety of tints. Conglomerates of material derived from these older rocks supply the rivers which drain the Sātpurā Range in the Central Provinces. The jasper of Mohenjo-daro, therefore, may well have come from Rājputāna. Bloodstone, i.e. green jasper

variegated with red, has been noted as occurring near Tankāra (22° 40': 70° 48' 30") in Kāthiāwēr and in the bed of the Mota Mola river between Fīrozābād and Sindaghi in the District of Agra. It is also found in Rājputāna.

Agate-jasper is mentioned as occurring with common agate in the Rājpīpla Hills, Broach, and the beds of the Kistna, Godāvarī, and Bhīma rivers. The Mohenjo-daro specimens

may have come from Rājpīpla or Rājputāna.

PLASMA

The bright green and more or less translucent variety of chalcedony known as plasma has been noticed in the beds of the Kistna, Godāvarī, and Bhīma rivers. It seems just as likely, however, to have been obtained from Rāiputāna.

TIN

The best known tinelocality in Asia is the Malay peninsula, including the Tenasserim Division (Tavoy and Mergui Districts) of Southern Burma. Here cassiterite occurs in considerable quantities, the locality being one of the principal sources of the world's tin.

Cassiterite is also known to occur in the Pālanpur State (Bombay Presidency), and in the Dhārwār District (Bombay), and is reported to have been found in Rewā Kāntha (Nārukot); none of these occurrences has proved of commercial importance. In the Hazāribāgh District of Bihār and Orissa, tin ore is found in more noticeable quantity and unsuccessful attempts to work it have been made.

Tin is known to occur in the Kūh Banān and the Kārā Dāgh in Persia. Tin-stone has been found in five provinces of China—Yünnan, Kwangsi, Hunan, Kwangtung, and Fukien, but deposits of economic importance are restricted to a few areas in the first-named three provinces, the chief producing centre to-day being about 30 miles west of the town of Mengtsze in Yünnan.

It would be difficult to surmise from which of these sources, if any, the tin found in Mohenjo-daro was obtained.

BITUMEN

A large deposit of bitumen occurs at Hit on the Euphrates, and was known to the old Babylonians. It is a conspicuous deposit, and must have been known to the earlier Sumerians.

Bitumen is also to be found near Isa Khel on the right bank of the Indus (N.W.F. Province) in India. The quantity is small, but may have been a little greater in olden times.

The nearest bitumen deposits to Mohenjo-daro would be those of Balūchistān. At Khattān (29° 34′: 68° 31′), in the Marri hills N.E. of Sibi, there is a considerable deposit. Another occurs on the other side of the Sibi plain at Sanni, S.W. of Sibi.

It is difficult to say which of these is more likely to have been the source for the Mohenjo-daro specimens without knowing more about the relationship between that city's civilization and the surrounding regions.

RED! OCHRE

Red ochre is of wide occurrence in India, especially in Central India and the Central Provinces. In the latter province the deposits of Jauli, Jubbulgore District, are well known

and still exploited. Extensive beds occur in the Kaimur plateau, and many places on the Decean Trap are characterized by the mineral. Amongst the deposits nearest to Sind are:—

(i) Those of Lakhpat (23° 50': 68° 50') in Cutch.

(ii) Those of Padvānia (21° 41': 73° 18') and elsewhere in the Rewā Kāntha Agency. From Padvānia some 120 tons are said to be carried away annually by Muslim traders.

The red ochre of Hormuz and other Persian Gulf Islands is worth mention on account of its brilliant colour, which must have attracted the very early notice of civilization. Its association with salt and gypsum makes it the more conspicuous, and there is little doubt that it must have acquired a celebrity since very early times? Even to-day it is dug out in large quantities and shipped to India for use as a pigment. Hormuz, Bū Mūsa, and Hālūl are the principal islands from which this material is obtained, and the Mohenjo-daro supplies might well have come by sea from any one or all of them.

BASALT

Basalt is one of the commonest rocks in India and covers a total area exceeding 200,000 square miles in the Bombay Presidency (including Kāthiāwār and Cutch), Hyderābād, Central India, and the Central Provinces. The Mohenjo-daro material might have come from the Kāthiāwār Peninsula, but basalt was even nearer at hand than that, namely in western Sind; an important band of this rock from 40 to 90 feet thick stretches for about 22 miles from Rānīkot to Jakhwāri, and may well have been used by the ancient inhabitants.

TACHYLITE

Tachylite is a basaltic or ultra-basaltic glass and frequently accompanies dykes in the Deccan Trap. The specimens found at Mohenjo-daro may have come from any part of the Deccan Trap area, as, for instance, the Kāthiāwār peninsula or Central India.

NEPHELINE-SODALITE ROCK

Amongst the many Mohenjo-daro beads sent to the Geological Survey of India for identification, two are of peculiar interest in that they consist of an uncommon rock—nepheline-sodalite rock—which is found at Kishangarh in Rājpūtāna. The source of the material, therefore, is almost undoubtedly the neighbourhood of Kishangarh. The present uninteresting dull grey colour of the beads is the result of weathering and the effect of time. Sodalite when fresh is of a beautiful azure blue colour, and the beads, when fresh, must have done credit to their neighbours in jade, agate, jasper, turquoise, etc.

JADEITE 1

Jadeite, or the hard form of jadestone, of which all the Mohenjo-daro jade beads consist, is found typically in the Myitkyinā district of north Burma, where it has been worked for many years past. The same mineral is reported to occur also in the neighbouring Chinese province of Yunnan, and further north-east in Shensi, but there is some doubt about these reports.

The material from Rewah State in Central India is the nephrite variety. Specimens of jadeite have been described as coming from Tibet; they probably occur as boulders in alluvial deposits, but the precise locality from which they come is unknown.

1 See, however, pp. 541-2 supra. -[ED.]

The Aosta valley of the Alps of Piedmont is known to contain jadeite.

The jade from the celebrated mines of the Kārākāsh valley of Turkestān belongs mostly to the nephrite variety, but it is accompanied by some jadeite. In the Pāmīr region jadeite occurs in the valley of the Tunga, a left-bank tributary of the Rāskam Dariā; this material was once quarried by the Chinese.

Objects of pre-historic age, worked in jadeite, have been frequently found in Europe, Asia, America, and Africa, but in most cases the source of the rough material is unknown.

For the source of the Mohenjo-daro material, therefore, we have the choice of some three localities: the Pāmīrs and Eastern Turkestān, Tibet, or North Burma. If we reject the European Alps as a possible source, the finding of jadeite objects in Mohenjo-daro points with strong probability to communications with Central Asia.

LÖLLINGITE

Löllingite is essentially a di-arsenide of iron, FeAs₂, but passes into leucopyrite, Fe₃As₄, and frequently tends towards arsenopyrite, FeAsS. Other sulphides of arsenic are: orpiment, As₂S₃, and realgar, AsS. Iron pyrites, FeS₂, sometimes contains arsenic in small amounts; it will be best, however, to restrict the inquiry to known occurrences of any of the sulphides of arsenic.

In Europe löllingite occurs in the Lölling-Hüttenberg district of Carinthia, and sparingly in a number of other districts; a sulphur-bearing variety (geyerite) is obtained from Geyer, Saxony. Arsenopyrite is abundant at Freiberg, and at other places in Saxony; at Andreasberg in the Harz Mountains, Germany; at Sala, Sweden; at Skutterud, Norway; and at several localities in Cornwall. It is also known in the Binnenthal, Switzerland, and as the cobalt-beafing variety (Danaite) at Sulitjelma, Finland. Orpiment is found in Hungary, at Tajowa, Moldova, Kapnik and Felsöbánya, and, with realgar, at Allchar, Macedonia. A large deposit occurs near Julamerk in Kurdistān. Realgar occurs at Felsöbánya, Kapnik, and Nagyag in Hungary, at Allchar in Macedonia, and in the Binnenthal of Switzerland.

The Indian occurrences are as follows:-

(a) Sampthar Hill, Darjeeling (arsenical pyrites).

(b) Dabur and Dhab in the Hazāribāgh District, Bihār and Orissa; lumps of leucopyrite are occasionally found in the mica-bearing pegmatites. Recently, leucopyrite was found in the Gamaria mica mine, and löllingite in the Durria mica mine, of the Kodarma Forest area, Hazāribāgh.

(c) Barāli, Padar district, in the Bhutna valley, Kashnir (arsenopyrite).

(d) Chitral, North-west Frontier Province. Orpiment in the past was imported in considerable quantities from Chitral, but the supply has recently diminished.

(e) Arsenical pyrites has been mined at Manikaran in the district of Kangra, Panjab.

(f) On the Dharma and Juwar or Niti Ghats in the Almora district, United Provinces ("yellow arsenic", i.e. orpiment).

(g) Mansizri, United Provinces Himālaya. Small quantities of orpiment are

brought down for sale to the Bagesar Fair.

(h) Shankalpa Glacier, United Provinces Himālaya. Fragments of orpiment with a little realgar have been found on the moraine of the Shankalpa glacier.

Arsénic is brought into Kābul from Herāt, but its precise origin is unknown.

In the Caucasus, arsenical pyrites occurs in several localities, which it is unnecessary to enumerate. Orpiment and realgar are also known.

In Asia Minor arsenical pyrites, sometimes gold-bearing, is found in various places east and south-east of Smyrna, up to a distance of about 80 miles.

In Asia Minor, orpiment and realgar are known to occur in several localities, at some of

which they are exploited.

In northern Persia, corpiment and realgar occur in the region of the Caspian Sea, in the Kurdistan Mountains in the neighbourhood of Kazvīn, and on the Kaflan-Kūh. These minerals

are exported to Turkey.

Most of the above-mentioned localities are possible sources of the Mohenjo-daro material. No reliable conclusions, in fact, can be drawn from the occurrence of löllingite in Mohenjo-daro. Persia, Herāt, Kashmīr, Chitrāl, the Panjāb, Asia Minor, and the Caucasus might, each of them, equally well have supplied arsenic minerals to Mohenjo-daro.

"GREEN EARTH"

The specimen despatched to this department as "glauconite" was found to consist mostly of fine chlorite and calcite. Such material might be found in the Tertiary rocks of Sind itself, but it is far more likely to have been derived from the Deccan Trap. Green earth of this nature was discovered by Dr. Fermor from the basalt of Bhusāwal (Records, Geological Survey of India, vol. lviii, pp. 146-7). The Mohenjo-daro sample may have come from zeolitic material filling the vesicles of the trap, or it may represent the more massive form resulting from the alteration of the trap as a whole, which takes place chiefly at the base of a flow. Large masses of this trap occur in Kāthiāwār and Central India, but less extensive tracts occur in Cutch, in the Pab Range of Eastern Balūchistān (Kalāt State), and in the Kākar Range in the extreme north of the same province. It seems very probable that the material was obtained from either north-eastern or eastern Balūchistān.

APPENDIX I

NOTES AND ANALYSES

Ceramic Wares.

RICK, pottery, and miscellaneous terra-cotta objects have been found in abundance at the Indus Valley sites, and it can hardly be doubted that the local alluvial clay was employed for their making. The prevailing colours of these products are light red or salmon; black and grey are uncommon. These colours are due to the presence of iron compounds in the clay, which develop the red shades in the oxidizing atmosphere of the kiln, while black or grey ones are formed when a reducing or smoky atmosphere prevails in the course of burning. The pottery is sometimes covered with a slip of bright red colour, due to ferric oxide; or painted with designs in black or chocolate, which owe their colour to manganese oxide. The identity of the colouring materials with those employed by the Indian potter of the present day, as well as the simplicity of the latter's methods, leaves no doubt that the ancient technique has been handed down to him without any material alteration. He prepares the red slip by levigating red ochre or Multani matti (a yellow ochreous earth) with water, and employs a manganiferous hæmatite for the black or chocolate shades. manganese ores which are frequently associated with ferric oxide, impart a pure black colour when rich in manganese, but chocolate, when the proportion of iron preponderates.

A noteworthy variety belonging to this group is represented by a number of fine earthenware bangles, usually black in colour, sometimes mottled white, but all distinguished by their fine vitreous texture.1 The chemical analysis of one of the black specimens (Table I, p. 689) reveals an unusual composition, containing rather large proportions of lime and magnesia. These ingredients enhance the fusibility of the clay, and therefore account for the vitreous body of the specimens. Their black colour is due to ferrous oxide, which indicates also that the firing took place in a reducing atmosphere. On the other hand, under the oxidizing conditions prevailing in the kiln, the lime and magnesia would bleach the colour due to iron and the product would emerge white instead. The different colours of the bangles can thus

be accounted for easily.

Faience, which was very popular with the Indus people, has a hard, fine granular The prevailing colours are bluish-green and greenish-blue, body, covered with a glaze. The microscopic although white, chocolate, and red specimens have also been found. examination reveals a compact granular structure, composed of angular equarte grains bound together with a transparent cement. .. Its chemical analysis (Table I, p. 689) shows also that silica is the chief constituent, forming about 90 per cent of the total amount. From these facts it may be inferred that the original paste was composed of finely crushed quartz,

A dark red variety of the earthenware bangles has since been found at Harappa.

Faience.

or pure white sand, a glassy flux, and a colouring matter, if necessary. It is obvious that the moulded object had to be dried and fired to bring about the fusion of the flux ; but the question how precisely the various ingredients of the paste were endowed with the necessary coherence and plasticity, is difficult to answer. The suggestions that clay or gum might have been employed for this purpose are untenable, as the material is free from clay; while gum, or any other organic matter, would be consumed in the course of firing long before the flux underwent fusion. Possibly, silicate of soda, which forms a highly viscous solution with water, was employed as a constituent of the paste and served to impart the desired property to the wee paste. It may be added here that the preparation of an alkaline silicate by the fusion of soda with sand, was well known to the ancient nations who practised the art of glazing.1

The hollow objects were moulded on cores of sand, which was tied up in some fabric and raked out after firing. Impressions of the fabric, as well as remains of the sandy core,

have been found in several specimens.

The white body is free from any metallic colouring matter and forms the basis for the coloured varieties. The blue and green shades were produced by the addition of copper oxide to the paste, probably in the form of a natural ore of this metal; and the chocolate colour is due to cuprous oxide, which was the result of a reducing atmosphere in the kiln.

The light red variety was prepared by the addition of red ochre to the raw paste.

To form some idea of the brilliant effect of these objects, due allowance should be made for the changes produced on them by the corrosive action of the alkaline soil in which they were so long buried. As a fact, the original glaze has survived on very few specimens, although the body material is generally well preserved. In some cases the decomposition has penetrated deeper, changing the blue or green colour into dull white or brown, which have resulted from the bleaching out of copper oxide and the precipitation of basic carbonate of iron, respectively.

The body material of this peculiar class of ware is powdered steatite, which is bound Steatite together with a flux. Originally objects of this material must have been glazed, but they have Faience. undergone much decomposition, and not a vestige of the glaze has been left on them. The material is soft and cream white; but the presence of a little copper oxide in it, revealed by chemical analysis (Table I, p. 689), leaves no doubt that they were originally coloured blue or green, like ordinary faience. In fact, it is highly probable that their whole technique was identical with that of the faience described above, and that steatite was introduced to replace quartz, in order perhaps to get over the difficulty experienced in crushing this very hard mineral.

Faience objects are covered with a distinct layer of glaze which must have been applied Glaze. separately, as in the case of the steatite objects. It is highly probable that the glazing process was carried out in the second firing, as at present. The prevailing colours of the faience glaze are bluish-green or greenish-blue, although indigo blue, apple green, maroon, black, and colourless examples have also been found. The blue shades owe their colour to copper oxide, while the green contains iron oxide, in addition. The black or dark maroon glaze contains an excess of manganese oxide. It has been remarked already that the glaze has perished mostly through decomposition, and the material available is scanty for a complete chemical analysis. However, judging from its transparency, the nature of the colouring matter, and the iridescent films on these objects, one can safely conclude that it is of the nature of glass. Ancient specimens of glass consist of silicates of soda and lime and a metajlic oxide for the colour, besides certain impurities derived from the raw materials. They were prepared by the fusion of an alkali, sand, saltpetre, and chalk, with a metallic oxide for the coloured varieties.2 All

² Ibid.

¹ Campbell Thompson, The Chemistry of the Ancient Assyrians.

these ingredients were easily available to the Indus people, and were doubtless utilized for the art of glazing. For instance, alkaline efflorescences, which cover wide areas of soil in Upper India, could have been employed for this purpose. We shall see, too, that there is some possibility of silicate of soda (a water-soluble glass which is formed by the fusion of soda and quartz powder) having been used as a medium to produce the white slip on steatite seals. Taking all these facts into consideration, we are led to the conclusion that the glaze was produced by the simple methods indicated above, which were followed by the Assyrians down to the seventh century B.C.

Steatite is an impure massive variety of talc, containing 4-8 per cent of combined water. It is one of the softest minerals with a soapy feel; but at red heat it loses the water and is transformed into a very hard, white substance which can be polished.

The Indus Valley people were well acquainted with this property of steatite and made good use of it. The stone lent itself readily to carving with the aid of their bronze tools, and the finished product could be rendered hard and durable by careful ignition. The results of the chemical analyses (Table I, p. 689) leave no doubt that the material is steatite, which has been deprived of most of its combined water at a high temperature. Beads of various shapes were fashioned in large numbers out of steatite; but the largest piece of carved steatite is the statue illustrated in Plate XCVIII. The most important objects in this class, however, are the numerous inscribed seals which are finished with an exquisite white enamel-like surface.

Generally these seals bear evidence of strong ignition, containing only 1-3 per cent of water; but some have the characteristic soapy feel of ordinary unburnt steatite, with over 4 per cent of water. This fact has an important bearing on the problem of the technique of the white coating, as it leads to the definite conclusion that a high temperature was not essential for this process. Therefore, it is not in the nature of a glaze or enamel formed by fusion above red heat. It is curious that its composition (Table I, p. 689) conforms also to that of steatite, which is clearly its principal constituent. From these facts it may be inferred that this coating is a slip which was prepared by levigating steatite in water, with a suitable medium to serve as a cement. Regarding the nature of this medium, it must be borne in mind that the coating or slip, on these seals, is generally very well preserved, which should preclude the possibility of a gum or any other perishable organic substance. The writer has carried out various experiments in order to arrive at a solution of this interesting problem, and has found that durable coatings, similar to those on the seals, can be produced with a slip prepared by levigating ignited steatite in water with silicate of soda as the medium. After the application of the slip the object was dried in the over at 100° C. and polished with agate. It is highly probable that a similar method was followed by the Indus people.

Steatite objects with well preserved glaze are rare; but a careful search with the aid of a lens sometimes reveals traces of a green glaze. It is evident, therefore, that some of the objects (e.g. round and oblong beads) were originally glazed. The red paint on some of these objects consists of ferric oxide; for this yellow ochre appears to have been employed, which acquires a fine red colour after ignition at a moderate heat.

Analyses of the specimens of mortar found at Mohenjo-daro (Table II, p. 689) make it clear that pure gypsum and lime mortars, as well as their mixtures, were employed.

The pigments found on polychrome and painted pottery are black, white, red, yellow, and green. The black is carbon, which indicates lamp-black or ground charcoal. The white is a mixture of calcium sulphate and carbonate, which implies gypsum and lime. The red and yellow are the well-known ochres, which are widely distributed in Upper India. Specimens of the refined pigments have been found also in the form of small tablets and in tiny capsules.

Steatite.

Mortar.

Pigments.

The green is free from copper, owing its colour to an iron silicate, indicating terre verte. Lumps of a green earth which occurs in cavities in the Deccan Trap, have been found at Mohenjo-daro, and it is very probable that this material was employed as pigment, after necessary purification.

Table I.—Chemical Analyses of Ceramic Materials found at Mohenjo-daro

-												
,	Specimen.	Silica.	Alumina.	Ferric oxide.	Ferous oxide.	Manga- nese oxide.	Lime.	Mag- nesia.	Alkalies.	Copper oxide.	Water.	Analyst.
1.	Black bangle	54.28	19.63	_	8.70	0.13	9.63	4.39	3.43	- '	-	Mohd. Sana Ullah
2.	Greenish pottery .	52.39	17403	5.30	2.39	_	15.78	4.45	1.71	_,	1.05	do.
3.	Faience vase (bluish-	89.76	3.86	0.93	_	-	0.88	tr.	4.07	0.50	-	do.
4.	Faience bangle	88-12	3.02	1.82	-	-	1 26	,-	Na ₂ O, 4.50	0.46		, do.
5.	(bluish-green). Faience tubular bead	91.07	2.44	1.15	_	tr.	1.28	tr.	K ₂ O, 0.65	Cu2O, 1.98	-	do.
6.	(chocolate). Steatite) Disc.	57.99	4.	85		-	4.31	27.20	3.24	1.09	2.01	Dr. M. A. Hamid
7:	Faience Statuette .	57.23	3.0	69		-	6.39	28.99	1.88	0.46	1.36	do.
8.	Slip from steatite seal	61.2	2.	4	-	-	-	34.6	-	-	1.8	Mohd, Sana Ullah
9.	Steatite flat beads .	63.65		1	_	_	-	33.80	-	-	1.09	do.
-3.03		Section 1					1				1	

TABLE II.—MORTARS

Locality.	Gypsum.	Carbonate of lime.	Sand.	Alkaline salts.	Moisture.	Analyst.
Wall (HR Site)	74.12	2*50	20.41	1.18	1.79	• Mohd. Sana Ullah
do.	63.25	0.66	31.61	3.47	1.01	do.
Tank (SD Site)	. 43.75	13.78	38.04	2.47	1.96	, do.
Drain	56.73	24.87	16.64	•-	, 1.76	do.
(DM Site) Vat	nil	69.58	21.71	5.44	3.27	• Dr. M. A. Hamid
(HR Site) Drain and Cesspit (DK Site)	nil	39.96 Magnesium	46.44	0.74	3.74	Mohd. Sana Ullah
		Carbonate 8.82		,		•

A black coal-like substance found at Mohenjo-daro has been identified by the writer Silājīt. as silājīt or shilājātu, an ancient Indian medicine. It occurs as an exudation on rocks in the Himālayas, and is popular with the physicians following the old school. Charaka says that "there is hardly any curable disease which cannot be controlled or cured with the aid of

Shilājātu ": The composition of the Mohenjo-daro specimen (M) is shown against those of four specimens analysed by Hooper (JASB. 72 (1903), 98-103) in the table below :—

0		Analysis of o	Silājīt ,	0	
0	°M.	I.	II.e	· III.	IV.
Water	15.99	9.85	15.90	11.150	10.99
Organic matter	55.24	55.20	49'86	51.55	56.86
Ash	28.77	34.95	34.24	37.30	32.15
		,		-	-0
	100.00	100.00	100.00	100.00	100.00
Ash:—			0		0
Silica	8.23	1.35	1.62	18.10	10.15
Alumina	1.43	2.24	1.08	6.00	4.64
Ferric oxide .	1.44				
Lime	7.31	4.36	3.96	3.86	3.88
Magnesia	0.32	1.50	0.25	0.12	1.34
Alkalies	9.04	13.18	14.32	4.78	6.91
Carbonic acid, etc.	not	11.21	12.13	3.69	4.83
	determined				

(Analysis of M. by Dr. Hamid.)

Löllingite.

Specimens of löllingite or leucopyrite also deserve special mention as they bear evidence of having undergone ignition. Under the action of strong heat, these minerals give off arsenic; or its white oxide, when roasted in air. It is, therefore, highly probable that these minerals were employed for making arsenious preparations, either for medicinal purposes or for destroying life. The fatal properties of arsenic compounds evidently attracted attention very early. The red and yellow sulphides of arsenic have been mentioned by Aristotle, Theophrastos, Dioscorides, and Pliny, as well as in ancient Sanskrit medical works. Bergman in his De Arsenico said: "It is probable that arsenic was first discovered by those who wrought in the roasting and fusing of ores, for it would betray itself by its white smoke, its garlic smell, and its pernicious effects in depraving metals and destroying life." It has been shown by the writer in another section of this work that the Indus people were metallurgists of considerable experience and ability and were using also an alloy of copper and arsenic for their tools. It is obvious that they were well-acquainted with the working of arsenical ores of copper which would give off fumes of white oxide of arsenic on roasting. It is, therefore, quite conceivable that they had become acquainted with certain arsenical preparations and their properties, and utilized löllingite or leucopyrite for the extraction of arsenic.1

The composition of a natural löllingite specimen (B) is given in the table below along with those from the Indus Valley sites. It is obvious that the latter are very poor in arsenic, which is due to the effect of the heat to which they have been subjected. It is difficult to suggest whether löllingite, FeAs₂, or leucopyrite, Fe₃As₄, was employed.

				Analyse	es of	Löllingi	te			
			° B.	I.		II.	III.		IV.	a V.
Iron			27.14	54.55	•	49.3	45.6	3	51.7	48.1
Arsenic			72.17	34.02		43.6	47.1	2 0.	43.9	48.6
Copper	•		-	0.92		0.7	_		_	_
Sulphur			0.37	1.38		.0.16	_		-	-
Water	0		_	7.68		4.7	_		_	
Insole	,		_	1.45		0.8	_			1.9
Sp. gr.		10	-	4.0	0	5:6	0,-		_	

(Analysis of the natural specimen (B.) is by Brevik and those of the Indus specimens by the writer.)

[.] For the possible sources of lolling te and leucopyrite, see pp. 684-5 supra.—[ED.]

The use of cerussite (a natural carbonate of lead) and cinnabar (sulphide of mercury), Which have also been discovered at Mohenjo-daro, is difficult to understand. It is doubtful Cinnabar. if they were employed as pigments, as the analyses of the colours on polychrome pottery do not support this view. Possibly they were utilized for cosmetics or medicinal purposes. In this connection it may be mentioned that white lead was employed for plasters, eye salves, and hair washes in early times. Cinnabar may also have served as a medicine, but it is more probable that it was employed for the extraction of mercury. This metal was known to the ancient Egyptians, and a small vessel full of it was discovered by Schliemann in a grave at Kurna, belonging to the sixteenth or fifteenth century B.C.

Galena was very probably used for the preparation of eye salves or paints.

¹ A small faience flask containing cerusite powder has been found at Harappā.

² For the confusion in Roman times between red sulphide of mercury and the other cinnabar which was the exudation of a dracæna, see Schoff, The Periplus of the Erythræan Sea, pp. 137-9.—[ED.]

APPENDIX II

NOTE ON GLAZED POTTERY

THE fragments of pottery submitted to me bear a design in a series of parallel waves of a milky hue which have the appearance of being on a deep purplish-black ground. The surface is extremely thin, and to a certain extent contaminated with sand and mica. For this reason physical tests are more likely to be reliable than chemical analysis in ascertaining the true nature of the surface.

MICROSCOPIC EXAMINATION AND HARDNESS

(1) Evidence is here adduced that the milky striations are, in fact, glaze, while the dark groundwork is essentially non-vitreous.




Fig. 40.—Microphotograph of glazed pottery, showing scratch.



Fig. 41.—Microphotograph of glazed pottery, showing fracture of glaze.

(a) Scratch tests show the groundwork to have a hardness less than 5 (Moh's Scale of Hardness), whereas the milky portions are decidedly harder and correspond with 6, the figure required by glass and glaze.

(b) The microphotograph in Fig. 40 (× 20 diams.) shows a scratch made by lightly drawing a needle transversely over one of the milky lines. It will be noted that the needle has scratched the groundwork but has not affected the milky portion. The same photograph clearly shows blow-holes in the surface of the milky line, indicating that it has at one time been in a state of fusion.

(c) The microphotograph in Fig. 41 (× 30 diams.) shows a break in the glaze, and the conchoidal fracture is characteristic.

- (2) Certain further observations may help to explain the thinness of the surface and to give some indication of the technique of manufacture.
 - (a) A broad examination of the surface suggests that it has been rubbed down or burnished with a stone before firing, and microscopic examination tends to confirm this as regards the groundwork but not as regards the glaze. If the surface has been burnished, it seems certain that this has been done prior to glazing.

(b) Under a high power certain lines are noticed which for convenience we may refer to as "stream-lines". These stream-lines are noticed particularly along the groundwork, and they follow the lines of the glaze. Ref. Fig. 40, where a dark curved line will be seen near the edge; this line is, in reality, a part of the stream-line.

(c) The groundwork is almost, but not entirely, free from vitreous matter.

It is suggested that, after modelling, the pot was coated with a colouring clay, which was burnished into the surface with a blunt instrument. The surface was then dipped or painted with a slip, which may have been made from powdered slag, and sun-dried. The pattern was obtained by removing the slip in a regular fashion with the aid of a comb-like instrument, and the pot was then fired. From the appearance of the body, which is hard and white and contains traces of translucent material, it would seem that the firing has been conducted at a fairly high temperature.

TABLE OF MEASURES WITH METRIC EQUIVALENTS

```
5 inches
                                                                           = 12.70 centimetres
         = 2.54 millimetres
· I inch
                                                                              15.24
             5.08
                                                     6
             7.62
             I · OI centimetres
                                                    10 ,,
                                                                           = 27.94
                                                    I foot (= I2 inches)
                                                                          = 30.48
                                                    3 feet (= 1 yard)
                                                                                 ·91 metres
                                                                               3.04
                                                    10 ,,
                                                                               6.09
                                                    20 ,,
                                                    50 ,,
              3.04
                                                                           = 30.48
                                                   100 ,,
                                                                          == 60.96
                                                   200 ,,
                                                                          = 152.40
                                                   500 ,,
                                                     I furlong (= 220 yd.) = 201.16
                                                                               1.609 kilometres
             7.62
                                                                                 · 405 hectares
                                                     I acre
```

Abbé refractometer, \$535 Ablution place, 237 Accents in Indus script, 428-30 Adams, Proc. Zool. Soc., 671 n. 2 Additions, see Signs, modifications, etc. Aegean area, see alsq Western Asia and Aegean, Crete, Evans, Distribution. animal motified. w. that on Harappa seal, 70 signs analagous to Indus script, 419 use of copper and bronze, 482 Aelian on the dog, 28; weasel, 71 n. 2 Afrasian dry zone, climatic changes, 3, 4 Agate, 525-6, 585, 681; beads, 536-41, 544; agatejasper, 536-8, 540-1, 544, 681-2 Agriculture, 27-8; state of, shown by use of saddlequerns, 456 Agricultural civilization dependent on great rivers in chalcolithic age, 93-4; implements, 27 Aisles of pillared hall in L area, 23-4, 161-2 Alabaster, 33, 679; lattice-work, 21, 219; pedestal, 479-80; rings, see rings, stone; statue in three pieces fr. HR area, 178; vessels of, 367 Alexander the Great, lion-baiting in Panjab, 28; march through Gedrosia, 3 Alloys, of copper, 30-1; bronze, 481-2, 484-88; gold, 30, 524; silver, 524, 675 Alluvial plain, rise of Indus bed and, 7 Alphabet, absence of, in Indus Script, 41, 411-12 Alpine type, 106-7, 644 Al 'Ubaid, vases of Indian potstone from, 104 Amalaka-shaped object, 225 Amazon stone or microcline, 32, 523, 545-6, 678 Amethyst, 32, 526, 680 Amulet or gamesman, 571 n. 1; amulets, 557-9; possible use of miniature phallic emblems as, 61; of seals as, 380 Analysis, see Chemical analysis Anau, see also Pumpelly, Duerst, Distribution; chariot, 39, 554-5; copper and bronze, 482; faience, 579; jewellery, 523; wheat from, 587; wheel from, 554 n. I Ancient Egypt, 294 n. 1, 296 n. 2, 325 n. 2, 347 n. 6, 400 n. 2, 550 n. 1, 581 n. 2, 5, 7 Andrae, Die Archaischen Ischtartempel im Assur, 338 n. 3 Aniconic worship, see Iconic and aniconic worship Animals, classified list in relation to Indus civilization, 668-72 bones cfd. w. representations on seals, 392 in copper, 506; on copper tablets, 399-401 designs, see Designs on painted pottery

domesticated or semi-domesticated, 27-9, 668-9

figurines, 28-9, 43-4, 346-55; figurine not identified, 348; in Baluchistan, 101 file motif, 395, 398; in Sumerian and Elamitic glyptic, 424-5 · · food, 27, 668, 670 remains excavated, 224, 649-73; condition of, 649; classification followed, 650; list of, w. areas, levels, amounts, etc., 666-3, 672-3; species represented, 650-73 sacred, see Sacred animals; cults, 71-5; accompanying gods, 52, 54-5; as gods or manifestations of, 66-75 in script, 392 on seals, 2, 29, 43, 66-75, 382-90; direction of face, 370, 392, 399; mythological, 389-90; order of popularity, 391; sameness of device, 381 statues, 360; composite statue, 350 wild, 29, and lists above Annandale, A., The Indian Mud Turtles, 670 n. 1 Ann. Rep. Arch: Dept. South. Circ., 310 n. 3 Ann. Rep. Arch. Surv. Ind., 294 n. 1, 325 n. 4, 516 n. 3, 517 n. 2, 552 n. 3, 555 n. 9, 584 n. 2 Antelopes on seals, 389, 391; on vase, 222 Anthropologie, see L'Anthropologie Anthropomorphism and theriomorphism in pre-Āryan India, 74-5 Antiquaries' Journal, 104 n. 5, 194 n. 1, 263 n. 3, 264 n. 1, 265 n. 1, 275 n. 3, 276 n. 2, 284 n. 2, 296 n. 3, 7, 310 n. 4, 356 n. 2, 363 n. 3, 385 n. 3, 528 n. 1, 554 n. 2-3, 558 n. 8, 559 n. 1, 4, 580 n. 2 Antiquity, 292 n. 6, 380 n. 3, 420° n. 1 Anvils, 465 Aca granosa, Linn., 665 Arch. Mem., 3 n. I Arches, see Corbelled arches; true arches unknown at Mohenjo-daro, 263 Archæologia, 326 n. 6, 342 n. 1, 345 n. 1, 468 n. 3, 478 n. 2, 482 n. I Archæological Department, Annual Reports of, see ASR. Archæological Research in Kansu, 328 n. 6 Archaeological Survey of India, 138 n. 1, 146, n. 1, 193 n. 1; Ann. Rep., 552 n. 1; Arch. Surv. Rep., 424, 561 Archaeological Survey of Nubia, 310 n. 2, 367 n. 3 Architecture, 15-26, 262-286; of Mesopotamia and Indus Valley cfd., 263-8, 272, 284 Areas excavated by various officers, 10-14 Aristotle, 382

Arius sp., 664

Arrian, on deserts of Gedrosia, 3 Arrowheads, 499 Arsenic, in copper, 31; mixed with, 482, 484-5 Art, 42-7 Artefacts, see Household implements and utensils, Ornaments and artefacts, Neolithic artefacts Ārvans, see also Pre-Āryans; Āryans possibly in India previous to historical evidence, 432 Ashmolean Museum, 388 n I ASK, 12 n. 2, 13 n. 2, 52 n. 4, 53 n. 4, 55 n. 5, 60 n. 3, 96 n. 1, 104 n. 4, 127 n. 1, 2, 128 n. 3, 4, 550 n. 2 Assam, phallic or bætylic stones, 60 Assembly Hall of Buddhist Monastery, 117-8 Auditory meatus position index explained, 607; employed for comparisons, 639 Australoid, see Proto-Australoid Awls, 470-1, 504 Axes, copper, and resemblances to those fr. other sites, 230; see also Copper and bronze blade-axes Axis axis, see Cerous axis .

B-Bühler, 429 n. 1 Babelon, Manual of Oriental Antiquities, 296 n. 4, 334 n. 6, 568 n. 7 Babylonian houses cfd. as to size w. those in DK area, 241; type of seal, 220 Bætylic amulet, possible use of object as, 571 n. 1; stones, 56, 58, 60-1 Baking of painted pottery, see also Firing, 319 Baking pans, clay, 39, 550-1
Ball, Geog. and Geol. of South-eastern Egypt, 525 n. 5 Ballista balls, 35, 465-6 Balls and marbles, 552-3 Balüchi pottery classified, 97-100; comparisons w. Elam and Sumer, 293 Balüchistan, see also Stein, Sir Aurel, Distribution. burials fr. Nal and Shahi-tump, complete, 81-2; fractional, 85-6; post-cremation, 88, 90 climatic changes in, 2 cultural dependence on neighbours in chalcolithic times, 96-7 designs on painted pottery cfd, w. those fr. Mohenjo--daro, 325-6, 331-4 figurines of Mother Goddess, 49, 50, 101 figurines and models of humped cattle, 101, 347 Banerji, R. D., 10-11, 13-14; excavation of Buddhist Stūpa and Monastery, 113 Banks, Bismya, 465 n. 2, 566, n. 6 Bannister, see Garland and Barley, 27; fr. HR area, species, 586-7; fr. pre-Dynastic graves in Egypt, 587 Barth, The Religions of India, 52 n. 3, 56 n. 1, 57 n. 3-6, 58 n. 2, 77 n. 2, Barton, G. A., JAOS, 109 n. 2 Bases of jars, types, methods of finish, 289-90; pedestal and ring, see Jars w. pedestal bases Basins, type V, 306-7

Bath, 247; or ablution place, 169-70; in block 4,

S. of Bath buildings, 145; in chamber by Great

Batagur baska ?, 663-4

Bath, 141; Great, see Great Bath; rooms w. separate baths, 211 Bathrooms, 16, 29, 209, 241; in block 2, S. of Stupa area, 147; in block 5, 149; flooring of, 273; w. Great Bath, 26; in house in HR area, 201; in section A, area L, 153, 155-6; in D, area L, 174-5; wainscotting, 273-4 Battering of walls, 239; of building to S. of Great Bath, 143-4; possible origin of custom, 272; in Sind, Mesopotamia, Egypt, 265 Bauer and Spencer, Precious Stones, 535, 544 n. I, 677 n. I Bead, chemical analysis of, 514; patterns like those in Mesopotamia, 192 Beads, 194; bronze, 507; capped, 523, w. gold, 521; density of, 534-5; determination of, 534-48; manufacture, 526; materials described and cfd. w. similar materials fr. various places, 541-8, favourite material, 509; nomenclature, 535; physical properties, 534-5 types and materials: cylindrical, 510; ccg-wheel, 510; fluted tapered, 511; long barrel-cylinder, 511; short barrel, 512; long barrel, 512; barrel oval, 512-13; rectangular oval or half-round, 313; disc-shaped, 513; globular, 513; segmented, 514; pottery, 517; misc. unclass., 514-17 unfinished, 526 Beakers, see Pottery beakers; type C, 299; small, type H, 301 Beam-holes, 191, 197, 237, 277 Bear, 73-4 Becké line test, 535 Begging bowl in "burial urn", 121 Bench, brick, 163 Benches, possible construction of, 24 Berry, R. J., and Robertson, A. W. D., Dioptographic Tracings in Three Normæ of Ninety Australian Aboriginal Crania, 639 n. 3; In Four Norma of fifty-two Tasmanian Crania, 639 n. 4 Bhandarkar, Prof. D. R., Progress Report of the A.S.W.I., 53 n. 3; in ASR., 55 n. 5; Lectures on Ancient Indian Numismatics, 129 n. 2 Bhils, dog sect of, 74 Binary and decimal ratios of weights, 37 Birds, bones excavated, 662; copper, 506; models, 349 Bird-chariots, 550; in India, Europe, China, 560-1 Bitumen, use and sources of, 268, 682; in construction of Great Bath, 24 n. 2, 25; 132 Bituminous cement, possible use for shell-inlay, 566; used for stairways in Great Bath, 133 Blandford, W.T., JASB., 92 n. 4 Blanford, in Fauna of British India, Mammalia, 661, 671 Bloch, T., "Conservation in Assam," ASR., 60 n. 3 Blocks numbered on Plans, and described in Text, look

Bloodstone, 681-2

under HR area, VS area, Stūpa area, etc.

Blow-pipe, coppérsmith's, 198.
Blyth, Ed., "On the Flat-horned Taurine Cattle of S.E. Asía," 658

Bone, implements, 470-1; used for ornaments and artefacts, 32, 38

Bones, see Human, Animal, remains, Casting bones
Borders on painted pottery: Bead, 331; Chequer,
332; Hemispherical, 330; Hemisphere and
triangle, 331; Loop lines, 330; Misc., 332;
Roundel, 331; Triangles w. incurved sides, 331;
Zig-zag, 330

Bos bubalus, 659 Bos Indicus, 654-8

Bosses on seals, possible use, 380

Boulenger, G. A., in Fanna of British India, Reptilia, 662 n. 1, 663, 664

Boustrophedon writing, 40, 210, 428

Bow and arrow on seal, 392

Bowls, narrow-bases, type M, 303; type Q, 304 Bracelets, 505; of pottery, chemical analysis of, 530; manufacture, materials, details, 529-31.

Brāhmani or humped bull on seals, 43, 72, 197, 386-7
Brāhmī characters, suggested derivation ft. Indus script,
table, 41, 433; script in relation to Indus writing,
423; characters on pottery, 317; and Kharosthi
inscription on Stūpa plinth, 116

Brāhūi language, Dravidian speech preserved in, 109
Bread, making, 308; models of loaves of, 480
Brick, and clay filling for foundations, 204; jar-stand, 169; piers for carrying upper storey, 20

Bricklaying, technique, 271-80; flat, alternating w. bricks on edge, 231, 244

Brick-robbing, 144-6, 157, 282

Bricks, manufacture, 266-8; methods of laying at different periods, 262; of earlier periods re-used in later buildings, 262; dimensions at different periods, table, 267; dimensions, 115, 131-4, 139, 141-3, 147, 150, 153, 155-6, 160-2, 169, 175, 183, 233-4, 239, 271; difficulty of dating by dimensions, 262; shapes, 264-5, 268; wedge-shaped, 263, 269-70; unusual shape, 248; cut, 162; sawn, 267; specially marked, 266

burnt and sun-dried in ancient buildings, 2, alternating, 209; burnt, use in exposed parts of buildings indicating wetter and cooler climate in ancient Sind, 266; unburnt, not used in exposed parts, 15

Brickwork, see Masonry of Great Bath; 15-17; similarity at all periods, 103; of Buddhist Stupa and Monastery, 114-5; of Great Bath, 25; of Pillared Hall, 160-3

Broken metal, 520

Broken, figurines usually found, 340; condition of

statues, 363
Bronze, see also Copper and Bronze, 30; Analyses, 484-8; known at very early period, 481, 483; alloys of, 481-2; awls and needles, 470; artefacts, 38-9; casting, 489; cells for inlay, 584-5; dancing-

girl, 44-5, 345
Brunton and Caton-Thompson, The Badarian Civilization, 362 n. 3, 460 n. 3, 499 n. 1, 514 n. 1, 579

n. 1, 581 n. 1

Brush used to apply paint to pottery, 321, BSA. Suppl. Paper (1925), 555 n. 5

Bubalis bubalis, see Bos bubalus

Buddha, fragments of statue of, 115

Buddhism, probable adoption of pre-Āryan symbol, 55 Buddhist monuments at Mohenjo-daro, see Stūpa and Monastery; Temples suggesting possible arrangement of benches and corridors in pillared hall in L area, 23

L area, 23 Buffalo, 72, 659; on seals, 386

Buff Balūchī ware, 99

Buff ware, see Buff Balüchi ware, Grey ware, Shāhi-tump ware, Nāl ware

Bühler, Dr. Georg, Indische Palæographie, 41 n. 3, 426, 428 n. 2; On the Origin of the Indian Brāhma Alphabet, 426, 431

Building Stone, see Stone used for building

Buildings, classification of, 17; of uncertain use, 21;

surrounding Great Bath, 137-50

Bull, Brāhmani or humped, distribution (geographical) of models, 347; on seals, 43, 72, 386-7; copper, 506; diffusion of worship in prehistoric times, 72; bull and manger design on round press seal fr. Telloh, 424; bull-man motif on seal, 220
Bullæ, 533-4

Bullæ, 533-4 Bulls, models, 353-5; garlanded, 347, 354, 367, 386; on seals, 385-6; popularity of, in art, 347

Burgess, see Fergusson and Burgess

Burial customs, see also Burials; committal to river, 88; possible exhumation and re-burial, 82 n. 2; exposure to beasts and birds, 82

"Burial urns" in area of Buddhist Monastery, 121
Burials, complete, at Mohenjo-daro and Harappā,
79-81, probable date, 81; in Balūchistān, 81-2;
exceptional, 89-90; fractional, at Mohenjo-daro
and Harappā, probable dates, 82-4; in Balūchistān,

85-6; exceptional, 89-90
post-cremation, at Mohenjo-daro and Harappā,
86-8; in Balūchistān, 88-90

Burlington Magazine, 330 n. 4, 331 n. 3, 6, 332 n. 1,

333 n. I Burnishers, 459

Buttons, 533; w. V-shaped perforations, distribution, 533 n. 2

Buttresses, 239-40, 242
Buxton, Dr. L. H. Dudley, "On the Human Remains excavated at Kish," in Langdon, Kish I, 640-1, 640 n. 2, 643 n. 2

Cage-like object on seals? 383; cf. p. 69
Cake-moulds, 472-3
Cal. Journ. Nat. Hist., 676 n. 1

Cambridge Ancient History, 56 n. 1, 58 n. 2, 3, 64 n. 7, 288 n. 5, 334 n. 2, 361 n. 3, 419, 482 n. 6, 7,

Cambridge History of India, \$1 n. 3, 109 n. 3, 110 n. 1,

Camel, 28, 660
Campbell Thompson, pottery cones at Abu Shahrain 478; Chemistry of the Ancient, Assyrians, 687 n. 1
Canis familiaris, 28, 650-2; pontiatini, 651

Capital, possibly painted, 264; limestone, w. spiral volutes, 191

Cappeds beads, see Beads, capped Caps on figurines, 340

Carnelian, 31-2, 681; beads, 104, 544; long beads, 520; decorated w. white lines, 509, 515-16, 583; same from pre-Sargonic period at Kish, 526 n. 1, 583; same from N.W. India, 583 n. 11; same found by Sir Aurel Stein, 583 n. 12; same imitated, 584 Cart frames fr. Mohenjo-daro, 273 n. 2; 554 Carts, model, 39, 555 Casting bones, 39, 556-7 Casting bronze, 489; copper, 507 Catalogue des cylindres orient., Musée du Louvre, 374 n. 2, 3, 8, 375 n. 2, 376 n. 1, 385 n. 2, 424; see also e Delaporte Catalogues, look under Seals; Indus Script, Sign-list, Brahmi, Sumerian, Painted Pottery, Animal Remains, etc. Cattle, humped, see Humped cattle Cattle, humped and humpless, 28-9 Caton-Thompson, see Brunton and Cedrus deodara used for rafters, 19 Ceilings carried on rafters of decdar, 19 Cellars, 274 Cells filled w. sun-dried brick, see also Mud-filling, Brick and clay filling, Foundations; 208 Cemetery H at Harappa, 81, 84; cemetery not yet found at Mohenjo-daro, 510 Cemeteries, see Burials Censers, stands for, 334 Central Provinces, copper and bronze implements and weapons, 106-7 Ceramic materials, chemical analyses of, 689 Ceramic wares, slips, colours, clay used, 686 Ceramics, see Pottery Cereals used as food, 27, 586-7 Cerussite, 691 Cervus axis, 660; cashmerianus, 659-60; porcinus, 660; cf. p. 29 Cesspit w. objects, 228 Cesspits, brick-lined, 188, 208 Charcoal, 200 Chains of copper or bronze, 5080 Chairs, model, 560 Chalcedony, 509, 517, 681-2; beads, 544 Chalcolithic Age, relation of Indus Culture to others in, 93-101 Chalcolithic cultures, their similarities and differences, Chalcolithic period, population and climate in Balūchistān and Sind, 3 Chalcolithic sites in Sind and the Panjab, 91-2 Chambers numbered on Plans, dook under Areas and find Blocks in which they are Chambers surrounding Great Bath, mentioned by number in text: 5, 138; 15, 139; 16, 139, 142; 18, 140; 19, 141; 20, 141; 24, 139-40; 25, 140. Chanda, Rai Bahadur Ramaprasad, on yoga attitude of male statue, 54. Chanda, R. P., Indo-Aryan Races, 51 n. 3, 6, 55 n. 7, 57 p. 6, 58 n. 1, 65 n. 6, 77 n. 1 Chariot, model, fr. Anau, 39, 554-5; Egyptian, 555;

model, fr. Harappā, 39, 273 n. 2; toy, fr. Kish.

535; Syrian, 555; pictured, fr. Ur, 554

Chases used as flues for hot air, 26, 142-4 Chemical analysis, see Bead, Bracelet, Ceramic materials, Copper and Bronze, Faience, Glazed pottery, Mortars, Silājīt, Sherd, Vitreous paste Chert cubes as weights, 36-7, 589, 596; flake knives, 36 Chessmen, 217 Childe, V. Gordon, The Aryans, 107 n. 2, 523 n. 1; Bronze Age, 316 n. 4; Dawn of European Civilization, 311 n. 1, 461 n. 2, 489 n. 2, 514 n. 2, 555 n. 3; Danube in Pre-history, 316 no4; The Most Ancient East, 3 n. 2, 104 n. 2, 5, 495 n. 2 China, glazed pottery in, 581 Chinese Bird-chariots, 560-1; censer-stand, 334 Chisels, 39, 501-3 Chitra indica (Gray), 653 Chrematheism, 77 Christian, F. W., The Garoline Islands, 62 n. I Chronology of Indus Civilization, 102-7 afforded by bricks, 262, 267, 269-70; by pottery groups, 316; by seals of Indus type fr. Elam and Mesopotamia, 103-4, 426; by Susa seal for Indus Script, 425; by stratification, 9-10 of Buddhist Stupa and Monastery, 122-3; of houses in HR area, 188-9; of handled cups, 311; of painted pottery, 333-5; of use of glaze, 579; of Jemdet Nasr tablets, 453; of Indus Script, 427 Chute, vertical, built in wall, 208 Cinerary urns, 229 Cinnabar, 691 City walls possibly demolished by brick-robbers, 282 Clay used for pottery, see also Paste, Pottery types mentioned by letter; w. various admixtures, 289 Clay used for bricks and pottery, 266 Clemens on weasel, 71 n. 2 Climate and rainfall of Mohenjo-daro in ancient and modern times, 2; of ancient Sind and Babylonia, Climatic changes in Afrasian dry zone, 3, 4; in Balūchistān, 2-5; in Sind, 2-5 Clodd, E., Animism, 66 n. 4 Clothing shown on figurines, 338, 342, 344 Coggin-Brown, J., Cat. of Prehist. Antiq. in Indian Museum, 92 n. 4 Coins found in Stupa and Monastery area, 122-3, 127-30; manufacture of, 129; of Vasudeva, 120; illustrated in Plate CLXIII, 129-30 Colours of slips, 319-20 Column, round, reason for absence of, 263-4 Columns in pillared hall in L area, 160-1 Comb motif, possible appearance on seals, 377; and step motifs fr. various sites, 105 "Combed-slip ware," 578, 692 Combs, 532 Commerce, probable, between Indus Valley and Persia and Mesopotamia, 103-5 Commercial intercourse dependent on great rivers in Chalcolithic Age, 93-4 Congreve, H., Madras Joufn. Lit. and Sci., 546 n. 1 Cones on each side of face in statuettes, 339 Cones with pointed and rounded tops, materials and markings, 477-8 Conical Stones, 476-9

Cook, A. B., 60 n. 3, 62 n. 1, 70 n. 1 Coomaraswamy, Dr. A. K., Yakshas, 65 n. 3, 77 h. 1 Copper, where found, and possible source of that used, 30, 676; mines, 483; earliest and most useful, metal, 481 technique: casting, 507; copper-smith's blow-pipe, 198 artefalls: general use of copper for, 30, 38-9; axes, 229; bowl w. jewellery, 520-2; buttons, 198; wire chain, 211; coins, q.v.; implements in jar, . 490; seals, 220; statuette of elephant, 210; tablets classified and described, 398-401; wase, 194 Copper and bronze, blade-axes, 493-7; chemical analysis, 484-8 (fr. Balūchistān, 488); utensils and implements, 481-508; vessels, 488-93; weapons fr. Gangetic basin and Central Provinces, no light on chronology from, 106-7; weapons and implements cfd. w. Mesopotamian and Egyptian examples, 105-6 Coral, 666 Corbelled arches, 16, 276-7; in Indus Valley and Sumer, 263; drains, 24, 279; passage in Great Bath, 133 Cord decoration on pottery, 291 Corpus Inscriptionum Indicarum, 426 n. 2 Corridors in pillared hall, 23; in L Area, 1 to 9 Cotton as dress material, 33; fabric adhering to silver vase, and Mr. Turner's report, ibid, 194, 585-6; variety used in ancient Sind, 33 Countries, look under their names, and Distributions; countries fr. which metals and minerals come, 674-85 Courtyards, 144, 159-60, 173, 244; of Mesopotamia and Sind cfd., 265 Cousens, Antiquities of Sind, 5 n. 1, 2, 516 n. 3 Cow, apparently not sacred, 111, 355 Cow goddess worship possibly fused w. that of Mother Goddess, 339-40 Cranial capacity of 11 skulls, 637; of 3 skulls cfd. w. those of other peoples, 640 Cremation, see Burials, Post-cremation; probably usual method in Indus period, 89; pyres probable, 224 Cretan sign similar to Indus sign, 420 Crete, see also Distribution, Evans; drain-pipes cfd., 280 n. 1; faience known by E.M. II, 580 Crocidura bidiana, Pachyura stoliczkana, 652 Crocodile, see Gharial; head in shell-work, 200; models of, 348; on seals, 388; as vehicle of Ganges, 73 Crooke, Religion and Folk-lore of Northern India, 51 n. 8, 52 n. 1, 2, 59 n. 4, 63 n. 2-4, 64 n. 5, 65 n. 2, 6, 66 n. 1, 71 n. 2, 72 n. 1-3, 5, 6, 73 n. 2, 4, 74 n. 1, 3-5, 76 n. 2; ERE., 59 n. 1 Crystal, 512, 678 Ctesias, 3,82, 389, n. 2 Cult objects, possible use of human and animal figurines as, 549; probable use of ringstones as, 22; cult stones, three types at Mohenjo-dars and Harappa, 63 Cuneiform inscription on Indus seal, 406; on Indus seal at Ur, reading, 413

Cunningham, Sir A., on Indian Pictographic writing,

426; on derivation of Brahmi, fr. picture signs,

41; Archæol. Reports, 379 n. 2; Coins of the Indo-Scythians, 128 n. 3; Later Indo-Scythians, Cylinder seal found at Mohenjo-daro, 425 n. 1; of Indus type found at Susa, 424 Cylinder seals, 37 n, 381 n. 3 Cylindrical objects of pottery, 479; ware, type Z, 309 Cypræa arabica, Linn., 665; ocellata, Linn., 665 Dado, 241 Daggers, see Knives and Daily Telegraph, 60 n. 4 Dakshinamurii or Yogadahshinamurti, manifestation of Dalbergia sissoo, used for rafters, 19 Damonia hamiltoni Gray, 663 Dams, or gabr-bands, in Southern Balüchistan, 3 Dates, 587; seeds found in VS area, 215 Dating, see Chronology Datum' level for DK arch, 233 n. 1; for L area, 152; for SD area, 135 n. 1 DD 1-4, spots where deep digging was undertaken in VS area, 214 Deadman Lane, HR Area, 178-9 Decimal, see Binary and decimal ratios of weights Decoration of buildings, apparent absence of, 15, 262, of person, see Dress, Clothing, Personal Ornament, etc. of Pottery, see also Incised ware, Painted ware, Pottery types mentioned by letter, Pottery decorated, Designs, Borders, etc. in general, 37-8; by cord, 291; monochrome or polychrome, catalogued, 336-7 of statuette of dancing girl, 209-10 Deep digging, see DD 1-4 Deer, 659-60 Deer-throne of god on seal fr. Mohenjo-daro, 55 Deg, in post-cremation burial at Harappa, 87 Dégraissants, 289, 315 de la Füye, Col. Allotte, 424 Delaporte, Louis, Mesopotamia, 54 n. 3, 64 n. 7; see also Catalogue des cylindres orientaux, Musée du Louvre De Morgan, Prehistoric Man, 50 n. 2, 385 n. 2 De Morgan, La Préhistoirs Orientale, 374 n. 6, 460 Density of beads, formula for finding, 535 Designs on painted pottery, see also Borders; animal, 322-4; chequers, 327; comb, 328; fluting, 329; geometric, 325-7; hide motif, 327; plant, 324-5; scrabble marks, 329; sun, 329; unusual, 328; V motif, 328; vessel motif, 328 on seals, see Seals of written characters affected by material, 407 Dessication, period of in Balūchistan and Sind, 3 Determination of beads, 534-48 Determinatives in Indus Script, 430-1

Dhama, B. L., excavation at Stupa and Monastery,

Dice, 551-2

Diffusion of craft of faience, 580-1; cf. Distribution, Dikshit, K, N., work on DK Area, 11, 12, 14, 233 Dishes, type U, 306 Distribution, geographical, look also under Egypt, Mesopotamia, etc., and under names of objects not mentioned below; of Animal file motif, 398; of beads, materials for, 541-8; of Bird-chariots, 560-1; of buttons w. V-shaped perforations, 533 n. 2; of carnelian beads decorated w. white lines, 516; of handled cups, 310-11; of designs on painted pottery, 322, 324-335; of green felspar, 525; of glass, 582-3; of Grey ware, 311; of Knobbed ware, 315-16; of models of humped bull, 347; of humped cattle, 658; of images of Mother Goddess, 339-40; of Offeringstands, 295-6; of pottery cones, 478; of shellinlay designs, 566-70; of sling-balls, 466-7; of svastika design, 374 Djokha or Yokha (q.v.), description and pictograph of seal fr., 425-6 DK Area: Section A, Block 1, 233; 2, 233-4; 3, Section B, Block 1, 236; 2, 236-8; 3, 238-40; 4, 240-1 Section C, Block 1, 242; 2, 242-3; 3, 243-4; 4, 244-5; 5, 245; 6, 7, 246; 8, 246-7; 9, 247; 10, 248-9; 11, 249-50; 12-16, 250 Section E, 251-3 Dog, 28, 73-4, 650-2; models of, 348, 352 Domesticated animals, see Animals domesticated Doorless chambers, 274; compartment, 245 Door-socket of hard black stone, 154; sockets, 171, 274 Doorways, 16, 164, 167-8; 171-2, 243, 274-5; dimensions, 274-5; roofing of, 275; of interior rooms opening on courtyard, 209; at entrance of Great Bath, 137 Double-axe shaped stone for turning interiors of circular dishes, 226 Dove, model, 350 Drain, 163; in Section D, Area L, 168-9 Drainage system of Mohenjo-daro, 278-82; purpose of, 281-2; of houses, 18, 19, 21; in DK Area, 237, 240-45, 249-51; especially elaborate in Section C of same, 244-5; of Great Bath, 24, 131-4; of huildings surrounding Gleat Bath, 137-9, 141-50; of streets surrounding Great Bath, 146, 149; of HR Area, 179-80, 182, 196, 201-2, 207-9, 211; of houses in L Area, 153; in Stupa Area, 123-6; in VS Area, 216, 218 Drain-covers, 278 Drain pipes of pottery, 180, 280 Drains, 16; their possible uses at Mohenjo-daro, 2; curred, 279; in houses, 280; in First Street, HR Area, 187-8 Dravidian, see also pre-Aryan; type, 109-10; and Sumerian, 109

Dress, see also Clothing; 32-5; on pottery figurines,

of statue, 356-8

338-9; on figurines of Mother Goddess, 49-50;

of mele god, 52; w. trefoil pattern on male statue, 54; as represented on statuary, 362-3;

Drill, stone, similar to one fr. Egypt, 459; tubular, for boxing stone vessels, etc., 46, 367 Drinking place, 2054 Drum of Stūpa, 115 Duerst, "Animal Remains from the Excavations at Anau," in Explorations in Turkestan, 649, 651 n. 1, 653. 655, 657 Dustbins, 16, 179, 181 Dwelling houses, 17-22; see also Houses Dyeing, troughs possibly used for, 197 Eabani or Enkidu, possible Sumerian parallel to halfbovine creature on seals, 67; companion to Gilgamesh, 76; on seals, 356-7, 389 Earrings, 194-5, 344, 505, 519, 528; studs, 528 Earthenware, see Pottery Eburna spirata, Lamarck, 665 Egypt, see also Distribution, Petrie, Ancient Egypt, Lucas, barley fr. pre-Dynastic graves, 27; bricks, sun-dried, as evidence of climate in Chalcolithic Age, 5; chariots, fr. 555; chisels fr., 502; copper and bronze in, 482; drainage-system cfd., 282; faience fr., 576-7; funerary objects cfd., 550; glaze probably invented in, 579-80; hieroglyphs cfd. w. Indus Script, 424; mace-heads cfd., 460; orientation of buildings in, 263; sacred or "nome" animals, 69, 384-5; saws cfd., 39; sledge w. . rollers in tomb scene, 555 Elam, see also Proto-Elamitic, Persia, Distribution, Susa, Mém. Dél. en Perse; relations w. Indus Culture, 102-6; faience in, 579-80; designs on painted pottery fr., 332-4; barrel-shaped weights, 37 Electrum, 30, 509, 522, 524 Elephant, Indian, 72, 653; copper statuette of, 210; on seals, 388; models of, 348, 351; as vehicle of Earth goddess, 72 Encyc. Brit., 69 n. 1, 268 n. 1, 288 n. 3, 581 n. 10 Engravings of animals, 71 Enkidu, see Eabani Equus caballus, 28, 653-4 ERE., 49 n. 1, 3, 50, n. 1, 53 n. 5, 55 n. 1, 56 n. 1, 58 n. 1, 3, 59 n. 1, 3, 62 n. 1-3, 64 n. 3. 65 n. 4, 66 n. 4, 5, 69 n. 3, 72 n. 4, 8 Erosion of site of Mohenjo-daro, 1, 8 Ethnic types, see Racial types Euphemism in naming deity, 56 Europe, bird-chariots fr., 560-1; faience in, 580 Evans, Sir Arthur, Palace of Minos at Knossos, 49 n. 5, 50 n. 6, 65 n. 1, 70 n. 1, 280 n. 1, 288 n. 2, 295 n. 5, 296 n. 5, 300 n. 1, 316 n. 1, 374 n. 1, 392 n. 1, 398 n. 2, 467 n. 2, 508 n. 2, 514 n. 2, 517 n. 1, 527 n. 2, 530 n. 1, 549 n. 1, 555 n. 5, 566 n. 3, 567 n. 7, 9, 568 n. 3, 580 n. 3, 4, 582 n. 4, 583 n. 7; Myc. Tree and Pillar Cult, 70 n. 1 Evans, Sir John, Geol. Mag., 92 n. 4 Excavator's numbers, see Objects, Seals, mentioned by number in text Extent of site and city, 1, 9 a Ex-votos, 330 49 Eyebrows; 358, treatment in figurines, 344-5 Eyes, inlaid, on statues, 358-9, 361; representation of, 340, 342-3, 349-50

Faience, common to all levels, 579-80; chemical • analysis of, use, 575-6; paste of quartz on steatite used, 686-7; colours, 686; glaze, 687-8; early history of same, 579-81; use for ornaments and artefacts, 32; amulets or gamesmen, 558-9; animals, 346-53; handles, 472; Inlay and objects of faience, 570-4; objects moulded on sand cores, 687; buttons, 533; • beads, segmented, •514; sealings, 229, 394-0; squirrel, 205; squirrels and hare, 221; vessels, 37, 365-7, vessels mentioned by number in text, look under Objects

Farnell, I. R., Greece and Babylon, 50 n. 2, 55 n. 10, 11, 61 n. 2, 66 n. 7, 74 n. 6

Fasciolaria trapezium, Linn, 665

Fauna of British India, see Blanford, Boulenger, Preston Favia speciosa, 666

Features, represented on figurines, 340-1; on statuary, 357-9, 361-2

Feeding-cup, possible use of object as, 367 •

Felspar, green, 523, 545-6; distribution of, 525, 678 Female head in grey limestone, 357-8

Fenestrated walls on Great Bath site, 135-6

Fergusson and Burgess, Cave Temples of India, 23 n. 7 Fertility of Sind, ancient and modern, 1, 6

Ficus religiosa, see Pipal-tree

Figurines, of animals, see Animals, s.v.; decorated w. jewellery, 509; human, 338-46, 549-50; method of manufacture, 341, 349; mentioned by number in text, see Objects; of Mother Goddess, 49-50, 339-40; of same and of humped bulls fr. Balūchistān, 101

Fillets, see Gold; of gold or silver, 509, 527-8; on statuary, 357-9; on terra-cotta head, 225

Finger rings, 34, 504-5, 520, 528

Fireplaces, 16, 276; possible use of square brick troughs

Firing of pottery, 289, 686, 692, of steatite, 379, 688 First Street, HR Area, 187-8

Fishes, 664, 670, 673; as food, 27; on seals, 387, 392; on sealings, 394-5; in ivory, 557

Fish-hooks, 501 Fish-shaped pieces of ivory, 557

Flared mouths, jars w., type S, 304-5

Fleet, Indian Antiquary, 431 n. 1, 494 n. 1

Flesh-rubbers, 467-8 Fleure, see Peake and

Flint implements, 27, 458-9; types fr. different sites in Sind, 92-3

Floods, effect on site, 1; danger fr. in antiquity, 6, 7; precautions against, 19, 21, 190, 265; to be considered in chronology, 102-3

Floors of burnt brick resting on burnt clay nodules, 189;

varieties of, 16, 272-3

Floral patterns on polychrome pottery, 222 Flues for distributing hot air, 26, 142-3 Fluted pottery, type Y, 309

Food, animals used for, see Animals s.v.; fish, 29; plant, 27, see also Fruit; reptiles, 27

Foot-wheel, see Pottery Foote, R. Bruce, Indian Prehistoric and Proto-historic Antiquities, 95 n. 1

Forbes, A. K., Ras Mala, 62 n. 3

Fortifications of city, 9, 282

Foundations of buildings, 16; of building probably of sacred character, 204; built in sections in ornamental manner, 240; of house laid on débris of older structure, 203; resting on brick-kiln refuse, 239 Fowls, 323, 392, 662, 669

Francis, A., 13

Frankfort, Studies in Early Pottery of the Near East, 326 n. 2, 328 n. 2, 374 n. 2, 583 n. 4

Fruit used as food, 27, 587

Funeral vessels, 85-9; see Burial urns

Funerary objects, possible use of clay figures as, 550-1 et Furness, W. H., The Island of Stone Money, 62 n. 1

Gabr-bands, see Dams

Gadd, C. J., see Smith and

Galena, 524, 691

Gallery in area L, section D, 171

Galles sp. (?), 662 8

Games, 39; possible use of clay cones in, 478; of miniature phallic emblems in, 61; and Toys, 549-61; gamesman or amulet, 571 n. 1; gamesmen, 557-9

Gangetic basin, copper and bronze implements and

weapons, 106-7

Garland and Bannister, Ancient Egyptian Metallurgy,

485 n. 2, 489 n. I

Garlands on bulls, 347, 367, 386

Gastropoda, 665-6

Gavialis gangeticus, 662

Gazetteer of Bombay Province, 62 n. 2

Gazetteer of the Province of Sind, 7 n. 1, 35 n. 2, 75 n. 1

Geographical distribution, see Distribution

Geological Survey of India, 268

Geology of India, 543 n. I

Geometric designs, see Designs on painted pottery; on shell-inlay, 195

Gentlemen's Magazine, 674 n 1

Ghara type of urn in Buddhist Monastery, 121

Ghariāl or ghariyāl, 27, 73, 562, 670; models of, 352;

on seals, 388, 394-5

Gilgamesh, 76, 389

Chass, early history, 579-81; not found at Mohenjodaro of Harappā, 582; distribution of early, 582-3 Glaze, use of term, 578 n. 1; faience, 687-8; painted,

577; on steatite objects, 688

Glazed ware, 38, 366, 581-2; chemical analysis of, 577-8; microscopic examination of hardness, 692; fr. which slip and glaze had been partially removed by comb-like instrument before firing, 578 .

Glazebrook, R., Didionary of Applied Physics, 535 n. L

Glauconite, 32, 685

Glotz, Aegean Civilization, 499 n. 3

Goat, 73-4; on seals, 392; on seal impressions, 293, 396; on copper tablets, 399; on pottery, 322

Goblets, w. pointed bases in early Indus culture, 37; in ruins of Buddhist Monastery, 120-1; type R,

God, male, see Male god

Gold, 29-30; where found, 29, 674-5; probable source

of that used, 675; beads, 522; manufacture of same, 523; physical properties of same and comparison w. those fr. other places, 543; bracelet, 522; cap, conical, 519; fillets, 527-8; same, resembling those of Ur, 194; jewellery, 509, 517-24; netting needles, 521; studs, 521 Goldsmith's "hoard", 522; weighing scales, 205; work, 30, 194
Gowland, "Metals in Antiquity," JRAI., 483 n. 2
Grāmadevatās, village goddesses in India, 51 Gratings, 275 Grave-furniture: ornaments on skeletons at Mohenjodaro, 79; absence of usual furniture w. complete burials at Mohenjo-daro, 80-1; of complete burials at Harappa, 81 ; w. fractional burials at Mohenjo-daro, 82-4; in post-cremation burials, 86-9; in burials in Balūghistan, 81-2 Great Bath, 24-6; 131-7; dimensions, 131; levels of Bath and drains, 134-5; method of filling, 142; use of, 142; buildings surrounding, 137-50 Green earth, 321, 685, 689 Grey ware, 99, 319; group AD, 311-12; of paste similar to that fr. Kish, 289 Grinders for hollowing out stone vessels, 369 Grotesque statue, 360 Guha, Dr. R. S., see also Sewell and; on skulls fr. Harappā, 108 Gulati, A. N., and Turner, A. J., A Note on the Early History of Cotton, 33 n. 3, 585-6 Gungeria, axes cfd., 230 Gupta Age, terra-cotta relief depicting Mother Goddess, Gutters, 277-8 Gypsum, 679; chemical analysis, 269; mortar, 15, 25, 180, 263 n. 1; plaster, 197, 263, 278 Hæmatite, 680 Hafting, of knives and daggers, 500; of lances and spears, 498; of maces, 46r Haig, M. R., The Indus Delta Country, 73 n. 3; JRAS., Hair, method of dressing, 33-4; as shown on statues and figurines, 177-8, 210, 213, 343-4, 357-9, 362 Hair-pins, 359, 531-2 Hakrā, see Mihrān

Age, 51 n. 6, 288 n. 2, 375 n. 3, 419, 555 n. 5, 582 n. 3, 583 n. 3 Hall, H. R., and Woolley, C. L., Al 'Ubaid, 104 n. 2, 109 n. 1, 482 n. 3, 489 n. 1, 573 n. 1, 579 n. 5; Ur Excavations, 338 n. 1, 340 n. 1, 361 n. 1, 5-7, 478 m. 1, 482 n. 3 Hallstatt and Koban, buttons w. loop inside, 523 Framid, Dr. M. A., chemical analyses: of bead, 514; ceramics, mortars, 689; falence, 576-7; silājīt, 588, 690; sherd, 316; silver, 524; on colour of grey ware, 311 n. 2 Hammam, in DK Area, 236-7; attached to Great Bath, 26 '

Handbuch der Mineralogie, 543

Hall, see Pillared Hall in L Area Hall, H. R., The Civilization of Greece in the Bronze

Handcock, Archaeology of the Holy Land, 583 n. 6 Handled Cups, type AC, 310-11 Handles, 472 Hand-wheel, see Pottery Hansen, Soren, On Posthumous Deformation of Fossil Skulls, 637 n. 4 Harappa, burials: complete, 81; fractional, 84-5; post-cremation, 87; skeletal material fr., 108; o model carts fr., 555; clay fig. of woman grinding corn, 308 n. 2; copper maces fr., 36; seal w. two beasts, 70; sealing showing "unicorn" w. two horm, 68; sealing depicting sacred trees, 65; sealing depicting Earth or Mother Goddess, 52; seals quoted by number, 410-11, 416-17, 419-20; cf. Pls. CXIX-CXXIX; inscriptions older than those fr. Mohenjo-daro, 418; Stone statuettes fr., 45-7 Hare on copper tablets, 349; in faience, 221; model of, 351 Hargreaves, H., work in HR Area, 187; on burials at Mohenjo-daro, 79; on burials at Nal, 80-2; Excavations in Balūchistān, 82 n. 3, 85 n. 2, 96 n. 2, cap. xii Harrison, Pots and Pans, 581 n. 8, 11 Hatching, decoration, 324, 326, 375 Head-dress, 33; of figurines, 338 Heads, shapes shown in statues, 362 Heaters, type AF, 323 Heavy-based ware, type P, 304 Heliotrope beads, 544 Hemmy, A. S., on weights, used at Mohenjo-daro, 37, cap. xxix Herodotus, on clothing of Egyptians and Indians, 33 n. 1 Herpestes auropundatus, 650 Herzfeld, E. Ausgrabungen von Samarra, 374 n. 5 Heuzey, L., Découvertes en Chaldée, 376 n. 1, 424 Hewitt in JRAS., 66 n. 1 Hide motif, see Designs on painted pottery Hilzheimer, Die Wildrinder im alten Mesopotamien, 453 History of excavations at Mohenjo-daro, 11-14 Hogarth, D. G., ERE., 58 n. 1 Hooper, David, Analysis of silājīt, 588 Hopkins, The Religions of India, 48 n. 2, 51 n. 6, 52 n. 3, 54 n. 1, 2, 7, 55 n. 5, 56 n. 2, 57 n. 6, 66 n. 3, 69 n. 4, 78 n. 1 Hornblende pendants, 526-7 Hornblower, G. D., 347 n. 8 Horned male figure, 232, 341; on seals, 389. Hornell, James, in Memoirs of the Asiatic Society of Bengal, 563; Marine Zoology of Okhamandal, 666 n. 1, 670 n. 3

Horns, on head of male god, 52, 54, 55, 341; symbol of divinity, 67; on seals, 389

Horse, 28, 653-4

Hot-air baths, 26, 143

Household implements and utensils, 36-9, 456-80, 488-93

Houses, see also Dwelling Houses, and look under Area, rection, block, after reference to plan Houses in HR area described: Section A, I-IX,

176-84; VIII also 17-20, 182-3, 263, 280; Section B, I-LXVI, 188-213; X also 184-6

Houses in VS Area described: I-XXXVII, 215-32; XIII also 20-22

Houses in or near vahich bodies were found, 79-81; fractional burials, 82-4; post-cremation burials,

Cfd. as to size w. Babylonian, 241; as to alignment and orientation w. Egyptian and Babylonian, 263; no light on chronology fr., 106

HR Area, extent of excavations in 1926-7, 187

Section A, Block 1, 177-9; 2, 179-184 Section B, Block 1, 188-9; 2, 184-6, 189-99; 3,° 199-201; 4,°201-2; 5, 202-6; 6, 206; 0 7, 206-10; 8, 210-12; 9, 213

Human figures, 338-46; in baked clay, 549-50; w. bow on ivory plaque, 552-3; on seals and sealings

and copper tablets, 389, 392, 393, 395, 398, 400 Human remains, see also Skeletons, Skulls, etc.; 599-648 Human sacrifice, see Sacrifice

Human statues and statuettes, see also Statuettes; 44-7, 356-60; statuette of male seated in Indian fashion, 208

Human-headed animal on seal, 197; monster on seal, 226 Humped bulls, figurines fr. Balūchistān, 101

Humped cattle, 27-8, 70, 654-8, 669; on seals, 386-7; pottery figures, 347, 354; not on painted pottery from Mohenjo-daro, 324

Humpless bull, 70, 228

Huntington, Ellsworth, Civilization and Climate, 3 n. 2, 6 n. 1

Hybrid wares, see Polychrome banded ware, Mehi ware Hypocausts, 26, 143, 236-7

Ibex, see Deer-throne; on pottery, 322 Ibn Batūta's journey through Sind, 73 Iconic and aniconic worship, 56, 58-61 Ideographic nature of signs, 420-1

Illustrated London News, 347 n. 7, 356 n. 2; of 4th Oct., 1924, additions or alterations for Sign Manual there published, 407-8; 424, 426, 467 n. 1, 3, 556 n. 1, 567 n. 4

Immigration, possible influence on mode of burial, 90

Imperial Gazetteer of India, 4 n. 1° Implements, see Agricultural, Chert, Copper and bronze, Flint, Household implements and utensils

Incense-burners, 69, 293, 490-1

Incised decoration on stone boxes, 369; ware, 38, 291 Indexes of Mohenjo-daro skulls, 646; of four Mohenjodaro groups cfd., 647; of three skulls cfd. w. other peoples, 641; of six skulls cfd. w. other peoples, 643; see also Auditory Meatus Position

India, use of copper in, 482-3; history of painted pottery

in, 334-5 Indian Antiquary, see Fleet Indian Bird-chariots, 560-1

Indian Museum, Calcutta, Catalogue, 293 n. 1

Indoplanorbis exustus (Deshayes), 666

Indus Culture, authors of, 107-12; cfd., w. Vedic, o 110-12; diffusion in Sind and Panjab, 93; existant before and after Mohenjo-daro, 103; uniformity of, 91; remains in Stupa area, 123-30; relation to other cultures in Chalcolithic Age, 93-101;

evidence for eastward extension, 95-6; for westward, 96-101; resemblance to certain cultures of Elam and Mesopotamia, 102; relations w. same, 103-6; seatures of, absent fr. Nal, 100,

Indus period, cremation usual, 89-90

Indus River and Mihran, relation to fertility of Sind, 5-7 Indus Script, 39-42; Sign List on, 434-52; see also Sign Manual, Smith and Gadd; accents in, 428-30; chronology for, 432; determinatives in, 430-1; direction of writing, 427; material for study of, 424; similarities w. other pictographic scripts, 427; relation to Brahmi script, 423, table of Brahilii characters derived fr., 433; cfd. w. Egyptian hieroglyphs, 424; w. Sanskrit, 431-2; w. Sumerian, 423, 454

Indus ware, 97

Inlaid bead, 517; pottery, 366

Inlay, see Shell, Faience, 558; bronze cells for, 584-5; decoration of handles, 472; w. vitreous paste, 575-6 Inscribed pottery, see Pottery, inscribed

Inscription analyzed, 419-20; on seal depicting god,

52; goddess, 52

Inscriptions, see also Seals; 40, 42; order determined by impression, not by seal, 409-11; on seals, possible meaning of, 381; probably names and titles, 412; on Stūpa plinth, 116

Inundation, see Floods; of Indus and fertility of Sind,

Irrigation, possible use of certain jars for, 318 Ivory used for ornaments and artefacts, 32, 38; cylinders possibly seals, 563; objects, 562-3; pin, 196; plaque w. human figure and bow, 562-3

Jade, 32, 512; beads, 519; physical properties of same and cfn. w. specimens fr. other places, 541-2

Jadeite, 32, 34, 683-4 JAOS., 69 n. 4, 109 n. 2

Jar covers, type X, 398; handle, 506; stands, type AE, 312; stands, 368

Jars w. pedestal bases, type D, 299-300 JASB., 4 n. 1, 92 n. 4, 588 n. 1 Jasper, 32, 681-2; beads, 537-41, 545

astrow, Civilization of Babylonia and Assyria, 517 n. 1 Jemdet Nasr, jar cover fr., 105, 308; pictographic

script cfd. w. Indus, 453-5; wheat fr., 587 Jeweller's "hoard" w. broken metal, 520

Jewellery, see Personal Ornaments; found in copper vessel, 253; in silver vessel, 250, 493, 519-20; represented on figurines and statuary, 339, 346,

357; worn by both sexes, 509 Ihukar, Chalcolithic site on Western Nara, 6 Journ. of Bihar and Orista Research Society, 281 n. 3 Journ. Egypt. Arch., 338 n. 1, 339 n. 2, 346 n. 1, 347 n. 8, 352 n. 1, 392 n. 2, 523 n. 6, 555 n. 8 JRAI., 49, n. 2, 82 n. 2, 587 n. 3 FRAS., 66 n. 1, 73 n. 3, 424, 516 n. 1, 526 n. 1, 583 n. 9

Judges, xx, 16, 467 n. 4

Kālī, similarity to certain figures fr. Balūchistan, 50 Kamandalu- shaped vase, 228

Kaunakes, Sumerian dress, 33, 342 Keith, Sir Arthur, on skeletal remains fr. Al 'Ubaid and Ur, 109, 639 n. 2, 641-2; Antiquity of Man, 610 p. 1, 639 n. 6. Report on two Human Crania of Considerable but Uncertain Antiquity, 607 n. 3, 639 n. 1, 5; Human Skulls fr. Ancient Cemeteries in the Tarim Basin, 613 n. 1, 614 n. 1, 626 n. 1, 643 n. 1, 648 n. 1 Keith, see Macdonnell and; ERE., 53 n. 5, 6; Religion and Philosophy of the Veda, 56 n. 4 Kharosthi, see Brahmi and Kharosthi inscription Kiln, pottery, 193; not used in modern Sind, 289; -refuse, dump for, 174 Kilt like kaunakes, 342 King, L. W., History of Sumer and Accad, 220 n. I, 347 n. 3, 4, 387 n. 2, 482 n. 3

Kish, carnelian beads decorated w. white lines fr., 104,
583; chariots, toy, 555; "combed slip ware," 578; rosetted decoration similar to that on VS 2662, 291; faience whorl on copper shaft, 470; Indus seals fr., 103-4; Indus seal w. description and pictographs fr., 426; jar similar to type Y, 309 n. 1; jar handles, representation of eyes on, 340; Offering dishes and stands, 83-5, 292; pictographic stone tablet fr., 453-4; seal showing man in tree, 388; shell objects cfd., 475; sledge shown on pictographic tablet, 555; walls demolished by brick-robbers, 282; ware, pre-Sargonic, of paste similar to that fr. Mohenjo-daro, 289 Kitchen, probable use of room as, 22; Knives and daggers, 499-500; chert flake, 36; handles of, 472; rarity of bronze or copper, 39 Knobbed ware, type AH, 315-6 Knuckle-bones, absence of, 553 Kohl-sticks, possible use of metal rods as, 504 Koldewey, Excavations at Babylon, 263 n. 2, 5, 273 n. 1, 275 n. 3, 279 n. 1, 583 n. 5 Kushān beads, 517; period, glazed pottery in, 581; pottery, 317; pottery designs, 335 L Area, 151-75; Section A, 152-7, Blocks 6-8; B, 157-9, Blocks 9-11 C, 159-168, Blocks 4, 5, 11 (11 on pp. 159, 168) D, 168-75, Blocks 1-3 Labels, clay, on goods, 410, 412

Ladles, 471 Lagash, see Telloh Lamellidens marginalis (Lamarck), 664 Lance-heads, see Spear and Land of the Five Rivers, 589 n. 9 Langdon, Prof. S. H., Kish, I, 109 n. 2, 361 n. 3, 363 n. 3, 454, 555 n. 7; derivation of early Brahmi fr. Indus Script, 41; relation of Jemdet Nasr to Indus Script, 41 n. 1; bone cylinder seal oft. Susa II, 104; presence of horse in Mesopotamia, 28 . Earth Mother at Nippur, 50 n. 2; cap. xxiii Language of Inscriptions, 42' L'Anthropologie, 482 n. I Lapis lazeli, where found, probable source of that used,

32, 677; rare at Mohenjo-daro, common at Nal, 525; beads, physical properties of, and Cin. v. specimens fr. other places, 542-3

Latrines, 207, 281 Lattices, 465; lattice-work in alabaster, 21, 219 Laufer, B., on Bird-Chariots, 950 Layard, Menuments of Nineveh, 70 n. 1 Lead, 30, 524; where found, possible source of that used, 30, 676-7; mined for silver associated w. it, 524°; and silver deposits, 675; proportion in blonzes, 486 Leather cases perhaps copied in pottery, 534 Leather-cutter's stone, possible use of object as, 0167 Ledge-necked jars, type E, 300 Lee and Pearson, "A first Study of the Correlation of the Human Skull," 637 n. 1 Legrain Culture of the Babylonians, 390 n. 2 Leucopyrite, see Löllingite Level, see also Datum Level and Stratification; seasonal, of sub-soil water, 9; of streets, 10; of streets and adjacent buildings, 8, 9 Lime, use in making pottery, 318-9 Limestone, 31; capitals, 264; head, L 127, its position, 155; head, yellow, 358; jar stand, 312; rings, 174; vessels, 368
Linga, see Phallic emblems; -shaped cones, 212; -shaped stones, 202 Lintels, 10, 275 Lions (?) on seal fr. Harappa, 70; where depicted on seals, 391 Liverpool Annals of Archæology, 316 n. 2 Löllingite, 32, 485, 684-5; description and chemical analysis, 690 Lotas, in funeral urns, 86-7 Luard, Ethno. Survey, 72 n. 2, 74 n. 1 Lucas, Ancient Egyptian Materials, 269 n. 3, 525 n. 4, 575 n. 3, 576 n. 1, 581 n. 6; on silver, 523-4 Lyall, Berar Gaz., 72 n. 2 Lyddeker, R., Game Animals of India, 68 n. 1,348 n. 1, 387 n. 4, 388 n. 2

Mace-heads, 36, 459-61; mace-like objects, 475-6 Macdonnell, Vedic Mythology, 55 n. 2, 65 n. 5 Macdonnell and Keith, Vedic Index, SI n. 12, 94 n. 6, MacIver and Mace, El Amrah and Abydos, 583 n. 2 Mackay, Ernest, appointment at Mohenjo-daro, 1926, 13; Report on the Excavation of the "A" Cemetery at Kish, 292 n. 3, 296 n. 1, 2, 300 n. 2, 329 n. 6, 340 n. 2, 461 n. 3, 468, n. 2, 469 n. 2, 470 n. 2, 472 n. 2, 516 n. 1, 528 n. 1, 555 n. 2, 582 n. 1; A Sumerian Palace, 309, 461 n. 3, 466 n. 2, 472 n. 1, 495 n. 1, 501 n. 1,-511 n. 2, 555 n. 2, 7, 569 n. 4, 583 n. 10; JRAS., 406 r. 1; cap. x, xi, xv-xxi, and xxiv-viii Mackenzie, Ancient Civilizations, 516 n. 2

Maclaren, J. M., Gold, 675 n. 1 Modreporaria, 666 Magical properties of ring-stones, 62; or religious nature of animal figures, 71 Mahāyogī, a name of Siva, 53 Majumdar, N. G., on Chalcolithic sites in Sind, 92 n. 1, 3; on coine fr. Stūpa area, 127-30; on discoveries at Amri, 100 n. 1

INDEX

Male figures, rarity of representation, 340; male figures, 44, 45, 341; on plaque, 343; wearing jewellery, 346; stone statues, 356-60 Male god, prototype of Siva, 52-6 Male statue, 356, 358-9 Male statuette w. beard, 342 Mammals, 672-3; bones of, excavated, 650-661 Man, 482 n. 5 Mana of certain animals; 74 Manatt, See Tsountas and Manger, w animals, on reals, 385-88 Manouvrier, La détermination de la taille après les grandes os des membres, 600 n. 3 Manouvrier and Pearson, differences in statures calculated by their formulæ, 601-2 Manufacture of human figurines, 341; of animal, 349 Marbles, see Balls and Marshall, Sir John, Preface; cap. i to ix; Ed. Notes passim Martin, Rudolf, Lehrbuch der Anthropologie, 601 n. 2 Mask, panther-like, 350 Masks of clay, hollow, 341 Masonry, see also Bricklaying; 262-86; of Great Bath and surroundings, 131-50; of different periods in DK Area, 235-6 Materials, see Ornaments and artefacts, materials used; for dress, 32-3; of Seals, q.v.; of statues, 363 Measurements of Mohenjo-daro and other skulls, 645-8; See also Skeletons Medicines, 29, 587-8; animal horns used for, 669, 671-2 Mediterranean type, 642-3 Mehi ware, 98-9 Mem. Arch. Surv. Ind., 321 n. 3, 387 n. 3, 463 n. 1,

513 n. 1, 525 n. 2, 566 n. 4, 568 n. 1, 580 n. 1, 2 Mém. Dét: en Perse (Mémoires de la Mission Archéologique de Perse), 68 n. 2, 263 n. 5, 268 n. 2, 292 n. 4, 295 n. 1, 317 n. 2, 323 n. 2, 6, 326 n. 1, 5, 8, 328 n. 1, 4, 329 n. 1, 2, 330 n. 1, 2, 4-6, 331 n. 1, 2, 7, 332 n. 2, 342 n. 1, 344 n. 1, 347 n. 1, 348 n. 4, 351 n. 3, 374 n. 3, 4, 7, 9, 375 n. 1, 385 n. 2, 387 n. 1, 400 n. 1, 424, 460 n. 1, 466 n. 4, 468 n. 4, 469 n. 1, 475 n. 1, 495 n. 2, 516 n. 8, 517 n. 1, 518 n. 1, 523 n. 4, 534 n. 1, 562 n. 3, 566 n. 8, 567 n. 1-3, 568 n. 5, 6, 569 n. 1, 570 n. 1, 592 Mem. Geol. Surv. Ind., 391 n. 3.

Mesopotamia, see also Distribution, Langdon, Woolley, Mackay, Hall, Kish, Jemdet Nasr, etc.; archæology, Mackay's previous connection w., 13; buildings, orientation, use of arch and column, 263; climate in ancient and modern times, 3, 5; use of sun-dried brick as indication of climate, horse, possible presence of, before fourth millennium, 28

Relations w. Indus culture, 103-6; comparisons? architecture, 263-8, 272, 284; beads and bead patterns, 192, 311; copper and bronze, 482; drainage-system, 282; Eabani or Eakidu and creatures on seals, 67; faience, 32; gamesmen, 559; glaze and glazed pottery, 579-82; triads of gods, 53; grinders, 36 n. 5; horns as emblems

of divinity, 55; five Indus Seals found, 381, 406, 424; descriptions and pictographs fr., 424-6; pictographs cfd., 453-55; lion (?) motif and Harappa, 70; pottery types, 917; pottery, painted, 334-5; racial types, 107-9; religious contact, 76-8; shell-inlay, 32; temples, 22; trefoil, 54; weights, 593-5; barrel-shaped weights, 37 Metals, sources, use, 481, 674-77, 682; proportions of other in copper and bronze, 484-8; used for jewellery, 509; rods, 504; vessels, 37, 490-3 Metals and minerals, 29-32, 481-90, 674, 685-91 Mica, use in making pottery, 319 Microcline, see Amazon stone and Green felspar Microscopic examination of glazed pottery, 692 Middlemiss, C. S., on locality of Amazon stone, 546 n. 2 Mikrochemisches Praktikum, 547 n. I Mihran, the Great, course in ancient and modern times, 5, 6 Mills, Lhota Nagas, 72 n. 5

Minerals, sources of, etc., 677-85; see also Metals and Min. Mag., 546 n. 3 Miniature vessels, 292

Minoan signs, analogies w. Indus, 411 Miscellaneous shapes, group T., 305-6 Models, see Figurines, Animals, also animals under their names Mollusca, 664-5 Monastery, see Stupa and

Money, see Stone money of Caroline Islands Mongolian type, 643; type of eye on statuette, 345 Mongoose, 650; model of, 351

Monier-Williams, Sir M., Religious Thought and Life in India, 48 n. 2, 51 n. 5, 52 n. 6, 54 n. 5, 55 n. 3, 7, 57 n. 1, 5, 58 n. 2, 59 n. 3, 5, 63 n. 1, 64 n. I, 66 n. 4, 68 n. 4, 72 n. 7, 78 n. I

Monkey god, 73; models of monkeys, 349, 351-2 Monsoon, areas affected by, in ancient and modern

times, 4, 5 Mortar, 15, 688; chemical analyses, 689; composition, 263 n. 1, 269; of Monastery, 116; in Great Bath, 25; in houses in HR Area, 183; in wells, 270 Mother Goddess, at Mohenjo-daro and Harappa, 49, 32; in Baluchistan, 49-50, 101; in Wastern Asia and Ægean, 50; cult in India, 51-2, 57-8; on sealing fr. Harappa, 52; probably to be identified with certain figurines, 339

Mound in DR Area, 242 Mud-filling, 159; muchbrick filling, 234; mud and brick filling, 376 n. 2, 243; cells to contain, 253; methods of, in Sind and Babylonia, 265; on which pavement was laid, 234

Mukherji, Mr. S., 17 n. 4 Murex, 565 n. 2

Museum of Fine Arts Bulletin, Boston, 581 n. 7 Museum Journal, 276 n. 3, 559 n. 4

Mus rattus, 653 Musyan, complete and fractional burials in, 82; and Mehi pottery, 99 Myres, Prof. J. L., in CAH. on Mother Goddess cult,

50 n. 2, 4 Mythological animals on seals, 389-90

INDEX

	Nagas (?) doing homage to a deity, 68, 395; and	236, 353	2862, 460
	water-spirits, 75-6	356, 351	2899, 479
	Nal, see also Baluchistan; glazed beads fr., 580;		2927, 479
	Brāhmanī bull on sherd, 387; lapis lazuli, 525;	1717, 346	2936, 526
	ware, 99-100; intrusive in Eastern Balūchistan,	250%, 343 ,	2948, 469
	100-1	2737, 341	2991, 479
	Năra canal, 1, 5, 6	2/41, 343	2992, 571
	Narrow-mouthed ware, types J, Ja, 301-2	5067, 341	3002, 570
	Needles, 470, 504	Pottery °	3079, 463
	Necklaces found in silver vessel, 519-23; in copper	. Pottery	3090, 477
	vessel, 520; and girdle terminals, 507	*A 406,0291	3114, 479
0,	Negroid features on statuette of dancing-girl, 209	*B 341, 294	3201, 553
	Neolithic artefacts in Sind, 92-3 Nepheline-sodalite rock, 683; beads, determination of,	*C 1352, 311	3343, 505
	and comparison w. those of other countries, 546–8	2019, 311	3411, 505 0
	Net-sinkers, 464	3030, 311	4940, 501
	Niches in walls, 157, 217°	3156, 311	4563, 471
	Nickel, percentages in copper and bronze, 483-4,	*D 287, 314, 320	5774, 524
	486–88	6220 298	6314, 524
	Nilsson, The Minoan-Mycenaean Religion, 50 n. 5,		7056, 464
	64 n. 2, 69 n. 4	DK Area: Catalogue on	•
	"Nome" animals, 384-5	pages 253-61	Faience Vessels
	Normand, Dr. C. W., on climate of Sind and	DK 0, 557	
	Balūchistān, 4	7, 557	1933, 366, 572
	Nose ornament, 527; studs, 528	233, 470	2798, 368
	Nubia, glazed pottery fr. XIIth Dynasty tomb, 581	319, 554	ъ
	Numerical system possibly represented in signs, 412-3	430, 504	Figurines
	N.W. India, devices on coins similar to Indus pictures, 413	580, 588	485, 341
		774, 458	1380, 343
		896, 503	2014, 343
	Ochre, red, 32, 320, 682-3	961, 553	2091, 351
	Objects found in Area, Section, Block; look up Area,	1200, 552	2153, 352
	etc., and see Objects mentioned by number in	1246, 499	2189, 342
	text; buried w. dead, see Grave-furniture; found in and about Great Bath, 133-6, 138-41, 143-50;	1265, 462	2380a, b, 350
	fr. strata of Indus culture in Stūpa area, 124-7;	1341, 439, 519, 529	2384, 346
	imperfectly represented by pictographs, 407	1421, 526	2385, 342
	OBJECTS (EXCEPT SEALS) MENTIONED BY NUMBER IN	1462, 465	2505, 342
	TEXT: see the catalogues of them as follows: Animal	1554, 558 9	3158, 344
	remains, 650-4, 659-66, 672-3; Copper and	1602, 570	3188, 345
	bronze specimens, 486-7, 497-9; DK Area	1621, 492	Dottory
	catalogue. below under DK; Faience Vessels,	1695, 507	Pottery
	Figurines, Pottery separately catalogued under	1719, 550	DK138, 303
	each area below; Painted pottery catalegue,	1818, 570, 572	245, 309
	336-7; Seals, see seals, tabulation of; Weights,	1924, 472	455, 291
	591, 595-8	1933, 366, 572	700, 320
	*A 129, 577 2567, 551	2032, 462	711, 291
	*B 165, 462 2974, 462	2172, 571	895, 291
	441, 569 - 3063, 366, 572	2255, 462	1217, 310
	*C 46, 5:9 *D 368, 467	2256, 570, 572	1223, 306
	95, 490, 501 457, 465	2278, 507	. 1242, 305
	100-1, 490-1, 500, 603, 503	2279, 507, 584	1293, 309
	2 706 0	2361, 458	1764, 301
	160, 465	2362, 552	1863, 294, 298
	315, 463 *C 364, 366	2546, 532	2360, 315 2424, 316
	1853, 459 3063, 366, 572	2562, 572	2644, 291, 307
	1078, 400-8, 506	2632, 462	2782, 306
	2004, 556 Figurines	2691, 571	3108, 299
	2164, 557 *B 218, 351	2730, 572	
		0	

^{*} The letters A, B, C, D, and E refer to original rial trenches in the DK Area, some of which disappeared when the digging v subsequently expanded.—[ED.]

2528, 184, 171

257, 574

300, 470, 504

499-500, 503, 515,

^{*} The letters A, B, C, D, and E refer to original trial trenches in the DK Area, some of which disappeared when the digging was subsequently expanded.—[ED.]

708	INI	DEX	
٠,	FATT 470	Faience Vessels	2281, 314
4950, 204	5751, 479 5754, 189	546, 367	2286 207
4964, 198, 504, 50		206 268	2287, 303
4967, 198, 573	5775, 189	994, 366	2426g, 300
4972-2, 207	5797, 303, 498	1887, 368	2442, 307
4986, 196	5801, 203	2656, 179, 367	2842, 300
4987-8, 209	5804, 573	3739, 367	3121, 315, 467 3986, 314
4991, 209 4993, 188, 505	5805, 504 5811, 196	4944, 368	4598, 314
4999, 189, 505	5823, 213	5024, 197, 366	4768, 315
5006, 200	5825, 211	5214, 368	4812, 314
5012, 200	5826, 208	5548: 366	4861, 305
5024, 197, 366	5837, 573	5780, 368	5668, 300
5026, 516, 577	5842, 572	5843, 366, 575	5704, 211, 305
5035, 460	5843, 366, 575 5850, 207	5985, 368	5722, 300 5821, 300
5051, 190, 350 5127, 470	5854, 208	Pieurines	5872, 304
5196, 529	5858, 208	Figurines	5959, 310
5202, 205	5859, 207	0100, 350	
5205, 205	5861, 207	36, 354 1483, 3÷5	L Area
5292, 504	5 5863, 208	1854, 352	
5312, 206, 345	5870, 532	1924, 182, 352	4, 155, 341
5336, 204, 352	5880, 203 5894, 574	1935, 182, 350	29, 154 30, 153
5349, 207 5352, 209	5896, 213	2013, 183, 353	42, 153
5361, 189	5897, 213	2014, 180, 350	53, 136
. 5368, 213	5920, 208	2554, 184, 354	68, 156
5404, 210	5923-33, 191	2680, 352 3568, 346	76, 154
5409, 472	5925, 473	3690, 342	78, 154, 342
5415, 195, 498	5934-42, 191	4415, 203, 351	85, 153 86, 153
5436, 204 5459, 208	5934, 264 5935, 264	5051, 190, 350	95, 153
5463, 196, 480	5939, 191, 264	5161, 305	127, 155
5467, 196, 532	5943, 212	5312, 206, 345	139, 153
5514, 209	5980, 198	5321, 309 5336, 204, 352	179, 153
5521, 209	5988, 202	5550, 309	212, 153
5524, 209	6007, 553	5551, 344	216, 152° 225, 515, 583
5531, 201 5535, 201	6024, 196, 352 6029, 560	5585, 354	238, 156, 500
5536, 201, 573	2 6033, 196	5721, 209, 345	240, 153, 314
5539, 212, 478	6036, 195, 495, 505	5866, 343	245, 156
5540-2, 211	0041, 196, 471	5986, 343	271, 152
5549, 212	6057, 210	6024, 196, 352	306, 158
5562, 499	6058, 210	Pottery	307, 158 309–12, 158
5565, 574 5627, 205, 191	6070, 213 ° 0 6071-2, 213	465, 181, 302	316, 158
5647, 205	6088-9, 213	466, 294, 297	318, 159
5650, 202, 507	6097, 531	478, 297	320, 158
5652, 202	6104, 191	519, 178, 312	323, 158
5654, 202	6127, 198	565, 314	324, 159
5655, 205, 472	6138-9, 201	576, 297	327, 157, 354 328, 157
5659, 203, 205	6140, 201	596, 297	330, 158
5660, 507	6148, 465	741, 307 976, 297	332, 158,
5(66, 205 5673, 202, 471	6152, 201	980, 177, 298	340, 470
50/3, 202, 4/1	6170, 196	1093, 179, 302	342, 159
5707, 211	6173, 196	1153, 297	348, 158
5715, 212	6186, 197, 507, 533	1298, 307	350, 157, 354
5718, 571	6200, 198	1409, 303	351, 159 357, 159
5722, 209, 345	6202, 198	1422, 320	362, 155
5725, 210, 491	6213, 188, 549	1655, 320	366, 158
5741, 211	6216, 531	1874, 304	
		THE PARTY OF THE P	

```
892-3, 148
                                                               1016, 174
                                                                                         893, 558
898, 528
1049, 148, 299
                                  682, 164
    370, 466
                                                               1033, 174, 351
                                  687, 164 0
                                                               1108, 152, 174, 353
• • 371, 158
                                  689, 164, 514
  373-4, 266
                                                                1184, 530
                                                                                          1062, 499
                               702-3; 166
                                                                1186, 503
    375, 156, 562
                                  705, 166
710, 163
                                                                                          1106, 139
     383, 156, 495
                                                                                          1109, 150
                                                                   Figurines
    393, 159, 464
                                                                                          1198, 138, 515, 583
                                   711, 164.
     394, 158
                                                                                          1217, 148, 469,
                                   712, 163
                                                                   4, 155, 341
                                713, 166, 505
716-7, 167
     395, 158
                                                                                          1231, 136, 469, 573
                                                                  78, 154, 342
     400, 158
                                                                                           1291, 148
                                                                 324, 157, 354
   402, 515
                                                                                           1397, 573
                                   722, 167, 343
                                                                  350, 157, 354
     405, 174
                                   724, 171
                                                                                           1399, 139
                                                                  590, 156, 352
     490, 159
                                                                                           1407, 471
                                                                 600, 35<sup>2</sup>
722, 167, 343
                                 725-6, 167
     418, 158, 464
                                                                                           1535, 133, 572
                                 730-2, 168
      420, 171
                                                                                           1553, 149
                                   734, 168
                                                                  918, 173, 354
                                                                                           1567, 149, 176
   435-6, 171
                                   735, 161
                                                                 1033, 174, 351
      440, 1600
                                                                                            1629, 148
                                    737, 171
                                                                 1108, 152, 174, 358
      445, 160, 517
453, 160
                                                                                            1640, 149, 303, 305
                                • 763-4, 164
                                                                                            1705, 149, 366
                                 774-5, 191
780-1, 166
                                                                      Pottery
      454, 165
                                                                                            1731, 149
                                                                                            1759, 138
1781, 139, 504
                                                                   91, 306-7 8
      456, 165
                                    781, 565
      461, 160
                                                                   240, 153, 314
                                    785, 168
      464, 159
                                                                   829, 174, 304
                                                                                            1811, 149
                                    791, 173
      465, 163
                                                                   847, 174, 304
                                                                                             1814, 148
                                  796-7, 163
                                                                                             1823, 149, 584
       468, 515
                                                                   849, 174, 209
                                     801, 172
                                                                   865, 173, 304
       483, 170
                                                                                             1839, 148
                                     805, 172
                                                                   874, 173, 306
                                                                                             1845, 148
     487-9, 163
                                 809-10, 172
                                                                   878, 175, 306
                                                                                             1850, • 148
       490, 159
                                    809, 571
813, 163
                                                                   891, 173, 302
                                                                                             1885, 135
       493, 159
                                                                                             1894, 135, 469, 573
       494, 170
                                                                    911, 299
                                     814, 174
                                                                                             1899, 148, 502
1918, 149, 308
       508, 169
                                                                    927, 304
                                     818, 173
                                                                    944, 297
    509-10, 165
                                     820, 173
                                                                                              1930, 148
       512, 159
                                                                   1018, 304
                                      823, 173
        513, 165
                                                                   1060, 307
                                                                                              1963, 133
                                      826, 174
                                                                   1097, 308
                                                                                              1984, 138
        514, 165, 459
                                      829, 174, 304
                                                                                              1998, 140, 517, 584
    517-22, 170
                                      847, 174, 304
                                                                                              2007, 149, 499
        519, 171
                                                                   1192, 298
                                      849, 174, 299
      527-8, 171
                                                                                              2010, 144
                                     850, 173
                                                                                              2040, 150, 469, 572
        530, 171
                                      855, 176
                                                                SD Area
                                                                                              2052, 133, 502-3
        540, 159
                                     °857, 175
                                                                  SD123, 516
        541, 159
                                                                    207, 150, 476
                                                                                              2100, 143
                                      865, 173, 304
                                                                                              2101, 143, 297
        542, 171
                                      874; 173, 306
                                                                     233, 532
        544, 165
                                                                                               2148, 149
                                     • 876, 173
                                                                     254, 526
                                                                                              2172, 136
2184, 138, 154
2199, 145, 466
      546-7, 170
                                                                     427, 147, 530, 573
                                    878-9, 175
878, 306
         549, 170
                                                                      448, 149, 304
         550, 170
                                       885, 173
                                                                      479, 147
         552, 170
                                                                                               2214, 139
2278, 145, 353
                                       886, 173
                                                                      502, 530
          557, 165
                                       891, 173, 302
                                                                      526, 150
                                                                                               2297, 148
          561, 170
                                       895, 173
                                                                      533, 147 •
                                                                                               2310, 148, 466
          562, 165
                                       898, 175
                                                                      570, 138
                                                                                                2325, 144, 526
          564, 165
                                       899, 165
                                                                      590, 147, 30%
                                                                                                2375, 526
          565, 165
                                                                      642, 466
                                        904, 174
                                                                                                2390, 139 366
          568, 170
                                        918, 173, 354 .
                                                                      650, 146
          572, 507
                                                                                                2445, 144
                                     932-3, 175
                                                                       694, 147
                                                                                                2468, 506
          579, 130
                                     950, 175
957–9, 174
977, 174
                                                                       717, 136, 571
                                                                                                2483, 145, 302
          590, 156, 352
                                                                       818, 148
                                                                                                2508, 443, 511
          629, 164
                                                                       820, 585
                                                                                                 2511, 144, 470, 504
2552, 141, 368
           642, 173
                                                                       835, 148
                                        982, 164
           652, 505
                                        987, 174
                                                                       846, 148
                                                                                                 2577, 146, 457
        655-7, 167
660, 167
                                       993, 164, 512
1012, 174
                                                                        847, 149
                                                                                               • 2600, 145, 355
                                                                       872, 585
        661-3, 160
668, 167, 516
                                        Po13, 174
```

									0			,		
2617, 471 "		851, 4	70			0	2546,	515,	583		3241,	216		
2686, 148	0	875, 2					25725			0	3287,	216	0	.0
							2585,				0 3310,			
2830, 559		958, 2					2500,	219			3316,	218		
		1025, 4					2589,	219		0.				
Faience Vessels	0	1054, 5	331				2601,		503		3322-3,	210		
		1107, 2					2626,	224			3347,	218		
258, 366		1173, 4					2648,		221.	470	3355,	216		
1705, 149, 366										T/7	3360,	216		
2390, 139, 366		1182, 2	20				2651,							
2390, 139, 300		1192, 5	58				2662,		558		3362,			
2552, 141, 368		1218, 4				-	2667,	23I	0		3368,	216	0	
		1251, 2					2671,		367		3372,	218		
Figurines											3374,	216	0 0	
		1346, 2				0	2672,		305		33/4	0		
250, 352		1447, 5	34				2675,				3388,	218		
2184, 138, 354		: 1450, 2		105-6			2701,	221,	503		3392,	216		
				,,,			2716,				3429,	216	0	
2278, 145, 353		1530, 4		- 0					5-5		34543			
2600, 145, 355		15374, 2		520			2743,							
		1537, 2	26				2745,			0	3464-6,			
Pottery		1555, 2					2747,	226			3497,	217		
rottery							2766,				3528,	215		
229, 297		1575, 2									3529,			
246, 306 1		1596, 2					2767,		•					
		1636, 5	75			1	2835,				3541,			0
354, 299		1637, 2				1	2869,	22 I			3554,	215		
448, 149, 304		1695, 2					2877,		367		3575,	216		
1049, 148, 299							2881,				3586,	216		
1229, 294		1731, 5							309					
		1800, 2				1	2894,				3588-9,	215		
1640a, 149, 303		1802, 5	OI				2298,	219			3598,			
16406, 149, 305		1821, 2		162			2939,	219,	369		3599,	216,	502	
1918, 149, 308		1853, 2				20	952-3,				3602-3,			
2101, 143, 297				10/		_					3612,		,	
2483, 145, 302		1888, 2		,			2958,		0					
2403, 143, 302		1899, 2	18, 4	163			2961,				3622-62,			
2685, 317		1900, 2	21				2962,	221,	553		3627,	215,	587	
2688, 314		1925, 2		157			2982,				3638,	215.	309	
				10/			2985,				3639,			
VS Area		1947, 2												
		1957, 4				1	2994,				3642,			
3, 558		2028, 2	27			1	3008,	231			3648,			
38, 509		2041, 5				30	28-32,	224			3666,	215	0	
	F20						3038,			3	3868,			
63, 222, 229,	529	2079, 4									6178,			
74, 460		2101, 5					3040,		9		01/0,	4//		
125, 228		2109, 2	31				3046,	460	•					
127, 228		2 2139, 2	25				3050,	23I			Faie	nce V	ressels	
130, 516		2142, 2					3052,							
											2505,	219,	309	3)
195, 574, 575		2144, 2					3054,				2671,	219,	367	
206, 229, 309	0	2148, 2	24				3091,		527		2868,	367		
210, 87		2762, 5	51				3092,	222			2877,		267	
256, 326, 459		2172, 5			9 8		3097,							
250, 520, 459				360			3099,				2881,			
416, 457		2182, 4									2939,	219,	309	
441-2, 224, 303		2187, 4					3113,							
467, 224, 564		2231, 2	18, 4	.76		3	15-6,	, 231			F	igurir	ies	
502, 530		2269, 2			0	31	37-40,	224				-6		
							3153,				45.	352		
506, 225		2327, 50								-	191,			
540, 504		2393, 40	60			31	62-4,							
572, 224		2417, 2					3170,					344-	0	
639, 224		2430, 22					3174,		301		961,	344		
679, 224						21	78-9,		. 0		1284,	353		
673, 224		2468-96, 22		,		51					1369,			0
679, 459		2505, 21	19, 3	09		-	3185,							
7=0 228, 503	-	2507, 47		The same of		. 0	3167,	515			1555,			
		2509, 46					3192,				1564,		0	
779, 228	-				3		3206,			0	· 1947,			
790, 457		2512, 21				0					2046,	353		
791, 228, 307		2521, 22	20				2208,	23!	0,,					
792, 223		2529, 55					3210,	221	462	0	2165,			
		2540, 46		1			3211,		-		2215,			
804, 223, 552	1			-6	0		3234,	226		0	2276,	342		
838, 228		2545, 22	1, 5	50	1		3-34,	20.0						

	2667.,	353				163	3,	309		0	
0	· 2869,	351						305) .		
	2994,	35%		-		1934					
								303			
		Potter	y			2111					
	31,	305				247					
	95,	306			3	2662			558		
	125,	313	* 1			2672	2,	227,	385		
		300				2709	5,	394		3	
		229,	309						305	0	
	303,					2917	7,	299			
	366,	297	0 3	0		2961	,	278,	308		
	404,					2991	,	303			
4	14 Ia, b,	2,24,	303		-	3023	3,	311.			
	4,42,				0	3034	١,	294,	298		
	478,		298			3174	,	228,	301		
	547,				0			314			
	711,					3398					
	720,					3638	3,	213	315,	309	
	791,		307			36390,			307		
	, 920,							314		. 3	
	1022,					36420, 6			302		
	1026,							306			
	1108,							215,	305		
	1220,							305,			
	15716,	306				7915	,	298			
				- 1							

Offerings to dead, see also Grave-forniture, 83-8 Offering-stands or censers 83-7; type A, various forms, 293-8; uses of, 206; distribution and history, 292, 295-6

Oldenberg, Die Religion des Veda, 65 n. 5

Onyx, 523, 525, 536-7, 681 Oppert, Gustav, The Original Inhabitants of India, 48 n. 3, 51 n. 1, 2, 4, 7, 9, 11, 56 n. 3, 57 n. 3, 58 n. 2, 3, 59 n. 2, 66 n. 2, 68 n. 4

Orientation, look under Burials, Houses, Streets, etc. Ornament, see also Personal Ornament; of male god, 52; love of personal, as shown on figurines, 346; absence of on weapons, implements, etc., 42

Ornamentation, see Decoration

Ornaments represented on statues, see also Jewellery, 363; on figurines of Mother Goddess, 49-50

Ornaments and artefacts, materials used, see Gold, silver, lead, copper, bronze, stone, bone, ivory, shell, faience, etc.

Ovis sp., 659

Oxford Editions of Cuneiform Texts, vii, 295 n. 2, 3, 400 n. 2, 453, 579 n. 5

Pachyura stoliczkana, see Crocidura bidiana Paint, kinds used for pottery, 320-1; colours catalogued, o 336-7; method of applying, 321; paint over , slip, 319-20; red, on figurines, 341 Painted bands on faience jar, 366 Painted Glaze, see Glaze, painted Painted jars, misc., group AB, 309-10 Painted Pottery, see also Borders, Pottery, painted; 318-37; Catalogue, 336-7; chronology, 333-5; classified by decoration, 319; Designs on, see Designs on Painted pottery; Distribution of designs,

see Distribution; shapes, 322; and unpainted pottery, 292 Painted statuette of nude man, 213 Painted ware, small, group C, 303 Palæontologia Sinica, 326 n. 7, 329 n. 3, 334 n. 7 Palestine, glass, fr., 583 Palettes, 457 Palm-rat, 351 Panjāb, Chalcolithic sites in, 91-2 Pannier-like objects on heads of figurines, 338 Panther-like mask, 350 Pans, type W, 307-8 Parreysia favidens (Benson), 664 Party-wails, see Walls, party-Pascoe, Sir Edwin, on nietals, 29; on lead mining, 524; cap. xxxii Passages surrounding Great Bath, 138-40 Paste, see also Vitreous Paste; kinds used for painted pottery catalogued, 336-7; their manufacture, Pasupati, Lord of the Beasts, 54 Paton, Professor, 51 n. 6 Pavement of Pillared Hall in L Area, 23, 161; in section A, Area L, 154 Paving, varieties of, 272-3; in DK Area, 233, 237 Peacock, model, 350 Peake, Harold, "The Copper Mountain of Magan," 30 n. 4, 482 n. 4; 586 n. 2 Peake and Fleure, Peasants and Potters, 350 n. 1; Priests and Kings, 295 n. 6, 386 n. 2, 549 n. 1, Pearson, Karl, see also Lee and, Manouvrier and, Math. Contributions to Theory of Evolution: On the Reconstruction of the Stature of Prehistoric Races, 600 n. 4 Pedestal of alabaster, 479-80 Peet, Stone and Bronze Ages in Italy, 308 n. 3, 316 n. 4 Pendants for necklaces, 522 Percival, Professor, 587 n. 1 Perferation of beads, 511-12, 517, 520; of maces, 460-1; of pottery, 231; V-shaped, 533 n. 2 Periods, see Chronology Persia, see Susa, Elam, Distribution, Mém. Dél. en Perse; possible influence of its culture on certain modes of burial in Sind, 90 "Persian wheel," 318 Personal Ornaments, 34-5, 509-48 Personification of Tree spirits, 65-6 Petrie, Sir Flinders, see Ancient Egypt; Arts and Crafts of Ancient Egypt, 508 n. 1, 575 n. 3; Metals in Egypt, 482 n. 2; Prehistoric Civilization, 581 n. 2; Prehistoric Egypt, 461 n. 4, 553 n. 3, 579 n. 2, 583 n. 1; Tools and Weapons, 369 n. 2, 459 n. 1, 495 n. 3, 497 n. 1, 498 n. 1, 499 n. 2, 500 n. 1, 502 n. I Phallic emblems, 58-60, 191; object, 476 Physical properties, see Beads, etc., s.v. Piau or drinking place, 205
Pictographs, see Indus Script; possible identification of objects represented, 407-8; on bracelets, 531; on copper tablet, 210; on ivory bar, 209;

On both sides of a seal, 203; fr. Kish and

Piers, 237, 247

Pigments, and paints, 320-1, 517, 685, 688-9; colours catalogued, 336-7 Pillared Hall in L Area, 23, 160-5 Pipal-tree, worshipped, 64; on seals, 390 Piping, 506 Pipkins, scored, type AA, 309 Plano-convex bricks, not found at Mohenjo-daro, 264; found at Kish, 284 n. 3 Plant designs, see Designs on painted pottery Plant forms on seals, 390 Plaque w. male figure, 343 Plasma, or green chalcedony, 511, 545, 682 Plaster, composition of, 263 ? preservation of, 262 n. 3; on house walls, 18; painted, on Stupa plinth, 115-6; -cement for shell-inlay, 566 Plates CXIX-aCXXIX described in cap. xxii; CLXI, CLXII, explained on page 672 Platform supported on mud-filled masonry cells, 135-6 Platforms, houses built on artificial, 252; in Mesopotamia, 265 Plenderleith, Dr. H. S., 578, Appendix II Plinth of Stupa, 114, 116 Pliny, on one-horned animals, 69 n. 1 Pointed bases for jars and bowls, see also Goblets, Vases, 217 Polak, Persien, 676 Polished slips, 320; ware, 311 Polychrome ware, 38, 321; with floral patterns, 222; polychrome banded ware, 98 Pot set in pavement, 184 Pot-marks, 291-2 Potter's art, antiquity in Sind, 38 Potsherd, analysis of, 316; sherds used as filling for Pottery, 287-337; see also Bases, Clay, Ceramic wares, Glazed Pottery, Painted pottery, Slips, etc. Burials, in: 82-9; in "buriah urns" in Buddhist Monastery, 121 Chronologicai grouping, 316 Decoration, 37-8; basket-work patterns, 333; comb and step motifs, 105; inscribed, 317; lines, 319; triangles, stepped, 333 Excavator's numbers: see Objects mentioned by number in text s.s. Pottery, Painted pottery Forms copied, in bronze, 489; in stone, 368-9 Monufacture: wheel-made, 37; foot- and handwheel in ancient and modern times, 287-9; handmade, 287; made in two or more parts, 290, 293, built up fr. strips of clay, 315; firing or baking, 289, 686; kilns, 193, 226 Objects of: balls, 465-7; beads, 517, w. two-coloured

glazes 516; beakers, position of, 163; bracelets, 530; cones, 477-9; cylindrical objects, 479;

drain pipes, 280; flesh-rubbers and rasps, 467-8; 559; miniature vessels,

perforated, 231; soak-pits, 279; spindle whorls,

168-70; tablets, 480; toys, 549

gamesmen,

Jemdet Nasr, 453-5; on seal fr. Djokha, 380,

- Pig, 73-4, 660-1, 669; models, 348, 352

Painted: universal knowledge of manufacture in Chalcolithic Age, 94; w. antelopes, 222 Fredand-black, 37-8; plain black bands, 170; as guide to extent of Indus culture, 96-101 Scarcity as cfd. w. Mesopotamian sites, 287 Sites, other: Balüchi classified, 97; Nal, Jemdet Nasr, Proto-Elamitic sites, 82; fr. Ægean w. signs similar to Indus signs, 419 Types, 37; types mentioned by letter and described, 293-316, 289, 290; fr. Mound F resembling those fr. Cemetery at Harappa, 81 Porter's lodge in dwelling house, 20 Portrait statuary, 356, 364 Prashad, Baini, in Rec. Ind. Mus., 662 n. 2, 663 n. 2; Notes on Aquatic Chelonia of the Indus, 570 n. 2 Pre-Āryan contribution to Hinduism, 76-8; character of Mother Goddess cult, 51; religion, conflict of views on, 48-9; prototype of Siva, 52-6; origin of Tree worship, 65; nature of Zoolatry, 73 Pregnant, clay figure represented as, 549 Preston, Fauna of British India, Mollusca, etc., 604 Prithivi, Earth-goddess of Vedic Āryans, 51 Privies, 21, 207 Proceedings of the Society of Biblical Archæology, 370 n. 2 Prognathi9m, 641-2 Proto-Australoid type, 106-7, 638-42 Proto-Elamitic civilization older than that of pre-dynastic Egypt, 581 Publication of results of excavation, 12-14 Pumpelly, Explorations in Turkestan, 292 n. 5, 295 n. 4, 310 n. 5, 326 n. 3, 327 n. 1, 331 n. 4, 333 n. 3, 398 n. 1, 457 n. 1, 461 n. 1, 466, 468 n. 5, 482 n. 6, 523 n. 2, 533 n. 1, 554 n. 1, 555 n. 1, 566 n. 7,

Quartz paste, 576, 686 Querns, see Saddle-querns Quibell, Hierakonnolis, 384 n. 2

568 n. 2, 579 n. 6, 8, 587 n. 2

Racial types in detail, 638-644; possibly shown on statuary, 361-2; general discussion, 42, 107-9; represented by different kinds of burial, 81-2, 84 Rainfall, see Climate and; Table for Sind and Balūchistān, 4 Ram's head in terra-cotta, 231 Rams, models of, 347, 352-3; statues of, 360 Rao, T. A. Gopinatha, Elements of Hindu Iconography, 53, 55 n. 6 Rat, 653 Ratios of weights, 37 Raverty, Major Fi. G., on river system of Sind, 4-6 Razors, 500 Reamers, 504 Recess in wall, 163 Rec. Geol. Surv. Ina., 542 m. 1, 547 n. 2 Red ochre, see Ochre, red; traces of, on capital, 264 Red-and-black Balüchi ware, 97-8 Red-and-black wares, see Indus ware, Red-and-black Balūchi, Sūrjangal

Religion of Indus people, cap. v Reed matting, possibly used for roof, 172 Refectory of Buddhist Monastery, 118 Relic casket in Buddhist Monastery, 120 Repair of stone vessels, 31 n. 3, 369 Reptiles, 662; as food, 27 "Reserved slip," see "Combed slip ware" Revue d'Assyriologie, 380 n. 2, 387 n. 6, 409 n. 1, 424 Reynolds, S. H., The Vertebrate Skeleton, 651, n. 3. Rhinoceros, 72; models of, 348, 353-4; on seals, 205, 387 Ribbed pottery, type F, 309-1 Ridgeway, Origin of Currency and Weight Standards, 595 Ridgway, R., Color Standards and Nomenclature, 535 Rings, see Einger rings Ring-bases for jars, 299 Ringstones, 61-3, 191, 473-5; probable use as cult objects, 22; or beads, 584 Rita rita (?), 27, 664 River system of Sind in ancient and modern times, 1, 5-7 Rivers, importance in evolution of Chalcolithic civilization, 93-4 Rivet-holes in stone vessels, 369 Robertson, A. W. D., see Berry and Roofing, 277-8; of Hall in L Area, 164 Roofs, probable nature of, 17; possibly of reed matting, 172 Rooms numbered on Plans, look under Areas by Letters, then Sections, then Blocks in which they are;

Sabæan alphabet, sign similar to Indus sign, 419-20 Sacred animals, see also Animals; 74, 355; possibly kept in captivity, 391-2 Sacred buildings, 204, 284 Sacrifice, possibly buman, to the dead, 81 Saddle-querns, 27, 456-7
Sālagrāma, symbol of Vishņu, 56; -stone wedded to

Salts in soil, effect on antiquities, 1, 289, 579, 599; unusual amount in DK Area, 241, 265

Sahni, Rai Bahadur Ram, 11, 15-4, 45, cap. xiii, xiv Saktism in India, 57; parallels in Nearer East, 57-8 Sandas, 181

Sank shell, identification and distribution, 665-6; see also under Shell-inlay, Shell Objects, shells

rooms w. baths, 211

Rope pattern on stud, 529

Rubbers, see Flesh-rubbers

Rubble filling for walls, 271

Roundel of Steatite, 480

Rubbish chutes, 16, 181

tulsi plant, 66

Sanskrit and Indus script, 431-2 Sarasin, P. and F. Die Weddas von Geylon, 639 n. 5 Sarkar, Prof. S. C., Some Aspeds of the Social History of India, 24 n: I

Saws, 500-1; use in manufacture of seals, 377 Sayce, Rev. Prof. A. H., 73 n. 8, 370 n. 2

Scheil, Dr., on cylinder seal fr. Susa II, 104: Receuil, de signes archaiques, 387 n. 1; in Revue d'Assyriologie, 410 n. 1; Textes de Comptabilité Proto-Elamites, 424

Schoff, The Periplus of the Erythraan Sec, 691 n. 2 Schrader, E., Sitzungsberichte d. kgl. preuss. Akad. zu

Scored pottery, type B, 298-9

Scott, Alex., The Cleaning and Restoration of Museum Exhibits, 546,n. 5

Screen wall, 222

Script, see Indus Script; animals used in, 392; apparently unconnected w. device on seal, 407

Sculptures and racial types, 108

SD area, 131-50

Seal, cylinder, at Mohenjo-daro, 381 n. 3 Seal fr. Harappā, w. picture of building, 25 Seal showing method of reading script, 225

Seal impressions, 380; classification and description, 393-8; as material for study of Indus Script, 424; as labels, 410, 412; impression of yellow faience in funeral urn, 87; on pottery, 292

Seals, tabulation of, 402-5; types described, 370-7; materials of, 371-6, 688 (and see tabulation); nænufacture of, 37?-9, 688; purpose of, 379-82; possible disposal of, after death of owner, 382; similarity at all periods, 103

Indus type, fr. Elam and Mesopotamia, affording chronological evidence, 103-4, 381, 424

Chemical analysis of coating, 379

Inscriptions on, 406-453

Method of photographing and describing, 370

To contain amulets, 380

Depicting animals, see Animals, s.v.; gods or goddesses, 52, 63-75; cult object on fillet, 527; statue framed in doorway, 23

Seated figures, 342-3 Seats, see Benches

Sections, look under Areas

Sediment-pits, 279-80

Seligman, Dr. C. G., on Bird-Chariots, 560-1 Semi-precious stones, see Stones, semi-precious

Sen, Dr. Hem Chandra, in Indian Medical Record,

587 n. 4 Sergi, G., "Description of some skulls fr. the North Kurgan, Anau," in Pumpelly, Explorations in Turkestan, 643 n. 3

Serpent Nagas, 75, 395

Servants' quarters, 202

Sewage, drains not used for, 281

Sewell, Col. R. B., and Dr. B. S. Guha, on animals of Sind, 27 n. 4, 28-9; on racial types, 82, 84, 107-8; "Report on the Bones excavated at Nal," 599-601 nn., 607, 616 n. 1, cap. xxx and xxxi

Sex, see Skulls described in order Shadoof, represented on scal, 389 Shāhī-tump, see Balūchistar; ware, 99

Sheep, 659

Shell-inlay work, 32, 1713, 173, 195; method and designs, 565-70

Shell-fish, 664-6,673

Shell objects, 471, 478-9, 563-5; suggesting parallels fr. Kish, 475; bracelets, 531; cones, 558
Shells, species used, 563-4; methods of working, 564-5; cutting, 500; for bangles, 219; for

ornament or use, 669-71

Shell work found in Section D, Area L, 170 Sherd, see Potsherd. Shield-boss, 506 Shops, 205, 208-9, 212, 240 Shrews, 652 Shrines, possible use of structures as, 22, 235 Sickle-shaped blade, 501 Siebenrock, F., "Zur Systematik der Schildkröten-familie Trionychidæ Bell, etc.," 662 n. 3 Sign List on the Indus Script, 434-52 Sign Manual of the Indus Script, 40, plates CXIX-CXXIX Signs, division into classes, 415-8; difficulty in classifying, 406; position of, 410; modifications, combinations, 409: enclosures in, 409; ideographic nature of, 420-1; possible identification of objects represented, 407-8 analogies fr. Ægean legion, 419; w. Sumerian and Minoan, 411; w. Sumerian, 408-9; w. devices on coins in N.W. India, 413 Silājīt, 29, 587-8; chemical analysis and description, 689-90 Silt, volume carried by Indus, 7 Silver, sources of, 523-4; 675, 678; chemical analysis, 524; associated w. gold, 675; and lead, 675; beads, 546; earrings, 519; ring, 520; rough, 519; vases, 194; vessels, 493; vessel containing jewellery, 519 Sind, see Chalcolithic sites in, Neolithic Artefacts Siva, see Male god Skeletons described in order, 600-7; where found, circumstances, etc., 600, 42, 107-9; 122, 178-9, 181, 184-6, 191, 222-4; number, condition, preservation, 599-600; measurements and method on long bones, 600-5; stature, 600-5 Skeumorph, 534 Skulls, see Indexes, Measurements, Cranial capacity; described in order, 607-37; number measured, 606-7; posthumous deformation, 607 Slate, 31, 680-1; boxes w. compartments, 219; vessel, 368 Sledge in Egypt and Mesopotamia, 555 Sling balls, 36, 466-7 Sling-stones 173 Slip, see also under Pottery, types mentioned by lette., "Combed Slip ware"; Colours catalogued, 336-7; on figurines, 349 Slips, 290-1, 319-20 (and washes), 686; on Offering-Stands, 293-4 Smith, Catalogue of Coins in the Indian Museum, 128 n. 2, 3, 129 n. I, 2 Smith, G. Elliott, Evolution of Man, 640 n. 1 Smith, Sidney, Early History of Assyria, 363 n. 3, 385 n. 3 Smith, Sidney, and Gadd, C. J., see Sign Manual; Smith, Vincent, "On the Copper Age and Prehistoric Bronze Implements of India," 483 n. 1, 494 n. 2 Smithsonian Misc. Collections, 77 n. 1

Soak-pits, 17, 240, 244-6, 279-80

South Lane HR Area, 178

Spacers for necklaces and girdles, 507, 517-8 Spear and lance-heads, 35, 497-9; resemblance to some African types, 498 Species, see Animal remains Spencer, see Bauer and Spindle-whorks, 32, 468-70, 572-3; faience on copper shaft fr. Kish, 470 Spinning and weaving, universal in Chalcolithic Age, 94 Spiral decoration on pottery, 298; volutes on limestone capitals, 191 Spouted cup, 310; jars, rarity of, 228, 292 n. 7, 293 Squirrels, faience, 43, 205,0221; models, 351 Staff of excavators, 10-14 Stag's horn used as medicine, 29, 671-2 Stairways, 16, 20, 133, 140-1, 166, 172, 237-8, 248, Standard in front of "unicorn" on seals, 383; carried in procession, on seal impression, 395; on gold fillet, 527 Stands for storage jars, 170 Stapf, Dr. O., 586 Statuary, amount discovered, 356; no resemblance to foreign, 360 Statues, see Animals, s.v., Human statues; 33, 54, 175, 177-8, 237 Statuettes, see Animal, Human, Figurines Stature, see Skeletons Steatite, 526, 678-9; manufacture of seals, 377; method of using, 576, 688; paste, 576-7, 687; surface coating, 379, 688 Steatopygia, 344, 549 Step motifs, see Comb and Step Stein, Sir Aurel, references to his discoveries in Balūchistān, 2, 35, 49, 59, 82, 89, 96, 100-1, 313 n. 1, 331 n. 9, 488; Gedrosia, 3 n. 1, 96 n. 2; Ancient Khotan, 316 n. 3; Serindia, 583 n. 12; Wazīristān, 95 n. 2 Stevenson, M., ERE., 69 n. 3 Stone boxes, 369; money of Caroline Islands cfd. w. ring-stones, 61-2; monuments in Sind, 92-3; rings, see Ringstone; statuettes, statues, q.v., 44-7; used in building, 31; for statues, 31; vessels, 31, 367-9; worship, see Bætylic stones Stones, semi-precious, 31-2, 525-7, 536-41 Storage jars, 157, 169; group AG, 313-15; pits for, 216; stands for, 170 Stratification and chronology, 9-10; of remains of Indus culture in Stūpa alea, 124-7 Streets, 8, 176, 238, 242, 284; alignment, size, orientation, 282-3; barred, 284; levels cfd. w. those of buildings, 8-9; unpaved, 273 Stucco, painted, in Buddhist Monastery, 117 "Über einen Hund aus der Palæolithischen Studer, Zeit Russlands, Canis Poutiatini," 651 no 1 Stūpa area, buildings to South of, Blocks 1-8,-145-50; and Monastery, excavation, 113-123; remains of Indus culture in, 123-30 Subsoil water, hinders digging in VS Area, 214 Sulphur, percentages in Copper and Bronze, 484, 486 Sumerian, clook also under Mesopotamia; bricklaying cfd., 262; culture, 102; religious contact, 76-8;

script cfd., 408-9, 411, 423, 435-45; table of

INDEX

signs cfd. w. those of Indus Script, 454; toy chariet wheels, 554

Superimposed foundations, 226; structures, 223-4; walls, 238

Surjangal ware, 98

Sus cristatus, 660-1

Susa, see Elam, Distribution, Méss. Dél. en Perse;

Susa I pottery and Indus designs, 105; Susa II, bone cylinder seal, 104; Indus cylinder seal, 424-5; mace-heads, 460; shell objects, 475; weights, 593-5

Suspension, holes for, in jars, 293; in pottery, 311

Survey of site, 13

Svastika symbol, 206-7; characteristic of India, 426; on seals, 190, 200, 227, 374

Syrian chariots, 555

Tablets, copper, see Copper Taboo, 49 Tabulations, see Seals, Objects mentioned by number, etc. Tachylite or basaltic glass, 683; beads, 546 Talismanic use of seal impressions possible, 397 Tārnā, in Sind, visited by Ibn Batūta, 73 Taxila, ring-stones, fr. 62-3 Teeth, human, badly worn, 638; cfd. w. those of other races, 638; of cattle, 654-9; of dog, 652; of horses, 654; of pigs, 660-1 Telloh, seals fr., 376, 424-Temples, see also Sacred buildings; 22, 244, 252 Tenth Lane in HR Area, 212-3 Terminals for necklaces, etc., 518 Terraces attached to houses, 21 Testudo elegans, 663 Tetrahedral gamesmen, 559 Textiles, see Spinning and weaving, 585-6; cotton adhering to vase, 194 Theri-anthropic beasts, 66-8, 74 Theriomorphism, 74-5 Three-faced god on seal, 53 Thresholds, height above street-level, 266 Thureau-Dangin in Revue d'Assyriologie, 406 n. 1, Recherches sur l'Origine de l'Écriture Cunéiforme, 423 Tiger, on seals, 202, 349, 387-8; as vehicle of Mother Goddess, 72 Tilley, Min. Mag., 546 n. 3, 4 Timber, see also Wood; used in construction of upper floors, 19 Times, The, 341 n. 2, 587 n. 1 Times of India, 22nd Jan., 1928, signs published in,

Tin, 30, 682; Sources of, 483-4, 682; scarcity of, 481; percentage in bronze implements, 481, 484,

486-#; records of use in Mesopotamia, 482

Todd, Wingate, Cranial Capacity and Linear Dimension

Toys, see Games and; toy carts similar to models fr.

in White and Negro, 637 n. 2

Tortoise, 73, 662-4; tortoise-shell, 228 Town planning, 282

Anau and Ur, 39

Trans. Bomb. Geol. Soc., 679 n. 1

408

Tree goddess, 63-4, 393 Tree-guards, 165 Treg-worship, 63-6, 393 Trees, entrance of alien spirit into, 66; of knowledge, wisdom, or life, 64; marriage of, 66; on seals and sealings, 389, 399, 393 Trefoil pattern, 54, 356-7, 515-17, 558; on Indus and Sumerian objects, 104 Trellis-work in houses, 21 Trial pit and trench, 245, 247 Trident as attribute of divinity, 54-5 Trionyx gangeticus?, 662-3 Trimūrtis of Siva, Brahmā, Vishņu, 53 Triskillion, 390 Trisula, see Trident Tsountas and Manatt, The Mycenæan Age, 70 n. 1 Tube of copper, 506 Tubular drill, see Drill Turbinella pyrum, 666 Turkestan, see Anau, Distribution, Pumpelly Turquoise, 32, 523, 525, 677, 678; -matrix and electrum ornament, 521-2 Turner, A. J., see Gulati and Turner, Sir W., The Relations of the Dentary Arcades in the Crania of Australians, 639 n. 7 Turtles, 670; model, 352

Uap, see Stone money of the Caroline Islands Ubaid, see Al 'Ubaid Ullah, Mohammed Sana, archæological chemist, analyses of materials, 12, 30, 132, 269, 379, 484-8, 530, 574-5, 689, cap. xxv and Appendix i Umma, see Djokha "Unicorns" on seals, 68-9, 382-5; object in front of "unicorn" as design on fillet, 527 Univ. Penn. Anthrop. Pubs., 514 n. 3 Ur chariot, 554; gold fillets, 194; Indus seals fr., 103-4, 385-6; reading of Indus seal w. cuneiform inscription, 413; toilet set cfd. w. one fr. Harappa, 104; see also Mesopotamia Urns, funeral, 82, 85-9 U.S. Geol. Surv. Bull., 541 n. 1 Utensils, see Household implements and

Vases w. pointed base, 215; see also Goblets Vase-like jars, type G(?), 381 Vases, tall, type I, 301 Vats, M. S., VS Area, 17-14, 81, 84, 214 Vedic and Indus culture contrasted, 110-12 Vedic India, dicing an amusement of, 552 Vehicles, see Wheeled vehicles, Chariots, Carts, Sledges; Toy, 554-5 Ventilators, probable use of niches as, 276 Verandahs, 198, 202 Vessels, stone, see Stone vessels Virgin soil not reached in VS Area owing to inrush of sub-soil water, 214 Vitreous paste, chemical analysis and use, 574-6; Instory and possible place of invention, 582 Vitrified paste or clay, 32, 34, 530

Viviparus bengalensis (Lamarck), 666

Vogel, Indian Serpent Lore, 75 n. 2, 76 n. 3

Votive use of seal impressions possible, 397

Votive object, possible use of clay figure as, 550; see

Ex-votos

VS Area, Block 1, 214-17; 2, 217-22; 3, 222-4;

VS Area, Block 1, 214-17; 2, 217-22; 3, 222-4 4, 224-9; 5, 229-30; 6, 230; 7, 230-2

Wahindah, see Mihrān Wainscoting of bathrooms, 273-4 Wainwright, G. A., 316 n. 2 Wallago sp., 664 Walls, see also Fortifications; of ho

Walls, see also Fortifications; of houses, 13-16; relieved by ornamental recesses, 21; party-walls, 283-4; built on cellular system, 243; twice rebuilt, 231; enclosing Great Bath; of building of sacred character, 264

Ward, Seal Cylinders of Western Asia, 66 n. 6, 67 n. 2, 4, 347 n. 3, 389 n. 1, 392 n. 2, 394 n. 2, 567 n. 5 Wartekar, Mr., discovery of plaster on Stūpa plirth, 115 Waste metal, see also Broken Metal, 552

Water, seasonal variation of sub-soil, 9; supply of houses, 18-19; of Great Bath, 24

Water-chutes, 139, 141, 244, 246, 251, 279

Water-jars, 315 Water worship, 75-6

Wealth as shown by use of burnt brick, 286 Weapons, see Copper and bronze; 35-6

Weaving, see Spinning and

Wedge-shaped bricks, see Bricks s.v.; usually employed for wells, 193

Weighing scales, 205

Weights, 36, 193, 461-4; system of, at Mohenjo-daro and Harappā, 589-98; Assyrian system, 593; Babylonian system, found at Susa, 593

Wells, 16, 142, 148, 150, 160, 173, 179, 188, 202, 233, 234, 243, 245, 247; construction of, at different periods, 269-70; coping of, 248, 253, 270; diameters of, 269-70; in houses, 189; for public use, 239

Western Asia and Aegean, see Ægean; Mother Goddess cults and figurines, 50, 57-8; religious contact w. Indus valley, 76-8

Wheat, 27; species, 586; origin of cultivation, 587; found on floor of room, 172; fr. Jemdet Nasr, 587; fr. L Area, 586

Wheeled vehicles, see also Chariots; possible Central Asian origin, 555

Wheels, toy, 554 Whetstones, 464

Whistles, clay, in shape of birds, 551

Whitehead, Catalogue of Coins in the Lahore Museum, 130 n.

Wild animals, see Animals, wild Wilson, A. T., The Persian Gulf, 69 n. 1

Wilson, Sir Leslie, 13

Windlasses, possible use of, 270 Windows, 16, 275-6

Wire, 505

Wood, supply and use of, 133, 263-4

Wool, as dress material, 32-3

Woolley, C. L., see Hall and; The Sumerians, 70 n. 2, 109 n. 1, 265 n. 3, 555 n. 1; elsewhere quoted, 36 n. 5, 70, 276 n. 2, 3, 406 n. 2, 569 n. 5

Writing, see Script, etc., 39-42; external features of, 406-23; unifying principle underlying methods of, in Chalcolithic Age, 94; affected by materials, 407; date of Indus writing, 414

Yakshī tree spirit, 65 Yokha or Djokha (7.v.), seal impressions fr., 380-1
Yoga, origin among pre-Āryan population, 54
Yogī, attitude of statue, 44, 357 n. 1; position shown on seal, 229; posture of pre-Āryan god cfd. w. that

of Siva, 53-4 Yoni, see Phallic emblems

Zebu, 27-8 Zeit. für Ethn., 325 n. 1, 327 n. 2, 332 n. 5 Zoolatry, see Animals, sacred

Compiled Compiled

10

विषय संख्या भरतक संख्या माग्न प्रिका संख्या ति प्रकार सिकी प्रम का प्रमास स्थापन सिका है। इपया प्रमास स्थापन स्थापन क्रिया के प्रमण स्थापन स्थापने प्राप्त संस्थे।



गुरक्त कांपड़ी विश्वविद्यालय मुख्यालय (जिलार पुरमकालय (

